



August 2020

Bureau of Waste Site Cleanup
Southeast Regional Office
Massachusetts Department of Environmental Protection
C/o Angela Gallagher
Site Remediation Section
20 Riverside Drive
Lakeville, MA 02347

RE: Immediate Response Action Status and Remedial Monitoring Report #44
Barnstable County Fire Training Academy FTA Facility
155 South Flint Rock Road
Hyannis, Massachusetts
DEP Release Tracking No. 4-26179
Project Number #6206

Dear Ms. Gallagher:

BETA Group, Inc. (BETA) has prepared this Immediate Response Action (IRA) Status and Remedial Monitoring Report (RMR) for the Disposal Site (the Site) referenced as the Barnstable Country Fire Training Academy (the FTA Facility) located at 155 South Flint Rock Road in Hyannis, MA on the behalf of Barnstable County. This report was completed on behalf of Barnstable County and in accordance with Massachusetts Contingency Plan (MCP) - 310 CMR 40.0000.

This is the 43rd monthly IRA RMR Status report. It documents the IRA/RMR activities being conducted to address a release of PFOS/PFOA to groundwater, soils, surface water, and sediments located at the Site. A potential Imminent Hazard (IH) condition and Condition of Substantial Release Migration were previously identified at the Site. This letter report specifically addresses the status of the Site groundwater pumping and treatment systems (GWPTS) during the monthly reporting period from July 1 to July 31, 2020. In addition, this report describes the site-wide, quarterly groundwater monitoring event conducted on July 28 and 29, 2020 and presents the analytical sampling results of that groundwater monitoring.

The completed BWSC105 Immediate Response Action (IRA) Transmittal Form and attached BWSC105A and BWSC105B IRA Remedial Monitoring Report Forms are being submitted to the MassDEP electronically via the eDEP system. This letter is being submitted to the Massachusetts Department of Environmental Protection (MassDEP) as an attachment to those forms. Copies of these forms prior to electronic signature are included as Attachment A.

REMEDIAL MONITORING REPORT – JULY 2020

During the July 2020 reporting period, the primary treatment system (GWTS #1) and secondary system (GWTS #2) were in operation for all or portions of approximately 30 days. There was one scheduled shutdown during this reporting period for GWTS #1 and GWTS #2. Specifically, GWTS #1 was shut down on July 16, 2020 for a few hours to backwash the primary liquid granular activated carbon (LGAC) vessel. BETA collected performance samples from both GWTS #1 and GWTS #2 systems on July 28, 2020; both systems were in operation at the time of sample collection.

Health Advisories and Regulatory Standards Used for Comparison

During the initial two years of the GWPTS operation (July 2016 through June 2018), the USEPA revised Health Advisory (HA) of 0.070 µg/L for two PFAS chemicals, Perfluorooctanoic acid (PFOA) and Perfluorooctanesulfonic acid (PFOS), was used for comparison to the analytical results of GWPTS performance samples. The HA (revised downward to 0.070 µg/L in July 2016) applied to each compound individually or for the total concentration of the two (PFOS and PFOA). Subsequently, MassDEP adopted the USEPA HA. The USEPA considers its HA to still be in effect (as of March 2020). However, for MCP purposes it has been superseded by MassDEP guidelines and regulatory actions.

On June 11, 2018, MassDEP's Office of Research and Standards (ORS) issued an updated ORS Guideline/HA that applied to the individual concentrations or the total summed of five PFAS chemicals: PFOS, PFOA, Perfluorononanoic Acid (PFNA), Perfluorohexanesulfonic Acid (PFHxS), and Perfluoroheptanoic Acid (PFHpA). From June 11, 2018 until December 2019, individual concentrations of any of these five compounds or the total concentrations of all were compared to the MassDEP ORS HA of 0.070 µg/L.

On April 19, 2019, MassDEP released the Public Comment Draft of proposed revisions to the MCP, which included proposed Method 1 groundwater risk standards for the five PFAS compounds, plus an additional PFAS compound, Perfluorodecanoic Acid (PFDA). A Method 1 GW-1 risk standard of 0.020 µg/L was proposed for the individual concentrations of any of these six compounds or the total concentrations of all six. From May 2019 through the current reporting period, tabulated treatment system analytical results have been compared to the six regulated PFAS compounds of concern for informational purposes.

In December 2019, MassDEP published final MCP Method 1 risk standards for PFAS with an effective implementation date of December 27, 2019. The final MCP PFAS risk standards for groundwater include the 6 PFAS compounds of concern listed above and at 0.020 µg/L¹ the GW-1 numerical risk standard. These MCP risk standards are included in Table 1A and Table 1B. The total PFAS concentrations reported and discussed for comparison purposes in this report are based on the six regulated PFAS compounds included in the final MCP risk standards of December 27, 2019.

GWTS # 1 System Monitoring Results

¹ Concentrations of PFAS are presented in the data tables of this report in nanograms per liter (ng/L), also referred to as parts per trillion (ppt) and are reported by the laboratory in those units. However the published MCP Method GW-1 numerical risk standards for PFAS compounds (PFOS, PFOA, PFNA, PFHpA, PFHxS, and PFDA) are in presented in or micrograms per liter (µg/L), also referred to as parts per billion (ppb). In the relevant sections of this report, results are shown in both units.

As noted, system samples were collected on July 28, 2020 from the Influent (PRW-4), Midpoint and Effluent ports and were submitted to Bureau Veritas Laboratories (formerly Maxxam Analytics) of Mississauga, Ontario (Bureau Veritas) for the laboratory analysis of Total PFAs via USEPA Method 537 M.

The total sum of the six Massachusetts regulated PFAS concentrations in the Influent (PRW-4) sample was 2,051 ng/L (2.051 µg/L), well above the GW-1 risk standards. Five of the six individually regulated PFAS compounds were detected at concentrations exceeding the new MCP GW-1 risk standard (0.020 µg/l); PFDA was detected at concentrations below the applicable standards (12 ng/L). Refer to the attached Table 1A for a summary of the GWTS #1 PFAS analytical data. Recovery well PRW-4 is the source of the Influent groundwater. Based on the splitting of flow from PRW-4 to both groundwater treatment systems, the Influent analytical results apply to GWTS #2, as well as GWTS #1.

The six MA regulated PFAS compounds were detected above the laboratory reporting detection limits in the Midpoint sample; however, the PFOS result was the only compound above the MCP Method 1 GW-1 standard (at 130 ng/L). For the purposes of achieving the lowest MDLs and RDLs ² (for effective comparison to the MCP Method 1 Groundwater standards), Bureau Veritas reports the results for 21 PFAS compounds, including two (2) PFAS precursors; this allows the laboratory to achieve RDLs as low as 0.18 ng/L. The complete laboratory report is attached in Appendix B. The laboratory report provides details of MDLs and RDLs for each PFAS compound included in the analyte list.

None of the six MCP regulated PFAS compounds (PFOS, PFOA, PFNA, PFHxS, and PFHpA) were detected at concentrations above MDLs in the Effluent sample from System #1. Additionally, the 15 unregulated PFAS compounds were reported below the laboratory RDLs and MDLs. Refer to the attached Table 1A, for a summary of the GWTS #1 PFAS analytical data in the Midpoint and Effluent samples. The complete laboratory report is attached in Appendix B.

Although PFAS was not detected in the July 28, 2020 GWTS #1 Effluent sample, due to the observed PFAS detections in the Effluent samples collected during the June 2020 reporting period, the County began the coordination and scheduling of the changeout of the granular activated carbon (GAC or carbon) in the GWTS #1 treatment vessels. To note, due to the turnaround times associated with receiving the monthly performance sample laboratory analytical reports, the June 2020 report was not received until July 14, 2020. Therefore, the carbon changeout scheduling began during this July 2020 reporting period and a changeout date was scheduled in August 2020. Although PFAS was not detected in the July 28, 2020 Effluent sample, the continued detection of PFAS above GW-1 standards in the GWTS #1 Mid-point sample indicated that initiating GAC changeout was appropriate.

GWTS #1 Operational Details

The attached Table 2A presents the GWTS #1 performance data. For the July 2020 reporting period, the overall (average) system flow rate and gallons of groundwater treated are based on the effluent flow meter/totalizer readings reported for the system by the O&M contractor.

On this basis, approximately 0.40 million gallons of groundwater were treated during this July 2020 reporting period, at an average effluent flow rate of 8.9 gpm.

² Method Detection Limits and Reportable Detection Limits.

Based on the approximate 0.40 million gallons treated and total influent concentration of 2.051 µg/L (July 28, 2020 sample results), approximately 0.003 kilograms of PFAS were estimated to have been removed from the plume area during this reporting period.

The estimated, instantaneous combined influent flow rates (for both systems) ranged from approximately 16.3 gpm to 24.7 gpm; typically, the combined estimated instantaneous influent flow rate was over 20 gpm. As detailed in the IRA Status and RMR reports from the previous 2020 reporting periods, iron-oxide sediment has significantly accumulated in the equalization (EQ) tank and has caused a decrease in the observed system flow rates. The system operator reduced the flow rate at the transfer pump to help reduce iron carry over from the EQ tank into the bag filters and potentially into the carbon vessels. Reducing iron-oxide precipitate carry over into the carbon vessels aids in maintaining the life and PFAS treatment efficiency of the carbon, as it is likely that residual dissolved iron is being oxidized, precipitated, and captured in the LGAC, resulting in lower flow through rates. GWTT has conducted monthly backwashes of the primary LGAC vessel to help remedy this carry over and to maintain the treatment life of the carbon; a backwash on the primary LGAC vessel was conducted on July 20, 2020. The attached Table 2A presents the GWPTS performance details. In response to the iron-oxide sediment accumulation in the Eq. Tank, the County contracted for the removal and off-site disposal of the groundwater and solids in both treatment systems equalizations tanks. This work was conducted during a later reporting period.

Due to the method used to estimate the instantaneous influent flow rate (timing of rise of groundwater in the GWTS #1 Equalization Tank with both force mains discharging to it), the estimated influent flow rates noted above apply to both systems, combined.

Therefore, during the normal mode of operation, with the flow from each force main flowing to only one system, it is assumed that roughly 50% of the instantaneous influent rates stated above actually flows to GWTS #1 for treatment. However, the estimated, instantaneous combined influent flow rates are actual tabulated - assumed 50% values must be computed – (e.g., the actual average influent flow rate for GWTS #1 is estimated to be approximately 10.5 gpm). Refer to the attached Table 2A for a summary of the GWTS #1 performance details.

GWTS # 2 Monitoring Results

As previously mentioned, BETA collected performance samples from GWTS #2 system on July 28, 2020. Samples collected from the Influent (PRW-4), Midpoint, and Effluent ports were submitted to Bureau Veritas for the laboratory analysis of Total PFAS via USEPA Method 537 M. As noted above, recovery well PRW-4 is the source of the Influent groundwater to both groundwater treatment systems. Therefore, the Influent analytical results apply to GWTS #2, as well as GWTS #1.

As previously mentioned, the tabulated treatment system analytical results from GWTS #2 are reported and compared to all six regulated PFAS compounds and their respective MCP Method 1 GW-1 Standards. The total sum of the six PFAS concentrations in the Influent sample was 2,051 ng/L (2.051 µg/L), well above the GW-1 risk standards. Five of the six individually regulated PFAS compounds were detected at concentrations exceeding the new MCP GW-1 risk standard (0.020 µg/L); PFDA was detected at concentrations below the applicable standards (12 ng/L). The attached Table 1B, summarizes the GWTS #2 PFAS analytical data. The complete laboratory report is attached in Appendix B.

The six regulated PFAS compounds were detected at concentrations above the laboratory reporting detection limits (RDLs) or method detection limits (MDLs) in this July 2020 Midpoint sample; however, only the PFOS compound was detected at concentrations (in the Midpoint sample) above the applicable MCP GW-1 risk standards.

For the purposes of achieving the lowest MDLs and RDLs (for comparison to the new MCP Method 1 Groundwater standards,) Bureau Veritas reports the results for 21 PFAS compounds, including two (2) PFAS precursors; this allows the laboratory to achieve RDLs as low as 0.18 ng/L. The complete laboratory report (in Appendix B).

Although, the six regulated PFAS compounds were detected in the Midpoint Sample, as shown on Table 1B, none of the six regulated PFAS compounds were detected at concentrations above MDLs in the Effluent sample; the MDLs achieved by the laboratory were below the applicable Method 1 GW-1 standards). The remaining 15 PFAS compounds were reported below the laboratory RDLs and MDLs, the laboratory report is in Appendix B.

GWTS #2 Operational Details

The attached Table 2B presents the GWTS #2 performance data. For the July 2020 reporting period, the overall (average) system flow rate and gallons of groundwater treated are based on the effluent flow meter/totalizer readings reported for the system by the O&M contractor.

On this basis, approximately 0.43 million gallons of groundwater were treated during this July 2020 reporting period, at an average effluent flow rate of 9.6 gpm.

Based on the approximate 0.43 million gallons treated and total influent concentration of 2.051 µg/L (July 28, 2020 sample results), approximately 0.003 kilograms of PFAS were estimated to have been removed from the plume area during this reporting period.

The estimated, instantaneous combined influent flow rates (for both systems) ranged from approximately 16.3 gpm to 24.7 gpm; typically, the combined estimated instantaneous influent flow rate was over 20 gpm. As detailed in the IRA Status and RMR reports from the previous 2020 reporting periods, iron-oxide sediment has significantly accumulated in the equalization (EQ) tank from buildup in the force main piping. Reducing iron-oxide precipitate carry over into the carbon vessels aids in maintaining the life and PFAS treatment efficiency of the carbon, as it is likely that residual dissolved iron is being oxidized, precipitated, and captured in the LGAC, resulting in lower flow through rates. GWTT has conducted monthly backwashes of the primary LGAC vessel to help remedy this carry over and to maintain the treatment life of the carbon; a backwash on the primary LGAC vessel was conducted on July 20, 2020. The attached Table 2B presents the GWPTS performance details. In response to the iron-oxide sediment accumulation in the EQ. Tank, the County contracted for the removal and off-site disposal of the groundwater and solids in both treatment systems equalizations tanks. This work was scheduled and conducted during a later reporting period.

Due to the method used to estimate the instantaneous influent flow rate (timing of rise of groundwater in the GWTS #1 Equalization Tank with both force mains discharging to it), the estimated influent flow rates noted above apply to both systems, combined.

Therefore, during the normal mode of operation, with the flow from each force main flowing to only one system, it is assumed that roughly 50% of the instantaneous influent rates stated above for GWTS #1 actually flows to GWTS #2 for treatment. For GWTS #2, the estimated, instantaneous individual influent flow rate is tabulated (the assumed 50% value.) Therefore, the actual average influent flow rate for GWTS #2 is estimated to be approximately 10.5 gpm. Refer to the attached Table 2B for a summary of the GWTS #2 performance details.

GROUNDWATER TREATMENT PUMPING AND TREATMENT SUMMARY

During the July 2020 reporting period, the two treatment systems, GWTS #1 and GWTS #2, were in operation for all or portions of approximately 31 days. The overall (average) system flow rate and gallons of groundwater treated are based on the available Effluent flow totalizer readings reported for both systems by the O&M contractor. For the period of July 1 to July 31, 2020 both systems treated an approximate combined 0.83 million gallons of groundwater from the downgradient recovery well PRW-4 at an average, total (of the two systems) effluent flow rate of 18.5 gpm. Based on the total 0.83 million gallons treated, approximately 0.006 kilograms of PFAS were estimated to have been removed from the plume area.

4.4 QUARTERLY GROUNDWATER MONITORING

Groundwater monitoring activities related to the documented PFAS Release on Site have been ongoing since November 2013. BETA, formerly Nover-Armstrong Associates, was contracted by Barnstable County to provide LSP and environmental services in April 2018 and has conducted groundwater monitoring activities since June 2018.

In November 2018, BETA proposed a long-term monitoring sampling plan for Site-wide groundwater monitoring on a quarterly and annual basis. Following discussion, MassDEP approved of the sampling plan that included sampling of twelve (12) wells during three quarterly sampling events and sampling an additional eight (8) wells (for a total of twenty (20) during the annual sampling round. A copy of the plan can be found in previous IRA Status report submittals, including IRA Status Report and RMR No. 35 for the October 2019 reporting period. Additional monitoring points can be added to either the quarterly or annual sampling round, as warranted to meet specific objectives or provide additional coverage.

Prior to the current reporting period, BETA conducted quarterly groundwater assessments in February 2020 and May 2020 (the typical January annual monitoring event was delayed until February 2020 by logistical constraints, and the May 2020 event was delayed from the typical April period due to COVID-19 precautions).

July 2020 Site-Wide Quarterly Groundwater Sampling And Analysis

On July 28 and 29, 2020, BETA conducted a quarterly groundwater monitoring event based on the MassDEP approved sampling plan. A total of thirteen (13) monitoring wells were sampled for laboratory analysis of total PFAS by EPA Method 537 Modified.

On those dates, the following monitoring wells were sampled: HSW-6, PFW-1, PFW-5, OW-8a, PC-1, PC-6A, PC-11, PC-16d, PC-28, PC-30, PC-38, MW-12, and MW-22.

Figure 2 and Figure 3 depict sampling locations. Monitoring well PC-38 was added to the standard quarterly sampling round utilizing twelve (12) wells to provide additional coverage for the July 2020 sampling event.

All sampled wells and all wells located within the immediate vicinity of the FTA property were gauged prior to sampling. Groundwater gauging data and groundwater elevation data is included in Table 3.

Monitoring wells HSW-6, PFW-1, PFW-5, and OW-8a are located on the FTA property; HSW-6 is located within the former Hot Spot remediation area and PFW-1 is located approximately 130 feet downgradient (of the former Hot Spot remediation area), PFW-5 and OW-8a are located cross-gradient of the Hot Spot area and more northerly on the FTA property. The additional monitoring well sampled during this event, PC-38, is located south southeast of the FTA property.

The additional wells sampled during this reporting period are located (downgradient of the FTA) on the adjacent property that is owned by the Town of Barnstable and/or by Commonwealth Electric, depending on the exact location of the property line relative to the monitoring wells. These wells were chosen based on historic and relevant groundwater PFAS concentrations identified, and inferred upgradient and downgradient locations within the Disposal Site.

The downgradient monitoring wells (MW-12, MW-22, PC-1, PC-11, PC-38, and PC-6A), between the FTA and the recovery well (PRW-4), were selected, based on previous results, to evaluate current conditions within the main PFAS plume. Monitoring wells PC-16d, PC-28, PC-30, are located in the probable downgradient direction from the recovery well, PRW-4.

A tabulated summary of the PFAS analytical data for the monitoring wells within the Disposal Site Boundary, including the results of the most recent July 2020 sampling round is included as Table 4. Copies of the laboratory reports/certificates of analysis are included in Appendix B.

As previously discussed, effective December 27, 2019, MCP groundwater risk standards for 6 PFAS compounds, (PFOS, PFOA, PFHpA, PFNA, PFHxS, plus Perfluorodecanoic Acid (PFDA)) apply to the Site with a GW-1 risk standard of 20 ng/l for the total and/or any single compound. These new risk standards are included on Table 4. Individual concentrations of one or more of the (regulated) six PFAS compounds and Total Concentrations of the six PFAS documented in the samples from all wells during the July 2020 sampling event were above the MCP GW-1 risk standards.

In summary, PFAS concentrations detected in groundwater across the Disposal Site during the July 2020 round of groundwater assessment are similar to historic ranges (including the most recent May 2020 sampling round). Although the sum of the total PFAS concentrations (six PFAS compounds currently regulated by MassDEP) documented in groundwater within the Disposal Site are significantly above the current applicable MCP Method 1 risk standards, concentrations have trended towards a significant decrease, with exceptions discussed below, since PFAS assessment activities started at the Site in 2015, especially in the Hot Spot area. In the former Hot Spot/Phase 1 cap area, PFAS groundwater concentrations have been observed to be generally falling from historic highs since the completion of the Phase I stormwater improvements in January 2019. The trend of total PFAS concentrations in groundwater at the Disposal Site has been downward overall since PFAS assessment activities started at the Site in 2015. BETA has also observed increases in PFAS concentrations with increased rainfall and higher water tables the winter and spring seasons.

Figures 3A and Figure 3B depict the concentration trends observed in groundwater at monitoring wells HSW-1 and PFW-1, respectively. Since the implementation of the Phase I stormwater improvements during the winter of 2018/2019, which included installing an impermeable cap over the former Hot Spot removal area and adjacent areas and diverting stormwater, PFAS concentrations generally decreased significantly through mid-2019 and have since remained relatively steady at levels still elevated relative to the GW-1 risk standards.

BETA's review of the July 2020 groundwater data compared to historic sampling events indicates concentrations of PFAS documented in wells located on the FTA property and immediately east continue to appear to be falling or relatively stable. Figure 4 depicts the PFAS concentration trend observed in groundwater monitoring well OW-8A, which is located on the northeastern portion of the FTA. Figure 5 depicts the stable trend in PFAS concentrations documented at monitoring wells MW-12 and MW-22 respectively.

However, PFAS concentrations documented in wells located farther southeast and downgradient of the FTA, specifically PC-6A, PC-11, PC-28, PC-16D, and PC-30, have variable trends. During the July 2020 reporting period, concentration trends from PC-6A, PC-11, PC-30, and PC-16D show a steady decrease in concentrations. Groundwater concentration trends from PC-28 and PC-30 appeared to be increasing (compared to historic concentrations), but data since February 2020 appear to indicate a steadier decreasing trend in concentrations. Figures 6A, 6B, and 6C depict PFAS concentration trends in PC-11, PC-6A, and PC-28 and PC-30 respectively.

Monitoring well PC-38 was added to the February 2020, May 2020, and July 2020 monitoring programs. PC-38 is located south-southeast of the FTA in a location that may indicate the southeastern extent of the PFAS plume. Historically documented concentrations of PFAS from PC-38 (specifically PFOS, PFOA, and PFNA, PFHpA, PFNA, PFDA since 2019) have been below the laboratory reporting limits or less than 10 ng/L. In the July 28, 2020 PC-38 sample none of the six regulated PFAS were detected above the laboratory reporting limits, which were well below the 20 ng/l regulatory standard.

SITE-WIDE GROUNDWATER GAUGING AND ELEVATION SURVEY

BETA gauged depth to groundwater in the monitoring wells located on and within 100 feet of the FTA and in selected monitoring wells east and southeast of the FTA on July 27, 2020. The Table 3 presents a tabulated summary of the groundwater elevation data for selected monitoring points across the Disposal Site.

Groundwater flow is inferred to be to the south-southeasterly direction. Refer to Figure 7 for a depiction of the calculated groundwater flow from the July 2020 gauging event. The gauging results indicate moderate influence from the operating recovery well, PRW-4.

Ongoing IRA Activities

Sampling results, system performance, and additional assessment work related to the ongoing response actions, such as system improvement and enhancement details, will be presented in the next IRA Status and RMR Report for the August 2020 reporting period.


Public Involvement Activities

A copy of the municipal notification to the Barnstable Town Manager, with copies to other town officials, is included as Appendix C.


The Site has been designated a Public Involvement Plan Site under the MCP. The Draft Public Involvement Plan (PIP) was presented at a public meeting held at the Barnstable Town Hall on May 2, 2019. Following the end of the comment period, the PIP was finalized and filed with MassDEP on June 30, 2019. In accordance with the final PIP, a copy of this status report will be placed in the public repository. The report will be available on-line via the County website.

Sincerely,

BETA Group, Inc.



Mykel Mendes
Environmental Engineer



Roger Thibault, P.E., LSP
Senior Environmental Engineer

Copy: Jack Yunits, Barnstable County Administrator
Steve Tebo, Assistant County Administrator

Attachments:

TABLES

Table 1A – Summary of Groundwater Pump and Treatment System PFAS Analytical Data – System #1
Table 1B - Summary of Groundwater Pump and Treatment System PFAS Analytical Data – System #2
Table 2A - Summary of Groundwater Pump and Treatment System Operating and Maintenance Data-System #1
Table 2B- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data-System #2
Table 3 – Groundwater Elevation and Gauging Data 2018-2020
Table 4 – Summary of Groundwater PFAS Analytical Data

FIGURES

Figure 1 - Site Plan Detail - FTA Facility
Figure 2 - Site Plan
Figure 3A - ΣFAS Concentrations in HSW-1 from June 2018-October 2019
Figure 3B - ΣFAS Concentrations in PFW-1 from June 2018-October 2019
Figure 4 - ΣFAS Concentrations in OW-8A from June 2018-October 2019

Figure 5 - ΣFAS Concentrations in MW-12 and MW-22 from June 2018-October 2019

Figure 6A - ΣFAS Concentrations in PC-11 from June 2018-October 2019

Figure 6B - ΣFAS Concentrations in PC-6A from June 2018-October 2019

Figure 6C - ΣFAS Concentrations in PC-28 and PC-30 from June 2018-October 2019

Figure 7– Groundwater Flow Map – July 2020

APPENDICES

- A: BWSC 105, 105A, 105B Forms
- B: Laboratory Reports
- C: Municipal Notification Letter to Town Manager

Table 1A - Summary of Groundwater Pump and Treatment System Total PFAs Analytical Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	INFLUENT (PRW-4)						MIDPOINT						EFFLUENT					
USEPA Method 537.2	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)
MassDEP ORS Guideline*	70 ng/L						70 ng/L						70 ng/L					
MCP Method 1 GW-1 Standard ³	20 ng/L						20 ng/L						20 ng/L					
SAMPLE DATE																		
4/1/2015	760	60	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
7/17/2015	5600	460	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
8/4/2015	5900	550	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
9/30/2015	17000	840	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
10/15/2015	9900	560	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<9.4)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A	9.4	BRL (<5.8)	-- ^A	-- ^A	-- ^A	-- ^A
11/12/2015	9000	BRL (<2000)	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	--	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
1/6/2016	7600	260	-- ^A	-- ^A	-- ^A	-- ^A	120	75	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
1/21/2016	5200	160	-- ^A	-- ^A	-- ^A	-- ^A	270	16	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
2/3/2016	3500	140	-- ^A	-- ^A	-- ^A	-- ^A	540	26	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
2/17/2016	4500	140	-- ^A	-- ^A	-- ^A	-- ^A	520	24	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
3/8/2016	3700	140	-- ^A	-- ^A	-- ^A	-- ^A	420	19	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
3/23/2016	5000	150	-- ^A	-- ^A	-- ^A	-- ^A	650	39	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
4/14/2016	4800	140	-- ^A	-- ^A	-- ^A	-- ^A	610	26	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
4/28/2016	6300	BRL (<200)	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<20)	BRL (<20)	-- ^A	-- ^A	-- ^A	-- ^A
5/12/2016	6800	BRL (<200)	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<20)	BRL (<20)	-- ^A	-- ^A	-- ^A	-- ^A
5/25/2016	6900	BRL (<210)	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
6/16/2016	7800	160	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
7/6/2016	7600	270	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	10	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
8/11/2016	13000	160	-- ^A	-- ^A	-- ^A	-- ^A	1600	54	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
Carbon change conducted after sample collection on 08/11/16.																		
8/18/2016	9500	210	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
9/8/2016	9500	190	-- ^A	-- ^A	-- ^A	-- ^A	8.5	5.3	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
10/6/2016	17000	250	-- ^A	-- ^A	-- ^A	-- ^A	110	8.3	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
10/20/2016	7200	130	-- ^A	-- ^A	-- ^A	-- ^A	1000	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
11/3/2016	7900	110	-- ^A	-- ^A	-- ^A	-- ^A	650	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
11/17/2016	5400	99	-- ^A	-- ^A	-- ^A	-- ^A	1200	NA	-- ^A	-- ^A	-- ^A	-- ^A	17	NA	-- ^A	-- ^A	-- ^A	-- ^A
12/1/2016	5300	100	-- ^A	-- ^A	-- ^A	-- ^A	400	14	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
12/14/2016	5700	95	-- ^A	-- ^A	-- ^A	-- ^A	82	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A	8.1	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
1/4/2017	4900	95	-- ^A	-- ^A	-- ^A	-- ^A	360	15	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<3.3)	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
2/16/2017	2800	88	-- ^A	-- ^A	-- ^A	-- ^A	1000	39	-- ^A	-- ^A	-- ^A	-- ^A	25	BRL (<5.3)	-- ^A	-- ^A	-- ^A	-- ^A
3/1/2017	3700	120	-- ^A	-- ^A	-- ^A	-- ^A	1400	47	-- ^A	-- ^A	-- ^A	-- ^A	150	6.5	-- ^A	-- ^A	-- ^A	-- ^A
3/23/2017	3800	87	-- ^A	-- ^A	-- ^A	-- ^A	2000	71	-- ^A	-- ^A	-- ^A	-- ^A	160	9.5	-- ^A	-- ^A	-- ^A	-- ^A
5/3/2017	2400	86	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<2.6)	BRL (<4.6)	-- ^A	-- ^A	-- ^A	-- ^A
Carbon change conducted on 04/13/17.																		
4/19/2017	3200	110	-- ^A	-- ^A	-- ^A	-- ^A	160	BRL (<4.6)	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<2.6)	BRL (<4.6)	-- ^A	-- ^A	-- ^A	-- ^A
5/18/2017	3000	110	-- ^A	-- ^A	-- ^A	-- ^A	570	32	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<2.6)	BRL (<4.6)	-- ^A	-- ^A	-- ^A	-- ^A
6/1/2017	3200	110	-- ^A	-- ^A	-- ^A	-- ^A	730	33	-- ^A	-- ^A	-- ^A	-- ^A	4.1	BRL (<4.6)	-- ^A	-- ^A	-- ^A	-- ^A
6/27/2017	2600	99	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	210	15	-- ^A	-- ^A	-- ^A	-- ^A
7/18/2017	3500	97	-- ^A	-- ^A	-- ^A	-- ^A	2300	72	-- ^A	-- ^A	-- ^A	-- ^A	49	25	-- ^A	-- ^A	-- ^A	-- ^A
Carbon change conducted on 8/09/17																		
8/16/2017	3000	110	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<2.3)	BRL (<4.1)	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<2.3)	BRL (<4.1)	-- ^A	-- ^A	-- ^A	-- ^A
8/28/2017	2900	100	-- ^A	-- ^A	-- ^A	-- ^A	27	BRL (<20)	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A
10/2/2017	3200	85	-- ^A	-- ^A	-- ^A	-- ^A	510	25	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<2.6)	BRL (<4.6)	-- ^A	-- ^A	-- ^A	-- ^A
10/12/2017	4500	110	-- ^A	-- ^A	-- ^A	-- ^A	960	29	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<2.6)	BRL (<4.6)	-- ^A	-- ^A	-- ^A	-- ^A
11/9/2017	2400	77	-- ^A	-- ^A	-- ^A	-- ^A	--	--	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<6.0)	BRL (<3.3)	-- ^A	-- ^A	-- ^A	-- ^A
11/20/2017	2000	64	-- ^A	-- ^A	-- ^A	-- ^A	520	15	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<6.0)	BRL (<3.3)	-- ^A	-- ^A	-- ^A	-- ^A
12/7/2017	1600	64	-- ^A	-- ^A	-- ^A	-- ^A	780	34	-- ^A	-- ^A	-- ^A	-- ^A	11	BRL (<3.3)	-- ^A	-- ^A	-- ^A	-- ^A
2/5/2018	2100	27	-- ^A	-- ^A	-- ^A	-- ^A	390	13	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<6.0)	BRL (<3.3)	-- ^A	-- ^A	-- ^A	-- ^A
2/14/2018	2100	30	-- ^A	-- ^A	-- ^A	-- ^A	850	27	-- ^A	-- ^A	-- ^A	-- ^A	11	BRL (<3.3)	-- ^A	-- ^A	-- ^A	-- ^A
System shutdown on 2/14/18 due to transfer pump failure; system restart on 4/9/18.																		
4/9/2018	2,600	79	-- ^A	-- ^A	-- ^A	-- ^A	990	25	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<20)	BRL (<20)	-- ^A	-- ^A	-- ^A	-- ^A
4/13/2018	3100	62	-- ^A	-- ^A	-- ^A	-- ^A	1500	35	-- ^A	-- ^A	-- ^A	-- ^A	30	BRL (<33)	-- ^A	-- ^A	-- ^A	-- ^A
5/9/2018	1800	73	-- ^A	-- ^A	-- ^A	-- ^A	490	26	-- ^A	-- ^A	-- ^A	-- ^A	BRL (<6.0)	BRL (<33)	-- ^A	-- ^A	-- ^A	-- ^A
System shutdown on 5/9/18 after sampling collection due to carbon breakthrough and influent pump alarm fail.																		
Carbon change conducted on 06/05/18; system restarted on 06/07/18.																		
6/14/2018	2800	120	79	540	110	-- ^A	200	9.4	BRL (<8.7)	38	11	-- ^A	BRL (<6.0)	BRL (<3.3)	BRL (<8.7)	BRL (<5.6)	BRL (<7.4)	-- ^A
7/13/2018	2400	100	73	600	90	-- ^A	1100	44	27	24	35	-- ^A	BRL (<20)	BRL (<20)	BRL (<20)	BRL (<20)	BRL (<20)	-- ^A
8/7/2018	2900	95	73	460	86	-- ^A	630	31	22	130	34	-- ^A	27	5.3	BRL (<8.7)	9.1	BRL (<7.4)	-- ^A
9/2/2018	4300	69	50	360	190	-- ^A	3600	69	49	330	65	-- ^A	81	BRL (<3.3)	BRL (<8.7)	14	BRL (<7.4)	-- ^A
Carbon change conducted on 09/28/18; system restarted on 10/01/18.																		
10/30/2018	2800	65	46	320	71	-- ^A	100	6	1.9	16	78	-- ^A	BRL (<6.0)	BRL (<3.3)	BRL (<8.7)	BRL (<5.6)	BRL (<7.4)	-- ^A
11/16/2018	2900	62	50	290	77	-- ^A	460	24	17	94	26	-- ^A	BRL (<6.0)	BRL (<3.3)	BRL (<8.7)	BRL (<5.6)	BRL (<7.4)	-- ^A
12/14/2018																		

Table 1B - Summary of Groundwater Pump and Treatment System Total PFAs Analytical Data - GWTS #2
 Barnstable County Fire and Rescue Training Academy
 155 Flint Rock Road, Barnstable, MA
 RTN 4-26179

SAMPLE ID	INFLUENT (PRW-4)						MIDPOINT						EFFLUENT					
USEPA Method 537.2	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)
MassDEP ORS Guideline*	70 ng/L						70 ng/L						70 ng/L					
MCP Method 1 GW-1 Standard ¹⁵	20 ng/L						20 ng/L						20 ng/L					
SAMPLE DATE																		
System Startup on 11/11/19.																		
11/12/2019	4200	53	85	200	59	15	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
11/15/2019	--	--	--	--	--	--	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
11/19/2019	--	--	--	--	--	--	BRL (<5.2)	44	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	42	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
12/17/2019 ¹⁵	1500	43	51	180	54	10	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
1/17/2020	2200	57	60	220	69	13	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
2/13/2020	3100	74	66	310	92	17	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
3/3/2020	3300	72	64	300	81	14	5.6	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)	BRL (<0.43)	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)
4/28/2020	1900	52	42	210	56	42	64	2.2	1.7	9.7	3.0	0.27	0.47	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)
5/21/2020	1800	46	40	200	50	11	76	2.8	2.0	10	3.6	0.52	BRL (<0.43)	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)
6/24/2020	1400	41	41	160	49	19	39	2.9	2.3	12	4.3	1.1	0.84	BRL (<0.49)	BRL (<0.80)	BRL (<0.53)	BRL (<0.51)	BRL (<0.64)
7/28/2020	1700	44	43	200	52	12	84	3.8	3.3	17	5.7	0.76	BRL (<0.43)	BRL (<0.49)	BRL (<0.80)	BRL (<0.53)	BRL (<0.51)	BRL (<0.64)

Notes:

- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- MassDEP's Office of Research and Standards (ORS) expanded upon the USEPA's Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- Concentrations of the PFAS compound, PFDA, are presented based on the April 19, 2019, MassDEP draft of new/proposed groundwater standards for PFAS that includes a sixth, PFAS compound, PFDA. However the concentration of PFDA is not included in total PFAS removal calculations.
- BRL - Below Laboratory Reporting Limits; reporting limit shown in parentheses.
- Concentrations in bold exceed applicable MassDEP ORS Guideline
- PFOS - Perfluorooctanesulfonic acid
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- : Concentration data not available and/or sample was not collected on that date.
- Per MCP Regulations, the system was sampled one day, three days, and seven (7) days following the initial week of startup (11/11/19).
- On December 13, 2019, MassDEP published the newly established clean up standards for PFAS in soil and groundwater. These standards were effective as of December 27, 2019 and apply to the total sum of six PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA. Concentrations of the six PFAS compounds presented in the table were not compared to the new MassDEP standards until the January 2020 monthly system sample collection.
- The December monthly sample was collected from the system's effluent stream on 12/17/2019 following the receipt of the laboratory results from the 11/19/2019 sampling event on 12/16/2019. The effluent was resampled again to ensure significant breakthrough was not occurring from the secondary carbon vessel.

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ⁷	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁸	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
4/9/2018	CE	No	75	NA	NA	NA	75	NA	NA	NA	0	--	--	--	--	--		Yes	Yes	Conducted system pressure checks after restart.
4/10/2018	CE	Yes	94	74	NA	NA	77	74	2.07	59.3	1	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/11/2018	CE	Yes	76	NA	NA	NA	76	NA	2.78	44.0	2	--	--	--	--	--	0.001	Yes	No	PRW-4 well pump is operating at high level, high level float is not triggering pump to shut off. CS turned off PRW-4 manually at 1243 and restarted at 14:32. Carbon vessels were backwashed individually from 1313 to 1427.
4/12/2018	CE	Yes	NA	NA	NA	NA	75	75	2.78	44.0	3	--	--	--	--	--	0.002	Yes	No	Transfer pump is drawing down influent/holding tank faster than PRW-4 well is filling tank. No bag filter changes.
4/13/2018	CE	Yes	88	74	NA	NA	75	74	2.80	43.8	4	--	--	--	--	--	0.003	Yes	Yes	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/16/2018	CE	Yes	86	74	NA	NA	74	74	2.83	43.2	7	--	--	--	--	--	0.005	Yes	No	Pressure differential at 8 psi, no bags change. PRW-4 well high level float not triggering pump to shut off. Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/19/2018	CE	Yes	83		NA	NA	75		NA	NA	10	--	--	--	--	--	NA	Yes	No	Transfer pump is maintaining drawdown and flow through system ahead of the PRW-4 well pump, no bag changes.
4/20/2018	CE	Yes	89	75	NA	NA	75	75	3.07	39.9	11	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/23/2018	CE	Yes	92	76	NA	NA	77	76	3.18	38.5	14	--	--	--	--	--	0.009	Yes	No	High level float not triggering PRW-4 to shut down. Sean (B&B Electric) on site to inspect high float electrical issues. PRW-4 shut off at 13:40 to inspect control panel, PRW-4 restarted at 14:55. Transfer pump maintaining flow ahead of PRW-4 well pump. Both carbon vessels backwashed. Changed 3 bag filters (5 um).
4/24/2018	CE	Yes	74	NA	NA	NA	76		3.18	38.5	15	--	--	--	--	--	0.009	Yes	No	No bag change, conducted system pressure checks.
4/25/2018	CE	Yes	79	NA	NA	NA	75		3.30	37.1	16	--	--	--	--	--	0.009	Yes	No	Pressure differential of 4 psi, no bag filter change, transfer pump is maintaining flow ahead of the PRW-4 well pump.
4/26/2018	CE	Yes	83	NA	NA	NA	76		3.37	36.4	17	--	--	--	--	--	0.010	Yes	No	Pressure differential of 7 psi, no bag filter change, transfer pump is maintaining flow ahead of the PRW-4 well pump. While both the system transfer pump and PRW-4 well pump are on and operating, treatment takes 28 seconds to drawn down 1 inch in influent tank (~17.5 gallons)
4/27/2018	CE	Yes	84	73	NA	NA	75	75	3.42	35.8	18	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/30/2018	CE	Yes	87	73	NA	NA	75	75	3.53	34.7	21.00	--	--	--	--	--	0.012	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
Totals - April 2018										41.3	21.00						0.014			
5/1/2018	CS	Yes	83		NA	NA	75		3.83	32.0	0.00	--	--	--	--	--	0.0000	Yes	No	Adjusted /increased VFD of transfer pump from 35 psi to 40 psi to maintain drawdown ahead of PRW-4 well pump . No bag change. 1" drawdown ~ 1:41
5/2/2018	CS	Yes	94	75	NA	NA	80	75	3.63	33.7	1.00	--	--	--	--	--	0.0006	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks. Conducted a backwash on both carbon vessels, PRW-4 well pump would not shut off, float switch relay stuck in on position, PRW-4 shutoff at 0733 and restarted at 08:26 with float switch working properly. Adjusted transfer pump rate back to 35 psi.
5/4/2018	JES	Yes	110	73	NA	NA	73	75	3.65	33.6	3.00	--	--	--	--	--	0.0017	Yes	No	Changed 3 bag filters (10 um) and conducted system pressure checks.
5/7/2018	JES	Yes	110	73	NA	NA	74	74	3.7	33.1	6.00	--	--	--	--	--	0.0034	Yes	No	Changed 3 bag filters (5 um) and conducted system pressure checks.
Totals - May 2018										33.1	8.00						0.004			
6/5/2018	CE/MM	No	--	--	NR	NR	NR	NR	--	--	0	--	--	--	--	--	0	--	--	Carbon Change out- filled vessels with water and let to sit for ~24 hours, changed 3 bag filters (5 um)
6/6/2018	CE	Yes	--	--	NR	NR	NR	NR	3.45	35.5	1	--	--	--	--	--	0.001	No	No	Pump floats not operating correctly, low float turns pump off and when low float is in water again, transfer pump starts. System remained off.
6/7/2018	CE	Yes	62	52	NR	NR	NR	NR	3.18	38.5	2	--	--	--	--	--	0.001	Yes	No	Electrician on site in morning to correct float error; system operating normally.
6/11/2018	CE	Yes	56	61	NR	NR	NR	NR	3.63	33.7	6	--	--	--	--	--	0.003	Yes	No	No bag change, conducted system pressure checks.
6/12/2018	CE	Yes	56	63	NR	NR	NR	NR	3.68	33.3	7	--	--	--	--	--	0.004	Yes	No	No bag change, conducted system pressure checks.
6/13/2018	CE	Yes	58	54	NR	NR	NR	NR	3.46	35.4	8	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters.
6/13/2018	MM	Yes	--	--	NR	NR	NR	NR	--	--	8	--	--	--	--	--	--	--	Yes	Did not collect system data, only collected samples from Influent, Midpoint, and Effluent sample ports/locations.
6/16/2018	CE	Yes	77	60	NR	NR	NR	NR	--	--	11	--	--	--	--	--	--	--	No	Changed 3 bag filters.
6/19/2018	CE	Yes	92	65	NR	NR	NR	NR	--	--	14	--	--	--	--	--	--	No	No	Changed 3 bag filters and repaired holding basket for bags. Recovery well was not running, went out to the well and checked power, turned power to well on/off and did not hear contact relay pull in. System remained off until electrical issue in recovery well is fixed. Fixed at 15:45
6/20/2018	CE	Yes	72	60	NR	NR	NR	NR	3.73	32.8	15	--	--	--	--	--	0.008	Yes	No	No bag change, conducted system pressure checks.
6/21/2018	CE	Yes	79	60	NR	NR	NR	NR	--	--	16	--	--	--	--	--	--			No bag change, conducted system pressure checks. Worked by phone with Bob Simmonds on Control panel for transfer pump, pump will not change speed.
6/22/2018	CE	Yes	87	67	NR	NR	NR	NR	3.72	32.9	17	--	--	--	--	--	0.009	Yes	No	Changed 3 bag filters, conducted system pressure checks.
6/25/2018	CE	Yes	81	68	NR	NR	NR	NR	3.77	32.5	20	--	--	--	--	--	0.011	Yes	No	Changed 3 bag filters, conducted system pressure checks.
6/27/2018	CE	Yes	79	68	NR	NR	NR	NR	3.73	32.8	22	--	--	--	--	--	0.012	Yes	No	Changed 3 bag filters, conducted system pressure checks.
6/29/2018	CE	Yes	78	68	NR	NR	NR	NR	3.68	33.3	24	--	--	--	--	--	0.014	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - June 2018										33.9	24						0.013			
7/2/2018	CE	Yes	83	69	NR	NR	NR	NR	3.95	31.0	2	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/5/2018	CE	No	--	--	NR	NR	NR	NR	--	--	5	--	--	--	--	--	--	No	No	No power supplied to the recovery well.
7/6/2018	CE	Yes	86	69	NR	NR	NR	NR	3.87	31.7	5	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/9/2018	CE	Yes	89	72	NR	NR	NR	NR	3.77	32.5	8	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/11/2018	CE	Yes	88	72	NR	NR	NR	NR	3.85	31.8	10	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/13/2018	CE	Yes	89	72	NR	NR	NR	NR	4.08	30.0	12	--	--	--	--	--	0.006	Yes	Yes	Changed 3 bag filters, conducted system pressure checks.
7/16/2018	CE	Yes	98	70	NR	NR	NR	NR	3.97	30.9	15	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/18/2018	CE	No	--	--	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	No	No	No power supplied to the recovery well. Contact relay at recovery well pump out.
7/19/2018	CE	Yes	94	72	NR	NR	NR	NR	4.03	30.4	17	--	--	--	--	--	0.008	Yes	No	Electrician replaced the contact relay; recovery well operating again. Changed 3 bag filters and collected system pressure checks.
7/20/2018	CE	Yes	81	72	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	Yes	No	Changed 3 bag filters, conducted system pressure checks. Backwashed carbon vessels.
7/23/2018	CE	Yes	84	72	NR	NR	NR	NR	4.47	27.4	21	--	--	--	--	--	0.009	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/25/2018	CE	Yes	84	72	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	Yes	No	Collected system pressure checks.
7/26/2018	CE	Yes	80	72	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	Yes	No	Collected system pressure checks.
7/27/2018	CE	Yes	88	72	NR	NR	NR	NR	4.8	25.5	25	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/30/2018	CE	Yes	91	71	NR	NR	NR	NR	4.95	24.7	28	--	--	--	--	--	0.011	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - July 2018										29.6	28						0.015			
8/2/2018	CE	Yes	89	70	NR	NR	NR	NR	5.17	23.7	2	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/6/2018	CE	Yes	94	72	NR	NR	NR	NR	5.22	23.5	6	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/10/2018	CE	Yes	98	72	NR	NR	NR	NR	4.32	28.4	10	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks. System was sampled on August 7, 2018.
8/14/2018	CE	Yes	82	69	NR	NR	NR	NR	4.8	25.5	14	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/17/2018	CE	Yes	81	64	NR	NR	NR	NR	5.0	24.5	17	--	--	--	--	--	0.008	Yes	No	Changed 3 bag filters, conducted system pressure checks. Backwashed carbon vessels.
8/21/2018	CE	No	78	68	NR	NR	NR	NR	5.2	23.6	20	--	--	--	--	--	0.009	Yes	No	Recovery well down, due to contactor burnout/failure. System restarted at 14:45.
8/24/2018	CE	Yes	77	68	NR	NR	NR	NR	5.32	23.0	23	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/28/2018	CE	Yes	89	69	NR	NR	NR	NR	6.03	20.3	27	--	--	--	--	--	0.011	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Table										24.1	30						0.014			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ⁷	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁸	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
9/4/2018	CE	Yes	89	67	NR	NR	NR	NR	5.87	20.9	4	--	--	--	--	--	0.002	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/7/2018	CE	Yes	82	70	NR	NR	NR	NR	6.52	18.8	7	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/11/2018	CE	Yes	88	70	NR	NR	NR	NR	7.03	17.4	11	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/14/2018	CE	Yes	86	70	NR	NR	NR	NR	7.18	17.1	14	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/18/2018	CE	Yes	91	74	NR	NR	NR	NR	8.02	15.3	18	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/21/2018	CE	No	74	70	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	No	No	Recovery well down.
9/24/2018	CE	Yes	94	70	NR	NR	NR	NR	8.03	15.3	23	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/28/2018	CE	Yes	--	--	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	--	--	Carbon Change out- filled vessels with water and let to sit for ~24 hours, changed 3 bag filters (5 um), system sampled on 09/27/18.
Totals - September 2018										17.4	28						0.010			
10/1/2018	CE	No	78	57	NR	NR	NR	NR	5.83	21.0	1	--	--	--	--	--	0.000	Yes	No	System restarted after scheduled shutdown for carbon exchange. Changed 3 bag filters, conducted system pressure checks.
10/5/2018	CE	Yes	65	55	NR	NR	NR	NR	6.35	19.3	5	--	--	--	--	--	0.002	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/10/2018	CE	Yes	56	57	NR	NR	NR	NR	6.95	17.6	10	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/12/2018	CE	Yes	60	55	NR	NR	NR	NR	--	--	12	--	--	--	--	--	--	Yes	No	No bag change necessary.
10/15/2018	CE	Yes	70	60	NR	NR	NR	NR	6.9	17.8	15	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks. Repaired filter basket.
10/19/2018	CE	Yes	71	60	NR	NR	NR	NR	7.12	17.2	19	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/23/2018	CE	Yes	76	63	NR	NR	NR	NR	7.73	15.8	23	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks. Repaired holding basket in filter vessel.
10/26/2018	CE	Yes	72	64	NR	NR	NR	NR	8.83	13.9	26	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/30/2018	CE	Yes	80	65	NR	NR	NR	NR	7.52	16.3	30	--	--	--	--	--	0.009	Yes	Yes	Changed 3 bag filters, conducted system pressure checks. Repaired bag holder (basket) in filter vessel.
Totals - October 2018										17.4	31						0.011			
11/2/2018	CE	Yes	71	62	NR	NR	NR	NR	7.86	15.6	2	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/6/2018	CE	Yes	71	62	NR	NR	NR	NR	--	--	6	--	--	--	--	--		No	No	Changed 3 bag filters, conducted system pressure checks. Backwashed both carbon vessels. System shutdown at 10:00 for force main descaling and flush.
11/8/2018	CE	Yes	65	45	NR	NR	NR	NR	5.25	23.3	6	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks. System restarted at 12:40 following the completion of the force main descaling.
11/9/2018	CE	Yes	55	44	NR	NR	NR	NR	5.2	23.6	7	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/12/2018	CE	Yes	51	47	NR	NR	NR	NR	5.03	24.4	10	--	--	--	--	--	0.007	Yes	No	Conducted system pressure checks.
11/13/2018	CE	Yes	52	47	NR	NR	NR	NR	4.88	25.1	11	--	--	--	--	--	0.007	Yes	No	Conducted system pressure checks.
11/14/2018	CE	Yes	54	47	NR	NR	NR	NR	4.92	24.9	12	--	--	--	--	--	0.008	Yes	No	Conducted system pressure checks.
11/15/2018	CE	Yes	55	47	NR	NR	NR	NR	--	--	13	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
11/16/2018	CE	Yes	54	50	NR	NR	NR	NR	4.63	26.5	14	--	--	--	--	--	0.010	Yes	Yes	Changed 3 bag filters, conducted system pressure checks.
11/21/2018	CE	Yes	63	53	NR	NR	NR	NR	5.08	24.1	19	--	--	--	--	--	0.012	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/27/2018	CE	Yes	69	55	NR	NR	NR	NR	5.75	21.3	25	--	--	--	--	--	0.014	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/30/2018	CE	Yes	77	58	NR	NR	NR	NR	5.85	20.9	28	--	--	--	--	--	0.016	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - November 2018										23.0	28						0.012			
12/3/2018	CE	Yes	63	62	NR	NR	NR	NR	5.33	23.0	3	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/7/2018	CE	Yes	83	67	NR	NR	NR	NR	5.58	22.0	7	--	--	--	--	--	0.002	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/11/2018	CE	Yes	75	65	NR	NR	NR	NR	5.8	21.1	11	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/14/2018	CE	Yes	70	63	NR	NR	NR	NR	5.4	22.7	14	--	--	--	--	--	0.004	Yes	Yes	Changed 3 bag filters, conducted system pressure checks.
12/18/2018	CE	Yes	70	65	NR	NR	NR	NR	6.72	18.2	18	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/21/2018	CE	Yes	70	67	NR	NR	NR	NR	6.7	18.3	21	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/26/2018	CE	Yes	78	71	NR	NR	NR	NR	7.38	16.6	26	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/28/2018	CE	Yes	82	70	NR	NR	NR	NR	7.35	16.7	28	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/31/2018	CE	Yes	82	71	NR	NR	NR	NR	7.38	16.6	31	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - December 2018										19.5	31						0.008			
1/4/2019	RPT	Yes	72	72	NR	NR	NR	NR	6.5	18.8	4	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks, observed hole in pre-filter basket.
1/7/2019	PCB	Yes	80	71	NR	NR	NR	NR	6.2	19.8	7	--	--	--	--	--	0.002	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/10/2018	RPT	Yes	75	70	NR	NR	NR	NR	7.03	17.4	10	--	--	--	--	--	0.003	Yes	No	Conducted system pressure checks.
1/11/2018	MDM	Yes	79	71	NR	NR	NR	NR	7.62	16.1	11	--	--	--	--	--	0.003	Yes	Yes	Change 3 bag filters, conducted system pressure checks.
1/14/2019	PCB	Yes	76	71	NR	NR	NR	NR	--	--	14	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
1/15/2019	PCB	Yes	80	71	NR	NR	NR	NR	--	--	15	--	--	--	--	--	--	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/18/2019	PCB	Yes	76	71	NR	NR	NR	NR	8.65	14.2	18	--	--	--	--	--	0.004	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/21/2019	SCT	Yes	80	71	NR	NR	NR	NR	8.15	15.0	21	--	--	--	--	--	0.005	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/24/2019	SCT	Yes	85	69	NR	NR	NR	NR	9.1	13.5	24	--	--	--	--	--	0.005	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/27/2019	SCT	Yes	85	68	NR	NR	NR	NR	8.25	14.8	27	--	--	--	--	--	0.007	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/30/2019	PCB	Yes	86	71	NR	NR	NR	NR	9	13.6	30	--	--	--	--	--	0.007	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/31/2019	PCB	Yes	83	71	NR	NR	NR	NR	--	--	31	--	--	--	--	--	--	Yes	No	Change 3 bag filters, conducted system pressure checks.
Totals - January 2019										14.5	31						0.008			
2/4/2019	RPT	Yes	--	--	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	--	No	Carbon Change out- filled vessels with water and let to sit for ~24 hours, changed 3 bag filters (5 um).
2/5/2019	RPT	No	52	35	NR	NR	NR	NR	7.33	16.7	4	--	222.7	--	--	--	0.002	Yes	No	System restarted after scheduled shutdown for carbon exchange. Changed bag filters and conducted system pressure checks.
2/11/2019	PCB	Yes	83	45	NR	NR	NR	NR	11.58	10.6	10	--	--	--	--	--	--	Yes	No	Changed 3 bag filters, conducted system pressure checks.
2/13/2019	ST	Yes	55	43	NR	NR	NR	NR	8.12	15.1	12	--	--	--	--	--	--	Yes	No	Changed 3 bag filters, conducted system checks.
2/15/2019	MDM	Yes	--	--	NR	NR	NR	NR	7.5	16.3	14	--	131.7	--	--	--	0.007	Yes	Yes	Sampled system and collected system pressure checks.
2/22/2019	ST	Yes	--	--	NR	NR	NR	NR	10.75	11.4	21	--	43.75	--	--	--	0.007	Yes	No	Changed 3 bag filters, repaired filter basket, adjusted and lowered the speed drive on the transfer/discharge pump.
2/25/2019	MDM	Yes	25	15	NR	NR	NR	NR	7.5	16.3	23	--	--	--	--	--	--	Yes	No	System shutdown at 09:33 for the replacement of the submersible pump at PRW-4 and restarted at 14:04.
Totals - February 2019										14.4	26		132.7				0.011	Yes	No	
3/1/2019	ST	Yes	43	40	NR	NR	NR	NR	7.55	16.2	1	--	76.6	--	--	--	0.001	Yes	No	Conducted system pressure checks.
3/3/2019	ST	Yes	45	40	NR	NR	NR	NR	--	--	3	--	--	--	--	--	--	Yes	No	Conducted system pressure checks, changed bag filters, installed/replaced filters baskets with new stainless steel filter baskets.
3/5/2019	PCB	Yes	46	40	NR	NR	NR	NR	--	--	5	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
3/7/2019	PCB/ST	Yes	50	40	NR	NR	NR	NR	8.16	15.0	7	--	--	--	--	--	0.004	Yes	No	Conducted system pressure checks and changed bag filters.
3/9/2019	ST	Yes	44	41	NR	NR	NR	NR	7.75	15.8	9	--	--	--	--	--	0.005	Yes	No	Changed bag filters.
3/11/2019	ST	Yes	58	50	NR	NR	NR	NR	7.92	15.5	11	--	68.1	--	--	--	0.006	Yes	Yes	Changed bag filters.
3/13/2019	ST	Yes	65	50	NR	NR	NR	NR	4.62	26.5	13	--	--	--	--	--	--	Yes	No	Noticed low speed on transfer pump, adjusted VFD to increase pump speed to 55 Hz. Changed 3 bag filters twice.
3/14/2019	ST	Yes	75	50	NR	NR	NR	NR	5.16	23.7	14	--	70.0	--	--	--	0.012	Yes	No	Conducted system pressure checks and collected samples from EQ tank for analysis at County lab for disposal criteria.
3/16/2019	PCB	No	62	60	NR	NR	NR	NR	--	--	15	--	--	--	--	--	--	Yes	No	Pump at PRW-4 shut off upon arrival to system, contact relay failure, possibly due to power surge from thunderstorm. Restarted system after contact relay was replaced.
3/22/2019	ST	Yes	28	20	NR	NR	NR	NR	2.38	51.5	21	--	51.5	--	--	--	0.038	Yes	No	Replaced VFD drive for effluent transfer pump inside system shed.
3/23/2019	ST	Yes	23	20	NR	NR	NR	NR	--	--	22	--	--	--	--	--	--	No	No	Changed bag filters before system shutdown. System shutdown due to slow flow rate from transfer pump as a result of accumulating iron sediments in EQ tank from slow influent flow rate as a result of a the failing PRW-4 well pump.
3/29/2019	RPT/ST	No	--	--	NR	NR	NR	NR	--	--	23	--	--	--	--	--	--	Yes	No	Removed/pumped out the contents of the influent equalization (EQ) tank, repaired the system's pump electrical components, adjusted VFD on transfer pump, installed unions on influent piping manifold, replaced bag filters at discharge into the EQ tank, and restarted the system at 1645.

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ⁷	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁸	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
4/1/2019	ST	Yes	--	--	40	28	40	39	2.25	54.4	1	--	--	--	--	--	0.002	Yes	No	Conducted system pressure checks and changed bag filters.
4/3/2019	ST	Yes	--	--	40	39	--	--	--	--	3	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
4/6/2019	ST	Yes	--	--	50	41	50	50	2.23	54.9	6	--	--	--	--	--	0.014	Yes	No	Conducted system pressure checks and changed bag filters.
4/9/2019	GWTT	Yes	--	--	40	50	--	--	1.6	76.6	9	--	18.85	--	--	--	0.029	Yes	Yes	Conducted system pressure checks, backwashed the primary carbon vessel for ~30 minutes; inspected the transfer pump and removed excess iron oxide sedimentation from the inlet piping.
4/10/2019	ST	Yes	--	--	50	15	23	25	--	--	10	--	--	--	--	--	--	Yes	No	Conducted system pressure checks and changed bag filters.
4/11/2019	ST	Yes	--	--	40	35	35	35	--	--	11	--	--	--	--	--	--	Yes	No	Conducted system pressure checks and changed bag filters.
4/12/2019	GWTT	Yes	--	--	50	40	44	46	3	40.8	12	--	--	--	--	--	0.020	Yes	No	Conducted system pressure checks and changed bag filters.
4/15/2019	GWTT	Yes	--	--	55	45	55	55	4.08	30.0	15	--	--	--	--	--	0.019	Yes	No	Conducted system pressure checks and changed bag filters.
4/19/2019	GWTT	Yes	--	--	58	55	35	40	2.5	49.0	19	--	--	--	--	--	0.039	Yes	No	Conducted system pressure checks and changed bag filters.
4/23/2019	GWTT	Yes	--	--	48	47	50	55	4.00	30.6	23	--	33.4	--	--	--	0.029	Yes	No	Conducted system pressure checks and changed bag filters.
4/26/2019	GWTT	Yes	--	--	58	50	55	60	--	--	26	--	20.3	--	--	--	--	Yes	No	Conducted system pressure checks and changed bag filters, conducted general housekeeping duties.
4/30/2019	GWTT	No	--	--	--	--	--	--	--	--	29	--	--	--	--	--	--	--	Yes	System off on arrival due to contact relay failure for transfer pump operation; system restarted at 16:29 after contact relay was replaced.
Totals - April 2019										48.1	29	24.2					0.058			
5/3/2019	GWTT	Yes	--	--	55	35	45	50	2.18	56.2	3	--	32.93	--	--	--	0.003	Yes	No	Conducted system pressure checks and changed bag filters.
5/7/2019	GWTT	Yes	--	--	58	38	50	55	2.05	59.8	7	--	31.57	--	--	--	0.007	Yes	No	Conducted system pressure checks and changed bag filters.
5/10/2019	GWTT	No	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	System down as a result of failed VFD for transfer pump operation, changed bag filters.
5/17/2019	GWTT	No	--	--	55	38	--	--	--	--	10	--	--	--	--	--	--	Yes	No	Installed new VFD drive, system shutdown due to power surge from thunderstorm. Electrician added 15 minute- electrical control delay at the control panel in the system shed: creating a 15 minute delay before the pump at PRW-4 powers on at the "high level" float switch.
5/21/2019	MDM	No	--	--	57	30	57	60	1.83	66.9	14	--	33.38	--	--	--	0.016	Yes	Yes	Power surge from rogue ground voltage at electrical easement "fried" the electrical delay at control panel in system shed. Electrician bypassed delay to allow system restart at 11:15. Electrician will change coil at PRW-4 panel to lower voltage at later date. Conducted system pressure checks and changed bag filters.
5/24/2019	GWTT	Yes	--	--	58	35	58	60	2.083	58.8	17	--	25.36	--	--	--	0.017	Yes	No	Conducted system pressure checks and changed bag filters. Bypass installed to allow 15 minute delay on PRW-4 submersible pump float switch.
5/28/2019	GWTT	Yes	--	--	56	46	55	60	2.65	46.2	21	--	52.10	--	--	--	0.016	Yes	No	Conducted system pressure checks and changed bag filters twice. Backwashed both carbon vessels.
5/31/2019	GWTT	Yes	--	--	58	35	55	60	2.17	56.5	24	--	36.90	--	--	--	0.022	Yes	No	Conducted system pressure checks and changed bag filters, 3" butterfly valve on INF of LGACS #2 replaced. Installed a 3 inch flow totalizer and meter on
Totals - May 2019										57.4	24	35.4					0.023			
6/4/2019	GWTT	Yes	--	--	57	48	57	62	2.46	49.8	4	--	20.2	--	--	--	0.010	Yes	No	Conducted system pressure checks and changed bag filter. Replaced in-kind flow meter previously installed on 5/31/19.
6/7/2019	GWTT	Yes	--	--	57	45	57	62	2.43	50.4	7	--	16.2	--	--	--	0.017	Yes	No	Conducted system pressure checks and changed bag filters.
6/11/2019	GWTT	Yes	--	--	76	78	70	82	2.53	48.4	11	--	17.3	--	--	--	0.026	Yes	No	Conducted system pressure checks and changed bag filters. System shutdown due to high pressure measurement on the LGAC vessels, (from iron fouling), carbon change to occur on 6/13/19.
6/13/2019	MDM	No	--	--	--	--	--	--	--	--	11	--	--	--	--	--	--	No	No	System off for carbon change out.
6/14/2019	GWTT	No	--	--	--	--	25	28	2.3	53.3	12	--	167.1	--	--	--	0.032	Yes	No	System restarted at 13:00; adjusted flow rate via VFD to 55 Hz. GWTT recorded Effluent flow rate from drop in site glass to be 44 seconds, immediately after adjusting the VFD.
6/18/2019	GWTT	Yes	--	--	25	10	11	15	2.23	54.9	16	--	56.2	--	--	--	0.043	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 55 GPM.
6/21/2019	GWTT	Yes	--	--	17	15	17	20	2.12	57.8	19	--	58.6	--	--	--	0.054	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 28 Hz.
6/25/2019	GWTT	Yes	--	--	20	18	20	25	2.3	53.3	23	--	59.0	--	--	--	0.060	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 28 to 35 Hz.
6/27/2019	MDM	Yes	--	--	33	21	--	--	3.2	38.3	25	--	17.5	--	--	--	0.047	Yes	Yes	Conducted system checks, system VFD at 35 Hz; pressure gauges at LGAC 2 are 0 psi.
6/28/2019	GWTT	Yes	--	--	33	22	30	35	2.4	51.0	26	--	60.9	--	--	--	0.065	Yes	No	Conducted system checks, changed bag filters, VFD at 35 Hz. Effluent flow rate increased after bag filter changeout.
Totals - June 2019										50.8	27	62.4					0.068			
7/2/2019	GWTT	Yes	--	--	32	20	30	32	2.52	48.6	2	NR	52.6	20575	--	--	0.005	Yes	No	Conducted system checks, changed bag filters.
7/5/2019	GWTT	Yes	--	--	25	23	30	35	2.53	48.4	5	NR	52.6	242970	222395	--	0.013	Yes	No	Conducted system checks, changed bag filters, VFD at 35 Hz. Effluent flow rate increased after bag filter changeout.
7/9/2019	GWTT	Yes	--	--	32	25	36	40	2.35	52.1	9	NR	58.6	311680	68710	--	0.026	Yes	No	Conducted system checks, changed bag filters, VFD at 35 Hz. Effluent flow rate increased after bag filter changeout. Primary LGAC vessel requires a
7/12/2019	GWTT	Yes	--	--	39	35	39	43	2.42	50.6	12	NR	55.7	407920	96240	--	0.033	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 42 Hz.
7/15/2019	GWTT	Yes	--	--	46	40	35	50	3.00	40.8	15	NR	55.7	587740	179820	--	0.034	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 42 Hz to 40 Hz.
7/18/2019	GWTT	Yes	--	--	45	28	55	60	2.83	43.3	18	NR	47.48	NR	NR	--	0.043	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 40 Hz to 45 Hz.
7/23/2019	GWTT	Yes	--	--	56	43	55	61	3.22	38.0	23	NR	25.63	717580	129840	--	0.048	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 40 Hz to 45 Hz.
7/26/2019	GWTT	Yes	--	--	56	50	56	60	--	--	26	NR	11.93	722700	5120	--	--	Yes	No	Conducted system checks, changed bag filters.
7/29/2019	GWTT	Yes	--	--	--	--	56	60	2.50	49.0	29	NR	53.3	723360	660	--	0.078	Yes	Yes	Pumped out contents of exterior totes and conducted backwash of system (6,800 gallons removed by Global). Shutdown system for ~2 hours. VFD at 23 Hz on departure.
Totals - July 2019										46.9	31	45.1					0.079			
8/2/2019	GWTT	Yes	--	--	15	5	18	9	2.68	50.6	2	NR	19.68	723960	0	0.0	0.006	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 23 Hz to 28 Hz.
8/5/2019	GWTT	Yes	--	--	21	8	16	20	2.50	52.8	5	NR	49.00	726280	2320	0.5	0.014	Yes	No	Conducted system checks, changed bag filters, VFD at 28 Hz.
8/8/2019	GWTT	Yes	--	--	20	19	22	27	2.23	54.9	8	NR	53.50	729450	3170	0.7	0.024	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 32 Hz and 31 Hz. Visibility of site glass impaired due to iron fouling, possible obstruction in site glass causing error in flow calculations.
8/13/2019	GWTT	Yes	--	--	27	23	28	30	2.17	56.5	13	NR	56.45	738390	8940	1.2	0.040	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 23 Hz. Obstruction in site glass seems apparent, affecting flow rate calculations.
8/16/2019	GWTT	Yes	--	--	32	26	30	35	1.04	117.8	16	NR	34.83	744020	5630	1.3	0.103			Conducted system checks, changed bag filters, adjusted VFD from 23 Hz to 28 Hz.
8/20/2019	GWTT	Yes	--	--	40	27	36	38	NR	NR	20	NR	NR	757990	13970	2.4	--	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 38 Hz to 39 Hz. Could not calculate influent flow rate due to obstruction in site glass
8/23/2019	GWTT	Yes	--	--	41	29	38	44	--	--	23	NR	50.00	790720	32730	7.6	0.063	Yes	Yes	Conducted system checks, changed bag filters, and adjusted VFD from 39 Hz to 40 Hz. Collected montly system samples on 8/22/19.
8/27/2019	GWTT	Yes	--	--	45	35	44	49	--	--	27	NR	50.00	873750	83030	14.4	0.074	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 40 Hz to 42 Hz.
8/30/2019	GWTT	Yes	--	--	49	37	8	10	--	--	30	NR	49.00	976540	102790	23.8	0.081	Yes	No	Conducted system checks, changed bag filters after backwash of primary vessel.
Totals - August 2019										66.5	31	NR ¹¹					0.113			
9/3/2019	GWTT	Yes	--	--	18	7	10	14	NA	NA	3	--	NR	1044190	67650	15.7	0.001	Yes	No	Conducted system checks, changed bag filters, "High High Level" Alarm indicated, adjusted VFD, site glass plugged due to iron oxide sludge build up at bottom of EQ tank, could not collect influent flow rate.
9/6/2019	GWTT	Yes	--	--	27	14	22	25	NA	NA	6	--	NR	NR	NR	NR	--	Yes	No	Conducted system checks, changed bag filters, "High High Level" Alarm indicated, adjusted VFD to 35 Hz from 31 Hz.
9/10/2019	GWTT	Yes	--	--	35	18	30	35	NA	NA	10	--	NR	1203690	159500	27.7	0.008	Yes	No	
9/13/2019	GWTT	Yes	--	--	40	25	40	42	NA	NA	13	--	NR	1311290	107600	24.9	0.009	Yes	No	Conducted system checks, changed bag filters, observed approximately 20 in. of sludge in EQ Tank, and adjusted VFD to 40 Hz from 38 Hz.
9/16/2019	GWTT	Yes	--	--	45	26	44	48	NA	NA	16	--	NR	1413970	102680	23.8	0.011	Yes	No	Conducted system checks, changed bag filters, and adjusted VFD to 48 Hz.
9/20/2019	GWTT	Yes	--	--	68	35	12	14	NA	NA	20	--	NR	1543040	129070	22.4	0.013	Yes	No	Conducted system checks, changed bag filters, backwashed primary GAC vessel, and adjusted VFD to 29 Hz.
9/23/2019	GWTT	Yes	--	--	24	8	23	27	NA	NA	23	--	NR	1563850	20810	4.8	0.003	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 29 Hz to 34 Hz.
9/27/2019	GWTT	Yes	--	--	32	17	42	44	NA	NA	27	--	NR	1577890	14040	2.4	0.002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 34 Hz to 42 Hz, system samples collected on 9/26/19.
Totals - September 2019 ¹²										NA ⁷	30	NR ¹¹					0.015			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ²	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ³	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
10/1/2019	GWTT	Yes	--	--	50	28	18	19	NA	NA	1	--	NR	1620400	--	--	--	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 42 Hz to 31 Hz. Operator noticed a loud sound on discharge pipes at LGAC #1 as well as a pressure drop across the entire system, system was instantly turned off and restarted after the VFD was adjusted. Operator assumed an obstruction (i.e. iron oxide precipitates) was in LGAC#1 restricting flow and loud sound was the obstruction being dislodged.
10/3/2019	GWTT	Yes	--	--	--	--	--	--	NA	NA	3	--	NR	1639940	19540	6.8	0.0005	Yes	No	System was shut off at 8:00 during excavation of the effluent discharge piping. The discharge piping was repaired and the system was restarted at 16:00. The bag filters were changed.
10/7/2019	GWTT	Yes	--	--	27	14	22	20	NA	NA	6	--	NR	1645550	5610	1.3	0.0002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 31 Hz to 35 Hz.
10/11/2019	GWTT	Yes	--	--	32	30	19	20	NA	NA	10	--	NR	1683870	38320	6.7	0.0015	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 35 Hz to 32 Hz.
10/15/2019	GWTT	Yes	--	--	29	20	27	30	NA	NA	14	--	NR	1755270	71400	12.4	0.0040	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 32 Hz to 39 Hz.
10/18/2019	GWTT	Yes	--	--	38	22	30	35	NA	NA	18	--	NR	1867270	112000	19.4	0.0082	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 39 Hz to 35 Hz.
10/22/2019	GWTT	Yes	--	--	34	13	31	35	NA	NA	21	--	NR	1946590	79320	18.4	0.0090	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 35 Hz to 43 Hz.
10/25/2019	GWTT	Yes	--	--	44	34	35	42	NA	NA	24	--	NR	2043780	97190	22.5	0.0126	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 43 Hz to 40 Hz.
10/28/2019	GWTT	Yes	--	--	44	34	35	42	5.38	22.8	27	--	NR	2123880	80100	18.5	0.0117	Yes	No	Conducted system checks, changed bag filters, Global Cycle on site to vacuum pump out the contents from the EQ tank, bag filter unit, totes containing water from GAC vessel backwashes. The VFD was adjusted from 40 Hz to 24 Hz. Pressure gauge at P5 was replaced. System sampled on 10/30/19.
Totals - October 2019 ¹²										NA ⁷	30	NR ¹¹			503480	11.7	0.008			
11/1/2019	GWTT	Yes	--	--	15	2	19	19	5.00	24.5	1	NR	53.26	2128040	4160	2.9	--	Yes	No	Conducted system checks, changed bag filters, and adjusted the VFD frequency.
11/4/2019	GWTT	Yes	--	--	26	8	21	17	4.28	28.60	4	NR	45.37	2131870	3830	0.9	--	Yes	No	Conducted system checks, changed bag filters, and the VFD was adjusted from 30 Hz to 29 Hz.
11/7/2019	GWTT	Yes	--	--	25	10	30	27	3.70	33.1	7	NR	44.0	2042122	--	--	--	Yes	No	Conducted system checks, changed bag filters, exchanged 3" flow meter to 2" pulse turbine flow meter/totalizer. Adjusted the VFD from 29 Hz to 34 Hz on departure.
11/11/2019	GWTT	Yes	--	--	32	18	31	35	3.70	33.1	11	35	NR	2119390	77268	13.4	0.0037	Yes	Yes	Conducted system checks, changed bag filters, VFD left at 34 Hz. Force main Influent flow was split; temporary GWTPS expansion system started. System sampled on 11/12/19.
11/15/2019	GWTT	Yes	--	--	32	21	32	36	4.47	27.4	14	43	NR	2190828	71438	16.5	0.0058	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 34 Hz to 38 Hz on departure.
11/18/2019	GWTT	Yes	--	--	40	30	42	46	4.43	27.6	17	37	NR	2273202	82374	19.1	0.0081	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 38 Hz to 39 Hz upon departure.
11/22/2019	GWTT	Yes	--	--	42	27	41	45	3.50	35.0	21	33	NR	2391315	118113	20.5	0.0108	Yes	No	Conducted system checks, changed bag filters. VFD kept at 39 Hz. Cleared sludged out of bottom of sight glass on EQ tank.
11/25/2019	GWTT	Yes	--	--	43	32	43	46	3.90	31.4	24	42	NR	2486658	95343	22.1	0.0133	Yes	No	Conducted system checks, changed bag filters. VFD kept at 39 Hz.
11/29/2019	GWTT	Yes	--	--	45	32	44	48	4.10	29.9	28	39	NR	2601976	115318	20.0	0.0141	Yes	No	Conducted system checks, changed bag filters.
Totals - November 2019 ¹²										30.1	29	NR ¹¹			559854	21.6	0.016			
12/2/2019	BETA	Yes	--	--	--	--	--	--	--	--	2	--	--	2685088	83112	28.9	0.001	No	No	System shutdown at 10:00 for force main de-scale process.
12/4/2019	BETA	No	--	--	--	--	52	60	4.55	26.9	2	--	NR	2685088	0	0.0	0.000	Yes	No	Bag filters changed prior to system restart. System (PRW-4 and system) restarted at 12:12 following the force main de-scale and purging process. Collected post-bag filter checks after system restart.
12/6/2019	GWTT	Yes	--	--	55	25	52	58	2.17	62.0	4	50	NR	2735900	50812	17.6	0.001	Yes	No	Conducted system checks, flow into system #2 shutoff PRW-4 due to high level alarm. Changed the bag filters, and adjusted the VFD from 44 Hz to 46 Hz.
12/9/2019	GWTT	Yes	--	--	59	22	58	63	2.12	62.0	7	50	NR	2854135.0	118235	27.4	0.002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 48 Hz to increase the discharge/effluent flow rate. GWTT communicated that carbon vessels should be backwashed since the differential pressure between P3 and P4 is 50 psi.
12/13/2019	GWTT	Yes	--	--	64	66	45	71	1.95	62.8	11	--	48.0	3002260.0	148125	25.7	0.003	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 48 Hz to 49 Hz (49 GPM) at departure. GWTT noted the pressure on the carbon vessels was approaching their maximum limit.
12/16/2019	GWTT	Yes	--	--	66	70	56	74	2.02	60.6	14	--	40.0	3122091.0	119831	27.7	0.004	Yes	Yes	Conducted system pressure checks, changed bag filters, adjusted the VFD from 49 Hz to 50 Hz (45 GPM). GWTT noted the pressure on the carbon vessels was approaching their maximum limit. System sampled on 12/17/19.
12/20/2019	GWTT	Yes	--	--	45	63	41	67	NR	NR	18	--	16.00	3239075.0	116984	20.3	0.004	Yes	No	Conducted system pressure checks and changed bag filters and adjusted the VFD from 40 Hz to 47 Hz. Water waste from force main descale process removed from totes off-site by Global Cycle.
12/23/2019	GWTT	Yes	--	--	NR	NR	NR	NR	NR	NR	21	--	NR	--	--	--	--	No	No	System shutdown for carbon changeout at 08:00. Spent carbon removed from both vessels and replaced with new virgin carbon.
12/26/2019	GWTT	No	--	--	NR	11	NR	14	2.25	54.4	22	--	NR	3317372.0	78297	54.4	0.012	Yes	No	System restarted and requilibrated at 08:00 following carbon changeout and carbon hydration. Conducted system pressure checks, changed bag filters, adjusted the VFD to 23 Hz upon departure.
12/30/2019	GWTT	Yes	--	--	19	11	6	13	2.42	50.6	26	--	52.00	3460145.0	142773	24.8	0.006	Yes	No	Conducted system checks and changed bag filters, VFD at 26 Hz.
Totals - December 2019 ¹²										54.2	27	39.0			858169	22.1	0.006			
1/3/2020	GWTT	Yes	--	--	18	8	14	15	2.37	51.8	3	--	49.00	3588009.0	127864	29.6	0.001	Yes	No	Conducted system checks and changed bag filters, and adjusted VFD.
1/6/2020	GWTT	Yes	--	--	18	11	14	15	2.92	42.0	6	--	45.00	3692480.0	104471	24.2	0.002	Yes	No	Conducted system checks and changed bag filters, and adjusted VFD.
1/10/2020	GWTT	Yes	--	--	21	12	17	20	3.00	40.8	10	--	46.00	3809788.0	117308	20.4	0.003	Yes	No	Conducted system checks and changed bag filters, VFD at 27 Hz.
1/13/2020	GWTT	Yes	--	--	21	16	18	21	3.35	36.6	13	--	39.00	3899180.0	89392	20.7	0.004	Yes	No	Conducted system checks and changed bag filters.
1/17/2020	GWTT	Yes	--	--	25	20	23	26	3.62	33.9	17	--	24.00	3992818.0	93638	16.3	0.004	Yes	Yes	Conducted system checks and changed bag filters. Adjusted VFD to 33 Hz. Flushed iron sludge/sediment out of bottom of sight glass on EQ holding tank.
1/20/2020	GWTT	Yes	--	--	28	21	26	29	3.97	30.9	20	--	37.00	4065780.0	72962	16.9	0.005	Yes	No	Conducted system checks and changed bag filters.
1/24/2020	GWTT	Yes	--	--	29	22	27	30	5.13	23.9	24	--	34.00	4150180.0	84400	14.7	0.005	Yes	No	Conducted system checks and changed bag filters.
1/26/2020	GWTT	Yes	--	--	26	24	25	28	5.75	21.3	27	--	39.00	4205753.0	55573	12.9	0.005	Yes	No	Conducted system checks and changed bag filters.
1/31/2020	GWTT	Yes	--	--	28	23	26	30	6.80	18.0	31	--	36.00	4272375.0	66622	11.6	0.005	Yes	No	Conducted system checks, changed bag filters, cleaned sight glass on EQ tank; about 4-5 inches of sludge accumulated at bottom.
Totals - January 2020 ¹²										33.2	30.9	38.8			812230	18.3	0.009			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁷	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2		Combined Instantaneous Estimated Influent Flow Rate (GPM) ²		Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
2/4/2020	GWTT	Yes	--	--	28	22	26	30	8.00	15.3	4	--	36.00	4325997	120244	20.9	0.002	Yes	No	Conducted system checks and changed bag filters.
2/7/2020	GWTT	Yes	--	--	26	25	24	28	7.90	15.5	7	--	38.00	4360208	34211	7.9	0.001	Yes	No	Conducted system checks and changed bag filters.
2/11/2020	GWTT	Yes	--	--	26	25	26	30	11.07	11.1	11	--	43.00	4399300	39092	6.8	0.001	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel, adjusted transfer pump from 33 Hz to 23 Hz after backwash.
2/13/2020	GWTT	Yes	--	--	9	8	7	9	12.33	9.9	13	--	42.00	4418200	18900	6.6	0.002	Yes	Yes	Conducted system checks and changed bag filters. Adjusted transfer pump from 33 Hz to 23 Hz, recycled backwash water into GWTS #2 for treatment.
2/18/2020	GWTT	Yes	--	--	12	6	8	9	16.63	7.4	18	--	42.00	4454815	36615	5.1	0.002	Yes	No	Conducted system checks and changed bag filters.
2/21/2020	GWTT	Yes	--	--	10	8	9	11	22.67	5.4	21	--	40.00	4471238	16423	3.8	0.002	Yes	No	Conducted system checks and changed bag filters.
2/24/2020	GWTT	Yes	--	--	15	5	13	15	2.65	46.2	24	--	44.00	4490425	19187	4.4	0.002	Yes	No	Conducted system checks and changed bag filters. Bag filters packed with significant iron-oxide sediments, influent flow rate into EQ tank significantly increased; slug of iron-oxide must have broke through from accumulation in the force main. Adjusted VFD from 30 Hz to 35 Hz. Pressure readings at primary LGAC vessel indicating a need for a backwash.
2/26/2020	GWTT	Yes	--	--	25	10	20	24	2.60	47.1	26	--	37.00	4519500	29075	10.1	0.005	Yes	No	Conducted system checks and change bag filters. Increase discharge flow through VFD from 30 Hz to 35 Hz. Pressure readings at primary LGAC vessel indicating a need for a backwash.
2/28/2020	GWTT	Yes	--	--	29	10	13	15	2.55	48.0	28	--	52.00	4556491	36991	12.8	0.007	Yes	No	Conducted system checks and change bag filters. Conducted a backwash on primary LGAC vessel. Initial instantaneous Effluent flow rate was measured at 75 GPM after backwash. Adjusted VFD from 35 Hz to 26 Hz.
Totals - February 2020 ¹²										22.9	29	41.6		350738		8.4	0.004			
3/2/2020	GWTT	Yes	--	--	21	6	12	14	2.83	43.2	2	--	46.00	4645525	89034	20.6	0.001	Yes	Yes	Conducted system checks, changed bag filter, pumped water from large exterior tote through GWTS #2. System sampled on 3/3/2020
3/6/2020	GWTT	Yes	--	--	19	10	16	19	3.00	40.8	6	--	38.00	4723654	78129	13.6	0.002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 26 Hz to 30 Hz.
3/9/2020	GWTT	Yes	--	--	25	18	11	15	3.00	40.8	9	--	51.00	4785425	61771	14.3	0.003	Yes	No	Conducted system checks, changed bag filters, at departure, instantaneous effluent flow rate at 51 gpm (30 Hz).
3/13/2020	GWTT	Yes	--	--	23	8	13	16	3.23	37.9	13	--	51.00	4898555	113130	19.6	0.005	Yes	No	Conducted system checks, changed bag filters.
3/16/2020	GWTT	Yes	--	--	23	9	14	17	3.75	32.7	16	--	50.00	4968818	70263	16.3	0.005	Yes	No	Conducted system checks, changed bag filters.
3/20/2020	GWTT	Yes	--	--	25	9	18	21	3.60	34.0	20	--	42.00	5052480	83662	14.5	0.006	Yes	No	Conducted system checks, changed bag filters, backwashed the primary LGAC vessel, adjusted the VFD from 30 Hz to 25 Hz. 42 GPM. Observed significant iron-oxide sedimentation accumulation in EQ tank.
3/23/2020	GWTT	Yes	--	--	17	9	15	17	3.00	40.8	23	--	48.00	5097785	45305	10.5	0.005	Yes	No	Conducted system checks; had to change the bag filters twice because the accumulated iron-oxide sediment in the EQ tank is getting pulled into the transfer pump affecting total gallons treated. Sight glass on EQ tank was flushed. Adjusted VFD from 25 Hz to 35 Hz.
3/26/2020	GWTT	Yes	--	--	34	17	27	29	3.00	40.8	26	--	48.00	5163530	65745	15.2	0.008	Yes	No	Conducted system checks, changed bag filters and increased the VFD from 35 Hz to 38 Hz.
3/30/2020	GWTT	Yes	--	--	38	14	34	38	3.27	37.5	30	--	42.00	5264195	100665	17.5	0.011	Yes	No	Conducted system checks, changed bag filters and increased the VFD from 38 Hz to 40 Hz.
Totals - March 2020 ¹²										38.7	31	46.2		707704		15.9	0.012			
4/2/2020	GWTT	Yes	--	--	34	30	31	35	2.95	41.5	2	--	51.00	5304740	40545	14.1	0.000	Yes	No	Conducted system checks and changed bag filters.
4/6/2020	GWTT	Yes	--	--	33	33	31	35	3.12	39.3	6	--	50.00	5354280	49540	8.6	0.001	Yes	No	Conducted system checks and changed bag filters. Transfer pump VFD at 40 Hz.
4/9/2020	GWTT	Yes	--	--	--	--	15	18	3.47	35.3	8.5	--	49.00	5413745	59465	16.5	0.002	Yes	No	System shutdown for 2-4 hours at 7am for vac out of EQ tank and backwash of primary carbon vessel. Global removed 2,989 gallons of iron-oxide water mixture from EQ tank and exterior totes. Conducted system checks and changed bag filters. Adjusted VFD from 40 Hz (74 gpm) to 28 Hz (49 gpm).
4/13/2020	GWTT	Yes	--	--	16	10	11	15	3.92	31.3	12.5	--	44.00	5497360	83615	14.5	0.002	Yes	No	Conducted system checks and changed bag filters
4/16/2020	GWTT	Yes	--	--	18	15	15	19	4.32	28.4	15.5	--	35.00	5552940	55580	12.9	0.003	Yes	No	Conducted system checks and changed bag filters
4/20/2020	GWTT	Yes	--	--	19	14	19	23	5.00	24.5	19.5	--	30.00	5620048	67108	11.7	0.003	Yes	No	Conducted system checks and changed bag filters, adjusted VFD from 28 Hz to 32 Hz to allow higher pressure/flow through bag filters to help with iron-oxide sediment fouling.
4/24/2020	GWTT	Yes	--	--	26	21	26	30	5.25	23.3	23.5	--	30.00	5679610	59562	10.3	0.003	Yes	No	Conducted system checks and changed bag filters, adjusted the VFD from 32 Hz to 35 Hz.
4/27/2020	GWTT	Yes	--	--	30	28	30	34	6.37	19.2	26.5	--	28.00	5723132	43522	10.1	0.003	Yes	Yes	Conducted system checks and changed bag filters. System sampled on 4/28/2020.
Totals - April 2020 ¹²										30.4	29.5	39.6		458937		10.8	0.004			
5/1/2020	GWTT	Yes	--	--	31	26	31	35	3.75	32.7	1	--	26.00	5756710	33578	23.3	0.0003	Yes	No	Conducted system checks and changed bag filters.
5/5/2020	GWTT	Yes	--	--	31	20	30	35	3.40	36.0	5	--	26.00	5772378	15668	2.7	0.0002	Yes	No	Conducted system checks and changed bag filters.
5/8/2020	GWTT	Yes	--	--	33	24	14	15	3.38	36.2	8	--	48.00	5843400	71022	16.4	0.0015	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel, adjusted transfer pump from 35 Hz to 30 Hz after backwash.
5/11/2020	GWTT	Yes	--	--	24	11	17	20	3.72	33.0	11	--	47.00	5922710	79310	18.4	0.0024	Yes	No	Conducted system checks and changed bag filters.
5/15/2020	GWTT	Yes	--	--	27	16	24	28	4.80	25.5	15	--	35.00	6012638	89928	15.6	0.0027	Yes	No	Conducted system checks and changed bag filters.
5/18/2020	GWTT	Yes	--	--	26	26	25	30	4.60	26.6	18	--	35.00	6075320	62682	14.5	0.0031	Yes	No	Conducted system checks and changed bag filters. System sampled on 5/21/2020.
5/22/2020	GWTT	Yes	--	--	30	27	34	40	5.10	24.0	22	--	32.00	6154187	78867	13.7	0.0035	Yes	Yes	Conducted system checks and changed bag filters. Adjusted VFD from 35 Hz to 38 Hz.
5/26/2020	GWTT	Yes	--	--	35	34	34	40	4.15	29.5	26	--	32.00	6196369	42182	7.3	0.0022	Yes	No	Conducted system checks and changed bag filters.
5/29/2020	GWTT	Yes	--	--	32	36	32	38	4.15	29.5	29	--	35.00	6221412	25043	5.8	0.0020	Yes	No	Conducted system checks and changed bag filters.
Totals - May 2020 ¹²										30.3	31	35.1		498280		11.2	0.0041			
6/2/2020	GWTT	Yes	--	--	34	35	14	17	4.27	28.7	2	--	46.00	6230577	9165	3.2	0.000	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel; Transfer pump flow rate initially at 68 gpm after backwash. Adjusted VFD from 38 Hz to 30 Hz.
6/5/2020	GWTT	Yes	--	--	24	5	15	19	3.47	35.3	5	--	40.00	6273600	43023	10.0	0.000	Yes	No	Conducted system checks and changed bag filters.
6/9/2020	GWTT	Yes	--	--	24	10	19	24	3.85	31.8	9	--	40.00	6334345	60745	10.5	0.001	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD from 30 Hz to 35 Hz.
6/12/2020	GWTT	Yes	--	--	31	16	28	32	4.12	29.8	12	--	30.00	6404810	70465	16.3	0.002	Yes	No	Conducted system checks and changed bag filters..
6/16/2020	GWTT	Yes	--	--	32	24	30	35	4.67	26.3	16	--	47.00	6495449	90639	15.7	0.002	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 30 Hz and backwashed primary LGAC vessel.
6/19/2020	GWTT	Yes	--	--	22	8	14	18	5.00	24.5	19	--	43.00	6568815	73366	17.0	0.003	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 32 Hz.
6/22/2020	GWTT	Yes	--	--	24	14	19	24	5.72	21.4	22	--	36.00	6634380	65565	15.2	0.003	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 36 Hz.
6/25/2020	GWTT	Yes	--	--	24	19	22	25	5.63	21.7	25	--	40.00	6690810	56430	13.1	0.003	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 32 Hz. System samples collected on 6/24/2020.
6/29/2020	GWTT	Yes	--	--	27	18	13	15	5.15	23.8	29	--	43.00	6764833	74023	12.9	0.003	Yes	No	Conducted system checks and changed bag filters twice, backwashed primary LGAC vessel, and flushed iron oxide sediment from sight glass on EQ tank.
Totals - June 2020 ¹²										27.0	30	40.6		543421		12.6	0.0035			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT	Days System Operating	EFFLUENT					Estimated Total PFAS Removal (kg) ¹	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2		Combined Instantaneous Estimated Influent Flow Rate (GPM) ²		Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
7/2/2020	GWTT	Yes	--	--	25	13	20	25	4.60	26.6	2	--	39.00	6837610	72777	25.3	0.001	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD from 32 Hz to 34 Hz.
7/6/2020	GWTT	Yes	--	--	36	19	36	24	4.97	24.7	6	--	36.00	6913169	75559	13.1	0.001	Yes	No	Conducted system checks and changed bag filters, flushed out sight glass on the EQ tank. Adjusted VFD to 34 Hz.
7/10/2020	GWTT	Yes	--	--	24	24	22	28	4.97	24.7	10	--	39.00	6948605	35436	6.2	0.001	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 36Hz.
7/13/2020	GWTT	Yes	--	--	28	26	26	32	5.28	23.2	13	--	42.00	6996929	48324	11.2	0.002	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 38Hz.
7/16/2020	GWTT	Yes	--	--	32	33	11	15	6.03	20.3	16	--	44.00	7040815	43886	10.2	0.002	Yes	No	Conducted system checks and changed bag filters and adjusted VFD to 29 Hz. Conducted a backwash of primary LGAC vessel after initial readings. Reduced the transfer pump speed to reduce carry over of the Iron-oxide sedimentation from the EQ tank into the bag filters and LGAC vessels.
7/20/2020	GWTT	Yes	--	--	13	11	9	13	6.57	18.7	20	--	41.00	7091010	50195	8.7	0.002	Yes	No	Conducted system checks and changed bag filters filters and LGAC vessels.
7/24/2020	GWTT	Yes	--	--	15	12	11	16	7.20	17.0	24	--	39.00	7129271	38261	6.6	0.002	Yes	No	Conducted system checks and changed bag filters, VFD at 29 Hz.
7/27/2020	GWTT	Yes	--	--	18	8	11	15	7.50	16.3	27	--	40.00	7140929	11658	2.7	0.001	Yes	Yes	Conducted system checks and changed bag filters. System sampled on 7/28/2020.
7/30/2020	GWTT	Yes	--	--	12	14	11	15	6.80	18.0	30	--	40.00	7161465	20536	4.8	0.002	Yes	No	Conducted system checks and changed bag filters.
Totals - July 2020 ¹²										21.1	31		40.0		396632	8.9	0.0031			

Notes:

1. CE - Coastal Engineering. GWTT - Groundwater Treatment Technologies

2. Prior to November 2019, the instantaneous Influent (INF) and effluent (EFF) flow rates are calculated based on the cross-sectional volume per vertical foot of the influent tank and the measured/timed filling (INF) rate or draining (EFF) of the tank. The diameter of the influent tank is approximately 78 inches. The cross-sectional volume of the tank is approximately 33.1 cubic feet per vertical linear foot. Therefore the flow rate calculation factor is approximately 122.5 gallons per 6 inches. Since 11/7/2019 (following the replacement of the effluent totalizer, ONLY INF flow rates (from PRW-4) are calculated based on an approximation. This Combined Influent flow rate represents the combined flow within both force main pipes from recovery well PRW-4.

3. Prior to November 2019 the total mass of PFAS removed is calculated based on the calcuated influent flow rate, the number of days the system has been operating, and the average total Influent PFAs concentration for the month. Since November 2019, the total mass of PFAS removed is calculated based on the effluent flow rate.

4. NA or -- Not Applicable.

5. NR - Not Reported

6. As of April 1, 2019: the system's O&M data reporting was changed to include the differential pressure readings from the bag filter unit's pressure gauges before and after the bag filters are changed/replaced, if applicable.

7. Prior to November 2019, the average influent flow rate could not reliably be calculated/measured from September to (most of) October due to a blockage in the site glass on the EQ tank from accumulated iron-oxide precipitates in the bottom of the tank. The iron-oxide precipitates were removed from the EQ tank on Oct. 28, 2019.

8. Following the separation of the two force mains and the installation of GWTPS #2 on November 7, 2019, Instantaneous influent flow rates are estimated by approximating 50% of the Combined Instantaneou Influent flow rate values.

9. Instantaneous Effluent Flow Rate is recorded as the instantaneous flow rate as calculated or indicated from the totalizer flow meter on the system's effluent discharge piping - reading is collected after bag filter change and/or backwashing.

10. The Average effluent flow rate is calculated from the net gallons (Total Gallons Treated) obtained from the system's effluent totalizer flow meter and days that the system was in operation.

11. Prior to Nov. 7, 2019, calculated average effluent flow rates and the estimated PFAS removed total were calculated based on the reported totalizer readings. The totalizer flow meter readings on the effluent discharge piping were not reliable at flow rates less than 40 GPM. Therefore the data are shaded to indicate that they are approximations only and for this reason the July through October data are also considered approximates.

12. As of September 2019, the "Totals" shown (from left to right) include the Average Instantaneous Influent Flow Rate, Total Days of System Operation, Average Instantaneous Effluent Flow Rate, Total Gallons Treated, Average Net Effluent Flow Rate, and Estimated PFAS Removed for the respective monthly reporting period. Running average values shown for the effluent flow rate. Prior to November 7, 2019, totals shown (from left to right) included the Average Instantaneous Influent Flow Rate, Total Days of Operation, Average Instantaneous Effluent Flow Rate, and Estimated PFAS Removed for the respective monthly reporting period.

Table 2B - Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - System No. 2 (GWTS #2)
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Days System Operating	Transfer Pump Pres. (psi)	Pre-Filter Changeout Differential Pressure (psi) ²		Post-Filter Changeout Differential Pressure (psi)		Carbon Vessels. Pre-change out (psi)		Carbon Vessels. Post-change out (psi)		Instantaneous Estimated INFLUENT ⁷ Flow Rate (GPM) ^{3,4}	EFFLUENT				Estimated Total PFAs Removal (kg)	System Operating on Departure	System Sampled	Comments
				Gauge: P1	Gauge: P2	Gauge: P3	Gauge: P2	Gauge: P3	Gauge: P4	Gauge: P5	Gauge: P4	Gauge: P5		Totalizer (Gal)	Instant Flow Rate (GPM) ⁸	Total Net Gallons Treated ⁴	Average Effluent Flow Rate (GPM) ⁵				
11/11/2019	GWTT	Yes	1	38	0	0	0	0	<2	0	2	2	12.56	416900	32.00	0.0	--	0.00032	Yes	No	Influent flow stream from PRW-4 split and started system #2. Conducted system checks, changed bag filters after initial flush.
11/15/2019	GWTT	Yes	4	40	24	2	5	2	2	2	2	2	34.00	451645	34.00	34745.0	8.043	0.0008	Yes	Yes	Conducted system pressure checks and changed the bag filters. System shutdown temporarily to calculate influent flow rate at GWTPS #1. Collected system startup samples on 11/12/19 and 11/15/19.
11/18/2019	GWTT	Yes	7	--	32	2	6	6	2	2	4	4	44.00	491280	33.00	39635.0	9.175	0.0016	Yes	No	Conducted system pressure checks and changed the bag filters. System shutdown temporarily to calculate influent flow rate at GWTPS #1.
11/22/2019	GWTT	Yes	11	40	31	4	7	7	4	4	6	5	12.50	549022	34.00	57742.0	10.025	0.0028	Yes	No	Conducted system pressure checks and changed the bag filters. System shutdown temporarily to calculate influent flow rate at GWTPS #1.Colleected system startup samples on 11/19/19.
11/25/2019	GWTT	Yes	14	40	15	6	7	7	4	5	5	6	12.50	594623	33.00	45601.0	10.556	0.0037	Yes	No	Conducted system pressure checks and changed the bag filters.
11/29/2019	GWTT	Yes	18	40	18	6	8	8	3	3	4	4	NR	649150	34.00	54527.0	9.466	0.0043	Yes	No	Conducted system pressure checks and changed the bag filters.
Totals - November 2019 ⁶				19									23.11		33	232250	8.49	0.0040			
12/2/2019	BETA	Yes	2		--	--	--	--	--	--	--	--	--	686500	--	37350.0	13.0	--	No	Yes	System shutdown at 10:00 for force main de-scale process: system locked out and tagged out.
12/4/2019	BETA	No	2	40	--	--	7	7	--	--	4	4	22.70	686700	30.00	200.0	0.069	0.00000	Yes	No	System restarted at 12:12 upon finishing the de-scale purging process and restarted PRW-4.
12/6/2019	GWTT	No	4	35	--	--	14	13	--	--	10	8	25.0	707866	47.00	21166.0	7.349	0.00029	Yes	No	System off upon arrival and bag filters were completed clogged with iron sediments. Bag filters had to be changed after 20 minutes of operation, GWTT observed a high amount of solids floating in the EQ tank and pumped down the EQ tank and observed significant iron sediment sludge on the bottom of the tank. GWTT notified BETA that they would raise the floats in EQ tank to help lessen the agitation of the sludge and carryover into the bag filters. System was on high level alarm and continued to shutdown of PRW-4, which shut off system #1 due to significant iron oxide sediment accumulation in EQ tank.
12/9/2019	GWTT	Yes	7	37	39	8	16	16	7	5	14	8	25.0	813065	46.00	105199.0	24.4	0.00171	Yes	No	Conducted system checks, changed bag filters. Raising floats in EQ tank has not affected the iron sediment at the bottom.
12/13/2019	GWTT	Yes	11	38	43	11	21	20	10	5	18	7	25.0	943807	42.00	130742.0	22.7	0.00250	Yes	No	Conducted system checks, changed bag filters.
12/16/2019	GWTT	Yes	14	45	43	13	23	22	10	3	21	5	25.0	1049390	41.00	105583.0	24.4	0.00343	Yes	No	Conducted system checks, changed bag filters. EQ tank "High Level" alarm triggered.
12/20/2019	GWTT	Yes	18	42	33	14	20	20	10	4	18	6.00	25.0	1148998	43.00	99608.0	17.3	0.00312	Yes	No	Conducted system checks and changed the bag filters. System shutdown temporarily for pump out of iron oxide sediment accumulation in EQ tank.
12/23/2019	GWTT	Yes	21	--	--	--	--	--	--	--	--	--	--	1209649	NR	60651.0	14.0	0.00296	Yes	No	System shutdown at 08:00 for carbon changeout conducted on System #1.
12/26/2019	GWTT	Yes	22	38	30	15	19	19	14	6	18	7	24.2	1209820	42.00	171.0	0.1	0.00003	Yes	No	System restarted at 09:30 AM following carbon changeout conducted on System #1. Conducted system checks and changed bag filters.
12/30/2019	GWTT	Yes	26	38	38	13	22	22	12	5	20	7	24.00	1320824	40.00	111004.0	19.3	0.00503	Yes	No	Conducted system pressure checks and changed the bag filters. Reset pump control floats in EQ tank back to original depths (following the removal of iron sediments at bottom of the tank).
Totals - December 2019 ⁶				27									24.49		41	671674	17.3	0.005			
1/3/2020	GWTT	Yes	3	43	35	13	20	20	10	4	18	6	--	1422315	42.00	101491.0	23.5	0.00101	Yes	No	Conducted system checks, changed bag filters.
1/6/2020	GWTT	Yes	6	40	27	15	19	19	11	5	16	8	20.98	1507290	43.00	84975.0	19.7	0.00169	Yes	No	Conducted system checks, changed bag filters.
1/10/2020	GWTT	Yes	10	38	29	15	19	19	13	5	17	6	20.42	1602935	43.00	95645.0	16.6	0.00237	Yes	No	Conducted system checks, changed bag filters.
1/13/2020	GWTT	Yes	13	38	26	16	19	19	18	6	6	8	18.28	1674840	41.00	71905.0	16.6	0.00309	Yes	No	Conducted system checks, changed bag filters.
1/17/2020	GWTT	Yes	17	--	28	16	20	20	15	6	18	7	16.94	1750933	41.00	76093.0	13.2	0.00321	Yes	No	Conducted system checks, changed bag filters.
1/20/2020	GWTT	Yes	20	38	25	16	11	11	15	6	18	7	15.44	1808630	48.00	57697.0	13.4	0.00382	Yes	No	Conducted system checks, changed bag filters. Backwashed primary LGAC vessel.
1/24/2020	GWTT	Yes	24	35	19	9	11.5	11.5	6	7	8	8	11.93	1872940	48.00	64310.0	11.2	0.00383	Yes	No	Conducted system checks, changed bag filters.
1/27/2020	GWTT	Yes	27	35	16	10	12	11	7	7	9	8.00	10.65	1915785	46.00	42845.0	9.9	0.00383	Yes	No	Conducted system checks, changed bag filters, pumped backwash water through system's influent stream.
1/31/2020	GWTT	Yes	31	36	18	10	12	12	9	8	8	7	9.01	1962050	--	46265.0	8.0	0.00356	Yes	No	Conducted system checks, changed bag filters.
Totals - January 2020 ⁶				31									15.46		44	641226	14.4	0.004			
2/4/2020	GWTT	Yes	4	2	18	10	12	12	9	8	8	7	7.66	2000333	46.00	38283	6.6	0.00053	Yes	No	Conducted system checks, changed bag filters.
2/7/2020	GWTT	Yes	7	36	14	11	12	11	8	7	8	6	7.75	2023878	46.00	23545	5.5	0.00076	Yes	No	Conducted system checks, changed bag filters.
2/11/2020	GWTT	Yes	11	35	14	12	13	13	9	8	10	8	5.53	2049888	47.00	26010	4.5	0.00099	Yes	No	Conducted system checks, changed bag filters.
2/13/2020	GWTT	Yes	13	36	13	12	14	13	10	8	10	8	4.97	2060169	46.00	10281	3.6	0.00093	Yes	Yes	Conducted system checks, changed bag filters. Pumped backwash water from GWTS #1 through system.
2/18/2020	GWTT	Yes	18	36	15	12	13	14	9	8	9	8	3.68	2081950	57.00	21781	3.0	0.00109	Yes	Yes	Conducted system checks, changed bag filters.
2/21/2020	GWTT	Yes	21	36	15	13	14	13	10	8	10	8	2.70	2094054	48.00	12104	2.8	0.00117	Yes	Yes	Conducted system checks, changed bag filters.
2/24/2020	GWTT	Yes	24	37	43	5	16	16	2	2	13	7	23.11	2108080	47.00	14026	3.2	0.00156	Yes	Yes	Conducted system checks, changed bag filters. Bag filters packed with significant iron-oxide sediments, influent flow rate into EQ tank significantly increased: slug of iron must have broke through. Had to change bag filters twice.
2/26/2020	GWTT	Yes	26	36	43	6	16	15	6	2	16	8	23.56	2134241	45.00	26161	9.1	0.00472	Yes	Yes	Conducted system checks and changed bag filters.
2/28/2020	GWTT	Yes	28	36	44	5	21	20	5	2	18	7	24.02	2168295	42.00	34054	11.8	0.00661	Yes	Yes	Conducted system checks, changed bag filters. Approximately 6 inch of iron-oxide sludge has accumulated on bottom of EQ tank: control float switches were raised to reduce disruption of settled sludge.
Totals - February 2020 ⁶				29									11.44		47	206245	4.9	0.003			
3/2/2020	GWTT	Yes	2	36	35	10	15	15	9	5	10	11	21.6	2249000	48.00	80705	18.7	0.00078	Yes	Yes	Conducted system checks, changed bag filters. Backwashed primary LGAC vessel, vaccumed the iron-oxide sludge out of the EQ tank, and into 55-gal drums on site; water from the drum can be decanted back through the system. System sampled on 3/3/2020.
3/6/2020	GWTT	Yes	6	37	25	10	16	15	8	8	12	10	20.4	2315739	47.00	66739	11.6	0.00145	Yes	No	Conducted system checks, changed bag filters. System shutdown temporarily to pump backwash water from exterior totes through system.
3/9/2020	GWTT	Yes	9	37	30	9	16	16	7	6.5	14	10	20.4	2366315	44.00	50576	11.7	0.00220	Yes	No	Conducted system checks, changed bag filters.
3/13/2020	GWTT	Yes	13	38	37	9	20	20	8	5	18	10	18.9	2476035	42.00	109720	19.0	0.00518	Yes	No	Conducted system checks, changed bag filters.
3/16/2020	GWTT	Yes	16	38	29	15	20	20	12	8	18	10	16.3	2544858	41.00	68823	15.9	0.00533	Yes	No	Conducted system checks, changed bag filters.
3/20/2020	GWTT	Yes	20	38	28	17	19	19	10	7	17	10	17.0	2615618	41.00	70760	12.3	0.00514	Yes	No	Conducted system checks, changed bag filters. Observed significant iron-oxide accumulation in EQ tank.
3/23/2020	GWTT	Yes	23	38	26	16	21	20	14	8.5	18	10	20.4	2636761	41.00	21143	4.9	0.00235	Yes	No	Conducted system checks, changed bag filters.
3/26/2020	GWTT	Yes	26	38	29	14	20	19	14	8.5	18	10	20.4	2663514	41.00	26753	6.2	0.00337	Yes	No	Conducted system checks, changed bag filters.
3/30/2020	GWTT	Yes	30	46	44	5	24	24	2	1	20	9	18.8	2721065	37.00	57551	10.0	0.00627	Yes	No	Conducted system checks, changed bag filters.
Totals - March 2020 ⁶				31									19.37		42	552770	12.4	0.00549			
4/2/2020	GWTT	Yes	2	42	42	13	24	23	10	3	21	5	20.8	2768543	27.00	47478	16.5	0.00041	Yes	No	Conducted system checks, changed bag filters, and slowed down the effluent discharge flow rate to reduce carry over of significant iron sludge into the bag filters.
4/6/2020	GWTT	Yes	6	42.5	42	12	27	27	10	3	25	6	19.7	2833368	25.00	64825	11.3	0.00085	Yes	No	Conducted system checks and changed bag filters.
4/9/2020	GWTT	Yes	8.5	39	--	--	9	8	7	6.5	7	6.5	17.7	2903750	39.00	70382	19.6	0.00209	Yes	No	System shutdown for 2-4 hours at 7am for vac out of EQ holding tank and backwash of primary carbon vessel. Conducted system checks and changed bag filters.
4/13/2020	GWTT	Yes	12.5	39	24.5	7	10	9	4	5	8	6.0	15.6	3004475	38.00	100725	17.5	0.00275	Yes	No	Conducted system checks and changed bag filters. Lowered transfer pump "off control" float in EQ holding tank to allow longer run time and less cycling.
4/16/2020	GWTT	Yes	15.5	40	20.8	8	11	10	7	6	8	6.0	14.2	3074510	36.00	70035	16.2	0.00316	Yes	No	Conducted system checks and changed bag filters, pumped backwash water from exterior totes into (system #2) holding tank.
4/20/2020	GWTT	Yes	19.5	40	25	8	11	10	6	5	9	6.0	12.3	3156813	37.00	82303	14.3	0.00350	Yes	No	Conducted system checks and changed bag filters. Lowered transfer pump "off control" float in EQ holding tank to allow longer run time and less cycling.
4/24/2020	GWTT	Yes	23.5	42	26	10	15	14	7	5	10	6.0	11.7	3225480	33.00	68667	11.9	0.00352	Yes	No	Conducted system checks and changed bag filters.
4/27/2020	GWTT	Yes	26.5	40	21	12	15	14	10	6	12	6.0	9.6	3271810	33.00	46330	10.7	0.00357	Yes	Yes	Conducted system checks and changed bag filters. Collected system samples on 4/28/2020.
Totals - April 2020 ⁶				29.5									15.2		34	550745	13.0	0.00481			

Table 2B - Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - System No. 2 (GWTS #2)
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Days System Operating	Transfer Pump Pres. (psi)	Pre-Filter Changeout Differential Pressure (psi) ²		Post-Filter Changeout Differential Pressure (psi)		Carbon Vessels. Pre-change out (psi)		Carbon Vessels. Post-change out (psi)		Instantaneous Estimated INFLUENT ⁷ Flow Rate (GPM) ^{3,4}	EFFLUENT				Estimated Total PFAs Removal (kg)	System Operating on Departure	System Sampled	Comments
				Gauge: P1	Gauge: P2	Gauge: P3	Gauge: P2	Gauge: P3	Gauge: P4	Gauge: P5	Gauge: P4	Gauge: P5		Totalizer (Gal)	Instant. Flow Rate (GPM) ⁸	Total Net Gallons Treated ⁴	Average Effluent Flow Rate (GPM) ⁵				
5/1/2020	GWTT	Yes	1	47	43	9	22	22	8	3	20	5.0	16.3	3320924	32.00	49114	8.5	0.00310	Yes	No	Conducted system checks and changed bag filters twice during visit, system on idle upon arrival due to high level.
5/5/2020	GWTT	Yes	5	42	42	12	26	26	10	3	23	5.0	18.0	3359082	25.00	38158	6.6	0.00241	Yes	No	Conducted system checks and changed bag filters twice: influent flow rate has spiked but has caused a large influx of iron sediments.
5/8/2020	GWTT	Yes	8	42	35	13	22	22	10	4	20	6.0	18.1	3426824	34.00	67742	15.7	0.00570	Yes	No	Conducted system checks and changed bag filters.
5/11/2020	GWTT	Yes	11	42	25	16	22	22	14	5	20	6.0	16.5	3485100	32.00	58276	13.5	0.00490	Yes	No	Conducted system checks and changed bag filters. Pumped down green exterior tote holding backwash water from system #1.
5/15/2020	GWTT	Yes	15	39	35	17	8.5	8	16	4	7	6.0	12.8	3562051	38.00	76951	13.4	0.00485	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel.
5/18/2020	GWTT	Yes	18	39	16	8	9	9	6	6	7	6.0	13.3	3614934	39.00	52883	12.2	0.00445	Yes	Yes	Conducted system checks and changed bag filters. Pumped down green exterior tote holding backwash water from 5.15.20 through System #2. System sampled on 5/21/2020.
5/22/2020	GWTT	Yes	22	42	24	7	10	10	4	4	7	6.0	12.0	3682536	36.00	67602	11.7	0.00426	Yes	No	Conducted system checks and changed bag filters.
5/26/2020	GWTT	Yes	26	41	44	4	17	16	0	0	14	5.0	14.8	3735642	34.00	53106	9.2	0.00335	Yes	No	Conducted system checks and changed bag filters twice.
5/29/2020	GWTT	Yes	29	40	44	4	21	19	4	1	15	4.0	14.8	3785810	34.00	50168	11.6	0.00422	Yes	No	Conducted system checks and changed bag filters twice.
Totals - May 2020 ⁶				31									15.2		33.8	514000	11.5	0.00418			
6/2/2020	GWTT	Yes	2	43	42	8	23	23	8	3	21	5.0	14.4	3832928	32.00	47118	16.4	0.00471	Yes	No	Conducted system checks and changed bag filters, primary carbon vessel needs to be backwashed.
6/5/2020	GWTT	Yes	5	40	35	9	13	13	2	2	10	5.0	17.7	3887828	35.00	54900	12.7	0.00366	Yes	No	Conducted system checks and changed bag filters.
6/9/2020	GWTT	Yes	9	40	21	10	7.5	7	8	5	6	5.0	15.9	3922210	35.00	34382	6.0	0.00172	Yes	No	Conducted system checks and changed bag filters. Bakcwashed primary LGAC vessel, pumped down outside holding tank through system before backwashing carbon vessel.
6/12/2020	GWTT	Yes	12	40	21	10	7.5	7	8	5	6	5.0	14.9	3970210	35.00	48000	11.1	0.00320	Yes	No	Conducted system checks and changed bag filters.
6/16/2020	GWTT	Yes	16	41	23	8	10	10	6	5	8	6.0	13.1	4029179	36.00	58969	10.2	0.00295	Yes	No	Conducted system checks and changed bag filters. Pumped backwash water from exterior holding totes through system.
6/19/2020	GWTT	Yes	19	40	21	10	7.5	7	8	5	6	5.0	12.3	4069514	38.00	40335	9.3	0.00269	Yes	No	Conducted system checks and changed bag filters.
6/22/2020	GWTT	Yes	22	41	14	10	11	11	9	5	9	5.0	10.7	4102439	37.00	32925	7.6	0.00219	Yes	No	Conducted system checks and changed bag filters.
6/25/2020	GWTT	Yes	25	42	16	12	10	10	8	4	5	5.0	10.9	4128010	35.00	25571	5.9	0.00170	Yes	No	Conducted system checks and changed bag filters.
6/29/2020	GWTT	Yes	29	41	16	9	10	10	8	5	9	5.0	11.9	4154842	35.00	26832	4.7	0.00134	Yes	No	Conducted system checks and changed bag filters.
Totals - June 2020 ⁶				30									13.5		35.3	369032	8.5	0.00238			
7/2/2020	GWTT	Yes	2	42	43	4	12	11	0	0	10	5.0	13.3	4173048	34.00	18206	6.3	0.00219	Yes	No	Conducted system checks and changed bag filters.
7/6/2020	GWTT	Yes	6	42	37	8	16.5	16	7	3	14	5.0	12.3	4243300	34.00	70252	12.2	0.00423	Yes	No	Conducted system checks and changed bag filters.
7/9/2020	GWTT	Yes	9	43	42	8	23	23	8	3	21	5.0	12.3	4279505	31.00	36205	8.4	0.00291	Yes	No	Conducted system checks and changed bag filters.
7/12/2020	GWTT	Yes	12	47	47	18	18	18	7	3	16	5.0	11.6	4329440	32.00	49935	11.6	0.00401	Yes	No	Conducted system checks and changed bag filters.
7/16/2020	GWTT	Yes	16	42	25	13	16.5	16	12	5	14	7.0	10.2	4374349	33.00	44909	7.8	0.00271	Yes	No	Conducted system checks and changed bag filters.
7/20/2020	GWTT	Yes	20	40	34	12	7.5	7	10	3	6	5.0	9.3	4435010	40.00	60661	10.5	0.00365	Yes	No	Conducted system checks and changed bag filters. Pumped backwash water from System #1 through system and then backwashed primary LGAC vessel.
7/24/2020	GWTT	Yes	24	40	37	4	9.5	9	2	2	8	6.0	8.5	4493135	40.00	58125	10.1	0.00350	Yes	No	Changed bag filters and pumped excess backwash water through system.
7/27/2020	GWTT	Yes	27	41	43	6	13	12	2	0	10	5.0	8.2	4521639	38.00	28504	6.6	0.00229	Yes	No	Conducted system checks and changed bag filters twice due to iron-oxide accumulation in the EQ tank.
7/30/2020	GWTT	Yes	30	41	32	7	14	13	6	3	10	5.0	9.0	4585515	37.00	63876	14.8	0.00513	Yes	No	Conducted system checks: the system is receiving more water (influent) that GWTS#1, operator assumes it's related to the build up of iron in the force main piping.
Totals - July 2020 ⁶				31									10.5		35.4	430673	9.6	0.00335			

Notes:
1. GWTT - Groundwater Treatment Technologies
2. Pressure readings before filter bag changeout or if no changeout was done.
3. Influent flow is an instantaneous estimate of the flow rate from the submersible Well Pump at PRW-4.
4. During monthly reporting periods the net gallons are calculated from previous effluent totalizer readings. (Difference between the current totalizer reading - the last dated totalizer reading).
5. The Average effluent flow rate is calculated from the net gallons obtained from the system's effluent totalizer flow meter and days that the system was in operation.
6. The "Totals" shown (from left to right) include the, Total Days of System Operation, Average Instantaneous Influent Flow Rate, Average Instantaneous Effluent Flow Rate, Total Gallons Treated, Average Net Effluent Flow Rate, and Estimated PFAS Removed for the respective monthly reporting period.
7. Instantaneous influent flow rates are estimated by approximating 50% of the influent flow rate values calculated from GWPTS #1 (See Table 2A).
8. Instantaneous effluent flow rate estimated by stopwatch at totalizer meter.
9. Flow calculated based on gallons marking on EQ tank. Estimated flow rate = 25 GPM (i.e. flow is calculated based on an in-situ observation of flow into the EQ tank, and 100 gallons of groundwater flows into the EQ tank for a 4 minute duration.

Table 3 - Groundwater Elevation and Gauging Data 2018-2020
 Barnstable Country Fire and Rescue Training Academy
 155 Flint Rock Road, Barnstable, MA
 RTN 4-26179

Well ID	Location (From Academy)	Elev. (TOC) (Feet)	Groundwater Level from TOC (Feet)								Groundwater Elevation (Feet)							
			Date								Date							
			6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18-19/2020	5/11/2020	7/27/2020	6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18-19/2020	5/11/2020	7/27/2020
FS-1a2	Academy	41.839	--	12.45	10.96	11.78	--	11.56	10.82	13.47	--	29.389	30.879	30.059	--	30.279	31.019	28.369
FS-1Aa	Academy	41.769	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
FS-1aC	Academy	41.915	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
HSW-1/HS-1(a)	Academy	40.012	--	9.62	8.78	8.02	11.67	9.45	7.9	12.33	--	30.392	31.232	31.992	28.342	30.562	32.112	27.682
HSW-6/HS-2(a)	Academy	39.305	9.37	10.39	8.02	8.02	10.76	8.74	8.63	10.67	29.935	28.915	31.285	31.285	28.545	30.565	30.675	28.635
DW-2D	Academy	37.36	--	7.91	6.39	6.39	8.76	7.00	6.20	6.94	--	29.45	30.97	30.97	28.6	30.36	31.16	30.42
DW-2S	Academy	37.532	--	8.33	6.22	7.93	9.59	7.65	6.98	9.54	--	29.202	31.312	29.602	27.942	29.882	30.552	27.992
DW-4	Not Located	NS	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
DW-8A	Academy	42.471	12.33	12.21	11.75	12.59	14.37	12.4	11.57	14.26	30.141	30.261	30.721	29.881	28.101	30.071	30.901	28.211
DW-8i	Academy	42.579	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PRW-1	Academy	41.83	11.67	12.53	11.02	11.83	13.78	11.65	10.84	13.54	30.16	29.3	30.81	30	28.05	30.18	30.99	28.29
PRW-2	Academy	40.019	--	10.44	8.95	9.72	11.53	9.6	8.77	11.48	--	29.579	31.069	30.299	28.489	30.419	31.249	28.539
PRW-3	Academy	37.832	--	8.2	6.67	7.5	9.29	7.32	6.5	9.25	--	29.632	31.162	30.332	28.542	30.512	31.332	28.582
PRW-4	Academy	39.344	--	9.78	8.21	9.07	10.98	8.84	8.03	10.81	--	29.564	31.134	30.274	28.364	30.504	31.314	28.534
PRW-5	Academy	40.017	--	12.38	11.29	11.79	13.56	11.55	10.77	13.48	--	29.637	30.727	30.227	28.457	30.467	31.247	28.537
PRW-6	Academy	40.577	--	11.23	9.75	10.59	--	10.4	9.59	12.28	--	29.347	30.827	29.987	--	30.177	30.987	28.297
MW-1	Adjacent Academy	42.584	--	--	12.06	12.54	14.46	12.35	11.54	14.19	--	--	20.79	30.044	28.124	30.234	31.044	28.394
MW-2	Adjacent Academy	42.72	--	--	--	--	14.79	12.7	11.82	14.56	--	--	--	--	27.93	30.02	30.9	28.16
MW-3D	Adjacent Academy	43.654	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-3i	Adjacent Academy	43.823	--	13.8	12.31	13.14	15.04	--	--	--	--	29.24	30.73	29.9	28.783	--	--	--
MW-3S	Adjacent Academy-SE	43.535	--	13.64	12.17	12.99	14.89	12.8	11.99	14.69	--	29.22	30.75	29.93	28.645	30.735	31.545	28.845
MW-6	Adjacent Academy-SE	41.432	--	--	--	--	13.58	11.4	10.61	13.24	--	--	--	--	27.852	30.032	30.822	28.192
MW-7	Adjacent Academy-SE	43.126	--	--	12.8	13.6	15.59	13.42	12.63	15.24	--	--	30.326	27.536	27.536	29.706	30.496	27.886
MW-8	Adjacent Academy-SE	48.721	--	--	13.46	14.28	16.22	--	13.29	--	--	--	35.261	34.441	32.501	--	--	--
MW-8C	Adjacent Academy-SE	43.992	--	--	--	--	--	14.1	--	--	--	--	--	--	--	--	--	--
MW-9D (not viable)	Adjacent Academy-SE	45.079	--	--	14.21	--	17.08	14.9	--	--	--	--	30.869	--	27.999	30.179	--	--
MW-9S	Adjacent Academy-SE	44.629	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-10	Adjacent Academy	44.212	--	14.85	13.43	14.26	16.23	14.06	13.26	15.92	--	29.362	30.782	29.952	27.982	30.152	30.952	28.292
MW-10D	Adjacent Academy/Dock	NS	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-10S	Adjacent Academy/Dock	NS	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-11	Adjacent Academy/Dock	NS	--	--	--	--	15.5	--	--	--	--	--	--	--	--	--	--	--
MW-12s	DG-E	43.421	14.62	14.76	13.3	14.29	16.1	13.94	13.2	15.8	28.801	28.661	30.121	29.131	27.321	29.481	30.221	27.621
MW-12i	DG-E	43.448	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-13	DG-E	43.404	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-15D	DG-E	43.591	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-15S	DG-E	43.458	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-17	DG-E	NS	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-19A	DG-NE	44.06	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-19B	DG-NE	44.146	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-21	DG-NE	41.23	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-22	DG-NE	43.46	14.3	15.06	13.5	14.4	16.35	14.13	13.32	15.9	29.16	28.4	29.96	29.06	27.11	29.33	30.14	27.56
MW-23	DG-NE	49.491	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-27	DG-NE	41.909	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-28S	DG-NE	41.413	--	--	--	--	12.95	10.9	10.1	12.77	--	--	--	--	28.463	30.513	31.313	28.643
MW-28D (abandoned)	DG-NE	NS	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-32	DG-NE	41.984	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-33	DG-NE	52.612	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-35i	DG-NE	52.265	--	27.32	--	--	29.08	--	--	--	--	24.945	--	--	23.185	--	--	--
MW-35s	DG-NE	52.557	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-35D	DG-NE	52.481	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-36A	DG-NE	58.548	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-36B	DG-NE	58.498	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-36D	DG-NE	58.43	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-37D	DG-E	46.862	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-37i	DG-E	46.875	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-37s	DG-E	47.046	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
MW-99i	DG-E - North of PRW-4	49.98	--	--	--	--	22.94	--	--	--	--	--	--	--	27.04	--	--	--
PC-0	DG-SE	58.276	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-1	DG-SE	54.57	26.14	26.81	25.36	26.22	28.34	26	25.24	27.88	28.43	27.76	29.21	28.35	26.23	28.57	29.33	26.69
PC-2	DG-SE	51.776	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-3	DG-SE	52.047	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-4	DG-SE	NS	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-5	DG-SE	NS	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-6A	DG- Far east	59.322	31.05	31.52	30.13	31	33.2	30.89	30.2	32.9	28.272	27.802	29.192	28.322	26.122	28.432	29.122	26.422
PC-7	DG- Far east	57.612	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-8	DG- Far east	56.881	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-9	DG- Far east /fair conditi	43.278	--	17.3	--	--	19.1	--	--	--	--	25.978	--	--	24.178	--	--	--
PC-10	DG- Far east	51.099	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-11	DG- Far east	55.515	27.25	27.7	26.35	27.18	29.35	27	26.3	28.78	28.265	27.815	29.165	26.165	27.25	27.7	26.35	29.35
PC-12	DG- Far east	54.676	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-13	DG- Far east	49.386	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-14	DG- Far east	48.022	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
PC-15 (not viable)	DG- Far east	53.467	--	--	--	--	29.22	--	--	--	--	--	--	--	24.247	--	--	--
PC-16D	DG- Far east	56.276	29.53	29.75	28.4	29.35	31.4	29.15	28.4	30.68	26.746	26.526	27.876	26.926	24.876	27.126		

Table 3 - Groundwater Elevation and Gauging Data 2018-2020
 Barnstable Country Fire and Rescue Training Academy
 155 Flint Rock Road, Barnstable, MA
 RTN 4-26179

Well ID	Location (From Academy)	Elev. (TOC) (Feet)	Groundwater Level from TOC (Feet)								Groundwater Elevation (Feet)							
			Date								Date							
			6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18-19/2020	5/11/2020	7/27/2020	6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18-19/2020	5/11/2020	7/27/2020
TWS0-9	Piezometer- West of FP	36.594	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
WH-2D	Mary Dunn Pond (DG)	33.263	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
WH-2S	Mary Dunn Pond (DG)	33.17	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
WS-101	Mary Dunn Pond (DG)	36.529	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--
Pond	Pond Edge ⁹	NE	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	29.23
Pond Gauge ⁵	Flintrock Pond	30.97	--	--	4.5	3.8	--	4.35	--	--	--	--	35.47	34.77	--	35.32	--	--

- Notes:
1. -- indicates monitoring well has not been surveyed and/or is not gauged regularly.
 2. DG: Downgradient
 3. All monitoring wells located on the Academy property were surveyed in 2018.
 4. Monitoring wells located off Academy property were surveyed in 2007 by Cape Cod Commission.
 5. Pond Gauge was installed in April 2019.
 6. NS- Not Surveyed: unable to locate, not deemed a viable well.
 7. NA- Not Available: survey data is unavailable as it's being re-evaluated.
 8. Well IDs and Location displayed in gray indicate the well has been abandoned or destroyed.
 9. The Pond Edge elevation was collected during a simple survey on 7/27/2020 of Flintrock Pond water's edge. Monitoring well PFW-4 was utilized as a benchmark.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	HSW-6/HS-2(a)											HSW-1/HS-1(a)											
SAMPLING DATE			1/21/2016	3/30/2016	8/11/2016	4/10/2017	7/27/2017	11/17/2017	2/9/2018	6/26/2018	1/9/2019	10/28/2019	7/28/2020	1/21/2016	8/11/2016	4/10/2017	7/27/2017	11/17/2017	2/9/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																									
PFOS (ng/L)	70	20	77,000	320,000	41,000	28,000	21,000	45,000	25,000	950	1,300	3,600	2,300	110,000	56,000	38,000	24,000	25,000	13,000	1,800	2,000	1,100	1,800	740	1,300
PFOA (ng/L)	70	20	--	--	--	660	--	320	160	15	94	79	80	--	--	1,000	350	1,300	320	840	100	64	46	36	100
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	BRL (<87)	26	46	40	--	--	--	--	--	--	43	65	43	33	22	57
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	26	140	310	350	--	--	--	--	--	--	1,700	300	170	150	66	300
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	15	66	100	69	--	--	--	--	--	--	510	67	52	43	32	63
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	30	18	--	--	--	--	--	--	--	55	19	13	9	37
TOTAL Σ6 PFAS	70	20	77,000	320,000	41,000	28,660	21,000	45,320	25,160	1,006	1,626	1,626	2,857	110,000	56,000	39,000	24,350	26,300	13,320	4,893	2,587	1,448	2,085	905	1,857

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	HS-1 ¹³		HS-6 ¹³	HS-2 ¹³	HS-2S ¹³		PFW-1														
SAMPLING DATE			8/11/2016	12/8/2016	8/11/2016	7/27/2017	8/18/2016	5/3/2017	4/1/2015	10/7/2015	3/8/2016	3/30/2016	8/11/2016	4/10/2017	2/9/2018	6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020	7/28/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS (ng/L)	70	20	56,000	36,000	41,000	21,000	300	150	8,400	60,000	7,000	56,000	3,500	4,100	8,100	76,000	38,000	20,000	24,000	16,000	22,000	6,000	5,200
PFOA (ng/L)	70	20	460	1,800	450	370	BRL (<5.3)	8	360	800	--	--	--	--	470	1,500	160	300	560	130	220	250	210
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	3,900	330	360	210	570	230	94	110
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	7,400	960	1,500	4,800	910	1,000	890	820
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	610	140	290	500	150	200	220	160
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	110	160	120	200	81	89
TOTAL Σ6 PFAS	70	20	56,460	37,800	41,450	21,370	300	158	8,760	60,800	7,000	56000	3500	4,100	8,570	89,410	39,590	22,560	30,230	17,880	23,850	7,535	6,589

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-ex cavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PFW-2														PFW-3			PFW-4
SAMPLING DATE			4/1/2015	6/18/2015	10/27/2015	1/21/2016	3/30/2016	8/11/2016	12/8/2016	4/10/2017	7/27/2017	11/17/2017	2/9/2018	1/9/2019	10/28/2019	5/11/2020	4/1/2015	10/15/2015	4/18/2017	4/1/2015
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																				
PFOS (ng/L)	70	20	220,000	200,000	32,000	39,000	120,000	65,000	13,000	17,000	73,000	25,000	32,000	5,200	2,100	690	2,700	3,800	3,400	3,300
PFOA (ng/L)	70	20	5200	BRL (<800)	--	1,100	2,100	--	--	970	910	400	400	720	74	48	140	170	230	420
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	110	64	39	--	--	--	--
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	1,800	230	140	--	--	--	--
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	470	68	45	--	--	--	--
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	27	14	--	--	--	--
TOTAL Σ6 PFAS	70	20	225,200	200,000	32,000	40,100	122,100	65,000	13,000	17,970	73,910	25,400	32,400	8,300	2,563	976	2,840	3,970	3,630	3,720

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PFW-5									PFW-6				PRW-1	PRW-4 ³						
SAMPLING DATE			3/31/2015	4/11/2017	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020	7/28/2020	4/1/2015	3/8/2016	4/18/2016	1/9/2019	4/1/2015	4/1/2015	8/4/2015	11/12/2015	1/6/2016	4/28/2016	8/11/2016	11/16/2016
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS (ng/L)	70	20	2,700	2,100	1,100	1,900	1,600	2,400	1,000	1,200	980	3,400	2,400	850	1,500	1,600	760	5,900	9,000	7,600	6,300	9,500	5,400
PFOA (ng/L)	70	20	250	170	64	150	120	26	88	120	100	350	470	19	400	150	60	550	BRL (<2000)	260	BRL (<200)	210	99
PFNA (ng/L)	NE	20	--	--	BRL (<8.7)	25	16	BRL (<4.9)	11	22	15	--	--	--	140	--	--	--	--	--	--	--	--
PFHxS (ng/L)	NE	20	--	--	240	680	630	260	360	720	610	--	--	--	1,100	--	--	--	--	--	--	--	--
PFHpA (ng/L)	NE	20	--	--	30	82	54	22	56	66	44	--	--	--	220	--	--	--	--	--	--	--	--
PFDA (ng/L)	NE	20	--	--	--	12	11	BRL (<4.1)	10	13	11	--	--	--	--	--	--	--	--	--	--	--	--
TOTAL Σ6 PFAS	70	20	2,950	2,270	1,434	2,849	2,431	2,708	1,525	2,141	1,760	3,750	2,870	869	3,360	1,750	820	6,450	9,000	7,860	6,300	9,710	5,499

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PRW-4 ³							PC-0		PC-1													
SAMPLING DATE			1/4/2017	4/19/2017	8/28/2017	11/20/2017	2/14/2018	4/9/2018	6/14/2018	4/2/2015	4/24/2017	8/20/2014	6/17/2015	10/7/2015	3/30/2016	4/24/2017	2/6/2018	6/26/2018	1/11/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/28/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																									
PFOS (ng/L)	70	20	4,900	3,200	2,900	2,000	2,100	2,600	2,800	110	930	320	48,000	2,000	56,000	5,700	9,000	10,000	1,700	8,000	4,300	1,600	1,700	1,700	1,900
PFOA (ng/L)	70	20	95	110	100	64	27	79	120	BRL (<20)	58	--	1,100	BRL (<800)	1,200	--	370	190	140	300	150	72	180	110	63
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	140	62	150	140	75	70	110	58
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	850	380	650	430	380	450	400	240
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	200	200	180	230	150	240	150	98
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--										78	67	19	20	28	36	
TOTAL Σ6 PFAS	70	20	4,995	3,310	3,000	2,064	2,127	2,679	2,920	110	988	320	49,100	2,000	57,200	5,700	9,370	11,380	2,482	9,358	5,317	2,296	2,660	2,498	2,395

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.

2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.

3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.

4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.

5. BRL - Below Laboratory Detection Limits

6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion

7. Concentrations in bold exceed applicable Health Advisory Limit

8. PFOS - Perfluorooctanesulfonate

9. PFOA - Perfluorooctanoic Acid

10. PFNA - Perfluorononanoic Acid

11. PFHxS - Perfluorohexanesulfonic Acid

12. PFHpA - Perfluoroheptanoic Acid

13. PFDA - Perfluorodecanoic Acid

14. NA - Concentration data not available

15. Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.

16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PC-2		PC-3		PC-4		PC-6A									PC-7					
SAMPLING DATE			6/17/2015	4/24/2017	8/20/2014	6/17/2015	6/17/2015	3/8/2016	3/9/2016	4/27/2017	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	4/2/2015	6/17/2015	10/7/2015	3/8/2016	4/27/2017
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS (ng/L)	70	20	3,800	2,200	3,100	4,700	2,200	4,600	1,300	3,200	1,300	1,800	1,900	940	1,100	1,600	86	1,300	17,000	500	700	1,700	2,900
PFOA (ng/L)	70	20	220	110	180	200	79	160	110	150	60	30	68	33	62	67	4	37	3,500	27	98	140	130
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	55	25	60	36	48	65	4	44	--	--	--	--	--
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	300	190	310	150	290	180	23	99	--	--	--	--	--
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	75	37	83	45	86	71	9	43	--	--	--	--	--
PFDA (ng/L)	NE	20											10	BRL (<4.1)	7.4	5.9	0.7	11					
TOTAL Σ6 PFAS	70	20	4,020	2,310	3,280	4,900	2,279	4,760	1,410	3,350	1,790	2,082	2,431	1,204	1,593	1,989	127	1,534	20,500	527	798	1,840	3,030

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PC-8					PC-9						PC-10		PC-11												
SAMPLING DATE			6/17/2015	10/7/2015	3/8/2016	4/24/2017	2/6/2018	4/1/2015	10/7/2015	3/9/2016	3/30/2016	4/28/2017	1/10/2019	10/30/2019	4/6/2015	4/28/2017	4/2/2015	5/12/2016	4/24/2017	2/6/2018	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																												
PFOS (ng/L)	70	20	15,000	500	1,600	36,000	1,000	580	510	5,300	8,100	280	1,700	2,300	790	560	4,400	32,000	3,600	4,000	9,600	14,000	200,000	68,000	22,000	18,000	12,000	9,500
PFOA (ng/L)	70	20	2,800	370	97	--	71	30	40	1,200	1,600	31	64	100	50	67	550	430	250	180	250	410	640	BRL (<240)	150	290	140	130
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	53	90	--	--	--	--	--	--	230	190	1,700	540	320	140	130	110
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	360	420	--	--	--	--	--	--	1,500	1,500	2,400	1,200	800	1,300	720	610
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	81	120	--	--	--	--	--	--	200	310	210	BRL (<210)	160	210	140	130
PFDA (ng/L)	NE	20		--	--	--	--	--	--	--	--	--	--	15	--	--	--	--	--	--	--	--	450	BRL (<260)	73	69	56	55
TOTAL Σ6 PFAS	70	20	17800	870	1697	36000	1071	610	550	6500	9700	311	2258	3,030	840	627	4950	32430	3850	4180	11,780	16,410	204,950	69,740	23,503	20,009	13,186	10,535

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.

2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.

3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.

4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.

5. BRL - Below Laboratory Detection Limits

6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion

7. Concentrations in bold exceed applicable Health Advisory Limit

8. PFOS - Perfluorooctanesulfonate

9. PFOA - Perfluorooctanoic Acid

10. PFNA - Perfluorononanoic Acid

11. PFHxS - Perfluorohexanesulfonic Acid

12. PFHpA - Perfluoroheptanoic Acid

13. PFDA - Perfluorodecanoic Acid

14. NA - Concentration data not available

15. Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.

16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PC-12			PC-13		PC-14			PC-15			PC-16d										
SAMPLING DATE			6/17/2015	5/12/2016	4/26/2017	6/17/2015	4/24/2017	8/20/2014	3/30/2016	4/28/2017	4/2/2015	4/28/2017	10/30/2019	4/2/2015	10/7/2015	2/6/2018	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/28/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																								
PFOS (ng/L)	70	20	1,300	1,700	1,600	2,400	2,800	550	2,100	1,600	1,300	780	970	700	560	980	1,900	1,600	2,000	1,400	1,300	1,600	1,200	930
PFOA (ng/L)	70	20	140	150	150	280	170	40	250	160	100	80	55	70	84	64	150	9.3	140	33	75	130	57	99
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	52	--	--	--	100	BRL (<8.7)	110	36	79	110	63	49
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	290	--	--	--	670	60	520	270	220	360	170	260
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	77	--	--	--	170	13	140	74	80	92	61	68
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	4.9	--	--	--	--	--	9	BRL (<4.1)	7	7	9	11
TOTAL Σ6 PFAS	70	20	1440	1850	1750	2680	2,970	590	2,350	1,760	1,400	860	1,444	770	644	1044	2,990	1,682	2,919	1,813	1,761	2,299	1,560	1,417

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
5. BRL - Below Laboratory Detection Limits
6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion
7. Concentrations in bold exceed applicable Health Advisory Limit
8. PFOS - Perfluorooctanesulfonate
9. PFOA - Perfluorooctanoic Acid
10. PFNA - Perfluorononanoic Acid
11. PFHxS - Perfluorohexanesulfonic Acid
12. PFHpA - Perfluoroheptanoic Acid
13. PFDA - Perfluorodecanoic Acid
14. NA - Concentration data not available
15. Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PC-17			PC-18						PC-19				PC-20D	PC-21D	PC-22	
SAMPLING DATE			8/20/2014	10/7/2015	2/6/2018	6/17/2015	10/7/2015	4/27/2017	2/6/2018	1/10/2019	10/29/2019	4/2/2015	3/30/2016	4/27/2017	10/30/2019	3/9/2016	3/9/2016	4/2/2015	4/28/2017
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																			
PFOS (ng/L)	70	20	140	230	140	1,200	900	580	890	1,500	1,500	3,300	1,600	2,000	1,900	3,200	230	1,200	1,400
PFOA (ng/L)	70	20	BRL	24	17	110	590	--	70	110	75	260	120	290	170	200	19	100	170
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	130	79	--	--	--	130	--	--	--	--
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	540	220	--	--	--	450	--	--	--	--
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	140	80	--	--	--	95	--	--	--	--
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--	--	7.2	--	--	--	14	--	--	--	--
TOTAL Σ6 PFAS	70	20	140	254	157	1310	1490	580	960	2420	1,954	3560	1720	2290	2745	3,400	249	1300	1,570

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard: ⁴	PC-23D	PC-24		PC-25	PC-26				PC-28									
SAMPLING DATE			6/17/2015	3/30/2016	4/28/2017	6/17/2015	6/17/2015	10/8/2015	3/8/2016	4/24/2017	3/9/2016	4/28/2017	1/10/2019	4/24/2019	7/23/2019	10/28/2019	2/19/2020	5/12/2020	7/29/2020	
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	
PFAS (Method 537.2)																				
PFOS (ng/L)	70	20	1,000	420	320	2,300	1,000	1,900	1,200	380	400	770	38	18	82	270	270	430	200	
PFOA (ng/L)	70	20	73	22	33	260	210	190	98	21	27	61	BRL (<3.3)	BRL (<7.4)	190	12	BRL (<7.4)	18	12	
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	BRL (<8.7)	BRL (<4.9)	BRL (<4.9)	9	BRL (<4.9)	15	10	
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	17	15	30	94	72	120	71	
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	20	24	25	33	23	41	30	
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	2	BRL (<4.1)	
TOTAL Σ6 PFAS	70	20	1073	442	353	2,560	1,210	2,090	1,298	401	427	831	75	57	327	418	365	626	323	

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PC-29	PC-30											PC-31		PC-32		PC-33		PC-34S	PC-34D		
SAMPLING DATE			4/28/2017	3/9/2016	4/27/2017	2/6/2018	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	3/8/2016	4/27/2017	3/30/2016	4/27/2017	3/30/2016	4/27/2017	4/14/2016	4/14/2016	4/28/2017	
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	
PFAS (Method 537.2)																								
PFOS (ng/L)	70	20	1,400	980	2,500	1,900	1,600	2,200	1,200	4,300	960	1,200	880	1,100	1,200	12,000	1,200	960	2,700	2,100	1,300	1,400	1,500	
PFOA (ng/L)	70	20	BRL (<4.6)	88	--	98	99	85	85	79	55	130	45	38	110	160	130	54	250	210	72	150	130	
PFNA (ng/L)	NE	20	--	--	--	--	80	88	100	100	61	74	45	57	--	--	--	--	--	--	--	--	--	
PFHxS (ng/L)	NE	20	--	--	--	--	510	390	340	300	220	210	180	120	--	--	--	--	--	--	--	--	--	
PFHpA (ng/L)	NE	20	--	--	--	--	130	110	110	96	71	87	80	48	--	--	--	--	--	--	--	--	--	
PFDA (ng/L)	NE	20	--	--	--	--	--	--	12	BRL (<4.1)	6	6	8	7.7	--	--	--	--	--	--	--	--	--	
TOTAL Σ6 PFAS	70	20	1400	1068	2500	1998	2,419	2,873	1,847	4,875	1,373	1,707	1,238	1,371	1310	12160	1330	1014	2950	2310	1372	1550	1630	

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PC-35S	PC-35D		PC-36S			PC-36D		PC-37	PC-38				PC-39		MW-1			MW-3S	
SAMPLING DATE			4/14/2016	4/14/2016	4/28/2017	4/14/2016	1/11/2019	10/29/2019	4/14/2016	4/24/2017	4/10/2017	4/24/2017	10/29/2019	5/12/2020	7/28/2020	4/24/2017	2/19/2020	11/22/2013	6/3/2014	4/28/2017	6/3/2014	8/18/2016
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																						
PFOS (ng/L)	70	20	1,700	2,000	1,700	35	64	1,200	3,100	2,500	45	BRL (<2.6)	BRL (<5.2)	5	BRL (<5.2)	1,200	820	3,900	4,400	2,600	4,900	1,900
PFOA (ng/L)	70	20	130	140	97	BRL (<5.3)	BRL (<3.3)	54	150	120	BRL (<20)	BRL (<4.6)	BRL (<7.4)	BRL (<0.23)	BRL (<7.4)	46	28	320	880	290	530	690
PFNA (ng/L)	NE	20	--	--	--	--	BRL (<8.7)	80	--	--	--	--	BRL (<4.9)	BRL (<0.48)	BRL (<4.9)	--	61	--	--	--	--	--
PFHxS (ng/L)	NE	20	--	--	--	--	38	120	--	--	--	--	6	2	BRL (<5.2)	--	100	--	--	--	--	--
PFHpA (ng/L)	NE	20	--	--	--	--	BRL (<7.4)	62	--	--	--	--	BRL (<7.1)	BRL (<0.37)	BRL (<7.1)	--	28	--	--	--	--	--
PFDA (ng/L)	NE	20	--	--	--	--	--	11	--	--	--	--	BRL (<4.1)	BRL (<0.18)	BRL (<4.1)	--	BRL (<4.1)	--	--	--	--	--
TOTAL Σ6 PFAS	70	20	1830	2140	1797	35	102	1,516	3250	2620	45	BRL	6.1	6.7	BRL	1,246	1,037	4,220	5,280	2,890	5,430	2,590

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	MW-3D	SBV -3	MW-6		MW-7	MW-10		MW-12I	MW-12										MW-15	MW-15D	MW-19I
SAMPLING DATE			8/18/2016	11/22/2013	4/1/2015	4/25/2017	11/22/2013	11/22/2013	4/18/2016	4/24/2017	8/20/2014	4/1/2015	6/26/2018	1/11/2019	4/23/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	4/24/2017	4/2/2015	8/20/2014
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS (ng/L)	70	20	98	1,100	5,700	2,400	3,100	2,000	1,700	490	2,500	4,800	3,000	2,700	2,800	2,800	2,300	3,100	3,500	2,900	19	60	BRL
PFOA (ng/L)	70	20	10	350	510	140	580	670	440	36	400	470	280	650	920	250	380	580	280	220	27	60	BRL
PFNA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	56	64	92	87	80	78	86	51	--	--	--
PFHxS (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	1,200	1,500	1,700	880	1,300	1,200	1,100	900	--	--	--
PFHpA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	130	490	440	170	310	390	140	120	--	--	--
PFDA (ng/L)	NE	20	--	--	--	--	--	--	--	--	--	--	--	16	11	10	8	23	18	--	--	--	--
TOTAL Σ6 PFAS	70	20	108	1,450	6,210	2,540	3,680	2,670	2,140	526	2,900	5,270	4,666	5,404	5,968	4,198	4,380	5,356	5,129	4,209	46	120	BRL

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	MW-22										MW-28S	MW-30	MW-31	MW-32	MW-35i				MW-36D	MW-37	MW-37D	MW-99i		
SAMPLING DATE			6/3/2014	4/1/2015	6/26/2018	1/11/2019	4/23/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	4/1/2015	4/1/2015	8/18/2016	5/3/2017	8/20/2014	5/3/2017	1/10/2019	10/30/2019	4/6/2015	4/26/2017	4/2/2015	4/6/2015	4/26/2017	10/29/2019
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																										
PFOS (ng/L)	70	20	4,900	600	320	350	320	410	510	460	380	790	2,100	1,400	3,200	240	60	42	BRL (<6)	BRL (<5.2)	140	77	60	730	240	630
PFOA (ng/L)	70	20	530	90	30	140	160	190	150	230	120	92	90	130	170	36	BRL	14	BRL (<3.3)	BRL (<7.4)	<20	77	90	70	18	50
PFNA (ng/L)	NE	20	--	--	9	BRL (<8.7)	81	8	8	5	10	14	--	--	--	--	--	--	BRL (<8.7)	BRL (<4.9)	--	--	--	--	--	58
PFHxS (ng/L)	NE	20	--	--	130	680	600	520	690	540	330	360	--	--	--	--	--	--	BRL (<5.6)	6.0	--	--	--	--	--	340
PFHpA (ng/L)	NE	20	--	--	13	69	49	33	61	38	32	27	--	--	--	--	--	--	BRL (<7.4)	BRL (<7.1)	--	--	--	--	--	46
PFDA (ng/L)	NE	20	--	--	--	--	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	1	5.2	--	--	--	--	--	--	--	BRL (<4.1)	--	--	--	--	--	5.5
TOTAL Σ6 PFAS	70	20	5,430	690	502	1,239	1,210	1,161	1,419	1,273	873	1,288	2,190	1,530	3,370	276	60	56	BRL	6.0	140	154	150	800	258	1,130

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable Country Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	OW-8A												FS-1SA	FS-1	RW-1		HW-1D ¹⁴			HW-2S	OW-2A	OW-2S	OW-2D
SAMPLING DATE			11/22/2013	6/3/2014	4/11/2017	8/16/2017	6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020	7/28/2020	6/16/2016	4/11/2017	4/1/2015	4/11/2017	5/3/2017	1/10/2019	10/28/2019	5/3/2017	6/3/2014	4/14/2016	4/14/2016
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																									
PFOS (ng/L)	70	20	2,700	8,600	1,700	770	2,800	990	880	780	220	650	150	170	1,700	1,700	2,300	1,000	25	BRL (<6)	BRL (<5.2)	15	1,300	2,400	6
PFOA (ng/L)	70	20	430	1,000	2,000	120	65	420	66	55	130	62	18	12	550	730	240	58	8	BRL (<3.3)	BRL (<7.4)	8.2	150	250	BRL (<5.3)
PFNA (ng/L)	NE	20	--	--	--	--	310	150	120	78	10	110	12	11	--	--	--	--	--	BRL (<8.7)	BRL (<4.9)	--	--	--	--
PFHxS (ng/L)	NE	20	--	--	--	--	250	890	140	100	750	190	77	30	--	--	--	--	--	BRL (<5.6)	BRL (<5.2)	--	--	--	--
PFHpA (ng/L)	NE	20	--	--	--	--	43	210	40	26	190	35	9	7.4	--	--	--	--	--	BRL (<7.4)	BRL (<7.1)	--	--	--	--
PFDA (ng/L)	NE	20	--	--	--	--	--	--	15	18	14	17	4	10	--	--	--	--	--	--	BRL (<4.1)	--	--	--	--
TOTAL Σ6 PFAS	70	20	3,130	9,600	3,700	890	3,468	2,660	1,261	1,057	1,314	1,064	270	240	2,250	2,430	2,540	1,058	33	BRL	BRL	23.2	1,450	2,650	6

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.

2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.

3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.

4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.

5. BRL - Below Laboratory Detection Limits

6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion

7. Concentrations in bold exceed applicable Health Advisory Limit

8. PFOS - Perfluorooctanesulfonate

9. PFOA - Perfluorooctanoic Acid

10. PFNA - Perfluorononanoic Acid

11. PFHxS - Perfluorohexanesulfonic Acid

12. PFHpA - Perfluoroheptanoic Acid

13. PFDA - Perfluorodecanoic Acid

14. NA - Concentration data not available

15. Monitoring well HS-1 was destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.

16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.

Table 1B - Summary of Groundwater Pump and Treatment System Total PFAs Analytical Data - GWTS #2
 Barnstable County Fire and Rescue Training Academy
 155 Flint Rock Road, Barnstable, MA
 RTN 4-26179

SAMPLE ID	INFLUENT (PRW-4)						MIDPOINT						EFFLUENT					
USEPA Method 537.2	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)	PFOS (ng/L)	PFOA (ng/L)	PFNA (ng/L)	PFHxS (ng/L)	PFHpA (ng/L)	PFDA (ng/L)
MassDEP ORS Guideline*	70 ng/L						70 ng/L						70 ng/L					
MCP Method 1 GW-1 Standard ¹⁵	20 ng/L						20 ng/L						20 ng/L					
SAMPLE DATE																		
System Startup on 11/11/19.																		
11/12/2019	4200	53	85	200	59	15	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
11/15/2019	--	--	--	--	--	--	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
11/19/2019	--	--	--	--	--	--	BRL (<5.2)	44	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	42	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
12/17/2019 ¹⁶	1500	43	51	180	54	10	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
1/17/2020	2200	57	60	220	69	13	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
2/13/2020	3100	74	66	310	92	17	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)	BRL (<5.2)	BRL (<7.4)	BRL (<4.9)	BRL (<5.2)	BRL (<7.1)	BRL (<4.1)
3/3/2020	3300	72	64	300	81	14	5.6	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)	BRL (<0.43)	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)
4/28/2020	1900	52	42	210	56	42	64	2.2	1.7	9.7	3.0	0.27	0.47	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)
5/21/2020	1800	46	40	200	50	11	76	2.8	2.0	10	3.6	0.52	BRL (<0.43)	BRL (<0.23)	BRL (<0.48)	BRL (<0.33)	BRL (<0.37)	BRL (<0.18)
6/24/2020	1400	41	41	160	49	19	39	2.9	2.3	12	4.3	1.1	0.84	BRL (<0.49)	BRL (<0.80)	BRL (<0.53)	BRL (<0.51)	BRL (<0.64)
7/28/2020	1700	44	43	200	52	12	84	3.8	3.3	17	5.7	0.76	BRL (<0.43)	BRL (<0.49)	BRL (<0.80)	BRL (<0.53)	BRL (<0.51)	BRL (<0.64)

Notes:

- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- MassDEP's Office of Research and Standards (ORS) expanded upon the USEPA's Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- Concentrations of the PFAS compound, PFDA, are presented based on the April 19, 2019, MassDEP draft of new/proposed groundwater standards for PFAS that includes a sixth, PFAS compound, PFDA. However the concentration of PFDA is not included in total PFAS removal calculations.
- BRL - Below Laboratory Reporting Limits; reporting limit shown in parentheses.
- Concentrations in bold exceed applicable MassDEP ORS Guideline
- PFOS - Perfluorooctanesulfonic acid
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- : Concentration data not available and/or sample was not collected on that date.
- Per MCP Regulations, the system was sampled one day, three days, and seven (7) days following the initial week of startup (11/11/19).
- On December 13, 2019, MassDEP published the newly established clean up standards for PFAS in soil and groundwater. These standards were effective as of December 27, 2019 and apply to the total sum of six PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA. Concentrations of the six PFAS compounds presented in the table were not compared to the new MassDEP standards until the January 2020 monthly system sample collection.
- The December monthly sample was collected from the system's effluent stream on 12/17/2019 following the receipt of the laboratory results from the 11/19/2019 sampling event on 12/16/2019. The effluent was resampled again to ensure significant breakthrough was not occurring from the secondary carbon vessel.

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ⁷	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁸	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
4/9/2018	CE	No	75	NA	NA	NA	75	NA	NA	NA	0	--	--	--	--	--		Yes	Yes	Conducted system pressure checks after restart.
4/10/2018	CE	Yes	94	74	NA	NA	77	74	2.07	59.3	1	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/11/2018	CE	Yes	76	NA	NA	NA	76	NA	2.78	44.0	2	--	--	--	--	--	0.001	Yes	No	PRW-4 well pump is operating at high level, high level float is not triggering pump to shut off. CS turned off PRW-4 manually at 1243 and restarted at 14:32. Carbon vessels were backwashed individually from 1313 to 1427.
4/12/2018	CE	Yes	NA	NA	NA	NA	75	75	2.78	44.0	3	--	--	--	--	--	0.002	Yes	No	Transfer pump is drawing down influent/holding tank faster than PRW-4 well is filling tank. No bag filter changes.
4/13/2018	CE	Yes	88	74	NA	NA	75	74	2.80	43.8	4	--	--	--	--	--	0.003	Yes	Yes	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/16/2018	CE	Yes	86	74	NA	NA	74	74	2.83	43.2	7	--	--	--	--	--	0.005	Yes	No	Pressure differential at 8 psi, no bags change. PRW-4 well high level float not triggering pump to shut off. Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/19/2018	CE	Yes	83		NA	NA	75		NA	NA	10	--	--	--	--	--	NA	Yes	No	Transfer pump is maintaining drawdown and flow through system ahead of the PRW-4 well pump, no bag changes.
4/20/2018	CE	Yes	89	75	NA	NA	75	75	3.07	39.9	11	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/23/2018	CE	Yes	92	76	NA	NA	77	76	3.18	38.5	14	--	--	--	--	--	0.009	Yes	No	High level float not triggering PRW-4 to shut down. Sean (B&B Electric) on site to inspect high float electrical issues. PRW-4 shut off at 13:40 to inspect control panel, PRW-4 restarted at 14:55. Transfer pump maintaining flow ahead of PRW-4 well pump. Both carbon vessels backwashed. Changed 3 bag filters (5 um).
4/24/2018	CE	Yes	74	NA	NA	NA	76		3.18	38.5	15	--	--	--	--	--	0.009	Yes	No	No bag change, conducted system pressure checks.
4/25/2018	CE	Yes	79	NA	NA	NA	75		3.30	37.1	16	--	--	--	--	--	0.009	Yes	No	Pressure differential of 4 psi, no bag filter change, transfer pump is maintaining flow ahead of the PRW-4 well pump.
4/26/2018	CE	Yes	83	NA	NA	NA	76		3.37	36.4	17	--	--	--	--	--	0.010	Yes	No	Pressure differential of 7 psi, no bag filter change, transfer pump is maintaining flow ahead of the PRW-4 well pump. While both the system transfer pump and PRW-4 well pump are on and operating, treatment takes 28 seconds to drawn down 1 inch in influent tank (~17.5 gallons)
4/27/2018	CE	Yes	84	73	NA	NA	75	75	3.42	35.8	18	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
4/30/2018	CE	Yes	87	73	NA	NA	75	75	3.53	34.7	21.00	--	--	--	--	--	0.012	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks.
Totals - April 2018										41.3	21.00						0.014			
5/1/2018	CS	Yes	83		NA	NA	75		3.83	32.0	0.00	--	--	--	--	--	0.0000	Yes	No	Adjusted /increased VFD of transfer pump from 35 psi to 40 psi to maintain drawdown ahead of PRW-4 well pump . No bag change. 1" drawdown ~ 1:41
5/2/2018	CS	Yes	94	75	NA	NA	80	75	3.63	33.7	1.00	--	--	--	--	--	0.0006	Yes	No	Changed 3 bag filters (5 µm) and conducted system pressure checks. Conducted a backwash on both carbon vessels, PRW-4 well pump would not shut off, float switch relay stuck in on position, PRW-4 shutoff at 0733 and restarted at 08:26 with float switch working properly. Adjusted transfer pump rate back to 35 psi.
5/4/2018	JES	Yes	110	73	NA	NA	73	75	3.65	33.6	3.00	--	--	--	--	--	0.0017	Yes	No	Changed 3 bag filters (10 um) and conducted system pressure checks.
5/7/2018	JES	Yes	110	73	NA	NA	74	74	3.7	33.1	6.00	--	--	--	--	--	0.0034	Yes	No	Changed 3 bag filters (5 um) and conducted system pressure checks.
Totals - May 2018										33.1	8.00						0.004			
6/5/2018	CE/MM	No	--	--	NR	NR	NR	NR	--	--	0	--	--	--	--	--	0	--	--	Carbon Change out- filled vessels with water and let to sit for ~24 hours, changed 3 bag filters (5 um)
6/6/2018	CE	Yes	--	--	NR	NR	NR	NR	3.45	35.5	1	--	--	--	--	--	0.001	No	No	Pump floats not operating correctly, low float turns pump off and when low float is in water again, transfer pump starts. System remained off.
6/7/2018	CE	Yes	62	52	NR	NR	NR	NR	3.18	38.5	2	--	--	--	--	--	0.001	Yes	No	Electrician on site in morning to correct float error; system operating normally.
6/11/2018	CE	Yes	56	61	NR	NR	NR	NR	3.63	33.7	6	--	--	--	--	--	0.003	Yes	No	No bag change, conducted system pressure checks.
6/12/2018	CE	Yes	56	63	NR	NR	NR	NR	3.68	33.3	7	--	--	--	--	--	0.004	Yes	No	No bag change, conducted system pressure checks.
6/13/2018	CE	Yes	58	54	NR	NR	NR	NR	3.46	35.4	8	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters.
6/13/2018	MM	Yes	--	--	NR	NR	NR	NR	--	--	8	--	--	--	--	--	--	--	Yes	Did not collect system data, only collected samples from Influent, Midpoint, and Effluent sample ports/locations.
6/16/2018	CE	Yes	77	60	NR	NR	NR	NR	--	--	11	--	--	--	--	--	--	--	No	Changed 3 bag filters.
6/19/2018	CE	Yes	92	65	NR	NR	NR	NR	--	--	14	--	--	--	--	--	--	No	No	Changed 3 bag filters and repaired holding basket for bags. Recovery well was not running, went out to the well and checked power, turned power to well on/off and did not hear contact relay pull in. System remained off until electrical issue in recovery well is fixed. Fixed at 15:45
6/20/2018	CE	Yes	72	60	NR	NR	NR	NR	3.73	32.8	15	--	--	--	--	--	0.008	Yes	No	No bag change, conducted system pressure checks.
6/21/2018	CE	Yes	79	60	NR	NR	NR	NR	--	--	16	--	--	--	--	--	--			No bag change, conducted system pressure checks. Worked by phone with Bob Simmonds on Control panel for transfer pump, pump will not change speed.
6/22/2018	CE	Yes	87	67	NR	NR	NR	NR	3.72	32.9	17	--	--	--	--	--	0.009	Yes	No	Changed 3 bag filters, conducted system pressure checks.
6/25/2018	CE	Yes	81	68	NR	NR	NR	NR	3.77	32.5	20	--	--	--	--	--	0.011	Yes	No	Changed 3 bag filters, conducted system pressure checks.
6/27/2018	CE	Yes	79	68	NR	NR	NR	NR	3.73	32.8	22	--	--	--	--	--	0.012	Yes	No	Changed 3 bag filters, conducted system pressure checks.
6/29/2018	CE	Yes	78	68	NR	NR	NR	NR	3.68	33.3	24	--	--	--	--	--	0.014	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - June 2018										33.9	24						0.013			
7/2/2018	CE	Yes	83	69	NR	NR	NR	NR	3.95	31.0	2	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/5/2018	CE	No	--	--	NR	NR	NR	NR	--	--	5	--	--	--	--	--	--	No	No	No power supplied to the recovery well.
7/6/2018	CE	Yes	86	69	NR	NR	NR	NR	3.87	31.7	5	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/9/2018	CE	Yes	89	72	NR	NR	NR	NR	3.77	32.5	8	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/11/2018	CE	Yes	88	72	NR	NR	NR	NR	3.85	31.8	10	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/13/2018	CE	Yes	89	72	NR	NR	NR	NR	4.08	30.0	12	--	--	--	--	--	0.006	Yes	Yes	Changed 3 bag filters, conducted system pressure checks.
7/16/2018	CE	Yes	98	70	NR	NR	NR	NR	3.97	30.9	15	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/18/2018	CE	No	--	--	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	No	No	No power supplied to the recovery well. Contact relay at recovery well pump out.
7/19/2018	CE	Yes	94	72	NR	NR	NR	NR	4.03	30.4	17	--	--	--	--	--	0.008	Yes	No	Electrician replaced the contact relay; recovery well operating again. Changed 3 bag filters and collected system pressure checks.
7/20/2018	CE	Yes	81	72	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	Yes	No	Changed 3 bag filters, conducted system pressure checks. Backwashed carbon vessels.
7/23/2018	CE	Yes	84	72	NR	NR	NR	NR	4.47	27.4	21	--	--	--	--	--	0.009	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/25/2018	CE	Yes	84	72	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	Yes	No	Collected system pressure checks.
7/26/2018	CE	Yes	80	72	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	Yes	No	Collected system pressure checks.
7/27/2018	CE	Yes	88	72	NR	NR	NR	NR	4.8	25.5	25	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters, conducted system pressure checks.
7/30/2018	CE	Yes	91	71	NR	NR	NR	NR	4.95	24.7	28	--	--	--	--	--	0.011	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - July 2018										29.6	28						0.015			
8/2/2018	CE	Yes	89	70	NR	NR	NR	NR	5.17	23.7	2	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/6/2018	CE	Yes	94	72	NR	NR	NR	NR	5.22	23.5	6	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/10/2018	CE	Yes	98	72	NR	NR	NR	NR	4.32	28.4	10	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks. System was sampled on August 7, 2018.
8/14/2018	CE	Yes	82	69	NR	NR	NR	NR	4.8	25.5	14	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/17/2018	CE	Yes	81	64	NR	NR	NR	NR	5.0	24.5	17	--	--	--	--	--	0.008	Yes	No	Changed 3 bag filters, conducted system pressure checks. Backwashed carbon vessels.
8/21/2018	CE	No	78	68	NR	NR	NR	NR	5.2	23.6	20	--	--	--	--	--	0.009	Yes	No	Recovery well down, due to contactor burnout/failure. System restarted at 14:45.
8/24/2018	CE	Yes	77	68	NR	NR	NR	NR	5.32	23.0	23	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters, conducted system pressure checks.
8/28/2018	CE	Yes	89	69	NR	NR	NR	NR	6.03	20.3	27	--	--	--	--	--	0.011	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Table										24.1	30						0.014			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ⁷	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁸	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
9/4/2018	CE	Yes	89	67	NR	NR	NR	NR	5.87	20.9	4	--	--	--	--	--	0.002	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/7/2018	CE	Yes	82	70	NR	NR	NR	NR	6.52	18.8	7	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/11/2018	CE	Yes	88	70	NR	NR	NR	NR	7.03	17.4	11	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/14/2018	CE	Yes	86	70	NR	NR	NR	NR	7.18	17.1	14	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/18/2018	CE	Yes	91	74	NR	NR	NR	NR	8.02	15.3	18	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/21/2018	CE	No	74	70	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	No	No	Recovery well down.
9/24/2018	CE	Yes	94	70	NR	NR	NR	NR	8.03	15.3	23	--	--	--	--	--	0.010	Yes	No	Changed 3 bag filters, conducted system pressure checks.
9/28/2018	CE	Yes	--	--	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	--	--	Carbon Change out- filled vessels with water and let to sit for ~24 hours, changed 3 bag filters (5 um), system sampled on 09/27/18.
Totals - September 2018										17.4	28						0.010			
10/1/2018	CE	No	78	57	NR	NR	NR	NR	5.83	21.0	1	--	--	--	--	--	0.000	Yes	No	System restarted after scheduled shutdown for carbon exchange. Changed 3 bag filters, conducted system pressure checks.
10/5/2018	CE	Yes	65	55	NR	NR	NR	NR	6.35	19.3	5	--	--	--	--	--	0.002	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/10/2018	CE	Yes	56	57	NR	NR	NR	NR	6.95	17.6	10	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/12/2018	CE	Yes	60	55	NR	NR	NR	NR	--	--	12	--	--	--	--	--	--	Yes	No	No bag change necessary.
10/15/2018	CE	Yes	70	60	NR	NR	NR	NR	6.9	17.8	15	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks. Repaired filter basket.
10/19/2018	CE	Yes	71	60	NR	NR	NR	NR	7.12	17.2	19	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/23/2018	CE	Yes	76	63	NR	NR	NR	NR	7.73	15.8	23	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks. Repaired holding basket in filter vessel.
10/26/2018	CE	Yes	72	64	NR	NR	NR	NR	8.83	13.9	26	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
10/30/2018	CE	Yes	80	65	NR	NR	NR	NR	7.52	16.3	30	--	--	--	--	--	0.009	Yes	Yes	Changed 3 bag filters, conducted system pressure checks. Repaired bag holder (basket) in filter vessel.
Totals - October 2018										17.4	31						0.011			
11/2/2018	CE	Yes	71	62	NR	NR	NR	NR	7.86	15.6	2	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/6/2018	CE	Yes	71	62	NR	NR	NR	NR	--	--	6	--	--	--	--	--		No	No	Changed 3 bag filters, conducted system pressure checks. Backwashed both carbon vessels. System shutdown at 10:00 for force main descaling and flush.
11/8/2018	CE	Yes	65	45	NR	NR	NR	NR	5.25	23.3	6	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks. System restarted at 12:40 following the completion of the force main descaling.
11/9/2018	CE	Yes	55	44	NR	NR	NR	NR	5.2	23.6	7	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/12/2018	CE	Yes	51	47	NR	NR	NR	NR	5.03	24.4	10	--	--	--	--	--	0.007	Yes	No	Conducted system pressure checks.
11/13/2018	CE	Yes	52	47	NR	NR	NR	NR	4.88	25.1	11	--	--	--	--	--	0.007	Yes	No	Conducted system pressure checks.
11/14/2018	CE	Yes	54	47	NR	NR	NR	NR	4.92	24.9	12	--	--	--	--	--	0.008	Yes	No	Conducted system pressure checks.
11/15/2018	CE	Yes	55	47	NR	NR	NR	NR	--	--	13	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
11/16/2018	CE	Yes	54	50	NR	NR	NR	NR	4.63	26.5	14	--	--	--	--	--	0.010	Yes	Yes	Changed 3 bag filters, conducted system pressure checks.
11/21/2018	CE	Yes	63	53	NR	NR	NR	NR	5.08	24.1	19	--	--	--	--	--	0.012	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/27/2018	CE	Yes	69	55	NR	NR	NR	NR	5.75	21.3	25	--	--	--	--	--	0.014	Yes	No	Changed 3 bag filters, conducted system pressure checks.
11/30/2018	CE	Yes	77	58	NR	NR	NR	NR	5.85	20.9	28	--	--	--	--	--	0.016	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - November 2018										23.0	28						0.012			
12/3/2018	CE	Yes	63	62	NR	NR	NR	NR	5.33	23.0	3	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/7/2018	CE	Yes	83	67	NR	NR	NR	NR	5.58	22.0	7	--	--	--	--	--	0.002	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/11/2018	CE	Yes	75	65	NR	NR	NR	NR	5.8	21.1	11	--	--	--	--	--	0.003	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/14/2018	CE	Yes	70	63	NR	NR	NR	NR	5.4	22.7	14	--	--	--	--	--	0.004	Yes	Yes	Changed 3 bag filters, conducted system pressure checks.
12/18/2018	CE	Yes	70	65	NR	NR	NR	NR	6.72	18.2	18	--	--	--	--	--	0.004	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/21/2018	CE	Yes	70	67	NR	NR	NR	NR	6.7	18.3	21	--	--	--	--	--	0.005	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/26/2018	CE	Yes	78	71	NR	NR	NR	NR	7.38	16.6	26	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/28/2018	CE	Yes	82	70	NR	NR	NR	NR	7.35	16.7	28	--	--	--	--	--	0.006	Yes	No	Changed 3 bag filters, conducted system pressure checks.
12/31/2018	CE	Yes	82	71	NR	NR	NR	NR	7.38	16.6	31	--	--	--	--	--	0.007	Yes	No	Changed 3 bag filters, conducted system pressure checks.
Totals - December 2018										19.5	31						0.008			
1/4/2019	RPT	Yes	72	72	NR	NR	NR	NR	6.5	18.8	4	--	--	--	--	--	0.001	Yes	No	Changed 3 bag filters, conducted system pressure checks, observed hole in pre-filter basket.
1/7/2019	PCB	Yes	80	71	NR	NR	NR	NR	6.2	19.8	7	--	--	--	--	--	0.002	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/10/2018	RPT	Yes	75	70	NR	NR	NR	NR	7.03	17.4	10	--	--	--	--	--	0.003	Yes	No	Conducted system pressure checks.
1/11/2018	MDM	Yes	79	71	NR	NR	NR	NR	7.62	16.1	11	--	--	--	--	--	0.003	Yes	Yes	Change 3 bag filters, conducted system pressure checks.
1/14/2019	PCB	Yes	76	71	NR	NR	NR	NR	--	--	14	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
1/15/2019	PCB	Yes	80	71	NR	NR	NR	NR	--	--	15	--	--	--	--	--	--	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/18/2019	PCB	Yes	76	71	NR	NR	NR	NR	8.65	14.2	18	--	--	--	--	--	0.004	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/21/2019	SCT	Yes	80	71	NR	NR	NR	NR	8.15	15.0	21	--	--	--	--	--	0.005	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/24/2019	SCT	Yes	85	69	NR	NR	NR	NR	9.1	13.5	24	--	--	--	--	--	0.005	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/27/2019	SCT	Yes	85	68	NR	NR	NR	NR	8.25	14.8	27	--	--	--	--	--	0.007	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/30/2019	PCB	Yes	86	71	NR	NR	NR	NR	9	13.6	30	--	--	--	--	--	0.007	Yes	No	Change 3 bag filters, conducted system pressure checks.
1/31/2019	PCB	Yes	83	71	NR	NR	NR	NR	--	--	31	--	--	--	--	--	--	Yes	No	Change 3 bag filters, conducted system pressure checks.
Totals - January 2019										14.5	31						0.008			
2/4/2019	RPT	Yes	--	--	NR	NR	NR	NR	--	--	--	--	--	--	--	--	--	--	No	Carbon Change out- filled vessels with water and let to sit for ~24 hours, changed 3 bag filters (5 um).
2/5/2019	RPT	No	52	35	NR	NR	NR	NR	7.33	16.7	4	--	--	222.7	--	--	0.002	Yes	No	System restarted after scheduled shutdown for carbon exchange. Changed bag filters and conducted system pressure checks.
2/11/2019	PCB	Yes	83	45	NR	NR	NR	NR	11.58	10.6	10	--	--	--	--	--	--	Yes	No	Changed 3 bag filters, conducted system pressure checks.
2/13/2019	ST	Yes	55	43	NR	NR	NR	NR	8.12	15.1	12	--	--	--	--	--	--	Yes	No	Changed 3 bag filters, conducted system checks.
2/15/2019	MDM	Yes	--	--	NR	NR	NR	NR	7.5	16.3	14	--	--	131.7	--	--	0.007	Yes	Yes	Sampled system and collected system pressure checks.
2/22/2019	ST	Yes	--	--	NR	NR	NR	NR	10.75	11.4	21	--	--	43.75	--	--	0.007	Yes	No	Changed 3 bag filters, repaired filter basket, adjusted and lowered the speed drive on the transfer/discharge pump.
2/25/2019	MDM	Yes	25	15	NR	NR	NR	NR	7.5	16.3	23	--	--	--	--	--	--	Yes	No	System shutdown at 09:33 for the replacement of the submersible pump at PRW-4 and restarted at 14:04.
Totals - February 2019										14.4	26		132.7				0.011	Yes	No	
3/1/2019	ST	Yes	43	40	NR	NR	NR	NR	7.55	16.2	1	--	--	76.6	--	--	0.001	Yes	No	Conducted system pressure checks.
3/3/2019	ST	Yes	45	40	NR	NR	NR	NR	--	--	3	--	--	--	--	--	--	Yes	No	Conducted system pressure checks, changed bag filters, installed/replaced filters baskets with new stainless steel filter baskets.
3/5/2019	PCB	Yes	46	40	NR	NR	NR	NR	--	--	5	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
3/7/2019	PCB/ST	Yes	50	40	NR	NR	NR	NR	8.16	15.0	7	--	--	--	--	--	0.004	Yes	No	Conducted system pressure checks and changed bag filters.
3/9/2019	ST	Yes	44	41	NR	NR	NR	NR	7.75	15.8	9	--	--	--	--	--	0.005	Yes	No	Changed bag filters.
3/11/2019	ST	Yes	58	50	NR	NR	NR	NR	7.92	15.5	11	--	--	68.1	--	--	0.006	Yes	Yes	Changed bag filters.
3/13/2019	ST	Yes	65	50	NR	NR	NR	NR	4.62	26.5	13	--	--	--	--	--	--	Yes	No	Noticed low speed on transfer pump, adjusted VFD to increase pump speed to 55 Hz. Changed 3 bag filters twice.
3/14/2019	ST	Yes	75	50	NR	NR	NR	NR	5.16	23.7	14	--	--	70.0	--	--	0.012	Yes	No	Conducted system pressure checks and collected samples from EQ tank for analysis at County lab for disposal criteria.
3/16/2019	PCB	No	62	60	NR	NR	NR	NR	--	--	15	--	--	--	--	--	--	Yes	No	Pump at PRW-4 shut off upon arrival to system, contact relay failure, possibly due to power surge from thunderstorm. Restarted system after contact relay was replaced.
3/22/2019	ST	Yes	28	20	NR	NR	NR	NR	2.38	51.5	21	--	--	51.5	--	--	0.038	Yes	No	Replaced VFD drive for effluent transfer pump inside system shed.
3/23/2019	ST	Yes	23	20	NR	NR	NR	NR	--	--	22	--	--	--	--	--	--	No	No	Changed bag filters before system shutdown. System shutdown due to slow flow rate from transfer pump as a result of accumulating iron sediments in EQ tank from slow influent flow rate as a result of a the failing PRW-4 well pump.
3/29/2019	RPT/ST	No	--	--	NR	NR	NR	NR	--	--	23	--	--	--	--	--	--	Yes	No	Removed/pumped out the contents of the influent equalization (EQ) tank, repaired the system's pump electrical components, adjusted VFD on transfer pump, installed unions on influent piping manifold, replaced bag filters at discharge into the EQ tank, and restarted the system at 1645.

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ⁷	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁸	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
4/1/2019	ST	Yes	--	--	40	28	40	39	2.25	54.4	1	--	--	--	--	--	0.002	Yes	No	Conducted system pressure checks and changed bag filters.
4/3/2019	ST	Yes	--	--	40	39	--	--	--	--	3	--	--	--	--	--	--	Yes	No	Conducted system pressure checks.
4/6/2019	ST	Yes	--	--	50	41	50	50	2.23	54.9	6	--	--	--	--	--	0.014	Yes	No	Conducted system pressure checks and changed bag filters.
4/9/2019	GWTT	Yes	--	--	40	50	--	--	1.6	76.6	9	--	18.85	--	--	--	0.029	Yes	Yes	Conducted system pressure checks, backwashed the primary carbon vessel for ~30 minutes; inspected the transfer pump and removed excess iron oxide sedimentation from the inlet piping.
4/10/2019	ST	Yes	--	--	50	15	23	25	--	--	10	--	--	--	--	--	--	Yes	No	Conducted system pressure checks and changed bag filters.
4/11/2019	ST	Yes	--	--	40	35	35	35	--	--	11	--	--	--	--	--	--	Yes	No	Conducted system pressure checks and changed bag filters.
4/12/2019	GWTT	Yes	--	--	50	40	44	46	3	40.8	12	--	--	--	--	--	0.020	Yes	No	Conducted system pressure checks and changed bag filters.
4/15/2019	GWTT	Yes	--	--	55	45	55	55	4.08	30.0	15	--	--	--	--	--	0.019	Yes	No	Conducted system pressure checks and changed bag filters.
4/19/2019	GWTT	Yes	--	--	58	55	35	40	2.5	49.0	19	--	--	--	--	--	0.039	Yes	No	Conducted system pressure checks and changed bag filters.
4/23/2019	GWTT	Yes	--	--	48	47	50	55	4.00	30.6	23	--	33.4	--	--	--	0.029	Yes	No	Conducted system pressure checks and changed bag filters.
4/26/2019	GWTT	Yes	--	--	58	50	55	60	--	--	26	--	20.3	--	--	--	--	Yes	No	Conducted system pressure checks and changed bag filters, conducted general housekeeping duties.
4/30/2019	GWTT	No	--	--	--	--	--	--	--	--	29	--	--	--	--	--	--	--	Yes	System off on arrival due to contact relay failure for transfer pump operation; system restarted at 16:29 after contact relay was replaced.
Totals - April 2019										48.1	29	24.2					0.058			
5/3/2019	GWTT	Yes	--	--	55	35	45	50	2.18	56.2	3	--	32.93	--	--	--	0.003	Yes	No	Conducted system pressure checks and changed bag filters.
5/7/2019	GWTT	Yes	--	--	58	38	50	55	2.05	59.8	7	--	31.57	--	--	--	0.007	Yes	No	Conducted system pressure checks and changed bag filters.
5/10/2019	GWTT	No	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	System down as a result of failed VFD for transfer pump operation, changed bag filters.
5/17/2019	GWTT	No	--	--	55	38	--	--	--	--	10	--	--	--	--	--	--	Yes	No	Installed new VFD drive, system shutdown due to power surge from thunderstorm. Electrician added 15 minute- electrical control delay at the control panel in the system shed: creating a 15 minute delay before the pump at PRW-4 powers on at the "high level" float switch.
5/21/2019	MDM	No	--	--	57	30	57	60	1.83	66.9	14	--	33.38	--	--	--	0.016	Yes	Yes	Power surge from rogue ground voltage at electrical easement "fried" the electrical delay at control panel in system shed. Electrician bypassed delay to allow system restart at 11:15. Electrician will change coil at PRW-4 panel to lower voltage at later date. Conducted system pressure checks and changed bag filters.
5/24/2019	GWTT	Yes	--	--	58	35	58	60	2.083	58.8	17	--	25.36	--	--	--	0.017	Yes	No	Conducted system pressure checks and changed bag filters. Bypass installed to allow 15 minute delay on PRW-4 submersible pump float switch.
5/28/2019	GWTT	Yes	--	--	56	46	55	60	2.65	46.2	21	--	52.10	--	--	--	0.016	Yes	No	Conducted system pressure checks and changed bag filters twice. Backwashed both carbon vessels.
5/31/2019	GWTT	Yes	--	--	58	35	55	60	2.17	56.5	24	--	36.90	--	--	--	0.022	Yes	No	Conducted system pressure checks and changed bag filters, 3" butterfly valve on INF of LGACS #2 replaced. Installed a 3 inch flow totalizer and meter on
Totals - May 2019										57.4	24	35.4					0.023			
6/4/2019	GWTT	Yes	--	--	57	48	57	62	2.46	49.8	4	--	20.2	--	--	--	0.010	Yes	No	Conducted system pressure checks and changed bag filter. Replaced in-kind flow meter previously installed on 5/31/19.
6/7/2019	GWTT	Yes	--	--	57	45	57	62	2.43	50.4	7	--	16.2	--	--	--	0.017	Yes	No	Conducted system pressure checks and changed bag filters.
6/11/2019	GWTT	Yes	--	--	76	78	70	82	2.53	48.4	11	--	17.3	--	--	--	0.026	Yes	No	Conducted system pressure checks and changed bag filters. System shutdown due to high pressure measurement on the LGAC vessels, (from iron fouling), carbon change to occur on 6/13/19.
6/13/2019	MDM	No	--	--	--	--	--	--	--	--	11	--	--	--	--	--	--	No	No	System off for carbon change out.
6/14/2019	GWTT	No	--	--	--	--	25	28	2.3	53.3	12	--	167.1	--	--	--	0.032	Yes	No	System restarted at 13:00; adjusted flow rate via VFD to 55 Hz. GWTT recorded Effluent flow rate from drop in site glass to be 44 seconds, immediately after adjusting the VFD.
6/18/2019	GWTT	Yes	--	--	25	10	11	15	2.23	54.9	16	--	56.2	--	--	--	0.043	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 55 GPM.
6/21/2019	GWTT	Yes	--	--	17	15	17	20	2.12	57.8	19	--	58.6	--	--	--	0.054	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 28 Hz.
6/25/2019	GWTT	Yes	--	--	20	18	20	25	2.3	53.3	23	--	59.0	--	--	--	0.060	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 28 to 35 Hz.
6/27/2019	MDM	Yes	--	--	33	21	--	--	3.2	38.3	25	--	17.5	--	--	--	0.047	Yes	Yes	Conducted system checks, system VFD at 35 Hz; pressure gauges at LGAC 2 are 0 psi.
6/28/2019	GWTT	Yes	--	--	33	22	30	35	2.4	51.0	26	--	60.9	--	--	--	0.065	Yes	No	Conducted system checks, changed bag filters, VFD at 35 Hz. Effluent flow rate increased after bag filter changeout.
Totals - June 2019										50.8	27	62.4					0.068			
7/2/2019	GWTT	Yes	--	--	32	20	30	32	2.52	48.6	2	NR	52.6	20575	--	--	0.005	Yes	No	Conducted system checks, changed bag filters.
7/5/2019	GWTT	Yes	--	--	25	23	30	35	2.53	48.4	5	NR	52.6	242970	222395	--	0.013	Yes	No	Conducted system checks, changed bag filters, VFD at 35 Hz. Effluent flow rate increased after bag filter changeout.
7/9/2019	GWTT	Yes	--	--	32	25	36	40	2.35	52.1	9	NR	58.6	311680	68710	--	0.026	Yes	No	Conducted system checks, changed bag filters, VFD at 35 Hz. Effluent flow rate increased after bag filter changeout. Primary LGAC vessel requires a
7/12/2019	GWTT	Yes	--	--	39	35	39	43	2.42	50.6	12	NR	55.7	407920	96240	--	0.033	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 42 Hz.
7/15/2019	GWTT	Yes	--	--	46	40	35	50	3.00	40.8	15	NR	55.7	587740	179820	--	0.034	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 42 Hz to 40 Hz.
7/18/2019	GWTT	Yes	--	--	45	28	55	60	2.83	43.3	18	NR	47.48	NR	NR	--	0.043	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 40 Hz to 45 Hz.
7/23/2019	GWTT	Yes	--	--	56	43	55	61	3.22	38.0	23	NR	25.63	717580	129840	--	0.048	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 40 Hz to 45 Hz.
7/26/2019	GWTT	Yes	--	--	56	50	56	60	--	--	26	NR	11.93	722700	5120	--	--	Yes	No	Conducted system checks, changed bag filters.
7/29/2019	GWTT	Yes	--	--	--	--	56	60	2.50	49.0	29	NR	53.3	723360	660	--	0.078	Yes	Yes	Pumped out contents of exterior totes and conducted backwash of system (6,800 gallons removed by Global). Shutdown system for ~2 hours. VFD at 23 Hz on departure.
Totals - July 2019										46.9	31	45.1					0.079			
8/2/2019	GWTT	Yes	--	--	15	5	18	9	2.68	50.6	2	NR	19.68	723960	0	0.0	0.006	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 23 Hz to 28 Hz.
8/5/2019	GWTT	Yes	--	--	21	8	16	20	2.50	52.8	5	NR	49.00	726280	2320	0.5	0.014	Yes	No	Conducted system checks, changed bag filters, VFD at 28 Hz.
8/8/2019	GWTT	Yes	--	--	20	19	22	27	2.23	54.9	8	NR	53.50	729450	3170	0.7	0.024	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 32 Hz and 31 Hz. Visibility of site glass impaired due to iron fouling, possible obstruction in site glass causing error in flow calculations.
8/13/2019	GWTT	Yes	--	--	27	23	28	30	2.17	56.5	13	NR	56.45	738390	8940	1.2	0.040	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 23 Hz. Obstruction in site glass seems apparent, affecting flow rate calculations.
8/16/2019	GWTT	Yes	--	--	32	26	30	35	1.04	117.8	16	NR	34.83	744020	5630	1.3	0.103			Conducted system checks, changed bag filters, adjusted VFD from 23 Hz to 28 Hz.
8/20/2019	GWTT	Yes	--	--	40	27	36	38	NR	NR	20	NR	NR	757990	13970	2.4	--	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 38 Hz to 39 Hz. Could not calculate influent flow rate due to obstruction in site glass
8/23/2019	GWTT	Yes	--	--	41	29	38	44	--	--	23	NR	50.00	790720	32730	7.6	0.063	Yes	Yes	Conducted system checks, changed bag filters, and adjusted VFD from 39 Hz to 40 Hz. Collected montly system samples on 8/22/19.
8/27/2019	GWTT	Yes	--	--	45	35	44	49	--	--	27	NR	50.00	873750	83030	14.4	0.074	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 40 Hz to 42 Hz.
8/30/2019	GWTT	Yes	--	--	49	37	8	10	--	--	30	NR	49.00	976540	102790	23.8	0.081	Yes	No	Conducted system checks, changed bag filters after backwash of primary vessel.
Totals - August 2019										66.5	31	NR ¹¹					0.113			
9/3/2019	GWTT	Yes	--	--	18	7	10	14	NA	NA	3	--	NR	1044190	67650	15.7	0.001	Yes	No	Conducted system checks, changed bag filters, "High High Level" Alarm indicated, adjusted VFD, site glass plugged due to iron oxide sludge build up at bottom of EQ tank, could not collect influent flow rate.
9/6/2019	GWTT	Yes	--	--	27	14	22	25	NA	NA	6	--	NR	NR	NR	NR	--	Yes	No	Conducted system checks, changed bag filters, "High High Level" Alarm indicated, adjusted VFD to 35 Hz from 31 Hz.
9/10/2019	GWTT	Yes	--	--	35	18	30	35	NA	NA	10	--	NR	1203690	159500	27.7	0.008	Yes	No	
9/13/2019	GWTT	Yes	--	--	40	25	40	42	NA	NA	13	--	NR	1311290	107600	24.9	0.009	Yes	No	Conducted system checks, changed bag filters, observed approximately 20 in. of sludge in EQ Tank, and adjusted VFD to 40 Hz from 38 Hz.
9/16/2019	GWTT	Yes	--	--	45	26	44	48	NA	NA	16	--	NR	1413970	102680	23.8	0.011	Yes	No	Conducted system checks, changed bag filters, and adjusted VFD to 48 Hz.
9/20/2019	GWTT	Yes	--	--	68	35	12	14	NA	NA	20	--	NR	1543040	129070	22.4	0.013	Yes	No	Conducted system checks, changed bag filters, backwashed primary GAC vessel, and adjusted VFD to 29 Hz.
9/23/2019	GWTT	Yes	--	--	24	8	23	27	NA	NA	23	--	NR	1563850	20810	4.8	0.003	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 29 Hz to 34 Hz.
9/27/2019	GWTT	Yes	--	--	32	17	42	44	NA	NA	27	--	NR	1577890	14040	2.4	0.002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 34 Hz to 42 Hz, system samples collected on 9/26/19.
Totals - September 2019 ¹²										NA ⁷	30	NR ¹¹					0.015			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT Combined Instantaneous Estimated Influent Flow Rate (GPM) ²	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ³	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2				Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
10/1/2019	GWTT	Yes	--	--	50	28	18	19	NA	NA	1	--	NR	1620400	--	--	--	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 42 Hz to 31 Hz. Operator noticed a loud sound on discharge pipes at LGAC #1 as well as a pressure drop across the entire system, system was instantly turned off and restarted after the VFD was adjusted. Operator assumed an obstruction (i.e. iron oxide precipitates) was in LGAC#1 restricting flow and loud sound was the obstruction being dislodged.
10/3/2019	GWTT	Yes	--	--	--	--	--	--	NA	NA	3	--	NR	1639940	19540	6.8	0.0005	Yes	No	System was shut off at 8:00 during excavation of the effluent discharge piping. The discharge piping was repaired and the system was restarted at 16:00. The bag filters were changed.
10/7/2019	GWTT	Yes	--	--	27	14	22	20	NA	NA	6	--	NR	1645550	5610	1.3	0.0002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 31 Hz to 35 Hz.
10/11/2019	GWTT	Yes	--	--	32	30	19	20	NA	NA	10	--	NR	1683870	38320	6.7	0.0015	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 35 Hz to 32 Hz.
10/15/2019	GWTT	Yes	--	--	29	20	27	30	NA	NA	14	--	NR	1755270	71400	12.4	0.0040	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 32 Hz to 39 Hz.
10/18/2019	GWTT	Yes	--	--	38	22	30	35	NA	NA	18	--	NR	1867270	112000	19.4	0.0082	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 39 Hz to 35 Hz.
10/22/2019	GWTT	Yes	--	--	34	13	31	35	NA	NA	21	--	NR	1946590	79320	18.4	0.0090	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 35 Hz to 43 Hz.
10/25/2019	GWTT	Yes	--	--	44	34	35	42	NA	NA	24	--	NR	2043780	97190	22.5	0.0126	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 43 Hz to 40 Hz.
10/28/2019	GWTT	Yes	--	--	44	34	35	42	5.38	22.8	27	--	NR	2123880	80100	18.5	0.0117	Yes	No	Conducted system checks, changed bag filters, Global Cycle on site to vacuum pump out the contents from the EQ tank, bag filter unit, totes containing water from GAC vessel backwashes. The VFD was adjusted from 40 Hz to 24 Hz. Pressure gauge at P5 was replaced. System sampled on 10/30/19.
Totals - October 2019 ¹²										NA ⁷	30	NR ¹¹			503480	11.7	0.008			
11/1/2019	GWTT	Yes	--	--	15	2	19	19	5.00	24.5	1	NR	53.26	2128040	4160	2.9	--	Yes	No	Conducted system checks, changed bag filters, and adjusted the VFD frequency.
11/4/2019	GWTT	Yes	--	--	26	8	21	17	4.28	28.60	4	NR	45.37	2131870	3830	0.9	--	Yes	No	Conducted system checks, changed bag filters, and the VFD was adjusted from 30 Hz to 29 Hz.
11/7/2019	GWTT	Yes	--	--	25	10	30	27	3.70	33.1	7	NR	44.0	2042122	--	--	--	Yes	No	Conducted system checks, changed bag filters, exchanged 3" flow meter to 2" pulse turbine flow meter/totalizer. Adjusted the VFD from 29 Hz to 34 Hz on departure.
11/11/2019	GWTT	Yes	--	--	32	18	31	35	3.70	33.1	11	35	NR	2119390	77268	13.4	0.0037	Yes	Yes	Conducted system checks, changed bag filters, VFD left at 34 Hz. Force main Influent flow was split; temporary GWTPS expansion system started. System sampled on 11/12/19.
11/15/2019	GWTT	Yes	--	--	32	21	32	36	4.47	27.4	14	43	NR	2190828	71438	16.5	0.0058	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 34 Hz to 38 Hz on departure.
11/18/2019	GWTT	Yes	--	--	40	30	42	46	4.43	27.6	17	37	NR	2273202	82374	19.1	0.0081	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 38 Hz to 39 Hz upon departure.
11/22/2019	GWTT	Yes	--	--	42	27	41	45	3.50	35.0	21	33	NR	2391315	118113	20.5	0.0108	Yes	No	Conducted system checks, changed bag filters. VFD kept at 39 Hz. Cleared sludged out of bottom of sight glass on EQ tank.
11/25/2019	GWTT	Yes	--	--	43	32	43	46	3.90	31.4	24	42	NR	2486658	95343	22.1	0.0133	Yes	No	Conducted system checks, changed bag filters. VFD kept at 39 Hz.
11/29/2019	GWTT	Yes	--	--	45	32	44	48	4.10	29.9	28	39	NR	2601976	115318	20.0	0.0141	Yes	No	Conducted system checks, changed bag filters.
Totals - November 2019 ¹²										30.1	29	NR ¹¹			559854	21.6	0.016			
12/2/2019	BETA	Yes	--	--	--	--	--	--	--	--	2	--	--	2685088	83112	28.9	0.001	No	No	System shutdown at 10:00 for force main de-scale process.
12/4/2019	BETA	No	--	--	--	--	52	60	4.55	26.9	2	--	NR	2685088	0	0.0	0.000	Yes	No	Bag filters changed prior to system restart. System (PRW-4 and system) restarted at 12:12 following the force main de-scale and purging process. Collected post-bag filter checks after system restart.
12/6/2019	GWTT	Yes	--	--	55	25	52	58	2.17	62.0	4	50	NR	2735900	50812	17.6	0.001	Yes	No	Conducted system checks, flow into system #2 shutoff PRW-4 due to high level alarm. Changed the bag filters, and adjusted the VFD from 44 Hz to 46 Hz.
12/9/2019	GWTT	Yes	--	--	59	22	58	63	2.12	62.0	7	50	NR	2854135.0	118235	27.4	0.002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD to 48 Hz to increase the discharge/effluent flow rate. GWTT communicated that carbon vessels should be backwashed since the differential pressure between P3 and P4 is 50 psi.
12/13/2019	GWTT	Yes	--	--	64	66	45	71	1.95	62.8	11	--	48.0	3002260.0	148125	25.7	0.003	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 48 Hz to 49 Hz (49 GPM) at departure. GWTT noted the pressure on the carbon vessels was approaching their maximum limit.
12/16/2019	GWTT	Yes	--	--	66	70	56	74	2.02	60.6	14	--	40.0	3122091.0	119831	27.7	0.004	Yes	Yes	Conducted system pressure checks, changed bag filters, adjusted the VFD from 49 Hz to 50 Hz (45 GPM). GWTT noted the pressure on the carbon vessels was approaching their maximum limit. System sampled on 12/17/19.
12/20/2019	GWTT	Yes	--	--	45	63	41	67	NR	NR	18	--	16.00	3239075.0	116984	20.3	0.004	Yes	No	Conducted system pressure checks and changed bag filters and adjusted the VFD from 40 Hz to 47 Hz. Water waste from force main descale process removed from totes off-site by Global Cycle.
12/23/2019	GWTT	Yes	--	--	NR	NR	NR	NR	NR	NR	21	--	NR	--	--	--	--	No	No	System shutdown for carbon changeout at 08:00. Spent carbon removed from both vessels and replaced with new virgin carbon.
12/26/2019	GWTT	No	--	--	NR	11	NR	14	2.25	54.4	22	--	NR	3317372.0	78297	54.4	0.012	Yes	No	System restarted and requilibrated at 08:00 following carbon changeout and carbon hydration. Conducted system pressure checks, changed bag filters, adjusted the VFD to 23 Hz upon departure.
12/30/2019	GWTT	Yes	--	--	19	11	6	13	2.42	50.6	26	--	52.00	3460145.0	142773	24.8	0.006	Yes	No	Conducted system checks and changed bag filters, VFD at 26 Hz.
Totals - December 2019 ¹²										54.2	27	39.0			858169	22.1	0.006			
1/3/2020	GWTT	Yes	--	--	18	8	14	15	2.37	51.8	3	--	49.00	3588009.0	127864	29.6	0.001	Yes	No	Conducted system checks and changed bag filters, and adjusted VFD.
1/6/2020	GWTT	Yes	--	--	18	11	14	15	2.92	42.0	6	--	45.00	3692480.0	104471	24.2	0.002	Yes	No	Conducted system checks and changed bag filters, and adjusted VFD.
1/10/2020	GWTT	Yes	--	--	21	12	17	20	3.00	40.8	10	--	46.00	3809788.0	117308	20.4	0.003	Yes	No	Conducted system checks and changed bag filters, VFD at 27 Hz.
1/13/2020	GWTT	Yes	--	--	21	16	18	21	3.35	36.6	13	--	39.00	3899180.0	89392	20.7	0.004	Yes	No	Conducted system checks and changed bag filters.
1/17/2020	GWTT	Yes	--	--	25	20	23	26	3.62	33.9	17	--	24.00	3992818.0	93638	16.3	0.004	Yes	Yes	Conducted system checks and changed bag filters. Adjusted VFD to 33 Hz. Flushed iron sludge/sediment out of bottom of sight glass on EQ holding tank.
1/20/2020	GWTT	Yes	--	--	28	21	26	29	3.97	30.9	20	--	37.00	4065780.0	72962	16.9	0.005	Yes	No	Conducted system checks and changed bag filters.
1/24/2020	GWTT	Yes	--	--	29	22	27	30	5.13	23.9	24	--	34.00	4150180.0	84400	14.7	0.005	Yes	No	Conducted system checks and changed bag filters.
1/26/2020	GWTT	Yes	--	--	26	24	25	28	5.75	21.3	27	--	39.00	4205753.0	55573	12.9	0.005	Yes	No	Conducted system checks and changed bag filters.
1/31/2020	GWTT	Yes	--	--	28	23	26	30	6.80	18.0	31	--	36.00	4272375.0	66622	11.6	0.005	Yes	No	Conducted system checks, changed bag filters, cleaned sight glass on EQ tank; about 4-5 inches of sludge accumulated at bottom.
Totals - January 2020 ¹²										33.2	30.9	38.8			812230	18.3	0.009			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT	Days System Operating	EFFLUENT					Estimated Total PFAs Removal (kg) ⁷	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2		Combined Instantaneous Estimated Influent Flow Rate (GPM) ²		Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
2/4/2020	GWTT	Yes	--	--	28	22	26	30	8.00	15.3	4	--	36.00	4325997	120244	20.9	0.002	Yes	No	Conducted system checks and changed bag filters.
2/7/2020	GWTT	Yes	--	--	26	25	24	28	7.90	15.5	7	--	38.00	4360208	34211	7.9	0.001	Yes	No	Conducted system checks and changed bag filters.
2/11/2020	GWTT	Yes	--	--	26	25	26	30	11.07	11.1	11	--	43.00	4399300	39092	6.8	0.001	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel, adjusted transfer pump from 33 Hz to 23 Hz after backwash.
2/13/2020	GWTT	Yes	--	--	9	8	7	9	12.33	9.9	13	--	42.00	4418200	18900	6.6	0.002	Yes	Yes	Conducted system checks and changed bag filters. Adjusted transfer pump from 33 Hz to 23 Hz, recycled backwash water into GWTS #2 for treatment.
2/18/2020	GWTT	Yes	--	--	12	6	8	9	16.63	7.4	18	--	42.00	4454815	36615	5.1	0.002	Yes	No	Conducted system checks and changed bag filters.
2/21/2020	GWTT	Yes	--	--	10	8	9	11	22.67	5.4	21	--	40.00	4471238	16423	3.8	0.002	Yes	No	Conducted system checks and changed bag filters.
2/24/2020	GWTT	Yes	--	--	15	5	13	15	2.65	46.2	24	--	44.00	4490425	19187	4.4	0.002	Yes	No	Conducted system checks and changed bag filters. Bag filters packed with significant iron-oxide sediments, influent flow rate into EQ tank significantly increased; slug of iron-oxide must have broke through from accumulation in the force main. Adjusted VFD from 30 Hz to 35 Hz. Pressure readings at primary LGAC vessel indicating a need for a backwash.
2/26/2020	GWTT	Yes	--	--	25	10	20	24	2.60	47.1	26	--	37.00	4519500	29075	10.1	0.005	Yes	No	Conducted system checks and change bag filters. Increase discharge flow through VFD from 30 Hz to 35 Hz. Pressure readings at primary LGAC vessel indicating a need for a backwash.
2/28/2020	GWTT	Yes	--	--	29	10	13	15	2.55	48.0	28	--	52.00	4556491	36991	12.8	0.007	Yes	No	Conducted system checks and change bag filters. Conducted a backwash on primary LGAC vessel. Initial instantaneous Effluent flow rate was measured at 75 GPM after backwash. Adjusted VFD from 35 Hz to 26 Hz.
Totals - February 2020 ¹²										22.9	29	41.6		350738		8.4	0.004			
3/2/2020	GWTT	Yes	--	--	21	6	12	14	2.83	43.2	2	--	46.00	4645525	89034	20.6	0.001	Yes	Yes	Conducted system checks, changed bag filter, pumped water from large exterior tote through GWTS #2. System sampled on 3/3/2020
3/6/2020	GWTT	Yes	--	--	19	10	16	19	3.00	40.8	6	--	38.00	4723654	78129	13.6	0.002	Yes	No	Conducted system checks, changed bag filters, adjusted VFD from 26 Hz to 30 Hz.
3/9/2020	GWTT	Yes	--	--	25	18	11	15	3.00	40.8	9	--	51.00	4785425	61771	14.3	0.003	Yes	No	Conducted system checks, changed bag filters, at departure, instantaneous effluent flow rate at 51 gpm (30 Hz).
3/13/2020	GWTT	Yes	--	--	23	8	13	16	3.23	37.9	13	--	51.00	4898555	113130	19.6	0.005	Yes	No	Conducted system checks, changed bag filters.
3/16/2020	GWTT	Yes	--	--	23	9	14	17	3.75	32.7	16	--	50.00	4968818	70263	16.3	0.005	Yes	No	Conducted system checks, changed bag filters.
3/20/2020	GWTT	Yes	--	--	25	9	18	21	3.60	34.0	20	--	42.00	5052480	83662	14.5	0.006	Yes	No	Conducted system checks, changed bag filters, backwashed the primary LGAC vessel, adjusted the VFD from 30 Hz to 25 Hz. 42 GPM. Observed significant iron-oxide sedimentation accumulation in EQ tank.
3/23/2020	GWTT	Yes	--	--	17	9	15	17	3.00	40.8	23	--	48.00	5097785	45305	10.5	0.005	Yes	No	Conducted system checks; had to change the bag filters twice because the accumulated iron-oxide sediment in the EQ tank is getting pulled into the transfer pump affecting total gallons treated. Sight glass on EQ tank was flushed. Adjusted VFD from 25 Hz to 35 Hz.
3/26/2020	GWTT	Yes	--	--	34	17	27	29	3.00	40.8	26	--	48.00	5163530	65745	15.2	0.008	Yes	No	Conducted system checks, changed bag filters and increased the VFD from 35 Hz to 38 Hz.
3/30/2020	GWTT	Yes	--	--	38	14	34	38	3.27	37.5	30	--	42.00	5264195	100665	17.5	0.011	Yes	No	Conducted system checks, changed bag filters and increased the VFD from 38 Hz to 40 Hz.
Totals - March 2020 ¹²										38.7	31	46.2		707704		15.9	0.012			
4/2/2020	GWTT	Yes	--	--	34	30	31	35	2.95	41.5	2	--	51.00	5304740	40545	14.1	0.000	Yes	No	Conducted system checks and changed bag filters.
4/6/2020	GWTT	Yes	--	--	33	33	31	35	3.12	39.3	6	--	50.00	5354280	49540	8.6	0.001	Yes	No	Conducted system checks and changed bag filters. Transfer pump VFD at 40 Hz.
4/9/2020	GWTT	Yes	--	--	--	--	15	18	3.47	35.3	8.5	--	49.00	5413745	59465	16.5	0.002	Yes	No	System shutdown for 2-4 hours at 7am for vac out of EQ tank and backwash of primary carbon vessel. Global removed 2,989 gallons of iron-oxide water mixture from EQ tank and exterior totes. Conducted system checks and changed bag filters. Adjusted VFD from 40 Hz (74 gpm) to 28 Hz (49 gpm).
4/13/2020	GWTT	Yes	--	--	16	10	11	15	3.92	31.3	12.5	--	44.00	5497360	83615	14.5	0.002	Yes	No	Conducted system checks and changed bag filters
4/16/2020	GWTT	Yes	--	--	18	15	15	19	4.32	28.4	15.5	--	35.00	5552940	55580	12.9	0.003	Yes	No	Conducted system checks and changed bag filters
4/20/2020	GWTT	Yes	--	--	19	14	19	23	5.00	24.5	19.5	--	30.00	5620048	67108	11.7	0.003	Yes	No	Conducted system checks and changed bag filters, adjusted VFD from 28 Hz to 32 Hz to allow higher pressure/flow through bag filters to help with iron-oxide sediment fouling.
4/24/2020	GWTT	Yes	--	--	26	21	26	30	5.25	23.3	23.5	--	30.00	5679610	59562	10.3	0.003	Yes	No	Conducted system checks and changed bag filters, adjusted the VFD from 32 Hz to 35 Hz.
4/27/2020	GWTT	Yes	--	--	30	28	30	34	6.37	19.2	26.5	--	28.00	5723132	43522	10.1	0.003	Yes	Yes	Conducted system checks and changed bag filters. System sampled on 4/28/2020.
Totals - April 2020 ¹²										30.4	29.5	39.6		458937		10.8	0.004			
5/1/2020	GWTT	Yes	--	--	31	26	31	35	3.75	32.7	1	--	26.00	5756710	33578	23.3	0.0003	Yes	No	Conducted system checks and changed bag filters.
5/5/2020	GWTT	Yes	--	--	31	20	30	35	3.40	36.0	5	--	26.00	5772378	15668	2.7	0.0002	Yes	No	Conducted system checks and changed bag filters.
5/8/2020	GWTT	Yes	--	--	33	24	14	15	3.38	36.2	8	--	48.00	5843400	71022	16.4	0.0015	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel, adjusted transfer pump from 35 Hz to 30 Hz after backwash.
5/11/2020	GWTT	Yes	--	--	24	11	17	20	3.72	33.0	11	--	47.00	5922710	79310	18.4	0.0024	Yes	No	Conducted system checks and changed bag filters.
5/15/2020	GWTT	Yes	--	--	27	16	24	28	4.80	25.5	15	--	35.00	6012638	89928	15.6	0.0027	Yes	No	Conducted system checks and changed bag filters.
5/18/2020	GWTT	Yes	--	--	26	26	25	30	4.60	26.6	18	--	35.00	6075320	62682	14.5	0.0031	Yes	No	Conducted system checks and changed bag filters. System sampled on 5/21/2020.
5/22/2020	GWTT	Yes	--	--	30	27	34	40	5.10	24.0	22	--	32.00	6154187	78867	13.7	0.0035	Yes	Yes	Conducted system checks and changed bag filters. Adjusted VFD from 35 Hz to 38 Hz.
5/26/2020	GWTT	Yes	--	--	35	34	34	40	4.15	29.5	26	--	32.00	6196369	42182	7.3	0.0022	Yes	No	Conducted system checks and changed bag filters.
5/29/2020	GWTT	Yes	--	--	32	36	32	38	4.15	29.5	29	--	35.00	6221412	25043	5.8	0.0020	Yes	No	Conducted system checks and changed bag filters.
Totals - May 2020 ¹²										30.3	31	35.1		498280		11.2	0.0041			
6/2/2020	GWTT	Yes	--	--	34	35	14	17	4.27	28.7	2	--	46.00	6230577	9165	3.2	0.000	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel; Transfer pump flow rate initially at 68 gpm after backwash. Adjusted VFD from 38 Hz to 30 Hz.
6/5/2020	GWTT	Yes	--	--	24	5	15	19	3.47	35.3	5	--	40.00	6273600	43023	10.0	0.000	Yes	No	Conducted system checks and changed bag filters.
6/9/2020	GWTT	Yes	--	--	24	10	19	24	3.85	31.8	9	--	40.00	6334345	60745	10.5	0.001	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD from 30 Hz to 35 Hz.
6/12/2020	GWTT	Yes	--	--	31	16	28	32	4.12	29.8	12	--	30.00	6404810	70465	16.3	0.002	Yes	No	Conducted system checks and changed bag filters..
6/16/2020	GWTT	Yes	--	--	32	24	30	35	4.67	26.3	16	--	47.00	6495449	90639	15.7	0.002	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 30 Hz and backwashed primary LGAC vessel.
6/19/2020	GWTT	Yes	--	--	22	8	14	18	5.00	24.5	19	--	43.00	6568815	73366	17.0	0.003	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 32 Hz.
6/22/2020	GWTT	Yes	--	--	24	14	19	24	5.72	21.4	22	--	36.00	6634380	65565	15.2	0.003	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 36 Hz.
6/25/2020	GWTT	Yes	--	--	24	19	22	25	5.63	21.7	25	--	40.00	6690810	56430	13.1	0.003	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 32 Hz. System samples collected on 6/24/2020.
6/29/2020	GWTT	Yes	--	--	27	18	13	15	5.15	23.8	29	--	43.00	6764833	74023	12.9	0.003	Yes	No	Conducted system checks and changed bag filters twice, backwashed primary LGAC vessel, and flushed iron oxide sediment from sight glass on EQ tank.
Totals - June 2020 ¹²										27.0	30	40.6		543421		12.6	0.0035			

Table 2A- Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - GWTS #1
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Influent Bag Filter Differential Pressure (psi) ⁶		Pre-Filter Changeout Differential Pressure (psi)		Post-Filter Changeout Differential Pressure (psi)		6" Influent Tank Fill Rate (min)	INFLUENT	Days System Operating	EFFLUENT					Estimated Total PFAS Removal (kg) ¹	System Operating on Departure	System Sampled	Comments
			Pre	Post	Gauge: P1	Gauge: P2	Gauge: P1	Gauge: P2		Combined Instantaneous Estimated Influent Flow Rate (GPM) ²		Instant. Effluent Flow Rate (GPM) ⁸	Instantaneous Effluent Flow Rate (GPM) ^{2,9}	Totalizer (Gal)	Total Gallons Treated	Average Effluent Flow Rate (GPM) ¹⁰				
7/2/2020	GWTT	Yes	--	--	25	13	20	25	4.60	26.6	2	--	39.00	6837610	72777	25.3	0.001	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD from 32 Hz to 34 Hz.
7/6/2020	GWTT	Yes	--	--	36	19	36	24	4.97	24.7	6	--	36.00	6913169	75559	13.1	0.001	Yes	No	Conducted system checks and changed bag filters, flushed out sight glass on the EQ tank. Adjusted VFD to 34 Hz.
7/10/2020	GWTT	Yes	--	--	24	24	22	28	4.97	24.7	10	--	39.00	6948605	35436	6.2	0.001	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 36Hz.
7/13/2020	GWTT	Yes	--	--	28	26	26	32	5.28	23.2	13	--	42.00	6996929	48324	11.2	0.002	Yes	No	Conducted system checks and changed bag filters. Adjusted VFD to 38Hz.
7/16/2020	GWTT	Yes	--	--	32	33	11	15	6.03	20.3	16	--	44.00	7040815	43886	10.2	0.002	Yes	No	Conducted system checks and changed bag filters and adjusted VFD to 29 Hz. Conducted a backwash of primary LGAC vessel after initial readings. Reduced the transfer pump speed to reduce carry over of the Iron-oxide sedimentation from the EQ tank into the bag filters and LGAC vessels.
7/20/2020	GWTT	Yes	--	--	13	11	9	13	6.57	18.7	20	--	41.00	7091010	50195	8.7	0.002	Yes	No	Conducted system checks and changed bag filters filters and LGAC vessels.
7/24/2020	GWTT	Yes	--	--	15	12	11	16	7.20	17.0	24	--	39.00	7129271	38261	6.6	0.002	Yes	No	Conducted system checks and changed bag filters, VFD at 29 Hz.
7/27/2020	GWTT	Yes	--	--	18	8	11	15	7.50	16.3	27	--	40.00	7140929	11658	2.7	0.001	Yes	Yes	Conducted system checks and changed bag filters. System sampled on 7/28/2020.
7/30/2020	GWTT	Yes	--	--	12	14	11	15	6.80	18.0	30	--	40.00	7161465	20536	4.8	0.002	Yes	No	Conducted system checks and changed bag filters.
Totals - July 2020 ¹²										21.1	31		40.0		396632	8.9	0.0031			

Notes:

1. CE - Coastal Engineering. GWTT - Groundwater Treatment Technologies

2. Prior to November 2019, the instantaneous Influent (INF) and effluent (EFF) flow rates are calculated based on the cross-sectional volume per vertical foot of the influent tank and the measured/timed filling (INF) rate or draining (EFF) of the tank. The diameter of the influent tank is approximately 78 inches. The cross-sectional volume of the tank is approximately 33.1 cubic feet per vertical linear foot. Therefore the flow rate calculation factor is approximately 122.5 gallons per 6 inches. Since 11/7/2019 (following the replacement of the effluent totalizer, ONLY INF flow rates (from PRW-4) are calculated based on an approximation. This Combined Influent flow rate represents the combined flow within both force main pipes from recovery well PRW-4.

3. Prior to November 2019 the total mass of PFAS removed is calculated based on the calcuated influent flow rate, the number of days the system has been operating, and the average total Influent PFAs concentration for the month. Since November 2019, the total mass of PFAS removed is calculated based on the effluent flow rate.

4. NA or -- Not Applicable.

5. NR - Not Reported

6. As of April 1, 2019: the system's O&M data reporting was changed to include the differential pressure readings from the bag filter unit's pressure gauges before and after the bag filters are changed/replaced, if applicable.

7. Prior to November 2019, the average influent flow rate could not reliably be calculated/measured from September to (most of) October due to a blockage in the site glass on the EQ tank from accumulated iron-oxide precipitates in the bottom of the tank. The iron-oxide precipitates were removed from the EQ tank on Oct. 28, 2019.

8. Following the separation of the two force mains and the installation of GWTPS #2 on November 7, 2019, Instantaneous influent flow rates are estimated by approximating 50% of the Combined Instantaneou Influent flow rate values.

9. Instantaneous Effluent Flow Rate is recorded as the instantaneous flow rate as calculated or indicated from the totalizer flow meter on the system's effluent discharge piping - reading is collected after bag filter change and/or backwashing.

10. The Average effluent flow rate is calculated from the net gallons (Total Gallons Treated) obtained from the system's effluent totalizer flow meter and days that the system was in operation.

11. Prior to Nov. 7, 2019, calculated average effluent flow rates and the estimated PFAS removed total were calculated based on the reported totalizer readings. The totalizer flow meter readings on the effluent discharge piping were not reliable at flow rates less than 40 GPM. Therefore the data are shaded to indicate that they are approximations only and for this reason the July through October data are also considered approximates.

12. As of September 2019, the "Totals" shown (from left to right) include the Average Instantaneous Influent Flow Rate, Total Days of System Operation, Average Instantaneous Effluent Flow Rate, Total Gallons Treated, Average Net Effluent Flow Rate, and Estimated PFAS Removed for the respective monthly reporting period. Running average values shown for the effluent flow rate. Prior to November 7, 2019, totals shown (from left to right) included the Average Instantaneous Influent Flow Rate, Total Days of Operation, Average Instantaneous Effluent Flow Rate, and Estimated PFAS Removed for the respective monthly reporting period.

Table 2B - Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - System No. 2 (GWTS #2)
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Days System Operating	Transfer Pump Pres. (psi)	Pre-Filter Changeout Differential Pressure (psi) ²		Post-Filter Changeout Differential Pressure (psi)		Carbon Vessels. Pre-change out (psi)		Carbon Vessels. Post-change out (psi)		Instantaneous Estimated INFLUENT ⁷	EFFLUENT				Estimated Total PFAs Removal (kg)	System Operating on Departure	System Sampled	Comments
				Gauge: P1	Gauge: P2	Gauge: P3	Gauge: P2	Gauge: P3	Gauge: P4	Gauge: P5	Gauge: P4	Gauge: P5	Flow Rate (GPM) ^{3,4}	Totalizer (Gal)	Instant Flow Rate (GPM) ⁸	Total Net Gallons Treated ⁴	Average Effluent Flow Rate (GPM) ⁵				
11/11/2019	GWTT	Yes	1	38	0	0	0	0	<2	0	2	2	12.56	416900	32.00	0.0	--	0.00032	Yes	No	Influent flow stream from PRW-4 split and started system #2. Conducted system checks, changed bag filters after initial flush.
11/15/2019	GWTT	Yes	4	40	24	2	5	2	2	2	2	2	34.00	451645	34.00	34745.0	8.043	0.0008	Yes	Yes	Conducted system pressure checks and changed the bag filters. System shutdown temporarily to calculate influent flow rate at GWTPS #1. Collected system startup samples on 11/12/19 and 11/15/19.
11/18/2019	GWTT	Yes	7	--	32	2	6	6	2	2	4	4	44.00	491280	33.00	39635.0	9.175	0.0016	Yes	No	Conducted system pressure checks and changed the bag filters. System shutdown temporarily to calculate influent flow rate at GWTPS #1.
11/22/2019	GWTT	Yes	11	40	31	4	7	7	4	4	6	5	12.50	549022	34.00	57742.0	10.025	0.0028	Yes	No	Conducted system pressure checks and changed the bag filters. System shutdown temporarily to calculate influent flow rate at GWTPS #1.Colleected system startup samples on 11/19/19.
11/25/2019	GWTT	Yes	14	40	15	6	7	7	4	5	5	6	12.50	594623	33.00	45601.0	10.556	0.0037	Yes	No	Conducted system pressure checks and changed the bag filters.
11/29/2019	GWTT	Yes	18	40	18	6	8	8	3	3	4	4	NR	649150	34.00	54527.0	9.466	0.0043	Yes	No	Conducted system pressure checks and changed the bag filters.
Totals - November 2019 ⁶				19									23.11		33	232250	8.49	0.0040			
12/2/2019	BETA	Yes	2		--	--	--	--	--	--	--	--	--	686500	--	37350.0	13.0	--	No	Yes	System shutdown at 10:00 for force main de-scale process: system locked out and tagged out.
12/4/2019	BETA	No	2	40	--	--	7	7	--	--	4	4	22.70	686700	30.00	200.0	0.069	0.00000	Yes	No	System restarted at 12:12 upon finishing the de-scale purging process and restarted PRW-4.
12/6/2019	GWTT	No	4	35	--	--	14	13	--	--	10	8	25.0	707866	47.00	21166.0	7.349	0.00029	Yes	No	System off upon arrival and bag filters were completed clogged with iron sediments. Bag filters had to be changed after 20 minutes of operation, GWTT observed a high amount of solids floating in the EQ tank and pumped down the EQ tank and observed significant iron sediment sludge on the bottom of the tank. GWTT notified BETA that they would raise the floats in EQ tank to help lessen the agitation of the sludge and carryover into the bag filters. System was on high level alarm and continued to shutdown of PRW-4, which shut off system #1 due to significant iron oxide sediment accumulation in EQ tank.
12/9/2019	GWTT	Yes	7	37	39	8	16	16	7	5	14	8	25.0	813065	46.00	105199.0	24.4	0.00171	Yes	No	Conducted system checks, changed bag filters. Raising floats in EQ tank has not affected the iron sediment at the bottom.
12/13/2019	GWTT	Yes	11	38	43	11	21	20	10	5	18	7	25.0	943807	42.00	130742.0	22.7	0.00250	Yes	No	Conducted system checks, changed bag filters.
12/16/2019	GWTT	Yes	14	45	43	13	23	22	10	3	21	5	25.0	1049390	41.00	105583.0	24.4	0.00343	Yes	No	Conducted system checks, changed bag filters. EQ tank "High Level" alarm triggered.
12/20/2019	GWTT	Yes	18	42	33	14	20	20	10	4	18	6.00	25.0	1148998	43.00	99608.0	17.3	0.00312	Yes	No	Conducted system checks and changed the bag filters. System shutdown temporarily for pump out of iron oxide sediment accumulation in EQ tank.
12/23/2019	GWTT	Yes	21	--	--	--	--	--	--	--	--	--	--	1209649	NR	60651.0	14.0	0.00296	Yes	No	System shutdown at 08:00 for carbon changeout conducted on System #1.
12/26/2019	GWTT	Yes	22	38	30	15	19	19	14	6	18	7	24.2	1209820	42.00	171.0	0.1	0.00003	Yes	No	System restarted at 09:30 AM following carbon changeout conducted on System #1. Conducted system checks and changed bag filters.
12/30/2019	GWTT	Yes	26	38	38	13	22	22	12	5	20	7	24.00	1320824	40.00	111004.0	19.3	0.00503	Yes	No	Conducted system pressure checks and changed the bag filters. Reset pump control floats in EQ tank back to original depths (following the removal of iron sediments at bottom of the tank).
Totals - December 2019 ⁶				27									24.49		41	671674	17.3	0.005			
1/3/2020	GWTT	Yes	3	43	35	13	20	20	10	4	18	6	--	1422315	42.00	101491.0	23.5	0.00101	Yes	No	Conducted system checks, changed bag filters.
1/6/2020	GWTT	Yes	6	40	27	15	19	19	11	5	16	8	20.98	1507290	43.00	84975.0	19.7	0.00169	Yes	No	Conducted system checks, changed bag filters.
1/10/2020	GWTT	Yes	10	38	29	15	19	19	13	5	17	6	20.42	1602935	43.00	95645.0	16.6	0.00237	Yes	No	Conducted system checks, changed bag filters.
1/13/2020	GWTT	Yes	13	38	26	16	19	19	18	6	6	8	18.28	1674840	41.00	71905.0	16.6	0.00309	Yes	No	Conducted system checks, changed bag filters.
1/17/2020	GWTT	Yes	17	--	28	16	20	20	15	6	18	7	16.94	1750933	41.00	76093.0	13.2	0.00321	Yes	No	Conducted system checks, changed bag filters.
1/20/2020	GWTT	Yes	20	38	25	16	11	11	15	6	18	7	15.44	1808630	48.00	57697.0	13.4	0.00382	Yes	No	Conducted system checks, changed bag filters. Backwashed primary LGAC vessel.
1/24/2020	GWTT	Yes	24	35	19	9	11.5	11.5	6	7	8	8	11.93	1872940	48.00	64310.0	11.2	0.00383	Yes	No	Conducted system checks, changed bag filters.
1/27/2020	GWTT	Yes	27	35	16	10	12	11	7	7	9	8.00	10.65	1915785	46.00	42845.0	9.9	0.00383	Yes	No	Conducted system checks, changed bag filters, pumped backwash water through system's influent stream.
1/31/2020	GWTT	Yes	31	36	18	10	12	12	9	8	8	7	9.01	1962050	--	46265.0	8.0	0.00356	Yes	No	Conducted system checks, changed bag filters.
Totals - January 2020 ⁶				31									15.46		44	641226	14.4	0.004			
2/4/2020	GWTT	Yes	4	2	18	10	12	12	9	8	8	7	7.66	2000333	46.00	38283	6.6	0.00053	Yes	No	Conducted system checks, changed bag filters.
2/7/2020	GWTT	Yes	7	36	14	11	12	11	8	7	8	6	7.75	2023878	46.00	23545	5.5	0.00076	Yes	No	Conducted system checks, changed bag filters.
2/11/2020	GWTT	Yes	11	35	14	12	13	13	9	8	10	8	5.53	2049888	47.00	26010	4.5	0.00099	Yes	No	Conducted system checks, changed bag filters.
2/13/2020	GWTT	Yes	13	36	13	12	14	13	10	8	10	8	4.97	2060169	46.00	10281	3.6	0.00093	Yes	Yes	Conducted system checks, changed bag filters. Pumped backwash water from GWTS #1 through system.
2/18/2020	GWTT	Yes	18	36	15	12	13	14	9	8	9	8	3.68	2081950	57.00	21781	3.0	0.00109	Yes	Yes	Conducted system checks, changed bag filters.
2/21/2020	GWTT	Yes	21	36	15	13	14	13	10	8	10	8	2.70	2094054	48.00	12104	2.8	0.00117	Yes	Yes	Conducted system checks, changed bag filters.
2/24/2020	GWTT	Yes	24	37	43	5	16	16	2	2	13	7	23.11	2108080	47.00	14026	3.2	0.00156	Yes	Yes	Conducted system checks, changed bag filters. Bag filters packed with significant iron-oxide sediments, influent flow rate into EQ tank significantly increased: slug of iron must have broke through. Had to change bag filters twice.
2/26/2020	GWTT	Yes	26	36	43	6	16	15	6	2	16	8	23.56	2134241	45.00	26161	9.1	0.00472	Yes	Yes	Conducted system checks and changed bag filters.
2/28/2020	GWTT	Yes	28	36	44	5	21	20	5	2	18	7	24.02	2168295	42.00	34054	11.8	0.00661	Yes	Yes	Conducted system checks, changed bag filters. Approximately 6 inch of iron-oxide sludge has accumulated on bottom of EQ tank: control float switches were raised to reduce disruption of settled sludge.
Totals - February 2020 ⁶				29									11.44		47	206245	4.9	0.003			
3/2/2020	GWTT	Yes	2	36	35	10	15	15	9	5	10	11	21.6	2249000	48.00	80705	18.7	0.00078	Yes	Yes	Conducted system checks, changed bag filters. Backwashed primary LGAC vessel, vaccumed the iron-oxide sludge out of the EQ tank, and into 55-gal drums on site; water from the drum can be decanted back through the system. System sampled on 3/3/2020.
3/6/2020	GWTT	Yes	6	37	25	10	16	15	8	8	12	10	20.4	2315739	47.00	66739	11.6	0.00145	Yes	No	Conducted system checks, changed bag filters. System shutdown temporarily to pump backwash water from exterior totes through system.
3/9/2020	GWTT	Yes	9	37	30	9	16	16	7	6.5	14	10	20.4	2366315	44.00	50576	11.7	0.00220	Yes	No	Conducted system checks, changed bag filters.
3/13/2020	GWTT	Yes	13	38	37	9	20	20	8	5	18	10	18.9	2476035	42.00	109720	19.0	0.00518	Yes	No	Conducted system checks, changed bag filters.
3/16/2020	GWTT	Yes	16	38	29	15	20	20	12	8	18	10	16.3	2544858	41.00	68823	15.9	0.00533	Yes	No	Conducted system checks, changed bag filters.
3/20/2020	GWTT	Yes	20	38	28	17	19	19	10	7	17	10	17.0	2615618	41.00	70760	12.3	0.00514	Yes	No	Conducted system checks, changed bag filters. Observed significant iron-oxide accumulation in EQ tank.
3/23/2020	GWTT	Yes	23	38	26	16	21	20	14	8.5	18	10	20.4	2636761	41.00	21143	4.9	0.00235	Yes	No	Conducted system checks, changed bag filters.
3/26/2020	GWTT	Yes	26	38	29	14	20	19	14	8.5	18	10	20.4	2663514	41.00	26753	6.2	0.00337	Yes	No	Conducted system checks, changed bag filters.
3/30/2020	GWTT	Yes	30	46	44	5	24	24	2	1	20	9	18.8	2721065	37.00	57551	10.0	0.00627	Yes	No	Conducted system checks, changed bag filters.
Totals - March 2020 ⁶				31									19.37		42	552770	12.4	0.00549			
4/2/2020	GWTT	Yes	2	42	42	13	24	23	10	3	21	5	20.8	2768543	27.00	47478	16.5	0.00041	Yes	No	Conducted system checks, changed bag filters, and slowed down the effluent discharge flow rate to reduce carry over of significant iron sludge into the bag filters.
4/6/2020	GWTT	Yes	6	42.5	42	12	27	27	10	3	25	6	19.7	2833368	25.00	64825	11.3	0.00085	Yes	No	Conducted system checks and changed bag filters.
4/9/2020	GWTT	Yes	8.5	39	--	--	9	8	7	6.5	7	6.5	17.7	2903750	39.00	70382	19.6	0.00209	Yes	No	System shutdown for 2-4 hours at 7am for vac out of EQ holding tank and backwash of primary carbon vessel. Conducted system checks and changed bag filters.
4/13/2020	GWTT	Yes	12.5	39	24.5	7	10	9	4	5	8	6.0	15.6	3004475	38.00	100725	17.5	0.00275	Yes	No	Conducted system checks and changed bag filters. Lowered transfer pump "off control" float in EQ holding tank to allow longer run time and less cycling.
4/16/2020	GWTT	Yes	15.5	40	20.8	8	11	10	7	6	8	6.0	14.2	3074510	36.00	70035	16.2	0.00316	Yes	No	Conducted system checks and changed bag filters, pumped backwash water from exterior totes into (system #2) holding tank.
4/20/2020	GWTT	Yes	19.5	40	25	8	11	10	6	5	9	6.0	12.3	3156813	37.00	82303	14.3	0.00350	Yes	No	Conducted system checks and changed bag filters. Lowered transfer pump "off control" float in EQ holding tank to allow longer run time and less cycling.
4/24/2020	GWTT	Yes	23.5	42	26	10	15	14	7	5	10	6.0	11.7	3225480	33.00	68667	11.9	0.00352	Yes	No	Conducted system checks and changed bag filters.
4/27/2020	GWTT	Yes	26.5	40	21	12	15	14	10	6	12	6.0	9.6	3271810	33.00	46330	10.7	0.00357	Yes	Yes	Conducted system checks and changed bag filters. Collected system samples on 4/28/2020.
Totals - April 2020 ⁶				29.5									15.2		34	550745	13.0	0.00481			

Table 2B - Summary of Groundwater Pump and Treatment System Operating and Maintenance Data - System No. 2 (GWTS #2)
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

Date	Operator ¹	System Operating on Arrival	Days System Operating	Transfer Pump Pres. (psi)	Pre-Filter Changeout Differential Pressure (psi) ²		Post-Filter Changeout Differential Pressure (psi)		Carbon Vessels. Pre-change out (psi)		Carbon Vessels. Post-change out (psi)		Instantaneous Estimated INFLUENT ⁷ Flow Rate (GPM) ^{3,4}	EFFLUENT				Estimated Total PFAs Removal (kg)	System Operating on Departure	System Sampled	Comments
				Gauge: P1	Gauge: P2	Gauge: P3	Gauge: P2	Gauge: P3	Gauge: P4	Gauge: P5	Gauge: P4	Gauge: P5		Totalizer (Gal)	Instant. Flow Rate (GPM) ⁸	Total Net Gallons Treated ⁴	Average Effluent Flow Rate (GPM) ⁵				
5/1/2020	GWTT	Yes	1	47	43	9	22	22	8	3	20	5.0	16.3	3320924	32.00	49114	8.5	0.00310	Yes	No	Conducted system checks and changed bag filters twice during visit, system on idle upon arrival due to high level.
5/5/2020	GWTT	Yes	5	42	42	12	26	26	10	3	23	5.0	18.0	3359082	25.00	38158	6.6	0.00241	Yes	No	Conducted system checks and changed bag filters twice: influent flow rate has spiked but has caused a large influx of iron sediments.
5/8/2020	GWTT	Yes	8	42	35	13	22	22	10	4	20	6.0	18.1	3426824	34.00	67742	15.7	0.00570	Yes	No	Conducted system checks and changed bag filters.
5/11/2020	GWTT	Yes	11	42	25	16	22	22	14	5	20	6.0	16.5	3485100	32.00	58276	13.5	0.00490	Yes	No	Conducted system checks and changed bag filters. Pumped down green exterior tote holding backwash water from system #1.
5/15/2020	GWTT	Yes	15	39	35	17	8.5	8	16	4	7	6.0	12.8	3562051	38.00	76951	13.4	0.00485	Yes	No	Conducted system checks and changed bag filters. Backwashed primary LGAC vessel.
5/18/2020	GWTT	Yes	18	39	16	8	9	9	6	6	7	6.0	13.3	3614934	39.00	52883	12.2	0.00445	Yes	Yes	Conducted system checks and changed bag filters. Pumped down green exterior tote holding backwash water from 5.15.20 through System #2. System sampled on 5/21/2020.
5/22/2020	GWTT	Yes	22	42	24	7	10	10	4	4	7	6.0	12.0	3682536	36.00	67602	11.7	0.00426	Yes	No	Conducted system checks and changed bag filters.
5/26/2020	GWTT	Yes	26	41	44	4	17	16	0	0	14	5.0	14.8	3735642	34.00	53106	9.2	0.00335	Yes	No	Conducted system checks and changed bag filters twice.
5/29/2020	GWTT	Yes	29	40	44	4	21	19	4	1	15	4.0	14.8	3785810	34.00	50168	11.6	0.00422	Yes	No	Conducted system checks and changed bag filters twice.
Totals - May 2020 ⁶				31									15.2		33.8	514000	11.5	0.00418			
6/2/2020	GWTT	Yes	2	43	42	8	23	23	8	3	21	5.0	14.4	3832928	32.00	47118	16.4	0.00471	Yes	No	Conducted system checks and changed bag filters, primary carbon vessel needs to be backwashed.
6/5/2020	GWTT	Yes	5	40	35	9	13	13	2	2	10	5.0	17.7	3887828	35.00	54900	12.7	0.00366	Yes	No	Conducted system checks and changed bag filters.
6/9/2020	GWTT	Yes	9	40	21	10	7.5	7	8	5	6	5.0	15.9	3922210	35.00	34382	6.0	0.00172	Yes	No	Conducted system checks and changed bag filters. Bakcwashed primary LGAC vessel, pumped down outside holding tank through system before backwashing carbon vessel.
6/12/2020	GWTT	Yes	12	40	21	10	7.5	7	8	5	6	5.0	14.9	3970210	35.00	48000	11.1	0.00320	Yes	No	Conducted system checks and changed bag filters.
6/16/2020	GWTT	Yes	16	41	23	8	10	10	6	5	8	6.0	13.1	4029179	36.00	58969	10.2	0.00295	Yes	No	Conducted system checks and changed bag filters. Pumped backwash water from exterior holding totes through system.
6/19/2020	GWTT	Yes	19	40	21	10	7.5	7	8	5	6	5.0	12.3	4069514	38.00	40335	9.3	0.00269	Yes	No	Conducted system checks and changed bag filters.
6/22/2020	GWTT	Yes	22	41	14	10	11	11	9	5	9	5.0	10.7	4102439	37.00	32925	7.6	0.00219	Yes	No	Conducted system checks and changed bag filters.
6/25/2020	GWTT	Yes	25	42	16	12	10	10	8	4	5	5.0	10.9	4128010	35.00	25571	5.9	0.00170	Yes	No	Conducted system checks and changed bag filters.
6/29/2020	GWTT	Yes	29	41	16	9	10	10	8	5	9	5.0	11.9	4154842	35.00	26832	4.7	0.00134	Yes	No	Conducted system checks and changed bag filters.
Totals - June 2020 ⁶				30									13.5		35.3	369032	8.5	0.00238			
7/2/2020	GWTT	Yes	2	42	43	4	12	11	0	0	10	5.0	13.3	4173048	34.00	18206	6.3	0.00219	Yes	No	Conducted system checks and changed bag filters.
7/6/2020	GWTT	Yes	6	42	37	8	16.5	16	7	3	14	5.0	12.3	4243300	34.00	70252	12.2	0.00423	Yes	No	Conducted system checks and changed bag filters.
7/9/2020	GWTT	Yes	9	43	42	8	23	23	8	3	21	5.0	12.3	4279505	31.00	36205	8.4	0.00291	Yes	No	Conducted system checks and changed bag filters.
7/12/2020	GWTT	Yes	12	47	47	18	18	18	7	3	16	5.0	11.6	4329440	32.00	49935	11.6	0.00401	Yes	No	Conducted system checks and changed bag filters.
7/16/2020	GWTT	Yes	16	42	25	13	16.5	16	12	5	14	7.0	10.2	4374349	33.00	44909	7.8	0.00271	Yes	No	Conducted system checks and changed bag filters.
7/20/2020	GWTT	Yes	20	40	34	12	7.5	7	10	3	6	5.0	9.3	4435010	40.00	60661	10.5	0.00365	Yes	No	Conducted system checks and changed bag filters. Pumped backwash water from System #1 through system and then backwashed primary LGAC vessel.
7/24/2020	GWTT	Yes	24	40	37	4	9.5	9	2	2	8	6.0	8.5	4493135	40.00	58125	10.1	0.00350	Yes	No	Changed bag filters and pumped excess backwash water through system.
7/27/2020	GWTT	Yes	27	41	43	6	13	12	2	0	10	5.0	8.2	4521639	38.00	28504	6.6	0.00229	Yes	No	Conducted system checks and changed bag filters twice due to iron-oxide accumulation in the EQ tank.
7/30/2020	GWTT	Yes	30	41	32	7	14	13	6	3	10	5.0	9.0	4585515	37.00	63876	14.8	0.00513	Yes	No	Conducted system checks: the system is receiving more water (influent) that GWTS#1, operator assumes it's related to the build up of iron in the force main piping.
Totals - July 2020 ⁶				31									10.5		35.4	430673	9.6	0.00335			

Notes:
1. GWTT - Groundwater Treatment Technologies
2. Pressure readings before filter bag changeout or if no changeout was done.
3. Influent flow is an instantaneous estimate of the flow rate from the submersible Well Pump at PRW-4.
4. During monthly reporting periods the net gallons are calculated from previous effluent totalizer readings. (Difference between the current totalizer reading - the last dated totalizer reading).
5. The Average effluent flow rate is calculated from the net gallons obtained from the system's effluent totalizer flow meter and days that the system was in operation.
6. The "Totals" shown (from left to right) include the, Total Days of System Operation, Average Instantaneous Influent Flow Rate, Average Instantaneous Effluent Flow Rate, Total Gallons Treated, Average Net Effluent Flow Rate, and Estimated PFAS Removed for the respective monthly reporting period.
7. Instantaneous influent flow rates are estimated by approximating 50% of the influent flow rate values calculated from GWPTS #1 (See Table 2A).
8. Instantaneous effluent flow rate estimated by stopwatch at totalizer meter.
9. Flow calculated based on gallons marking on EQ tank. Estimated flow rate = 25 GPM (i.e. flow is calculated based on an in-situ observation of flow into the EQ tank, and 100 gallons of groundwater flows into the EQ tank for a 4 minute duration.

Table 4 - Summary of Groundwater PFAS Analytical Data
Barnstable County Fire and Rescue Training Academy
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	HSW-6/HS-2(a)											HSW-1/HS-1(a)											
SAMPLING DATE			1/21/2016	3/30/2016	8/11/2016	4/10/2017	7/27/2017	11/17/2017	2/9/2018	6/26/2018	1/9/2019	10/28/2019	7/28/2020	1/21/2016	8/11/2016	4/10/2017	7/27/2017	11/17/2017	2/9/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	
PFAS (Method 537.2)																									
PFOS	70	20	77,000	320,000	41,000	28,000	21,000	45,000	25,000	950	1,300	3,600	2,300	110,000	56,000	38,000	24,000	25,000	13,000	1,800	2,000	1,100	1,800	740	1,300
PFOA	70	20	--	--	--	660	--	320	160	15	94	79	80	--	--	1,000	350	1,300	320	840	100	64	46	36	100
PFNA	NE	20	--	--	--	--	--	--	--	BRL (<87)	26	46	40	--	--	--	--	--	--	43	65	43	33	22	57
PFHxS	NE	20	--	--	--	--	--	--	--	26	140	310	350	--	--	--	--	--	--	1,700	300	170	150	66	300
PFHpA	NE	20	--	--	--	--	--	--	--	15	66	100	69	--	--	--	--	--	--	510	67	52	43	32	63
PFDA	NE	20	--	--	--	--	--	--	--	--	--	30	18	--	--	--	--	--	--	--	55	19	13	9	37
TOTAL Σ6 PFAS	70	20	77,000	320,000	41,000	28,660	21,000	45,320	25,160	1,006	1,626	1,626	2,857	110,000	56,000	39,000	24,350	26,300	13,320	4,893	2,587	1,448	2,085	905	1,857

Notes:

- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
- The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
- (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
- BRL - Below Laboratory Detection Limits
- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
- PFOS - Perfluorooctanesulfonate
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- NA - Concentration data not available
- Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
- Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
- NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	HS-1 ¹⁵		HS-6 ¹⁵	HS-2 ¹⁵	HS-2S ¹⁵		PFW-1														
SAMPLING DATE			8/11/2016	12/8/2016	8/11/2016	7/27/2017	8/18/2016	5/3/2017	4/1/2015	10/7/2015	3/8/2016	3/30/2016	8/11/2016	4/10/2017	2/9/2018	6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020	7/28/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS	70	20	56,000	36,000	41,000	21,000	300	150	8,400	60,000	7,000	56,000	3,500	4,100	8,100	76,000	38,000	20,000	24,000	16,000	22,000	6,000	5,200
PFOA	70	20	460	1,800	450	370	BRL (<5.3)	8	360	800	--	--	--	--	470	1,500	160	300	560	130	220	250	210
PFNA	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	3,900	330	360	210	570	230	94	110
PFHxS	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	7,400	960	1,500	4,800	910	1,000	890	820
PFHpA	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	610	140	290	500	150	200	220	160
PFDA	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	110	160	120	200	81	89
TOTAL Σ6 PFAS	70	20	56,460	37,800	41,450	21,370	300	158	8,760	60,800	7,000	56000	3500	4,100	8,570	89,410	39,590	22,560	30,230	17,880	23,850	7,535	6,589

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
5. BRL - Below Laboratory Detection Limits
6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion
7. Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
8. PFOS - Perfluorooctanesulfonate
9. PFOA - Perfluorooctanoic Acid
10. PFNA - Perfluorononanoic Acid
11. PFHxS - Perfluorohexanesulfonic Acid
12. PFHpA - Perfluoroheptanoic Acid
13. PFDA - Perfluorodecanoic Acid
14. NA - Concentration data not available
15. Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
17. NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PFW-2														PFW-3			PFW-4
SAMPLING DATE			4/1/2015	6/18/2015	10/27/2015	1/21/2016	3/30/2016	8/11/2016	12/8/2016	4/10/2017	7/27/2017	11/17/2017	2/9/2018	1/9/2019	10/28/2019	5/11/2020	4/1/2015	10/15/2015	4/18/2017	4/1/2015
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																				
PFOA	70	20	220,000	200,000	32,000	39,000	120,000	65,000	13,000	17,000	73,000	25,000	32,000	5,200	2,100	690	2,700	3,800	3,400	3,300
PFNA	70	20	5200	BRL (<800)	--	1,100	2,100	--	--	970	910	400	400	720	74	48	140	170	230	420
PFHxS	NE	20	--	--	--	--	--	--	--	--	--	--	--	110	64	39	--	--	--	--
PFHpA	NE	20	--	--	--	--	--	--	--	--	--	--	--	1,800	230	140	--	--	--	--
PFDA	NE	20	--	--	--	--	--	--	--	--	--	--	--	470	68	45	--	--	--	--
TOTAL Σ6 PFAS	70	20	225,200	200,000	32,000	40,100	122,100	65,000	13,000	17,970	73,910	25,400	32,400	8,300	2,563	976	2,840	3,970	3,630	3,720

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
 - NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy

Bamstable Country Fire and Rescue Training A

155 Flint Rock Road, Bamstable, MA

RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PFW-5									PFW-6				PRW-1	PRW-4 ³						
SAMPLING DATE			3/31/2015	4/11/2017	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020	7/28/2020	4/1/2015	3/8/2016	4/18/2016	1/9/2019	4/1/2015	4/1/2015	8/4/2015	11/12/2015	1/6/2016	4/28/2016	8/11/2016	11/16/2016
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS	70	20	2,700	2,100	1,100	1,900	1,600	2,400	1,000	1,200	980	3,400	2,400	850	1,500	1,600	760	5,900	9,000	7,600	6,300	9,500	5,400
PFOA	70	20	250	170	64	150	120	26	88	120	100	350	470	19	400	150	60	550	BRL (<2000)	260	BRL (<200)	210	99
PFNA	NE	20	--	--	BRL (<8.7)	25	16	BRL (<4.9)	11	22	15	--	--	--	140	--	--	--	--	--	--	--	--
PFHxS	NE	20	--	--	240	680	630	260	360	720	610	--	--	--	1,100	--	--	--	--	--	--	--	--
PFHpA	NE	20	--	--	30	82	54	22	56	66	44	--	--	--	220	--	--	--	--	--	--	--	--
PFDA	NE	20	--	--	--	12	11	BRL (<4.1)	10	13	11	--	--	--	--	--	--	--	--	--	--	--	--
TOTAL Σ6 PFAS	70	20	2,950	2,270	1,434	2,849	2,431	2,708	1,525	2,141	1,760	3,750	2,870	869	3,360	1,750	820	6,450	9,000	7,860	6,300	9,710	5,499

Notes:

- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
- The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
- (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
- BRL - Below Laboratory Detection Limits
- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
- PFOS - Perfluorooctanesulfonate
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- NA - Concentration data not available
- Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
- Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
- NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Bamstable Country Fire and Rescue Training A
155 Flint Rock Road, Bamstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PRW-4 ³							PC-0		PC-1													
SAMPLING DATE			1/4/2017	4/19/2017	8/28/2017	11/20/2017	2/14/2018	4/9/2018	6/14/2018	4/2/2015	4/24/2017	8/20/2014	6/17/2015	10/7/2015	3/30/2016	4/24/2017	2/6/2018	6/26/2018	1/11/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/28/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																									
PFOS	70	20	4,900	3,200	2,900	2,000	2,100	2,600	2,800	110	930	320	48,000	2,000	56,000	5,700	9,000	10,000	1,700	8,000	4,300	1,600	1,700	1,700	1,900
PFOA	70	20	95	110	100	64	27	79	120	BRL (<20)	58	--	1,100	BRL (<800)	1,200	--	370	190	140	300	150	72	180	110	63
PFNA	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	140	62	150	140	75	70	110	58
PFHxS	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	850	380	650	430	380	450	400	240
PFHpA	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	200	200	180	230	150	240	150	98
PFDA	NE	20	--	--	--	--	--	--	--										78	67	19	20	28	36	
TOTAL Σ6 PFAS	70	20	4,995	3,310	3,000	2,064	2,127	2,679	2,920	110	988	320	49,100	2,000	57,200	5,700	9,370	11,380	2,482	9,358	5,317	2,296	2,660	2,498	2,395

Notes:

- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
- The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
- (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
- BRL - Below Laboratory Detection Limits
- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
- PFOS - Perfluorooctanesulfonate
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- NA - Concentration data not available
- Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
- Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
- NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PC-2		PC-3		PC-4		PC-6A									PC-7					
SAMPLING DATE			6/17/2015	4/24/2017	8/20/2014	6/17/2015	6/17/2015	3/8/2016	3/9/2016	4/27/2017	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	4/2/2015	6/17/2015	10/7/2015	3/8/2016	4/27/2017
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS	70	20	3,800	2,200	3,100	4,700	2,200	4,600	1,300	3,200	1,300	1,800	1,900	940	1,100	1,600	86	1,300	17,000	500	700	1,700	2,900
PFOA	70	20	220	110	180	200	79	160	110	150	60	30	68	33	62	67	4	37	3,500	27	98	140	130
PFNA	NE	20	--	--	--	--	--	--	--	--	55	25	60	36	48	65	4	44	--	--	--	--	--
PFHxS	NE	20	--	--	--	--	--	--	--	--	300	190	310	150	290	180	23	99	--	--	--	--	--
PFHpA	NE	20	--	--	--	--	--	--	--	--	75	37	83	45	86	71	9	43	--	--	--	--	--
PFDA	NE	20											10	BRL (<4.1)	7.4	5.9	0.7	11					
TOTAL Σ6 PFAS	70	20	4,020	2,310	3,280	4,900	2,279	4,760	1,410	3,350	1,790	2,082	2,431	1,204	1,593	1,989	127	1,534	20,500	527	798	1,840	3,030

Notes:

- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
- The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
- (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
- BRL - Below Laboratory Detection Limits
- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
- PFOS - Perfluorooctanesulfonate
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- NA - Concentration data not available
- Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
- Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
- NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Bamstable Country Fire and Rescue Training A
155 Flint Rock Road, Bamstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PC-8					PC-9						PC-10		PC-11												
SAMPLING DATE			6/17/2015	10/7/2015	3/8/2016	4/24/2017	2/6/2018	4/1/2015	10/7/2015	3/9/2016	3/30/2016	4/28/2017	1/10/2019	10/30/2019	4/6/2015	4/28/2017	4/2/2015	5/12/2016	4/24/2017	2/6/2018	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																												
PFOS	70	20	15,000	500	1,600	36,000	1,000	580	510	5,300	8,100	280	1,700	2,300	790	560	4,400	32,000	3,600	4,000	9,600	14,000	200,000	68,000	22,000	18,000	12,000	9,500
PFOA	70	20	2,800	370	97	--	71	30	40	1,200	1,600	31	64	100	50	67	550	430	250	180	250	410	640	BRL (<240)	150	290	140	130
PFNA	NE	20	--	--	--	--	--	--	--	--	--	--	53	90	--	--	--	--	--	230	190	1,700	540	320	140	130	110	
PFHxS	NE	20	--	--	--	--	--	--	--	--	--	--	360	420	--	--	--	--	--	1,500	1,500	2,400	1,200	800	1,300	720	610	
PFHpA	NE	20	--	--	--	--	--	--	--	--	--	--	81	120	--	--	--	--	--	200	310	210	BRL (<210)	160	210	140	130	
PFDA	NE	20		--	--	--	--	--	--	--	--	--	--	15	--	--	--	--	--	--	--	--	450	BRL (<260)	73	69	56	55
TOTAL Σ6 PFAS	70	20	17800	870	1697	36000	1071	610	550	6500	9700	311	2258	3,030	840	627	4950	32430	3850	4180	11,780	16,410	204,950	69,740	23,503	20,009	13,186	10,535

Notes:

- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
- The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data. Data presented herein is summarized and data was selected based on quarterly sampling events.
- (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
- BRL - Below Laboratory Detection Limits
- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
- PFOS - Perfluorooctanesulfonate
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- NA - Concentration data not available
- Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
- Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
- NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} rearr Advisory	Method 1 GW-1 Standard ⁴	PC-12			PC-13		PC-14			PC-15			PC-16d										
SAMPLING DATE			6/17/2015	5/12/2016	4/26/2017	6/17/2015	4/24/2017	8/20/2014	3/30/2016	4/28/2017	4/2/2015	4/28/2017	10/30/2019	4/2/2015	10/7/2015	2/6/2018	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/28/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																								
PFOS	70	20	1,300	1,700	1,600	2,400	2,800	550	2,100	1,600	1,300	780	970	700	560	980	1,900	1,600	2,000	1,400	1,300	1,600	1,200	930
PFOA	70	20	140	150	150	280	170	40	250	160	100	80	55	70	84	64	150	9.3	140	33	75	130	57	99
PFNA	NE	20	--	--	--	--	--	--	--	--	--	--	52	--	--	--	100	BRL (<8.7)	110	36	79	110	63	49
PFHxS	NE	20	--	--	--	--	--	--	--	--	--	--	290	--	--	--	670	60	520	270	220	360	170	260
PFHpA	NE	20	--	--	--	--	--	--	--	--	--	--	77	--	--	--	170	13	140	74	80	92	61	68
PFDA	NE	20	--	--	--	--	--	--	--	--	--	--	4.9	--	--	--	--	--	9	BRL (<4.1)	7	7	9	11
TOTAL Σ6 PFAS	70	20	1440	1850	1750	2680	2,970	590	2,350	1,760	1,400	860	1,444	770	644	1044	2,990	1,682	2,919	1,813	1,761	2,299	1,560	1,417

Notes:

- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
- The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
- The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
- (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
- BRL - Below Laboratory Detection Limits
- Concentrations presented in ng/L - nanograms per Liter - parts per trillion
- Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
- PFOS - Perfluorooctanesulfonate
- PFOA - Perfluorooctanoic Acid
- PFNA - Perfluorononanoic Acid
- PFHxS - Perfluorohexanesulfonic Acid
- PFHpA - Perfluoroheptanoic Acid
- PFDA - Perfluorodecanoic Acid
- NA - Concentration data not available
- Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
- Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
- NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PC-17			PC-18						PC-19				PC-20D	PC-21D	PC-22	
SAMPLING DATE			8/20/2014	10/7/2015	2/6/2018	6/17/2015	10/7/2015	4/27/2017	2/6/2018	1/10/2019	10/29/2019	4/2/2015	3/30/2016	4/27/2017	10/30/2019	3/9/2016	3/9/2016	4/2/2015	4/28/2017
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																			
PFOS	70	20	140	230	140	1,200	900	580	890	1,500	1,500	3,300	1,600	2,000	1,900	3,200	230	1,200	1,400
PFOA	70	20	BRL	24	17	110	590	--	70	110	75	260	120	290	170	200	19	100	170
PFNA	NE	20	--	--	--	--	--	--	--	130	79	--	--	--	130	--	--	--	--
PFHxS	NE	20	--	--	--	--	--	--	--	540	220	--	--	--	450	--	--	--	--
PFHpA	NE	20	--	--	--	--	--	--	--	140	80	--	--	--	95	--	--	--	--
PFDA	NE	20	--	--	--	--	--	--	--	7.2		--	--	--	14	--	--	--	--
TOTAL Σ6 PFAS	70	20	140	254	157	1310	1490	580	960	2420	1,954	3560	1720	2290	2745	3,400	249	1300	1,570

- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
 - NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy

Barnstable County Fire and Rescue Training A

155 Flint Rock Road, Barnstable, MA

RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	PC-23D	PC-24		PC-25	PC-26				PC-28								
SAMPLING DATE			6/17/2015	3/30/2016	4/28/2017	6/17/2015	6/17/2015	10/8/2015	3/8/2016	4/24/2017	3/9/2016	4/28/2017	1/10/2019	4/24/2019	7/23/2019	10/28/2019	2/19/2020	5/12/2020	7/29/2020
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																			
PFOS	70	20	1,000	420	320	2,300	1,000	1,900	1,200	380	400	770	38	18	82	270	270	430	200
PFOA	70	20	73	22	33	260	210	190	98	21	27	61	BRL (<3.3)	BRL (<7.4)	190	12	BRL (<7.4)	18	12
PFNA	NE	20	--	--	--	--	--	--	--	--	--	--	BRL (<8.7)	BRL (<4.9)	BRL (<4.9)	9	BRL (<4.9)	15	10
PFHxS	NE	20	--	--	--	--	--	--	--	--	--	--	17	15	30	94	72	120	71
PFHpA	NE	20	--	--	--	--	--	--	--	--	--	--	20	24	25	33	23	41	30
PFDA	NE	20	--	--	--	--	--	--	--	--	--	--	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	2	BRL (<4.1)	
TOTAL Σ6 PFAS	70	20	1073	442	353	2,560	1,210	2,090	1,298	401	427	831	75	57	327	418	365	626	323

- Notes:
1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
 4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 5. BRL - Below Laboratory Detection Limits
 6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 7. Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
 8. PFOS - Perfluorooctanesulfonate
 9. PFOA - Perfluorooctanoic Acid
 10. PFNA - Perfluorononanoic Acid
 11. PFHxS - Perfluorohexanesulfonic Acid
 12. PFHpA - Perfluoroheptanoic Acid
 13. PFDA - Perfluorodecanoic Acid
 14. NA - Concentration data not available
 15. Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
 17. NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PC-29	PC-30											PC-31		PC-32		PC-33		PC-34S	PC-34D		
SAMPLING DATE			4/28/2017	3/9/2016	4/27/2017	2/6/2018	6/26/2018	1/10/2019	4/24/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	3/8/2016	4/27/2017	3/30/2016	4/27/2017	3/30/2016	4/27/2017	4/14/2016	4/14/2016	4/28/2017	
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	
PFAS (Method 537.2)																								
PFOS	70	20	1,400	980	2,500	1,900	1,600	2,200	1,200	4,300	960	1,200	880	1,100	1,200	12,000	1,200	960	2,700	2,100	1,300	1,400	1,500	
PFOA	70	20	BRL (<4.6)	88	--	98	99	85	85	79	55	130	45	38	110	160	130	54	250	210	72	150	130	
PFNA	NE	20	--	--	--	--	80	88	100	100	61	74	45	57	--	--	--	--	--	--	--	--	--	
PFHxS	NE	20	--	--	--	--	510	390	340	300	220	210	180	120	--	--	--	--	--	--	--	--	--	
PFHpA	NE	20	--	--	--	--	130	110	110	96	71	87	80	48	--	--	--	--	--	--	--	--	--	
PFDA	NE	20	--	--	--	--	--	--	12	BRL (<4.1)	6	6	8	7.7	--	--	--	--	--	--	--	--	--	
TOTAL Σ6 PFAS	70	20	1400	1068	2500	1998	2,419	2,873	1,847	4,875	1,373	1,707	1,238	1,371	1310	12160	1330	1014	2950	2310	1372	1550	1630	

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
5. BRL - Below Laboratory Detection Limits
6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion
7. Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
8. PFOS - Perfluorooctanesulfonate
9. PFOA - Perfluorooctanoic Acid
10. PFNA - Perfluorononanoic Acid
11. PFHxS - Perfluorohexanesulfonic Acid
12. PFHpA - Perfluoroheptanoic Acid
13. PFDA - Perfluorodecanoic Acid
14. NA - Concentration data not available
15. Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
17. NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	PC-35S	PC-35D		PC-36S			PC-36D		PC-37	PC-38				PC-39		MW-1			MW-3S	
SAMPLING DATE			4/14/2016	4/14/2016	4/28/2017	4/14/2016	1/11/2019	10/29/2019	4/14/2016	4/24/2017	4/10/2017	4/24/2017	10/29/2019	5/12/2020	7/28/2020	4/24/2017	2/19/2020	11/22/2013	6/3/2014	4/28/2017	6/3/2014	8/18/2016
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																						
PFOS	70	20	1,700	2,000	1,700	35	64	1,200	3,100	2,500	45	BRL (<2.6)	BRL (<5.2)	5	BRL (<5.2)	1,200	820	3,900	4,400	2,600	4,900	1,900
PFOA	70	20	130	140	97	BRL (<5.3)	BRL (<3.3)	54	150	120	BRL (<20)	BRL (<4.6)	BRL (<7.4)	BRL (<0.23)	BRL (<7.4)	46	28	320	880	290	530	690
PFNA	NE	20	--	--	--	--	BRL (<8.7)	80	--	--	--	--	BRL (<4.9)	BRL (<0.48)	BRL (<4.9)	--	61	--	--	--	--	--
PFHxS	NE	20	--	--	--	--	38	120	--	--	--	--	6	2	BRL (<5.2)	--	100	--	--	--	--	--
PFHpA	NE	20	--	--	--	--	BRL (<7.4)	62	--	--	--	--	BRL (<7.1)	BRL (<0.37)	BRL (<7.1)	--	28	--	--	--	--	--
PFDA	NE	20	--	--	--	--	--	11	--	--	--	--	BRL (<4.1)	BRL (<0.18)	BRL (<4.1)	--	BRL (<4.1)	--	--	--	--	--
TOTAL Σ6 PFAS	70	20	1830	2140	1797	35	102	1,516	3250	2620	45	BRL	6.1	6.7	BRL	1,246	1,037	4,220	5,280	2,890	5,430	2,590

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
5. BRL - Below Laboratory Detection Limits
6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion
7. Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
8. PFOS - Perfluorooctanesulfonate
9. PFOA - Perfluorooctanoic Acid
10. PFNA - Perfluorononanoic Acid
11. PFHxS - Perfluorohexanesulfonic Acid
12. PFHpA - Perfluoroheptanoic Acid
13. PFDA - Perfluorodecanoic Acid
14. NA - Concentration data not available
15. Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
17. NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy

Bamstable Country Fire and Rescue Training A

155 Flint Rock Road, Bamstable, MA

RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	MW-3D	SBV -3	MW-6		MW-7	MW-10		MW-12I	MW-12										MW-15	MW-15D	MW-19I
SAMPLING DATE			8/18/2016	11/22/2013	4/1/2015	4/25/2017	11/22/2013	11/22/2013	4/18/2016	4/24/2017	8/20/2014	4/1/2015	6/26/2018	1/11/2019	4/23/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	4/24/2017	4/2/2015	8/20/2014
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																							
PFOS	70	20	98	1,100	5,700	2,400	3,100	2,000	1,700	490	2,500	4,800	3,000	2,700	2,800	2,800	2,300	3,100	3,500	2,900	19	60	BRL
PFOA	70	20	10	350	510	140	580	670	440	36	400	470	280	650	920	250	380	580	280	220	27	60	BRL
PFNA	NE	20	--	--	--	--	--	--	--	--	--	--	56	64	92	87	80	78	86	51	--	--	--
PFHxS	NE	20	--	--	--	--	--	--	--	--	--	--	1,200	1,500	1,700	880	1,300	1,200	1,100	900	--	--	--
PFHpA	NE	20	--	--	--	--	--	--	--	--	--	--	130	490	440	170	310	390	140	120	--	--	--
PFDA	NE	20	--	--	--	--	--	--	--	--	--	--	--	--	16	11	10	8	23	18	--	--	--
TOTAL Σ6 PFAS	70	20	108	1,450	6,210	2,540	3,680	2,670	2,140	526	2,900	5,270	4,666	5,404	5,968	4,198	4,380	5,356	5,129	4,209	46	120	BRL

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
5. BRL - Below Laboratory Detection Limits
6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion
7. Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
8. PFOS - Perfluorooctanesulfonate
9. PFOA - Perfluorooctanoic Acid
10. PFNA - Perfluorononanoic Acid
11. PFHxS - Perfluorohexanesulfonic Acid
12. PFHpA - Perfluoroheptanoic Acid
13. PFDA - Perfluorodecanoic Acid
14. NA - Concentration data not available
15. Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
17. NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179

SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standard ⁴	MW-22										MW-28S	MW-30	MW-31	MW-32	MW-35I				MW-36D	MW-37	MW-37D	MW-99I		
SAMPLING DATE			6/3/2014	4/1/2015	6/26/2018	1/11/2019	4/23/2019	7/23/2019	10/29/2019	2/19/2020	5/12/2020	7/29/2020	4/1/2015	4/1/2015	8/18/2016	5/3/2017	8/20/2014	5/3/2017	1/10/2019	10/30/2019	4/6/2015	4/26/2017	4/2/2015	4/6/2015	4/26/2017	10/29/2019
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																										
PFOS	70	20	4,900	600	320	350	320	410	510	460	380	790	2,100	1,400	3,200	240	60	42	BRL (<6)	BRL (<5.2)	140	77	60	730	240	630
PFOA	70	20	530	90	30	140	160	190	150	230	120	92	90	130	170	36	BRL	14	BRL (<3.3)	BRL (<7.4)	<20	77	90	70	18	50
PFNA	NE	20	--	--	9	BRL (<8.7)	81	8	8	5	10	14	--	--	--	--	--	--	BRL (<8.7)	BRL (<4.9)	--	--	--	--	--	58
PFHxS	NE	20	--	--	130	680	600	520	690	540	330	360	--	--	--	--	--	--	BRL (<5.6)	6.0	--	--	--	--	--	340
PFHpA	NE	20	--	--	13	69	49	33	61	38	32	27	--	--	--	--	--	--	BRL (<7.4)	BRL (<7.1)	--	--	--	--	--	46
PFDA	NE	20	--	--	--	--	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	BRL (<4.1)	1	5.2	--	--	--	--	--	--	--	BRL (<4.1)	--	--	--	--	--	5.5
TOTAL Σ6 PFAS	70	20	5,430	690	502	1,239	1,210	1,161	1,419	1,273	873	1,288	2,190	1,530	3,370	276	60	56	BRL	6.0	140	154	150	800	258	1,130


- Notes:
- Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
 - The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
 - The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
 - (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
 - BRL - Below Laboratory Detection Limits
 - Concentrations presented in ng/L - nanograms per Liter - parts per trillion
 - Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
 - PFOS - Perfluorooctanesulfonate
 - PFOA - Perfluorooctanoic Acid
 - PFNA - Perfluorononanoic Acid
 - PFHxS - Perfluorohexanesulfonic Acid
 - PFHpA - Perfluoroheptanoic Acid
 - PFDA - Perfluorodecanoic Acid
 - NA - Concentration data not available
 - Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
 - Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
 - NE - Not Established

Table 4 - Summary of Groundwater PFAS Analy
Barnstable County Fire and Rescue Training A
155 Flint Rock Road, Barnstable, MA
RTN 4-26179


SAMPLE ID	USEPA ^{1,2} Health Advisory	Method 1 GW-1 Standards ⁴	OW-8A												FS-1SA	FS-1	RW-1		HW-1D ¹⁴			HW-2S	OW-2A	OW-2S	OW-2D
SAMPLING DATE			11/22/2013	6/3/2014	4/11/2017	8/16/2017	6/26/2018	1/9/2019	4/23/2019	7/22/2019	10/28/2019	2/18/2020	5/11/2020	7/28/2020	6/16/2016	4/11/2017	4/1/2015	4/11/2017	5/3/2017	1/10/2019	10/28/2019	5/3/2017	6/3/2014	4/14/2016	4/14/2016
UNITS	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L	ng/L
PFAS (Method 537.2)																									
PFOS	70	20	2,700	8,600	1,700	770	2,800	990	880	780	220	650	150	170	1,700	1,700	2,300	1,000	25	BRL (<6)	BRL (<5.2)	15	1,300	2,400	6
PFOA	70	20	430	1,000	2,000	120	65	420	66	55	130	62	18	12	550	730	240	58	8	BRL (<3.3)	BRL (<7.4)	8.2	150	250	BRL (<5.3)
PFNA	NE	20	--	--	--	--	310	150	120	78	10	110	12	11	--	--	--	--	--	BRL (<8.7)	BRL (<4.9)	--	--	--	--
PFHxS	NE	20	--	--	--	--	250	890	140	100	750	190	77	30	--	--	--	--	--	BRL (<5.6)	BRL (<5.2)	--	--	--	--
PFHpA	NE	20	--	--	--	--	43	210	40	26	190	35	9	7.4	--	--	--	--	--	BRL (<7.4)	BRL (<7.1)	--	--	--	--
PFDA	NE	20	--	--	--	--	--	--	15	18	14	17	4	10	--	--	--	--	--	--	BRL (<4.1)	--	--	--	--
TOTAL Σ6 PFAS	70	20	3,130	9,600	3,700	890	3,468	2,660	1,261	1,057	1,314	1,064	270	240	2,250	2,430	2,540	1,058	33	BRL	BRL	23.2	1,450	2,650	6

Notes:

1. Prior to June 11, 2018, the USEPA established the EPA Health Advisory for two PFAS chemicals, PFOA and PFOS, which was 70 ng/L. Subsequently, MassDEP's Office of Research and Standards (ORS) expanded on this Health Advisory and created the ORS Guideline that applies to the total summed of five PFAS chemicals, PFOS, PFOA, PFNA, PFHxS, and PFHpA, effective June 11, 2018.
2. The USEPA and MassDEP ORS Guideline applies to five PFAS chemicals of concern (PFOS, PFOA, PFNA, PFHpA, and PFHxS) individually as well as the sum of the five PFAS of concern.
3. The complete PFAS concentration data set collected from PRW-4 is detailed in the data table titled "Summary of Groundwater Pump and Treatment System PFOS/PFOA Analytical Data." Data presented herein is summarized and data was selected based on quarterly sampling events.
4. (--) Concentrations of the three additional PFAS chemicals, PFNA, PFHxS, and PFHpA were not presented until after the MassDEP ORS Guideline was in effect on 06.11.18. PFAS concentrations were regulated by the USEPA Health Advisory prior to 6.11.18. Concentrations of PFDA were not presented prior to April 19, 2019. MassDEP released drafted Method 1 groundwater risk standards for PFAS on April 19, 2019 that applies to the total sum and individual concentrations of six PFAS compounds (PFOS, PFOA, PFNA, PFHxS, PFHpA, and PFDA), which is 20 ng/L. These drafted groundwater standards were finalized and became effective on December 27, 2019.
5. BRL - Below Laboratory Detection Limits
6. Concentrations presented in ng/L - nanograms per Liter - parts per trillion
7. Concentrations in bold exceed applicable Health Advisory Limit or Method 1 GW-1 Standard
8. PFOS - Perfluorooctanesulfonate
9. PFOA - Perfluorooctanoic Acid
10. PFNA - Perfluorononanoic Acid
11. PFHxS - Perfluorohexanesulfonic Acid
12. PFHpA - Perfluoroheptanoic Acid
13. PFDA - Perfluorodecanoic Acid
14. NA - Concentration data not available
15. Monitoring well HS-1, HS-2, HS-2S, and HS-6 were destroyed or removed during soil removal activities in January 2017 as part of an Immediate Response Action Plan. The well was replaced with HSW-1/HS-1a as post-exacavation activities.
16. Monitoring well HW-1D is a downgradient well located on the north side of Mary Dunn Pond.
17. NE - Not Established



K:\6206 BARNSTABLE COUNTY\MCP LSP BASE SERVICES FMRLY 2018-2019 SERVICES\DRAWINGFILES\XREFS\GW CONTOUR\6206_EX_BASE_MM_4.2020.DWG



LEGEND


- MONITORING WELL
- RECOVERY WELL
- PUBLIC WATER SUPPLY WELL
- APPROX. PROPERTY BOUNDARY
- FORCE MAIN
- FACILITY BLDG. STRUCTURES

BETA
www.BETA-Inc.com

FIGURE 2 - SITE PLAN
Barnstable County Fire & Rescue Training Academy
155 South Flint Rock Road, Barnstable, MA
Plot Date: 04/20/2020

200 100 0 100 200 400
(IN FEET)
1 inch = 200 ft.

Figure 3A - Σ PFAS Concentrations in HSW-1 from January 2019 - May 2020




Barnstable County Fire & Rescue Training Academy
155 South Flint Rock Road, Barnstable, MA
RTN 4-26179



Notes:

1. Concentrations depicted represent the sum of the the five (5) PFAS compounds, PFOS, PFOA, PFHpA, PFHxS, and PFNA from June 2018 to April 2019. Concentrations depicted from April 2019 to to current graphical date represent the sum of the six (6) PFAS compounds PFOS, PFOA, PFHpA, PFHxS, PFNA, and PFDA.
2. Concentrations are in in micrograms per liter (µg/L) .
3. HSW-1 was not sampled in June 2018.

Figure 3B - Σ PFAS Concentrations in PFW-1 from June 2018 - July 2020




Barnstable County Fire & Rescue Training Academy
155 South Flint Rock Road, Barnstable, MA
RTN 4-26179



Notes:

1. Concentrations depicted represent the sum of the the five (5) PFAS compounds, PFOS, PFOA, PFHpA, PFHxS, and PFNA from June 2018 to April 2019. Concentrations depicted from April 2019 to current graphical date represent the sum of the six (6) PFAS compounds PFOS, PFOA, PFHpA, PFHxS, PFNA, and PFDA.
2. Concentrations are in in micrograms per liter (µg/L) or parts per billion (ppb).

Figure 4 - Σ PFAS Concentrations in OW-8A from January 2019-July 2020




Barnstable County Fire & Rescue Training
Academy
155 South Flint Rock Road, Barnstable, MA
RTN 4-26179



Notes:

1. Concentrations depicted represent the sum of the five (5) PFAS compounds, PFOS, PFOA, PFHpA, PFHxS, and PFNA from June 2018 to April 2019. Concentrations depicted from April 2019 to current graphical date represent the sum of the six (6) PFAS compounds: PFOS, PFOA, PFHpA, PFHxS, PFNA, and PFDA.
2. Concentrations are in micrograms per liter (µg/L) or parts per billion (ppb).

FIGURE 5 - ΣPFAS CONCENTRATIONS IN MW-12 AND MW-22 FROM JUNE 2018 - JULY 2020



Barnstable County Fire & Rescue Training Academy
155 South Flint Rock Road, Barnstable, MA
RTN 4-26179


—◆— MW-12 — MW-22



Notes:

1. Concentrations depicted represent the sum of the the five (5) PFAS compounds, PFOS, PFOA, PFHpA, PFHxS, and PFNA from June 2018 to April 2019. Concentrations depicted from April 2019 to October 2019 represent the sum of the six (6) PFAS compounds: PFOS, PFOA, PFHpA, PFHxS, PFNA, and PFDA.
2. Concentrations are in micrograms per liter (µg/L) or parts per billion (ppb).

Figure 6B - Σ PFAS Concentrations in PC-6A from June 2018-July 2020



Barnstable County Fire & Rescue Training Academy
155 South Flint Rock Road, Barnstable, MA
RTN 4-26179


PC-6A



Notes:

1. Concentrations depicted represent the sum of the five (5) PFAS compounds, PFOS, PFOA, PFHpA, PFHxS, and PFNA from June 2018 to April 2019. Concentrations depicted from April 2019 to October 2019 represent the sum of the six (6) PFAS compounds PFOS, PFOA, PFHpA, PFHxS, PFNA, and PFDA.
2. Concentrations are in micrograms per liter (µg/L) or parts per billion (ppb).

Figure 6C - ΣPFAS Concentrations in PC-28 and PC-30 from June 2018 - July 2020



Barnstable County Fire & Rescue Training Academy
155 South Flint Rock Road, Barnstable, MA
RTN 4-26179


—●— PC-30 —●— PC-28



Notes:

1. Concentrations depicted represent the sum of the five (5) PFAS compounds, PFOS, PFOA, PFHpA, PFHxS, and PFNA from June 2018 to April 2019. Concentrations depicted from April 2019 to the graphically represented date are represented as the sum of the six (6) PFAS compounds, PFOS, PFOA, PFHpA, PFHxS, PFNA, and PFDA.
2. Concentrations are in micrograms per liter (µg/L) or parts per billion (ppb).

K:\6206 BARNSTABLE COUNTY\MCP LSP BASE SERVICES FMRLY 2018-2019 SERVICES\DRAWINGFILES\XREFS\GW CONTOUR\6206_EX_BASE_MM_2020.DWG



**BETA**

www.BETA-Inc.com

FIGURE 7
Groundwater Contour Map - July 2020
Barnstable County Fire & Rescue Training Academy
155 South Flint Rock Road, Barnstable, MA
Plot Date: 09/14/2020 Drawn By: MM

GRAPHIC SCALE

2501250125250500

(IN FEET)

1 inch = 250 ft.



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

BWSC 105

Immediate Response Action (IRA) Transmittal Form

Pursuant to 310 CMR 40.0424 - 40.0427 (Subpart D)

Release Tracking Number

4 - 26179

A. SITE LOCATION:

1. Release Name/Location Aid: BARNSTABLE COUNTY FIRE TRAINING ACADEMY
2. Street Address: 155 SOUTH FLINT ROCK ROAD
3. City/Town: BARNSTABLE 4. Zip Code: 026300000
- ☐ 5. Check here if this location is Adequately Regulated, pursuant to 310 CMR 40.0110-0114.
- ☐ a. CERCLA ☐ b. HSWA Corrective Action ☐ c. Solid Waste Management
- ☐ d. RCRA State Program (21C Facilities)

B. THIS FORM IS BEING USED TO: (check all that apply)

1. List Submittal Date of Initial IRA Written Plan (if previously submitted): 9/26/2016
- ☐ 2. Submit an **Initial IRA Plan**.
- ☐ 3. Submit a **Modified IRA Plan** of a previously submitted written IRA Plan.
- ☐ 4. Submit an **Imminent Hazard Evaluation**. (check one)
- ☐ a. An Imminent Hazard exists in connection with this Release or Threat of Release.
- ☐ b. An Imminent Hazard does not exist in connection with this Release or Threat of Release.
- ☐ c. It is unknown whether an Imminent Hazard exists in connection with this Release or Threat of Release, and further assessment activities will be undertaken.
- ☐ d. It is unknown whether an Imminent Hazard exists in connection with this Release or Threat of Release. However, response actions will address those conditions that could pose an Imminent Hazard.
- ☐ 5. Submit a request to **Terminate an Active Remedial System or Response Action(s) Taken to Address an Imminent Hazard**.
- ☒ 6. Submit an **IRA Status Report**
- ☒ 7. Submit a **Remedial Monitoring Report**. (This report can only be submitted through eDEP.)
- a. Type of Report: (check one) ☐ i. Initial Report ☒ ii. Interim Report ☐ iii. Final Report
- b. Frequency of Submittal: (check all that apply)
- ☒ i. A Remedial Monitoring Report(s) submitted monthly to address an Imminent Hazard.
- ☐ ii. A Remedial Monitoring Report(s) submitted monthly to address a Condition of Substantial Release Migration.
- ☐ iii. A Remedial Monitoring Report(s) submitted every six months, concurrent with an IRA Status Report.
- ☐ iv. A Remedial Monitoring Report(s) submitted annually, concurrent with an IRA Status Report.
- c. Number of Remedial Systems and/or Monitoring Programs: 2

A separate BWSC105A, IRA Remedial Monitoring Report, must be filled out for each Remedial System and/or Monitoring Program addressed by this transmittal form.



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

BWSC 105

Immediate Response Action (IRA) Transmittal Form

Pursuant to 310 CMR 40.0424 - 40.0427 (Subpart D)

Release Tracking Number

4 - 26179

☐ 8. Submit an **IRA Completion Statement**.

☐ a. Check here if future response actions addressing this Release or Threat of Release notification condition will be conducted as part of the Response Actions planned or ongoing at a Site that has already been Tier Classified under a different Release Tracking Number (RTN)

b. Provide Release Tracking Number of Tier Classified Site (Primary RTN): _____

These additional response actions must occur according to the deadlines applicable to the Primary RTN. Use the Primary RTN when making all future submittals for the site unless specifically relating to this Immediate Response Action.

☐ 9. Submit a **Revised IRA Completion Statement**.

☐ 10. Submit a **Plan for the Application of Remedial Additives** near a sensitive receptor, pursuant to 310 CMR 40.0046(3).

(All sections of this transmittal form must be filled out unless otherwise noted above)

C. RELEASE OR THREAT OF RELEASE CONDITIONS THAT WARRANT IRA:

1. Media Impacted and Receptors Affected: (check all that apply)

- | | | |
|--|--|---|
| <input type="checkbox"/> a. Paved Surface | <input type="checkbox"/> b. Basement | <input type="checkbox"/> c. School |
| <input checked="" type="checkbox"/> d. Public Water Supply | <input checked="" type="checkbox"/> e. Surface Water | <input checked="" type="checkbox"/> f. Zone 2 |
| <input type="checkbox"/> g. Private Well | <input type="checkbox"/> h. Residence | <input checked="" type="checkbox"/> i. Soil |
| <input type="checkbox"/> j. Groundwater | <input checked="" type="checkbox"/> k. Sediments | <input type="checkbox"/> l. Wetland |
| <input type="checkbox"/> m. Storm Drain | <input type="checkbox"/> n. Indoor Air | <input type="checkbox"/> o. Air |
| <input type="checkbox"/> p. Soil Gas | <input type="checkbox"/> q. Sub-Slab Soil Gas | <input type="checkbox"/> r. Critical Exposure Pathway |
| <input type="checkbox"/> s. NAPL | <input type="checkbox"/> t. Unknown | |
| <input type="checkbox"/> r. Others | Specify: _____ | |

2. Sources of the Release or TOR: (check all that apply)

- | | | |
|--|--|-----------------------------------|
| <input type="checkbox"/> a. Transformer | <input type="checkbox"/> b. Fuel Tank | <input type="checkbox"/> c. Pipe |
| <input type="checkbox"/> d. OHM Delivery | <input type="checkbox"/> e. AST | <input type="checkbox"/> f. Drums |
| <input type="checkbox"/> g. Tanker Truck | <input type="checkbox"/> h. Hose | <input type="checkbox"/> i. Line |
| <input type="checkbox"/> j. UST | Describe: _____ | |
| <input type="checkbox"/> k. Vehicle | <input type="checkbox"/> l. Boat/Vessel | |
| <input type="checkbox"/> m. Unknown | <input checked="" type="checkbox"/> n. Other: FIRE FIGHTING FOAM | |

3. Type of Release or TOR: (check all that apply)

- | | | | |
|--|---|---|--------------------------------------|
| <input type="checkbox"/> a. Dumping | <input type="checkbox"/> b. Fire | <input type="checkbox"/> c. AST Removal | <input type="checkbox"/> d. Overfill |
| <input type="checkbox"/> e. Rupture | <input type="checkbox"/> f. Vehicle Accident | <input type="checkbox"/> g. Leak | <input type="checkbox"/> h. Spill |
| <input type="checkbox"/> i. Test failure | <input type="checkbox"/> j. TOR Only | | |
| <input type="checkbox"/> k. UST Removal | Describe: _____ | | |
| <input type="checkbox"/> l. Unknown | <input checked="" type="checkbox"/> m. Other: HISTORIC FOAM USE | | |

4. Identify Oils and Hazardous Materials Released: (check all that apply)

- | | |
|--|--|
| <input type="checkbox"/> a. Oils | <input type="checkbox"/> b. Chlorinated Solvents |
| <input type="checkbox"/> c. Heavy Metals | <input checked="" type="checkbox"/> d. Others |
| Specify: PFAS | |

D. DESCRIPTION OF RESPONSE ACTIONS: (check all that apply, for volumes list cumulative amounts)

- | | |
|---|---|
| <input checked="" type="checkbox"/> 1. Assessment and/or Monitoring Only | <input checked="" type="checkbox"/> 2. Temporary Covers or Caps |
| <input type="checkbox"/> 3. Deployment of Absorbent or Containment Materials | <input type="checkbox"/> 4. Temporary Water Supplies |
| <input type="checkbox"/> 5. Structure Venting System/HVAC Modification System | <input type="checkbox"/> 6. Temporary Evacuation or Relocation of Residents |
| <input type="checkbox"/> 7. Product or NAPL Recovery | <input type="checkbox"/> 8. Fencing and Sign Posting |
| <input checked="" type="checkbox"/> 9. Groundwater Treatment Systems | <input type="checkbox"/> 10. Soil Vapor Extraction |
| <input type="checkbox"/> 11. Remedial Additives | <input type="checkbox"/> 12. Air Sparging |
| <input type="checkbox"/> 13. Active Exposure Pathway Mitigation System | <input type="checkbox"/> 14. Passive Exposure Pathway Mitigation System |



Immediate Response Action (IRA) Transmittal Form

Pursuant to 310 CMR 40.0424 - 40.0427 (Subpart D)

Release Tracking Number

4 - 26179

D. DESCRIPTION OF RESPONSE ACTIONS: (cont.)

☒ 15. Excavation of Contaminated Soils.

☐ a. Re-use, Recycling or Treatment ☐ i. On Site Estimated volume in cubic yards _____

☐ ii. Off Site Estimated volume in cubic yards _____

iiia. Receiving Facility: _____ Town: _____ State: _____

iiib. Receiving Facility: _____ Town: _____ State: _____

iiic. Describe: _____

☐ b. Store ☐ i. On Site Estimated volume in cubic yards _____

☐ ii. Off Site Estimated volume in cubic yards _____

iiia. Receiving Facility: _____ Town: _____ State: _____

iiib. Receiving Facility: _____ Town: _____ State: _____

☒ c. Landfill ☐ i. Cover Estimated volume in cubic yards _____

Receiving Facility: _____ Town: _____ State: _____

☒ ii. Disposal Estimated volume in cubic yards 200

Receiving Facility: TAUNTON LANDFILL Town: TAUNTON State: MA

☐ 16. Removal of Drums, Tanks, or Containers:

a. Describe Quantity and Amount: _____

b. Receiving Facility: _____ Town: _____ State: _____

c. Receiving Facility: _____ Town: _____ State: _____

☐ 17. Removal of Other Contaminated Media:

a. Specify Type and Volume: _____

☐ 18. Other Response Actions:

Describe: _____

☐ 19. Use of Innovative Technologies:

Describe: _____



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

BWSC 105

Immediate Response Action (IRA) Transmittal Form

Pursuant to 310 CMR 40.0424 - 40.0427 (Subpart D)

Release Tracking Number

4 - 26179

E. LSP SIGNATURE AND STAMP:

I attest under the pains and penalties of perjury that I have personally examined and am familiar with this transmittal form, including any and all documents accompanying this submittal. In my professional opinion and judgment based upon application of (i) the standard of care in 309 CMR 4.02(1), (ii) the applicable provisions of 309 CMR 4.02(2) and (3), and 309 CMR 4.03(2), and (iii) the provisions of 309 CMR 4.03(3), to the best of my knowledge, information and belief,

> if Section B of this form indicates that an **Immediate Response Action Plan** is being submitted, the response action(s) that is(are) the subject of this submittal (i) has (have) been developed in accordance with the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000, (ii) is(are) appropriate and reasonable to accomplish the purposes of such response action(s) as set forth in the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000 and (iii) complies(y) with the identified provisions of all orders, permits, and approvals identified in this submittal;

> if Section B of this form indicates that an **Imminent Hazard Evaluation** is being submitted, this Imminent Hazard Evaluation was developed in accordance with the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000, and the assessment activity(ies) undertaken to support this Imminent Hazard Evaluation comply(ies) with the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000;

> if Section B of this form indicates that an **Immediate Response Action Status Report** and/or a **Remedial Monitoring Report** is(are) being submitted, the response action(s) that is (are) the subject of this submittal (i) is (are) being implemented in accordance with the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000, (ii) is (are) appropriate and reasonable to accomplish the purposes of such response action(s) as set forth in the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000 and (iii) comply(ies) with the identified provisions of all orders, permits, and approvals identified in this submittal;

> if Section B of this form indicates that an **Immediate Response Action Completion Statement** or a request to **Terminate an Active Remedial System or Response Action(s) Taken to Address an Imminent Hazard** is being submitted, the response action(s) that is(are) the subject of this submittal (i) has (have) been developed and implemented in accordance with the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000, (ii) is(are) appropriate and reasonable to accomplish the purposes of such response action(s) as set forth in the applicable provisions of M.G.L. c. 21E and 310 CMR 40.0000 and (iii) comply(ies) with the identified provisions of all orders, permits, and approvals identified in this submittal.

I am aware that significant penalties may result, including, but not limited to, possible fines and imprisonment, if I submit information which I know to be false, inaccurate or materially incomplete.

1. LSP #: 1443


2. First Name: ROGER P 3. Last Name: THIBAUT

4. Telephone: 508-331-2700 5. Ext: 6. Email:

7. Signature:

8. Date: (mm/dd/yyyy)

9. LSP Stamp:





Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

BWSC 105

Immediate Response Action (IRA) Transmittal Form

Pursuant to 310 CMR 40.0424 - 40.0427 (Subpart D)

Release Tracking Number

4 - 26179

F. PERSON UNDERTAKING IRA:

1. Check all that apply: ☐ a. change in contact name ☐ b. change of address ☐ c. change in the person undertaking response actions
2. Name of Organization: BARNSTABLE COUNTY COMMISSIONERS
3. Contact First Name: JACK 4. Last Name: YUNITS
5. Street: 3195 MAIN ST 6. Title: _____
7. City/Town: BARNSTABLE 8. State: MA 9. Zip Code: 026301105
10. Telephone: 508-375-6643 11. Ext: _____ 12. Email: JYUNITS@BARNSTABLECOUNTY.ORG

G. RELATIONSHIP TO RELEASE OR THREAT OF RELEASE OF PERSON UNDERTAKING IRA:

- ☐ Check here to change relationship
- ☒ 1. RP or PRP ☒ a. Owner ☐ b. Operator ☐ c. Generator ☐ d. Transporter
☐ e. Other RP or PRP Specify Relationship: _____
- ☐ 2. Fiduciary, Secured Lender or Municipality with Exempt Status (as defined by M.G.L. c. 21E, s. 2)
- ☐ 3. Agency or Public Utility on a Right of Way (as defined by M.G.L. c. 21E, s. 5(j))
- ☐ 4. Any Other Person Undertaking Response Actions: Specify Relationship: _____

H. REQUIRED ATTACHMENT AND SUBMITTALS:

- ☐ 1. Check here if any Remediation Waste, generated as a result of this IRA, will be stored, treated, managed, recycled or reused at the site following submission of the IRA Completion Statement. If this box is checked, you must submit one of the following plans, along with the appropriate transmittal form.
☐ a. A Release Abatement Measure (RAM) Plan (BWSC106) ☐ b. Phase IV Remedy Implementation Plan (BWSC108)
- ☒ 2. Check here if the Response Action(s) on which this opinion is based, if any, are (were) subject to any order(s), permit(s) and/or approval(s) issued by MassDEP or EPA. If the box is checked, you MUST attach a statement identifying the applicable provisions thereof.
- ☒ 3. Check here to certify that the Chief Municipal Officer and the Local Board of Health were notified of the implementation of an Immediate Response Action taken to control, prevent, abate or eliminate an Imminent Hazard.
- ☐ 4. Check here to certify that the Chief Municipal Officer and the Local Board of Health were notified of the submittal of a Completion Statement for an Immediate Response Action taken to control, prevent, abate or eliminate an Imminent Hazard.
- ☐ 5. Check here if any non-updatable information provided on this form is incorrect, e.g. Release Address/Location Aid. Send corrections to BWSC.eDEP@state.ma.us.
- ☒ 6. Check here to certify that the LSP Opinion containing the material facts, data, and other information is attached.



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

BWSC 105

Immediate Response Action (IRA) Transmittal Form

Pursuant to 310 CMR 40.0424 - 40.0427 (Subpart D)

Release Tracking Number

4 - 26179

I. CERTIFICATION OF PERSON UNDERTAKING IRA:

1. I, _____, attest under the pains and penalties of perjury (i) that I have personally examined and am familiar with the information contained in this submittal, including any and all documents accompanying this transmittal form; (ii) that, based on my inquiry of the/those individual(s) immediately responsible for obtaining the information, the material information contained herein is, to the best of my knowledge, information and belief, true, accurate and complete; (iii) that, to the best of my knowledge, information and belief, I/the person(s) or entity(ies) on whose behalf this submittal is made satisfy(ies) the criteria in 310 CMR 40.0183(2); (iv) that I/the person(s) or entity(ies) on whose behalf this submittal is made have provided notice in accordance with 310 CMR 40.0183(5); and (v) that I am fully authorized to make this attestation on behalf of the person(s) or entity(ies) legally responsible for this submittal. I/the person(s) or entity(ies) on whose behalf this submittal is made is/are aware that there are significant penalties, including, but not limited to, possible fines and imprisonment, for willfully submitting false, inaccurate, or incomplete information.

2. By: _____ 3. Title: _____

4. For: BARNSTABLE COUNTY COMMISSIONERS 5. Date: _____ (mm/dd/yyyy)

☐ 6. Check here if the address of the person providing certification is different from address recorded in Section F.

7. Street: _____

8. City/Town: _____ 9. State: _____ 10. Zip Code: _____

11. Telephone: _____ 12. Ext: _____ 13. Email: _____

YOU ARE SUBJECT TO AN ANNUAL COMPLIANCE ASSURANCE FEE OF UP TO \$10,000 PER BILLABLE YEAR FOR THIS DISPOSAL SITE. YOU MUST LEGIBLY COMPLETE ALL RELEVANT SECTIONS OF THIS FORM OR DEP MAY RETURN THE DOCUMENT AS INCOMPLETE. IF YOU SUBMIT AN INCOMPLETE FORM, YOU MAY BE PENALIZED FOR MISSING A REQUIRED DEADLINE.

Date Stamp (DEP USE ONLY:)



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup
IRA REMEDIAL MONITORING REPORT

BWSC105 -A

Pursuant to 310 CMR 40.0400 (SUBPART D)

Release Tracking Number

Remedial System or Monitoring Program: of:

-

A. DESCRIPTION OF ACTIVE OPERATION AND MAINTENANCE ACTIVITY:

1. Type of Active Operation and Maintenance Activity: (check all that apply)

☒ a. Active Remedial System: (check all that apply)

☐ i. NAPL Recovery

☐ ii. Soil Vapor Extraction/Bioventing

☐ iii. Vapor-phase Carbon Adsorption

☒ iv. Groundwater Recovery

☐ v. Dual/Multi-phase Extraction

☒ vi. Aqueous-phase Carbon Adsorption

☐ vii. Air Stripping

☐ viii. Sparging/Biosparging

☐ ix. Cat/Thermal Oxidation

☐ x. Other Describe: _____

☐ b. Active Exposure Pathway Elimination Measure

Active Exposure Pathway Mitigation System to address (check one): ☐ i. Indoor Air ☐ ii. Drinking Water

☐ c. Application of Remedial Additives: (check all that apply)

☐ i. To the Subsurface

☐ ii. To Groundwater (Injection)

☐ iii. To the Surface

☐ d. Active Remedial Monitoring Program Without the Application of Remedial Additives: (check all that apply; Sections C, D and E are not required; attach supporting information, data, maps and/or sketches needed by checking Section G5)

☐ i. Reactive Wall

☐ ii. Natural Attenuation

☐ iii. Other

Describe: _____

2. Mode of Operation: (check one)

☒ a. Continuous

☐ b. Intermittent

☐ c. Pulsed

☐ d. One-time Event Only

☐ e. Other: _____

3. System Effluent/Discharge: (check all that apply)

☐ a. Sanitary Sewer/POTW

☒ b. Groundwater Re-infiltration/Re-injection: (check one)

☐ i. Downgradient

☒ ii. Upgradient

☐ c. Vapor-phase Discharge to Ambient Air: (check one)

☐ i. Off-gas Controls

☐ ii. No Off-gas Controls

☐ d. Drinking Water Supply

☐ e. Surface Water (including Storm Drains)

☐ f. Other Describe: _____

B. MONITORING FREQUENCY:

1. Reporting period that is the subject of this submittal:

From: 7/1/2020

To: 7/31/2020

(mm/dd/yyyy)

(mm/dd/yyyy)

2. Number of monitoring events during the reporting period: (check one)

☐ a. System Startup: (if applicable)

☐ i. Days 1, 3, 6, and then weekly thereafter, for the first month.

☐ ii. Other Describe: _____

☒ b. Post-system Startup (after first month) or Monitoring Program:

☒ i. Monthly

☐ ii. Quarterly

☐ iii. Annually

☐ iv. Other Describe: _____

☐ 3. Check here to certify that the number of required monitoring events were conducted during the reporting period.

C. EFFLUENT/DISCHARGE REGULATION: (check one to indicate how the effluent/discharge limits were established)

☐ 1. NPDES: (check one)

☐ a. Remediation General Permit

☐ b. Individual Permit

☐ c. Emergency Exclusion

Effective Date of Permit: _____

(mm/dd/yyyy)

☐ 2. MCP Performance Standard

MCP Citations(s): _____

☒ 3. DEP Approval Letter

Date of Letter: 11/18/2016

(mm/dd/yyyy)

☐ 4. Other Describe: _____



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

IRA REMEDIAL MONITORING REPORT

Pursuant to 310 CMR 40.0400 (SUBPART D)

Remedial System or Monitoring Program: 1 of 2

BWSC105 -A

Release Tracking Number

4 - 26179

D. WASTEWATER TREATMENT PLANT OPERATOR: (check one)

☒ 1. Required due to Remedial Wastewater Treatment Plant in place for more than 30 days.

a. Name: TJMCGOFF

b. Grade: 4

c. License No: 15570

d. License Exp. Date: 12/31/2021

(mm/dd/yyyy)

☐ 2. Not Required

☐ 3. Not Applicable

E. STATUS OF ACTIVE REMEDIAL SYSTEM OR ACTIVE REMEDIAL MONITORING PROGRAM DURING REPORTING PERIOD: (check all that apply)

☒ 1. The Active Remedial System was functional one or more days during the Reporting Period.

a. Days System was Fully Functional: 31

b. GW Recovered (gals): 396632

c. NAPL Recovered (gals):

d. GW Discharged (gals): 396632

e. Avg. Soil Gas Recovery Rate (scfm):

f. Avg. Sparging Rate (scfm):

☐ 2. Remedial Additives: (check all that apply)

☐ a. No Remedial Additives applied during the Reporting Period.

☐ b. Enhanced Bioremediation Additives applied: (total quantity applied at the site for the current reporting period)

☐ i. Nitrogen/Phosphorus:

☐ ii. Peroxides:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units

☐ iii. Microorganisms:

☐ iv. Other:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units

☐ c. Chemical oxidation/reduction additives applied: (total quantity applied at the site for the current reporting period)

☐ i. Permanganates:

☐ ii. Peroxides:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units

☐ iii. Persulfates:

☐ iv. Other:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

IRA REMEDIAL MONITORING REPORT

Pursuant to 310 CMR 40.0400 (SUBPART D)

Remedial System or Monitoring Program: 1 of 2

BWSC105 -A

Release Tracking Number

4 - 26179

E. STATUS OF ACTIVE REMEDIAL SYSTEM OR ACTIVE REMEDIAL MONITORING PROGRAM DURING REPORTING PERIOD: (cont.)

☐ d. Other additives applied: (total quantity applied at the site for the current reporting period)

Name of Additive	Date	Quantity	Units	Name of Additive	Date	Quantity	Units

☐ e. Check here if any additional Remedial Additives were applied. Attach list of additional additives and include Name of Additive, Date Applied, Quantity Applied and Units (in gals. or lbs.)

F. SHUTDOWNS OF ACTIVE REMEDIAL SYSTEM OR ACTIVE REMEDIAL MONITORING PROGRAM: (check all that apply)

☐ 1. The Active Remedial System had unscheduled shutdowns on one or more occasions during the Reporting Period.

a. Number of Unscheduled Shutdowns: b. Total Number of Days of Unscheduled Shutdowns:

c. Reason(s) for Unscheduled Shutdowns:

☐ 2. The Active Remedial System had scheduled shutdowns on one or more occasions during the Reporting Period.

a. Number of Scheduled Shutdowns: b. Total Number of Days of Scheduled Shutdowns:

c. Reason(s) for Scheduled Shutdowns:

☐ 3. The Active Remedial System or Active Remedial Monitoring Program was permanently shutdown/discontinued during the Reporting Period.

a. Date of Final System or Monitoring Program Shutdown: (mm/dd/yyyy)

☐ b. No Further Effluent Discharges.

☐ c. No Further Application of Remedial Additives planned; sufficient monitoring completed to demonstrate compliance with 310 CMR 40.0046.

☐ d. No Further Submittals Planned.

☐ e. Other: Describe:

G. SUMMARY STATEMENTS: (check all that apply for the current reporting period)

☒ 1. All Active Remedial System checks and effluent analyses required by the approved plan and/or permit were performed when applicable.

☒ 2. There were no significant problems or prolonged (>25% of reporting period) unscheduled shutdowns of the Active Remedial System.

☒ 3. The Active Remedial System or Active Remedial Monitoring Program operated in conformance with the MCP, and all applicable approval conditions and/or permits.

4. Indicate any Operational Problems or Notes:

☐ 5. Check here if additional/supporting Information, data, maps, and/or sketches are attached to the form.



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup
IRA REMEDIAL MONITORING REPORT
MEASUREMENTS

BWSC105 -B

Pursuant to 310 CMR 40.0400 (SUBPART D)

Remedial System or Monitoring Program: 1 of 2

Release Tracking Number

4

26179

For each Point of Measurement, related to concentration indicate the highest concentration detected during the reporting period, of each oil, hazardous material and/or remedial additive.

For each Point of Measurement for pressure differentials, indicate the lowest pressure differential detected during the reporting period.

Point of Measurement	Date (mm/dd/yyyy)	Contaminant, Measurement and/or Indicator Parameter	Influent Concentration (where applicable)	Midpoint Concentration (where applicable)	(check one)	Check here, if ND/BDL	Permissible Concentration or Pressure Differential	Units	Within Permissible Limits? (Y/N)
					<input checked="" type="checkbox"/> Discharge <input type="checkbox"/> GroundWater Concentration <input type="checkbox"/> Pressure Differential				
SYSTEM	07/28/2020	PFAS	2.051	0.154		<input checked="" type="checkbox"/>	0.020	UG/L	YES

☐ Check here if any additional BWSC105 B, Measurements Form(s), are needed.



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup
IRA REMEDIAL MONITORING REPORT

BWSC105 -A

Pursuant to 310 CMR 40.0400 (SUBPART D)

Release Tracking Number

Remedial System or Monitoring Program: of:

-

A. DESCRIPTION OF ACTIVE OPERATION AND MAINTENANCE ACTIVITY:

1. Type of Active Operation and Maintenance Activity: (check all that apply)

☒ a. Active Remedial System: (check all that apply)

☐ i. NAPL Recovery

☐ ii. Soil Vapor Extraction/Bioventing

☐ iii. Vapor-phase Carbon Adsorption

☒ iv. Groundwater Recovery

☐ v. Dual/Multi-phase Extraction

☒ vi. Aqueous-phase Carbon Adsorption

☐ vii. Air Stripping

☐ viii. Sparging/Biosparging

☐ ix. Cat/Thermal Oxidation

☐ x. Other Describe: _____

☐ b. Active Exposure Pathway Elimination Measure

Active Exposure Pathway Mitigation System to address (check one): ☐ i. Indoor Air ☐ ii. Drinking Water

☐ c. Application of Remedial Additives: (check all that apply)

☐ i. To the Subsurface

☐ ii. To Groundwater (Injection)

☐ iii. To the Surface

☐ d. Active Remedial Monitoring Program Without the Application of Remedial Additives: (check all that apply; Sections C, D and E are not required; attach supporting information, data, maps and/or sketches needed by checking Section G5)

☐ i. Reactive Wall

☐ ii. Natural Attenuation

☐ iii. Other

Describe: _____

2. Mode of Operation: (check one)

☒ a. Continuous

☐ b. Intermittent

☐ c. Pulsed

☐ d. One-time Event Only

☐ e. Other: _____

3. System Effluent/Discharge: (check all that apply)

☐ a. Sanitary Sewer/POTW

☒ b. Groundwater Re-infiltration/Re-injection: (check one)

☐ i. Downgradient

☒ ii. Upgradient

☐ c. Vapor-phase Discharge to Ambient Air: (check one)

☐ i. Off-gas Controls

☐ ii. No Off-gas Controls

☐ d. Drinking Water Supply

☐ e. Surface Water (including Storm Drains)

☐ f. Other Describe: _____

B. MONITORING FREQUENCY:

1. Reporting period that is the subject of this submittal:

From: 7/1/2020

To: 7/31/2020

(mm/dd/yyyy)

(mm/dd/yyyy)

2. Number of monitoring events during the reporting period: (check one)

☐ a. System Startup: (if applicable)

☐ i. Days 1, 3, 6, and then weekly thereafter, for the first month.

☐ ii. Other Describe: _____

☒ b. Post-system Startup (after first month) or Monitoring Program:

☒ i. Monthly

☐ ii. Quarterly

☐ iii. Annually

☐ iv. Other Describe: _____

☐ 3. Check here to certify that the number of required monitoring events were conducted during the reporting period.

C. EFFLUENT/DISCHARGE REGULATION: (check one to indicate how the effluent/discharge limits were established)

☐ 1. NPDES: (check one)

☐ a. Remediation General Permit

☐ b. Individual Permit

☐ c. Emergency Exclusion

Effective Date of Permit: _____

(mm/dd/yyyy)

☐ 2. MCP Performance Standard

MCP Citations(s): _____

☒ 3. DEP Approval Letter

Date of Letter: 11/18/2016

(mm/dd/yyyy)

☐ 4. Other Describe: _____



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

IRA REMEDIAL MONITORING REPORT

Pursuant to 310 CMR 40.0400 (SUBPART D)

Remedial System or Monitoring Program: 2 of 2

BWSC105 -A

Release Tracking Number

4 - 26179

D. WASTEWATER TREATMENT PLANT OPERATOR: (check one)

☒ 1. Required due to Remedial Wastewater Treatment Plant in place for more than 30 days.

a. Name: TJMCGOFF

b. Grade: 4

c. License No: 15570

d. License Exp. Date: 12/31/2021

(mm/dd/yyyy)

☐ 2. Not Required

☐ 3. Not Applicable

E. STATUS OF ACTIVE REMEDIAL SYSTEM OR ACTIVE REMEDIAL MONITORING PROGRAM DURING REPORTING PERIOD: (check all that apply)

☒ 1. The Active Remedial System was functional one or more days during the Reporting Period.

a. Days System was Fully Functional: 31

b. GW Recovered (gals): 430673

c. NAPL Recovered (gals):

d. GW Discharged (gals): 430673

e. Avg. Soil Gas Recovery Rate (scfm):

f. Avg. Sparging Rate (scfm):

☐ 2. Remedial Additives: (check all that apply)

☐ a. No Remedial Additives applied during the Reporting Period.

☐ b. Enhanced Bioremediation Additives applied: (total quantity applied at the site for the current reporting period)

☐ i. Nitrogen/Phosphorus:

☐ ii. Peroxides:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units

☐ iii. Microorganisms:

☐ iv. Other:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units

☐ c. Chemical oxidation/reduction additives applied: (total quantity applied at the site for the current reporting period)

☐ i. Permanganates:

☐ ii. Peroxides:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units

☐ iii. Persulfates:

☐ iv. Other:

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup

IRA REMEDIAL MONITORING REPORT

Pursuant to 310 CMR 40.0400 (SUBPART D)

Remedial System or Monitoring Program: 2 of 2

BWSC105 -A

Release Tracking Number

4 - 26179

E. STATUS OF ACTIVE REMEDIAL SYSTEM OR ACTIVE REMEDIAL MONITORING PROGRAM DURING REPORTING PERIOD: (cont.)

☐ d. Other additives applied: (total quantity applied at the site for the current reporting period)

Name of Additive	Date	Quantity	Units

Name of Additive	Date	Quantity	Units

☐ e. Check here if any additional Remedial Additives were applied. Attach list of additional additives and include Name of Additive, Date Applied, Quantity Applied and Units (in gals. or lbs.)

F. SHUTDOWNS OF ACTIVE REMEDIAL SYSTEM OR ACTIVE REMEDIAL MONITORING PROGRAM: (check all that apply)

☐ 1. The Active Remedial System had unscheduled shutdowns on one or more occasions during the Reporting Period.

a. Number of Unscheduled Shutdowns: _____ b. Total Number of Days of Unscheduled Shutdowns: _____

c. Reason(s) for Unscheduled Shutdowns: _____

☐ 2. The Active Remedial System had scheduled shutdowns on one or more occasions during the Reporting Period.

a. Number of Scheduled Shutdowns: _____ b. Total Number of Days of Scheduled Shutdowns: _____

c. Reason(s) for Scheduled Shutdowns: _____

☐ 3. The Active Remedial System or Active Remedial Monitoring Program was permanently shutdown/discontinued during the Reporting Period.

a. Date of Final System or Monitoring Program Shutdown: _____
(mm/dd/yyyy)

☐ b. No Further Effluent Discharges.

☐ c. No Further Application of Remedial Additives planned; sufficient monitoring completed to demonstrate compliance with 310 CMR 40.0046.

☐ d. No Further Submittals Planned.

☐ e. Other: Describe: _____

G. SUMMARY STATEMENTS: (check all that apply for the current reporting period)

☒ 1. All Active Remedial System checks and effluent analyses required by the approved plan and/or permit were performed when applicable.

☒ 2. There were no significant problems or prolonged (>25% of reporting period) unscheduled shutdowns of the Active Remedial System.

☒ 3. The Active Remedial System or Active Remedial Monitoring Program operated in conformance with the MCP, and all applicable approval conditions and/or permits.

4. Indicate any Operational Problems or Notes:

☐ 5. Check here if additional/supporting Information, data, maps, and/or sketches are attached to the form.



Massachusetts Department of Environmental Protection
Bureau of Waste Site Cleanup
IRA REMEDIAL MONITORING REPORT
MEASUREMENTS

BWSC105 -B

Pursuant to 310 CMR 40.0400 (SUBPART D)

Remedial System or Monitoring Program: 2 of 2

Release Tracking Number

4

26179

For each Point of Measurement, related to concentration indicate the highest concentration detected during the reporting period, of each oil, hazardous material and/or remedial additive.

For each Point of Measurement for pressure differentials, indicate the lowest pressure differential detected during the reporting period.

Point of Measurement	Date (mm/dd/yyyy)	Contaminant, Measurement and/or Indicator Parameter	Influent Concentration (where applicable)	Midpoint Concentration (where applicable)	(check one)	Check here, if ND/BDL	Permissible Concentration or Pressure Differential	Units	Within Permissible Limits? (Y/N)
					<input checked="" type="checkbox"/> Discharge <input type="checkbox"/> GroundWater Concentration <input type="checkbox"/> Pressure Differential				
SYSTEM	07/28/2020	PFAS	2.051	0.115		<input checked="" type="checkbox"/>	0.020	UG/L	YES

☐ Check here if any additional BWSC105 B, Measurements Form(s), are needed.



Your Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY
Your C.O.C. #: 731070-03-01

Attention: Steven Tebo

Barnstable County
3195 Main Street
PO Box 427
Barnstable, MA
USA 02630

Report Date: 2020/08/17
Report #: R6295472
Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C0J4379

Received: 2020/07/31, 12:45

Sample Matrix: Water
Samples Received: 5

Analyses	Quantity	Date	Date	Laboratory Method	Analytical Method
		Extracted	Analyzed		
Low level PFOS and PFOA by SPE/LCMS (1)	2	2020/08/08	2020/08/08	CAM SOP-00894	EPA 537 m
Low level PFOS and PFOA by SPE/LCMS (1)	3	2020/08/08	2020/08/09	CAM SOP-00894	EPA 537 m

Remarks:

Bureau Veritas Laboratories are accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by BV Labs are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in BV Labs profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and BV Labs in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

BV Labs liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. BV Labs has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by BV Labs, unless otherwise agreed in writing. BV Labs is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by BV Labs, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Per- and polyfluoroalkyl substances (PFAS) identified as surrogates on the certificate of analysis represent the extracted internal standard.



Your Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY
Your C.O.C. #: 731070-03-01

Attention: Steven Tebo

Barnstable County
3195 Main Street
PO Box 427
Barnstable, MA
USA 02630

Report Date: 2020/08/17
Report #: R6295472
Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C0J4379

Received: 2020/07/31, 12:45

Encryption Key

Stephanie Pollen
Project Manager
17 Aug 2020 13:19:20

Please direct all questions regarding this Certificate of Analysis to your Project Manager.
Stephanie Pollen, Project Manager
Email: Stephanie.Pollen@bvlabs.com
Phone# (905)817-5830

=====

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



BUREAU
VERITAS

BV Labs Job #: COJ4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

RESULTS OF ANALYSES OF WATER

BV Labs ID		NGL716			NGL717			
Sampling Date		2020/07/28 14:45			2020/07/28 14:55			
COC Number		731070-03-01			731070-03-01			
	UNITS	INFLUENT(PRW-4)	RDL	MDL	SYSTEM#1 MIDPOINT	RDL	MDL	QC Batch
Perfluorinated Compounds								
Perfluorobutanoic acid (PFBA)	ng/L	30	20	6.7	6.6	2.0	0.67	6879185
Perfluoropentanoic acid (PFPeA)	ng/L	79	20	5.2	8.9	2.0	0.52	6879185
Perfluorohexanoic acid (PFHxA)	ng/L	81	20	7.0	8.0	2.0	0.70	6879185
Perfluoroheptanoic acid (PFHpA)	ng/L	52	20	5.1	3.9	2.0	0.51	6879185
Perfluorooctanoic acid (PFOA)	ng/L	44	20	4.9	3.4	2.0	0.49	6879185
Perfluorononanoic acid (PFNA)	ng/L	43	20	8.0	3.0	2.0	0.80	6879185
Perfluorodecanoic acid (PFDA)	ng/L	12	20	6.4	0.96	2.0	0.64	6879185
Perfluoroundecanoic acid (PFUnA)	ng/L	48	20	7.7	3.9	2.0	0.77	6879185
Perfluorododecanoic acid (PFDoA)	ng/L	<5.9	20	5.9	<0.59	2.0	0.59	6879185
Perfluorotridecanoic acid (PFTRDA)	ng/L	<4.8	20	4.8	<0.48	2.0	0.48	6879185
Perfluorotetradecanoic acid(PFTEDA)	ng/L	<3.7	20	3.7	<0.37	2.0	0.37	6879185
Perfluorobutanesulfonic acid (PFBS)	ng/L	8.6	20	4.7	0.59	2.0	0.47	6879185
Perfluoropentanesulfonic acid PFPes	ng/L	14	20	7.3	0.87	2.0	0.73	6879185
Perfluorohexanesulfonic acid(PFHxS)	ng/L	200	20	5.3	13	2.0	0.53	6879185
Perfluoroheptanesulfonic acid PFHpS	ng/L	<5.7	20	5.7	<0.57	2.0	0.57	6879185
Perfluorooctanesulfonic acid (PFOS)	ng/L	1700	200	43	130	20	4.3	6879185
Perfluorononanesulfonic acid (PFNS)	ng/L	<6.4	20	6.4	<0.64	2.0	0.64	6879185
Perfluorodecanesulfonic acid (PFDS)	ng/L	<5.3	20	5.3	<0.53	2.0	0.53	6879185
Perfluorooctane Sulfonamide (PFOSA)	ng/L	<8.1	40	8.1	<0.81	4.0	0.81	6879185
6:2 Fluorotelomer sulfonic acid	ng/L	140	40	5.9	9.6	4.0	0.59	6879185
8:2 Fluorotelomer sulfonic acid	ng/L	210	40	7.5	16	4.0	0.75	6879185
Surrogate Recovery (%)								
13C2-6:2-Fluorotelomersulfonic Acid	%	89	N/A	N/A	85	N/A	N/A	6879185
13C2-8:2-Fluorotelomersulfonic Acid	%	92	N/A	N/A	79	N/A	N/A	6879185
13C2-Perfluorodecanoic acid	%	101	N/A	N/A	73	N/A	N/A	6879185
13C2-Perfluorododecanoic acid	%	96	N/A	N/A	68	N/A	N/A	6879185
13C2-Perfluorohexanoic acid	%	99	N/A	N/A	76	N/A	N/A	6879185
13C2-perfluorotetradecanoic acid	%	86	N/A	N/A	61	N/A	N/A	6879185
13C2-Perfluoroundecanoic acid	%	93	N/A	N/A	70	N/A	N/A	6879185
13C3-Perfluorobutanesulfonic acid	%	98	N/A	N/A	89	N/A	N/A	6879185
13C4-Perfluorobutanoic acid	%	97	N/A	N/A	70	N/A	N/A	6879185
13C4-Perfluoroheptanoic acid	%	97	N/A	N/A	75	N/A	N/A	6879185
13C4-Perfluorooctanesulfonic acid	%	98	N/A	N/A	79	N/A	N/A	6879185
RDL = Reportable Detection Limit								
QC Batch = Quality Control Batch								
N/A = Not Applicable								



BUREAU
VERITAS

BV Labs Job #: COJ4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

RESULTS OF ANALYSES OF WATER

BV Labs ID		NGL716			NGL717			
Sampling Date		2020/07/28 14:45			2020/07/28 14:55			
COC Number		731070-03-01			731070-03-01			
	UNITS	INFLUENT(PRW-4)	RDL	MDL	SYSTEM#1 MIDPOINT	RDL	MDL	QC Batch
13C4-Perfluorooctanoic acid	%	105	N/A	N/A	78	N/A	N/A	6879185
13C5-Perfluorononanoic acid	%	102	N/A	N/A	79	N/A	N/A	6879185
13C5-Perfluoropentanoic acid	%	96	N/A	N/A	72	N/A	N/A	6879185
13C8-Perfluorooctane Sulfonamide	%	55	N/A	N/A	35	N/A	N/A	6879185
18O2-Perfluorohexanesulfonic acid	%	103	N/A	N/A	91	N/A	N/A	6879185
RDL = Reportable Detection Limit QC Batch = Quality Control Batch N/A = Not Applicable								

BUREAU
VERITAS

BV Labs Job #: C0J4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

RESULTS OF ANALYSES OF WATER

BV Labs ID		NGL718	NGL720	NGL721			
Sampling Date		2020/07/28 15:00	2020/07/28 15:10	2020/07/28 15:00			
COC Number		731070-03-01	731070-03-01	731070-03-01			
	UNITS	SYSTEM#1 EFFLUENT	SYSTEM#2 MIDPOINT	SYSTEM#2 EFFLUENT	RDL	MDL	QC Batch
Perfluorinated Compounds							
Perfluorobutanoic acid (PFBA)	ng/L	<0.67	10	<0.67	2.0	0.67	6879185
Perfluoropentanoic acid (PFPeA)	ng/L	<0.52	15	<0.52	2.0	0.52	6879185
Perfluorohexanoic acid (PFHxA)	ng/L	<0.70	11	<0.70	2.0	0.70	6879185
Perfluoroheptanoic acid (PFHpA)	ng/L	<0.51	5.7	<0.51	2.0	0.51	6879185
Perfluorooctanoic acid (PFOA)	ng/L	<0.49	3.8	<0.49	2.0	0.49	6879185
Perfluorononanoic acid (PFNA)	ng/L	<0.80	3.3	<0.80	2.0	0.80	6879185
Perfluorodecanoic acid (PFDA)	ng/L	<0.64	0.76	<0.64	2.0	0.64	6879185
Perfluoroundecanoic acid (PFUnA)	ng/L	<0.77	3.2	<0.77	2.0	0.77	6879185
Perfluorododecanoic acid (PFDoA)	ng/L	<0.59	<0.59	<0.59	2.0	0.59	6879185
Perfluorotridecanoic acid (PFTRDA)	ng/L	<0.48	<0.48	<0.48	2.0	0.48	6879185
Perfluorotetradecanoic acid (PFTEDA)	ng/L	<0.37	<0.37	<0.37	2.0	0.37	6879185
Perfluorobutanesulfonic acid (PFBS)	ng/L	<0.47	0.79	<0.47	2.0	0.47	6879185
Perfluoropentanesulfonic acid PFPeS	ng/L	<0.73	1.2	<0.73	2.0	0.73	6879185
Perfluorohexanesulfonic acid (PFHxS)	ng/L	<0.53	17	<0.53	2.0	0.53	6879185
Perfluoroheptanesulfonic acid PFHpS	ng/L	<0.57	<0.57	<0.57	2.0	0.57	6879185
Perfluorooctanesulfonic acid (PFOS)	ng/L	<0.43	84	<0.43	2.0	0.43	6879185
Perfluorononanesulfonic acid (PFNS)	ng/L	<0.64	<0.64	<0.64	2.0	0.64	6879185
Perfluorodecanesulfonic acid (PFDS)	ng/L	<0.53	<0.53	<0.53	2.0	0.53	6879185
Perfluorooctane Sulfonamide (PFOSA)	ng/L	<0.81	<0.81	<0.81	4.0	0.81	6879185
6:2 Fluorotelomer sulfonic acid	ng/L	<0.59	15	<0.59	4.0	0.59	6879185
8:2 Fluorotelomer sulfonic acid	ng/L	<0.75	12	<0.75	4.0	0.75	6879185
Surrogate Recovery (%)							
13C2-6:2-Fluorotelomersulfonic Acid	%	91	79	94	N/A	N/A	6879185
13C2-8:2-Fluorotelomersulfonic Acid	%	83	76	81	N/A	N/A	6879185
13C2-Perfluorodecanoic acid	%	88	86	96	N/A	N/A	6879185
13C2-Perfluorododecanoic acid	%	83	80	86	N/A	N/A	6879185
13C2-Perfluorohexanoic acid	%	93	86	90	N/A	N/A	6879185
13C2-perfluorotetradecanoic acid	%	85	75	83	N/A	N/A	6879185
13C2-Perfluoroundecanoic acid	%	80	78	82	N/A	N/A	6879185
13C3-Perfluorobutanesulfonic acid	%	96	89	101	N/A	N/A	6879185
13C4-Perfluorobutanoic acid	%	85	81	86	N/A	N/A	6879185
13C4-Perfluoroheptanoic acid	%	90	88	94	N/A	N/A	6879185
13C4-Perfluorooctanesulfonic acid	%	94	85	94	N/A	N/A	6879185
RDL = Reportable Detection Limit							
QC Batch = Quality Control Batch							
N/A = Not Applicable							



BUREAU
VERITAS

BV Labs Job #: C0J4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

RESULTS OF ANALYSES OF WATER

BV Labs ID		NGL718	NGL720	NGL721			
Sampling Date		2020/07/28 15:00	2020/07/28 15:10	2020/07/28 15:00			
COC Number		731070-03-01	731070-03-01	731070-03-01			
	UNITS	SYSTEM#1 EFFLUENT	SYSTEM#2 MIDPOINT	SYSTEM#2 EFFLUENT	RDL	MDL	QC Batch
13C4-Perfluorooctanoic acid	%	94	87	97	N/A	N/A	6879185
13C5-Perfluorononanoic acid	%	95	92	102	N/A	N/A	6879185
13C5-Perfluoropentanoic acid	%	86	82	89	N/A	N/A	6879185
13C8-Perfluorooctane Sulfonamide	%	55	58	60	N/A	N/A	6879185
18O2-Perfluorohexanesulfonic acid	%	103	102	106	N/A	N/A	6879185
RDL = Reportable Detection Limit QC Batch = Quality Control Batch N/A = Not Applicable							



BUREAU
VERITAS

BV Labs Job #: COJ4379
Report Date: 2020/08/17

Barnstable County
Client Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY
Sampler Initials: MM

TEST SUMMARY

BV Labs ID: NGL716
Sample ID: INFLUENT(PRW-4)
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Low level PFOS and PFOA by SPE/LCMS	LCMS	6879185	2020/08/08	2020/08/08	Adnan Khan

BV Labs ID: NGL717
Sample ID: SYSTEM#1 MIDPOINT
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Low level PFOS and PFOA by SPE/LCMS	LCMS	6879185	2020/08/08	2020/08/08	Adnan Khan

BV Labs ID: NGL718
Sample ID: SYSTEM#1 EFFLUENT
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Low level PFOS and PFOA by SPE/LCMS	LCMS	6879185	2020/08/08	2020/08/09	Adnan Khan

BV Labs ID: NGL720
Sample ID: SYSTEM#2 MIDPOINT
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Low level PFOS and PFOA by SPE/LCMS	LCMS	6879185	2020/08/08	2020/08/09	Adnan Khan

BV Labs ID: NGL721
Sample ID: SYSTEM#2 EFFLUENT
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Low level PFOS and PFOA by SPE/LCMS	LCMS	6879185	2020/08/08	2020/08/09	Adnan Khan



BUREAU
VERITAS

BV Labs Job #: C0J4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

GENERAL COMMENTS

Sample NGL716 [INFLUENT(PRW-4)] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL717 [SYSTEM#1 MIDPOINT] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, sample required dilution. Detection limits were adjusted accordingly.

Results relate only to the items tested.



BUREAU
VERITAS

BV Labs Job #: COJ4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

QUALITY ASSURANCE REPORT

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6879185	AKH	Spiked Blank	13C2-6:2-Fluorotelomersulfonic Acid	2020/08/08		97	%	50 - 150
			13C2-8:2-Fluorotelomersulfonic Acid	2020/08/08		85	%	50 - 150
			13C2-Perfluorodecanoic acid	2020/08/08		96	%	50 - 150
			13C2-Perfluorododecanoic acid	2020/08/08		82	%	50 - 150
			13C2-Perfluorohexanoic acid	2020/08/08		98	%	50 - 150
			13C2-perfluorotetradecanoic acid	2020/08/08		79	%	50 - 150
			13C2-Perfluoroundecanoic acid	2020/08/08		83	%	50 - 150
			13C3-Perfluorobutanesulfonic acid	2020/08/08		99	%	50 - 150
			13C4-Perfluorobutanoic acid	2020/08/08		101	%	50 - 150
			13C4-Perfluoroheptanoic acid	2020/08/08		102	%	50 - 150
			13C4-Perfluorooctanesulfonic acid	2020/08/08		98	%	50 - 150
			13C4-Perfluorooctanoic acid	2020/08/08		103	%	50 - 150
			13C5-Perfluorononanoic acid	2020/08/08		102	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/08		100	%	50 - 150
			13C8-Perfluorooctane Sulfonamide	2020/08/08		79	%	20 - 130
			18O2-Perfluorohexanesulfonic acid	2020/08/08		106	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/08		103	%	70 - 130
			Perfluoropentanoic acid (PFPeA)	2020/08/08		104	%	70 - 130
			Perfluorohexanoic acid (PFHxA)	2020/08/08		105	%	70 - 130
			Perfluoroheptanoic acid (PFHpA)	2020/08/08		102	%	70 - 130
			Perfluorooctanoic acid (PFOA)	2020/08/08		103	%	70 - 130
			Perfluorononanoic acid (PFNA)	2020/08/08		106	%	70 - 130
			Perfluorodecanoic acid (PFDA)	2020/08/08		106	%	70 - 130
			Perfluoroundecanoic acid (PFUnA)	2020/08/08		104	%	70 - 130
			Perfluorododecanoic acid (PFDoA)	2020/08/08		102	%	70 - 130
			Perfluorotridecanoic acid (PFTRDA)	2020/08/08		110	%	70 - 130
			Perfluorotetradecanoic acid (PFTEDA)	2020/08/08		108	%	70 - 130
			Perfluorobutanesulfonic acid (PFBS)	2020/08/08		102	%	70 - 130
			Perfluoropentanesulfonic acid PFPes	2020/08/08		105	%	70 - 130
			Perfluorohexanesulfonic acid (PFHxS)	2020/08/08		101	%	70 - 130
			Perfluoroheptanesulfonic acid PFHpS	2020/08/08		102	%	70 - 130
			Perfluorooctanesulfonic acid (PFOS)	2020/08/08		106	%	70 - 130
			Perfluorononanesulfonic acid (PFNS)	2020/08/08		89	%	70 - 130
			Perfluorodecanesulfonic acid (PFDS)	2020/08/08		93	%	70 - 130
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/08		107	%	70 - 130
			6:2 Fluorotelomer sulfonic acid	2020/08/08		100	%	70 - 130
			8:2 Fluorotelomer sulfonic acid	2020/08/08		110	%	70 - 130
6879185	AKH	Spiked Blank DUP	13C2-6:2-Fluorotelomersulfonic Acid	2020/08/08		92	%	50 - 150
			13C2-8:2-Fluorotelomersulfonic Acid	2020/08/08		84	%	50 - 150
			13C2-Perfluorodecanoic acid	2020/08/08		95	%	50 - 150
			13C2-Perfluorododecanoic acid	2020/08/08		82	%	50 - 150
			13C2-Perfluorohexanoic acid	2020/08/08		92	%	50 - 150
			13C2-perfluorotetradecanoic acid	2020/08/08		82	%	50 - 150
			13C2-Perfluoroundecanoic acid	2020/08/08		82	%	50 - 150
			13C3-Perfluorobutanesulfonic acid	2020/08/08		94	%	50 - 150
			13C4-Perfluorobutanoic acid	2020/08/08		92	%	50 - 150
			13C4-Perfluoroheptanoic acid	2020/08/08		93	%	50 - 150
			13C4-Perfluorooctanesulfonic acid	2020/08/08		95	%	50 - 150
			13C4-Perfluorooctanoic acid	2020/08/08		94	%	50 - 150
			13C5-Perfluorononanoic acid	2020/08/08		94	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/08		94	%	50 - 150

BUREAU
VERITAS

BV Labs Job #: C0J4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

QUALITY ASSURANCE REPORT(CONT'D)

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6879185	AKH	RPD	13C8-Perfluorooctane Sulfonamide	2020/08/08		70	%	20 - 130
			18O2-Perfluorohexanesulfonic acid	2020/08/08		106	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/08		104	%	70 - 130
			Perfluoropentanoic acid (PFPeA)	2020/08/08		103	%	70 - 130
			Perfluorohexanoic acid (PFHxA)	2020/08/08		104	%	70 - 130
			Perfluoroheptanoic acid (PFHpA)	2020/08/08		103	%	70 - 130
			Perfluorooctanoic acid (PFOA)	2020/08/08		106	%	70 - 130
			Perfluorononanoic acid (PFNA)	2020/08/08		106	%	70 - 130
			Perfluorodecanoic acid (PFDA)	2020/08/08		105	%	70 - 130
			Perfluoroundecanoic acid (PFUnA)	2020/08/08		109	%	70 - 130
			Perfluorododecanoic acid (PFDoA)	2020/08/08		105	%	70 - 130
			Perfluorotridecanoic acid (PFTRDA)	2020/08/08		107	%	70 - 130
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/08		107	%	70 - 130
			Perfluorobutanesulfonic acid (PFBS)	2020/08/08		103	%	70 - 130
			Perfluoropentanesulfonic acid PFPes	2020/08/08		105	%	70 - 130
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/08		95	%	70 - 130
			Perfluoroheptanesulfonic acid PFHpS	2020/08/08		101	%	70 - 130
			Perfluorooctanesulfonic acid (PFOS)	2020/08/08		110	%	70 - 130
			Perfluorononanesulfonic acid (PFNS)	2020/08/08		92	%	70 - 130
			Perfluorodecanesulfonic acid (PFDS)	2020/08/08		95	%	70 - 130
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/08		104	%	70 - 130
			6:2 Fluorotelomer sulfonic acid	2020/08/08		99	%	70 - 130
			8:2 Fluorotelomer sulfonic acid	2020/08/08		111	%	70 - 130
			Perfluorobutanoic acid (PFBA)	2020/08/08	1.1		%	30
			Perfluoropentanoic acid (PFPeA)	2020/08/08	1.7		%	30
			Perfluorohexanoic acid (PFHxA)	2020/08/08	0.89		%	30
			Perfluoroheptanoic acid (PFHpA)	2020/08/08	0.93		%	30
			Perfluorooctanoic acid (PFOA)	2020/08/08	2.7		%	30
			Perfluorononanoic acid (PFNA)	2020/08/08	0.58		%	30
			Perfluorodecanoic acid (PFDA)	2020/08/08	0.50		%	30
			Perfluoroundecanoic acid (PFUnA)	2020/08/08	4.6		%	30
			Perfluorododecanoic acid (PFDoA)	2020/08/08	3.3		%	30
			Perfluorotridecanoic acid (PFTRDA)	2020/08/08	2.8		%	30
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/08	1.5		%	30
			Perfluorobutanesulfonic acid (PFBS)	2020/08/08	0.50		%	30
			Perfluoropentanesulfonic acid PFPes	2020/08/08	0.065		%	30
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/08	5.3		%	30
			Perfluoroheptanesulfonic acid PFHpS	2020/08/08	0.62		%	30
			Perfluorooctanesulfonic acid (PFOS)	2020/08/08	3.5		%	30
			Perfluorononanesulfonic acid (PFNS)	2020/08/08	3.0		%	30
			Perfluorodecanesulfonic acid (PFDS)	2020/08/08	1.2		%	30
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/08	2.7		%	30
			6:2 Fluorotelomer sulfonic acid	2020/08/08	1.1		%	30
			8:2 Fluorotelomer sulfonic acid	2020/08/08	0.51		%	30
6879185	AKH	Method Blank	13C2-6:2-Fluorotelomersulfonic Acid	2020/08/08		102	%	50 - 150
			13C2-8:2-Fluorotelomersulfonic Acid	2020/08/08		95	%	50 - 150
			13C2-Perfluorodecanoic acid	2020/08/08		114	%	50 - 150
			13C2-Perfluorododecanoic acid	2020/08/08		97	%	50 - 150
			13C2-Perfluorohexanoic acid	2020/08/08		109	%	50 - 150
			13C2-perfluorotetradecanoic acid	2020/08/08		89	%	50 - 150
			13C2-Perfluoroundecanoic acid	2020/08/08		99	%	50 - 150



BUREAU
VERITAS

BV Labs Job #: C0J4379
Report Date: 2020/08/17

Barnstable County
Client Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY
Sampler Initials: MM

QUALITY ASSURANCE REPORT(CONT'D)

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
			13C3-Perfluorobutanesulfonic acid	2020/08/08		103	%	50 - 150
			13C4-Perfluorobutanoic acid	2020/08/08		106	%	50 - 150
			13C4-Perfluoroheptanoic acid	2020/08/08		110	%	50 - 150
			13C4-Perfluorooctanesulfonic acid	2020/08/08		105	%	50 - 150
			13C4-Perfluorooctanoic acid	2020/08/08		109	%	50 - 150
			13C5-Perfluorononanoic acid	2020/08/08		117	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/08		108	%	50 - 150
			13C8-Perfluorooctane Sulfonamide	2020/08/08		71	%	20 - 130
			18O2-Perfluorohexanesulfonic acid	2020/08/08		113	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/08	<0.67		ng/L	
			Perfluoropentanoic acid (PFPeA)	2020/08/08	<0.52		ng/L	
			Perfluorohexanoic acid (PFHxA)	2020/08/08	<0.70		ng/L	
			Perfluoroheptanoic acid (PFHpA)	2020/08/08	<0.51		ng/L	
			Perfluorooctanoic acid (PFOA)	2020/08/08	<0.49		ng/L	
			Perfluorononanoic acid (PFNA)	2020/08/08	<0.80		ng/L	
			Perfluorodecanoic acid (PFDA)	2020/08/08	<0.64		ng/L	
			Perfluoroundecanoic acid (PFUnA)	2020/08/08	<0.77		ng/L	
			Perfluorododecanoic acid (PFDoA)	2020/08/08	<0.59		ng/L	
			Perfluorotridecanoic acid (PFTRDA)	2020/08/08	<0.48		ng/L	
			Perfluorotetradecanoic acid (PFTEDA)	2020/08/08	<0.37		ng/L	
			Perfluorobutanesulfonic acid (PFBS)	2020/08/08	<0.47		ng/L	
			Perfluoropentanesulfonic acid (PFPeS)	2020/08/08	<0.73		ng/L	
			Perfluorohexanesulfonic acid (PFHxS)	2020/08/08	<0.53		ng/L	
			Perfluoroheptanesulfonic acid (PFHpS)	2020/08/08	<0.57		ng/L	
			Perfluorooctanesulfonic acid (PFOS)	2020/08/08	<0.43		ng/L	
			Perfluorononanesulfonic acid (PFNS)	2020/08/08	<0.64		ng/L	
			Perfluorodecanesulfonic acid (PFDS)	2020/08/08	<0.53		ng/L	
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/08	<0.81		ng/L	
			6:2 Fluorotelomer sulfonic acid	2020/08/08	<0.59		ng/L	
			8:2 Fluorotelomer sulfonic acid	2020/08/08	<0.75		ng/L	

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

Surrogate: A pure or isotopically labeled compound whose behavior mirrors the analytes of interest. Used to evaluate extraction efficiency.



BUREAU
VERITAS

BV Labs Job #: COJ4379

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

Sampler Initials: MM

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

Colm McNamara, Senior Analyst, Liquid Chromatography

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



CHAIN OF CUSTODY RECORD

Page 10

INVOICE TO:		REPORT TO:		PROJECT INFORMATION:		Laboratory Use Only:			
Company Name: #29803 Barnstable County		Company Name: Steven Tebo		B57344		BV Labs Job #:			
Attention: Accounts Payable		Attention: Steven Tebo		P.O. #:		Bottle Order #:			
Address: 3195 Main Street PO Box 427		Address: 1 Roger Thibault		Project: 6206-BETA		731070			
Barnstable MA 02630		Address: BETA Group		Project Name: Barnstable County		COC #:			
Tel: (508) 362-3828 Ext: 1234		Tel: (508) 375-6603		Site #:		Project Manager:			
Email: eoconnell@barnstablecounty.org, stebo@barnstableco		Email: stebo@barnstablecounty.org, rthibault@barnstableco		Sampled By: M. Mendes		Patricia Legette			
MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE BV LABS DRINKING WATER CHAIN OF CUSTODY				ANALYSIS REQUESTED (PLEASE BE SPECIFIC)				Turnaround Time (TAT) Required: Please provide advance notice for rush projects.	
Regulation 153 (2011)		Other Regulations		Special Instructions		Regular (Standard) TAT:		(will be applied if Rush TAT is not specified):	
<input type="checkbox"/> Table 1 <input type="checkbox"/> Res/Park <input type="checkbox"/> Medium/Fine		<input type="checkbox"/> CCME <input type="checkbox"/> Sanitary Sewer Bylaw		Include 21 PFAS compounds w/ lower KOLs		Standard TAT = 5-7 Working days for most tests.		Please note: Standard TAT for certain tests such as BOD and Dioxins/Furans are > 5 days - contact your Project Manager for details.	
<input type="checkbox"/> Table 2 <input type="checkbox"/> Ind/Comm <input type="checkbox"/> Coarse		<input type="checkbox"/> Reg 558 <input type="checkbox"/> Storm Sewer Bylaw				Job Specific Rush TAT (if applies to entire submission)		Date Required: Time Required:	
<input type="checkbox"/> Table 3 <input type="checkbox"/> Agri/Other <input type="checkbox"/> For RSC		<input type="checkbox"/> MISA <input type="checkbox"/> Municipality				Rush Confirmation Number:		(call lab for #)	
<input type="checkbox"/> Table <input type="checkbox"/>		<input type="checkbox"/> PWQO <input type="checkbox"/> Other				# of Bottles		Comments	
Include Criteria on Certificate of Analysis (Y/N)?				Field Filtered (please circle):		Total PFAS			
Sample Barcode Label		Sample (Location) Identification		Time Sampled		Matrix			
1		INFLUENT (PRW-4)		20/07/28 1445		GW		X	
2		SYSTEM #1 MIDPOINT		1455				X	
3		SYSTEM #1 EFFLUENT		1500				X	
4		SYSTEM #2 MIDPOINT		1510				X	
5		SYSTEM #2 EFFLUENT		20/07/28 1500		GW		X	
6									
7									
8									
9									
10									
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		# jars used and not submitted	
M. Mendes / Mike Mendes				20/07/28		1200		0000/31 1245	
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		Laboratory Use Only	
M. Mendes / Mike Mendes				20/07/28		1200		Time Sensitive	
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		Temperature (°C) on Recd	
M. Mendes / Mike Mendes				20/07/28		1200		4.2/3.4/4.7	
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		Custody Seal	
M. Mendes / Mike Mendes				20/07/28		1200		Present	
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		Intact	
M. Mendes / Mike Mendes				20/07/28		1200		Yes	
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		No	
M. Mendes / Mike Mendes				20/07/28		1200		No	
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		White: BV Labs	
M. Mendes / Mike Mendes				20/07/28		1200		Yellow: Client	
RECEIVED BY: (Signature/Print)				Date: (YY/MM/DD)		Time		SAMPLES MUST BE KEPT COOL (< 10° C) FROM TIME OF SAMPLING UNTIL DELIVERY TO BV LABS	
M. Mendes / Mike Mendes				20/07/28		1200			



Your Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY
Your C.O.C. #: 731070-05-01, 731070-02-01

Attention: Steven Tebo

Barnstable County
3195 Main Street
PO Box 427
Barnstable, MA
USA 02630

Report Date: 2020/08/17
Report #: R6295473
Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C0J4359

Received: 2020/07/31, 12:45

Sample Matrix: Water
Samples Received: 16

Analyses	Quantity	Date	Date	Laboratory Method	Analytical Method
		Extracted	Analyzed		
PFAS in water by SPE/LCMS (1)	13	2020/08/10	2020/08/11	CAM SOP-00894	EPA 537 m
PFAS in water by SPE/LCMS (1)	3	2020/08/06	2020/08/10	CAM SOP-00894	EPA 537 m

Remarks:

Bureau Veritas Laboratories are accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by BV Labs are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in BV Labs profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and BV Labs in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

BV Labs liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. BV Labs has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by BV Labs, unless otherwise agreed in writing. BV Labs is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by BV Labs, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

* RPDs calculated using raw data. The rounding of final results may result in the apparent difference.

(1) Per- and polyfluoroalkyl substances (PFAS) identified as surrogates on the certificate of analysis represent the extracted internal standard.



Your Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY
Your C.O.C. #: 731070-05-01, 731070-02-01

Attention: Steven Tebo

Barnstable County
3195 Main Street
PO Box 427
Barnstable, MA
USA 02630

Report Date: 2020/08/17
Report #: R6295473
Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C0J4359

Received: 2020/07/31, 12:45

Encryption Key

Stephanie Pollen
Project Manager
17 Aug 2020 13:26:11

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Stephanie Pollen, Project Manager

Email: Stephanie.Pollen@bvlabs.com

Phone# (905)817-5830

=====

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL656			NGL657			NGL658			
Sampling Date		2020/07/28 14:25			2020/07/28			2020/07/28 14:20			
COC Number		731070-05-01			731070-05-01			731070-05-01			
	UNITS	PFW-1	RDL	MDL	PFW-5	RDL	MDL	HSW-6	RDL	MDL	QC Batch

Perfluorinated Compounds

Perfluorobutanoic acid (PFBA)	ug/L	0.068	0.020	0.0070	0.021	0.020	0.0070	0.020	0.020	0.0070	6874512
Perfluoropentanoic acid (PFPeA)	ug/L	0.26	0.020	0.0041	0.063	0.020	0.0041	0.13	0.020	0.0041	6874512
Perfluorohexanoic acid (PFHxA)	ug/L	0.26	0.020	0.0064	0.075	0.020	0.0064	0.23	0.020	0.0064	6874512
Perfluoroheptanoic acid (PFHpA)	ug/L	0.16	0.020	0.0071	0.044	0.020	0.0071	0.069	0.020	0.0071	6874512
Perfluorooctanoic acid (PFOA)	ug/L	0.21	0.020	0.0074	0.10	0.020	0.0074	0.080	0.020	0.0074	6874512
Perfluorononanoic acid (PFNA)	ug/L	0.11	0.020	0.0049	0.015	0.020	0.0049	0.040	0.020	0.0049	6874512
Perfluorodecanoic acid (PFDA)	ug/L	0.089	0.020	0.0041	0.011	0.020	0.0041	0.018	0.020	0.0041	6874512
Perfluoroundecanoic acid (PFUnA)	ug/L	0.23	0.020	0.0043	0.033	0.020	0.0043	0.15	0.020	0.0043	6874512
Perfluorododecanoic acid (PFDoA)	ug/L	<0.0068	0.020	0.0068	<0.0068	0.020	0.0068	<0.0068	0.020	0.0068	6874512
Perfluorotridecanoic acid (PFTRDA)	ug/L	<0.0069	0.020	0.0069	<0.0069	0.020	0.0069	<0.0069	0.020	0.0069	6874512
Perfluorotetradecanoic acid (PFTEDA)	ug/L	<0.0067	0.020	0.0067	<0.0067	0.020	0.0067	<0.0067	0.020	0.0067	6874512
Perfluorobutanesulfonic acid (PFBS)	ug/L	0.031	0.020	0.0051	0.012	0.020	0.0051	0.024	0.020	0.0051	6874512
Perfluorohexanesulfonic acid (PFHxS)	ug/L	0.82	0.020	0.0052	0.61	0.020	0.0052	0.35	0.020	0.0052	6874512
Perfluoroheptanesulfonic acid (PFHpS)	ug/L	0.039	0.020	0.0033	0.024	0.020	0.0033	0.0078	0.020	0.0033	6874512
Perfluorooctanesulfonic acid (PFOS)	ug/L	5.2	0.20	0.052	0.98	0.020	0.0052	2.3	0.20	0.052	6874512
Perfluorodecanesulfonic acid (PFDS)	ug/L	<0.0072	0.020	0.0072	<0.0072	0.020	0.0072	<0.0072	0.020	0.0072	6874512
Perfluorooctane Sulfonamide (PFOSA)	ug/L	<0.0066	0.020	0.0066	0.12	0.020	0.0066	<0.0066	0.020	0.0066	6874512
EtFOSA	ug/L	<0.0090	0.020	0.0090	<0.0090	0.020	0.0090	<0.0090	0.020	0.0090	6874512
MeFOSA	ug/L	<0.0035	0.020	0.0035	<0.0035	0.020	0.0035	<0.0035	0.020	0.0035	6874512
EtFOSE	ug/L	<0.0094	0.020	0.0094	<0.0094	0.020	0.0094	<0.0094	0.020	0.0094	6874512
MeFOSE	ug/L	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	6874512
6:2 Fluorotelomer sulfonic acid	ug/L	0.70	0.020	0.0059	0.070	0.020	0.0059	0.25	0.020	0.0059	6879899
8:2 Fluorotelomer sulfonic acid	ug/L	1.3	0.20	0.0059	0.13	0.020	0.0059	0.17	0.020	0.0059	6874512

Surrogate Recovery (%)

13C2-6:2-Fluorotelomersulfonic Acid	%	91	N/A	N/A	95	N/A	N/A	91	N/A	N/A	6879899
13C2-8:2-Fluorotelomersulfonic Acid	%	80	N/A	N/A	79	N/A	N/A	78	N/A	N/A	6874512
13C2-Perfluorodecanoic acid	%	92	N/A	N/A	93	N/A	N/A	83	N/A	N/A	6874512
13C2-Perfluorododecanoic acid	%	86	N/A	N/A	82	N/A	N/A	73	N/A	N/A	6874512
13C2-Perfluorohexanoic acid	%	100	N/A	N/A	96	N/A	N/A	94	N/A	N/A	6874512
13C2-perfluorotetradecanoic acid	%	89	N/A	N/A	78	N/A	N/A	79	N/A	N/A	6874512
13C2-Perfluoroundecanoic acid	%	86	N/A	N/A	85	N/A	N/A	77	N/A	N/A	6874512
13C3-Perfluorobutanesulfonic acid	%	97	N/A	N/A	98	N/A	N/A	92	N/A	N/A	6874512
13C4-Perfluorobutanoic acid	%	103	N/A	N/A	105	N/A	N/A	91	N/A	N/A	6874512
13C4-Perfluoroheptanoic acid	%	99	N/A	N/A	97	N/A	N/A	96	N/A	N/A	6874512

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL656			NGL657			NGL658			
Sampling Date		2020/07/28 14:25			2020/07/28			2020/07/28 14:20			
COC Number		731070-05-01			731070-05-01			731070-05-01			
	UNITS	PFW-1	RDL	MDL	PFW-5	RDL	MDL	HSW-6	RDL	MDL	QC Batch
13C4-Perfluorooctanesulfonic acid	%	90	N/A	N/A	93	N/A	N/A	100	N/A	N/A	6874512
13C4-Perfluorooctanoic acid	%	100	N/A	N/A	99	N/A	N/A	96	N/A	N/A	6874512
13C5-Perfluorononanoic acid	%	99	N/A	N/A	95	N/A	N/A	92	N/A	N/A	6874512
13C5-Perfluoropentanoic acid	%	99	N/A	N/A	98	N/A	N/A	95	N/A	N/A	6874512
13C8-Perfluorooctane Sulfonamide	%	92	N/A	N/A	90	N/A	N/A	85	N/A	N/A	6874512
18O2-Perfluorohexanesulfonic acid	%	96	N/A	N/A	97	N/A	N/A	91	N/A	N/A	6874512
D3-MeFOSA	%	77	N/A	N/A	77	N/A	N/A	68	N/A	N/A	6874512
D5-EtFOSA	%	78	N/A	N/A	76	N/A	N/A	65	N/A	N/A	6874512
D7-MeFOSE	%	87	N/A	N/A	85	N/A	N/A	77	N/A	N/A	6874512
D9-EtFOSE	%	89	N/A	N/A	85	N/A	N/A	73	N/A	N/A	6874512
RDL = Reportable Detection Limit QC Batch = Quality Control Batch N/A = Not Applicable											

BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL659			NGL660			NGL661			
Sampling Date		2020/07/28			2020/07/28 11:00			2020/07/28 15:00			
COC Number		731070-05-01			731070-05-01			731070-05-01			
	UNITS	OW-84	RDL	MDL	DUPLICATE	RDL	MDL	EQUIP-BLANK1	RDL	MDL	QC Batch

Perfluorinated Compounds

Perfluorobutanoic acid (PFBA)	ug/L	<0.0070	0.020	0.0070	0.056	0.020	0.0070	<0.0070	0.020	0.0070	6880244
Perfluoropentanoic acid (PFPeA)	ug/L	0.0076	0.020	0.0041	0.21	0.020	0.0041	<0.0041	0.020	0.0041	6880244
Perfluorohexanoic acid (PFHxA)	ug/L	0.0076	0.020	0.0064	0.20	0.020	0.0064	<0.0064	0.020	0.0064	6880244
Perfluoroheptanoic acid (PFHpA)	ug/L	0.0074	0.020	0.0071	0.13	0.020	0.0071	<0.0071	0.020	0.0071	6880244
Perfluorooctanoic acid (PFOA)	ug/L	0.012	0.020	0.0074	0.17	0.020	0.0074	<0.0074	0.020	0.0074	6880244
Perfluorononanoic acid (PFNA)	ug/L	0.011	0.020	0.0049	0.088	0.020	0.0049	<0.0049	0.020	0.0049	6880244
Perfluorodecanoic acid (PFDA)	ug/L	0.010	0.020	0.0041	0.073	0.020	0.0041	<0.0041	0.020	0.0041	6880244
Perfluoroundecanoic acid (PFUnA)	ug/L	0.031	0.020	0.0043	0.15	0.020	0.0043	<0.0043	0.020	0.0043	6880244
Perfluorododecanoic acid (PFDoA)	ug/L	<0.0068	0.020	0.0068	<0.0068	0.020	0.0068	<0.0068	0.020	0.0068	6880244
Perfluorotridecanoic acid (PFTRDA)	ug/L	<0.0069	0.020	0.0069	<0.0069	0.020	0.0069	<0.0069	0.020	0.0069	6880244
Perfluorotetradecanoic acid (PFTEDA)	ug/L	<0.0067	0.020	0.0067	<0.0067	0.020	0.0067	<0.0067	0.020	0.0067	6880244
Perfluorobutanesulfonic acid (PFBS)	ug/L	<0.0051	0.020	0.0051	0.027	0.020	0.0051	<0.0051	0.020	0.0051	6880244
Perfluorohexanesulfonic acid (PFHxS)	ug/L	0.030	0.020	0.0052	0.61	0.020	0.0052	<0.0052	0.020	0.0052	6880244
Perfluoroheptanesulfonic acid (PFHpS)	ug/L	<0.0033	0.020	0.0033	0.034	0.020	0.0033	<0.0033	0.020	0.0033	6880244
Perfluorooctanesulfonic acid (PFOS)	ug/L	0.17	0.020	0.0052	4.6	0.20	0.052	<0.0052	0.020	0.0052	6880244
Perfluorodecanesulfonic acid (PFDS)	ug/L	<0.0072	0.020	0.0072	<0.0072	0.020	0.0072	<0.0072	0.020	0.0072	6880244
Perfluorooctane Sulfonamide (PFOSA)	ug/L	<0.0066	0.020	0.0066	0.0075	0.020	0.0066	<0.0066	0.020	0.0066	6880244
EtFOSA	ug/L	<0.0090	0.020	0.0090	<0.0090	0.020	0.0090	<0.0090	0.020	0.0090	6880244
MeFOSA	ug/L	<0.0035	0.020	0.0035	<0.0035	0.020	0.0035	<0.0035	0.020	0.0035	6880244
EtFOSE	ug/L	<0.0094	0.020	0.0094	<0.0094	0.020	0.0094	<0.0094	0.020	0.0094	6880244
MeFOSE	ug/L	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	6880244
6:2 Fluorotelomer sulfonic acid	ug/L	<0.0059	0.020	0.0059	0.57	0.020	0.0059	<0.0059	0.020	0.0059	6880244
8:2 Fluorotelomer sulfonic acid	ug/L	<0.0059	0.020	0.0059	1.3	0.20	0.059	<0.0059	0.020	0.0059	6880244

Surrogate Recovery (%)

13C2-4:2-Fluorotelomersulfonic Acid	%	85	N/A	N/A	88	N/A	N/A	102	N/A	N/A	6880244
13C2-6:2-Fluorotelomersulfonic Acid	%	90	N/A	N/A	83	N/A	N/A	98	N/A	N/A	6880244
13C2-8:2-Fluorotelomersulfonic Acid	%	101	N/A	N/A	84	N/A	N/A	99	N/A	N/A	6880244
13C2-Perfluorodecanoic acid	%	96	N/A	N/A	92	N/A	N/A	95	N/A	N/A	6880244
13C2-Perfluorododecanoic acid	%	90	N/A	N/A	94	N/A	N/A	91	N/A	N/A	6880244
13C2-Perfluorohexanoic acid	%	106	N/A	N/A	105	N/A	N/A	103	N/A	N/A	6880244
13C2-perfluorotetradecanoic acid	%	87	N/A	N/A	96	N/A	N/A	82	N/A	N/A	6880244
13C2-Perfluoroundecanoic acid	%	91	N/A	N/A	96	N/A	N/A	95	N/A	N/A	6880244
13C3-Perfluorobutanesulfonic acid	%	101	N/A	N/A	103	N/A	N/A	98	N/A	N/A	6880244
13C4-Perfluorobutanoic acid	%	105	N/A	N/A	103	N/A	N/A	100	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL659			NGL660			NGL661			
Sampling Date		2020/07/28			2020/07/28 11:00			2020/07/28 15:00			
COC Number		731070-05-01			731070-05-01			731070-05-01			
	UNITS	OW-84	RDL	MDL	DUPLICATE	RDL	MDL	EQUIP-BLANK1	RDL	MDL	QC Batch
13C4-Perfluoroheptanoic acid	%	109	N/A	N/A	102	N/A	N/A	103	N/A	N/A	6880244
13C4-Perfluorooctanesulfonic acid	%	102	N/A	N/A	100	N/A	N/A	99	N/A	N/A	6880244
13C4-Perfluorooctanoic acid	%	103	N/A	N/A	102	N/A	N/A	101	N/A	N/A	6880244
13C5-Perfluorononanoic acid	%	103	N/A	N/A	105	N/A	N/A	103	N/A	N/A	6880244
13C5-Perfluoropentanoic acid	%	107	N/A	N/A	103	N/A	N/A	103	N/A	N/A	6880244
13C8-Perfluorooctane Sulfonamide	%	89	N/A	N/A	85	N/A	N/A	85	N/A	N/A	6880244
18O2-Perfluorohexanesulfonic acid	%	103	N/A	N/A	99	N/A	N/A	100	N/A	N/A	6880244
D3-MeFOSA	%	67	N/A	N/A	65	N/A	N/A	64	N/A	N/A	6880244
D5-EtFOSA	%	69	N/A	N/A	71	N/A	N/A	66	N/A	N/A	6880244
D7-MeFOSE	%	76	N/A	N/A	74	N/A	N/A	75	N/A	N/A	6880244
D9-EtFOSE	%	76	N/A	N/A	78	N/A	N/A	77	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL662			NGL663			NGL664			
Sampling Date		2020/07/29 12:25			2020/07/29 10:40			2020/07/29 12:30			
COC Number		731070-05-01			731070-05-01			731070-05-01			
	UNITS	PC-6A	RDL	MDL	PC-38	RDL	MDL	PC-11	RDL	MDL	QC Batch

Perfluorinated Compounds

Perfluorobutanoic acid (PFBA)	ug/L	0.024	0.020	0.0070	<0.0070	0.020	0.0070	0.070	0.040	0.014	6880244
Perfluoropentanoic acid (PFPeA)	ug/L	0.060	0.020	0.0041	<0.0041	0.020	0.0041	0.23	0.040	0.0082	6880244
Perfluorohexanoic acid (PFHxA)	ug/L	0.058	0.020	0.0064	<0.0064	0.020	0.0064	0.22	0.040	0.013	6880244
Perfluoroheptanoic acid (PFHpA)	ug/L	0.043	0.020	0.0071	<0.0071	0.020	0.0071	0.13	0.040	0.014	6880244
Perfluorooctanoic acid (PFOA)	ug/L	0.037	0.020	0.0074	<0.0074	0.020	0.0074	0.13	0.040	0.015	6880244
Perfluorononanoic acid (PFNA)	ug/L	0.044	0.020	0.0049	<0.0049	0.020	0.0049	0.11	0.040	0.0098	6880244
Perfluorodecanoic acid (PFDA)	ug/L	0.011	0.020	0.0041	<0.0041	0.020	0.0041	0.055	0.040	0.0082	6880244
Perfluoroundecanoic acid (PFUnA)	ug/L	0.040	0.020	0.0043	<0.0043	0.020	0.0043	0.12	0.040	0.0086	6880244
Perfluorododecanoic acid (PFDoA)	ug/L	<0.0068	0.020	0.0068	<0.0068	0.020	0.0068	<0.014	0.040	0.014	6880244
Perfluorotridecanoic acid (PFTRDA)	ug/L	<0.0069	0.020	0.0069	<0.0069	0.020	0.0069	<0.014	0.040	0.014	6880244
Perfluorotetradecanoic acid (PFTEDA)	ug/L	<0.0067	0.020	0.0067	<0.0067	0.020	0.0067	<0.013	0.040	0.013	6880244
Perfluorobutanesulfonic acid (PFBS)	ug/L	0.0064	0.020	0.0051	<0.0051	0.020	0.0051	0.030	0.040	0.010	6880244
Perfluorohexanesulfonic acid (PFHxS)	ug/L	0.099	0.020	0.0052	<0.0052	0.020	0.0052	0.61	0.040	0.010	6880244
Perfluoroheptanesulfonic acid (PFHpS)	ug/L	0.0068	0.020	0.0033	<0.0033	0.020	0.0033	0.031	0.040	0.0066	6880244
Perfluorooctanesulfonic acid (PFOS)	ug/L	1.3	0.20	0.052	<0.0052	0.020	0.0052	9.5	0.40	0.10	6880244
Perfluorodecanesulfonic acid (PFDS)	ug/L	<0.0072	0.020	0.0072	<0.0072	0.020	0.0072	<0.014	0.040	0.014	6880244
Perfluorooctane Sulfonamide (PFOSA)	ug/L	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	0.017	0.040	0.013	6880244
EtFOSA	ug/L	<0.0090	0.020	0.0090	<0.0090	0.020	0.0090	<0.018	0.040	0.018	6880244
MeFOSA	ug/L	<0.0035	0.020	0.0035	<0.0035	0.020	0.0035	<0.0070	0.040	0.0070	6880244
EtFOSE	ug/L	<0.0094	0.020	0.0094	<0.0094	0.020	0.0094	<0.019	0.040	0.019	6880244
MeFOSE	ug/L	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	<0.013	0.040	0.013	6880244
6:2 Fluorotelomer sulfonic acid	ug/L	0.016	0.020	0.0059	<0.0059	0.020	0.0059	0.40	0.040	0.012	6880244
8:2 Fluorotelomer sulfonic acid	ug/L	0.0092	0.020	0.0059	<0.0059	0.020	0.0059	1.1	0.040	0.012	6880244

Surrogate Recovery (%)

13C2-4:2-Fluorotelomersulfonic Acid	%	95	N/A	N/A	98	N/A	N/A	96	N/A	N/A	6880244
13C2-6:2-Fluorotelomersulfonic Acid	%	103	N/A	N/A	102	N/A	N/A	94	N/A	N/A	6880244
13C2-8:2-Fluorotelomersulfonic Acid	%	109	N/A	N/A	108	N/A	N/A	96	N/A	N/A	6880244
13C2-Perfluorodecanoic acid	%	108	N/A	N/A	104	N/A	N/A	100	N/A	N/A	6880244
13C2-Perfluorododecanoic acid	%	98	N/A	N/A	98	N/A	N/A	99	N/A	N/A	6880244
13C2-Perfluorohexanoic acid	%	115	N/A	N/A	111	N/A	N/A	110	N/A	N/A	6880244
13C2-perfluorotetradecanoic acid	%	82	N/A	N/A	88	N/A	N/A	88	N/A	N/A	6880244
13C2-Perfluoroundecanoic acid	%	103	N/A	N/A	100	N/A	N/A	100	N/A	N/A	6880244
13C3-Perfluorobutanesulfonic acid	%	113	N/A	N/A	108	N/A	N/A	104	N/A	N/A	6880244
13C4-Perfluorobutanoic acid	%	113	N/A	N/A	108	N/A	N/A	105	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL662			NGL663			NGL664			
Sampling Date		2020/07/29 12:25			2020/07/29 10:40			2020/07/29 12:30			
COC Number		731070-05-01			731070-05-01			731070-05-01			
	UNITS	PC-6A	RDL	MDL	PC-38	RDL	MDL	PC-11	RDL	MDL	QC Batch
13C4-Perfluoroheptanoic acid	%	117	N/A	N/A	116	N/A	N/A	111	N/A	N/A	6880244
13C4-Perfluorooctanesulfonic acid	%	87	N/A	N/A	105	N/A	N/A	100	N/A	N/A	6880244
13C4-Perfluorooctanoic acid	%	118	N/A	N/A	115	N/A	N/A	109	N/A	N/A	6880244
13C5-Perfluorononanoic acid	%	119	N/A	N/A	113	N/A	N/A	110	N/A	N/A	6880244
13C5-Perfluoropentanoic acid	%	115	N/A	N/A	111	N/A	N/A	108	N/A	N/A	6880244
13C8-Perfluorooctane Sulfonamide	%	92	N/A	N/A	93	N/A	N/A	90	N/A	N/A	6880244
18O2-Perfluorohexanesulfonic acid	%	115	N/A	N/A	107	N/A	N/A	105	N/A	N/A	6880244
D3-MeFOSA	%	63	N/A	N/A	71	N/A	N/A	67	N/A	N/A	6880244
D5-EtFOSA	%	66	N/A	N/A	69	N/A	N/A	71	N/A	N/A	6880244
D7-MeFOSE	%	78	N/A	N/A	78	N/A	N/A	76	N/A	N/A	6880244
D9-EtFOSE	%	75	N/A	N/A	77	N/A	N/A	74	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL665			NGL666			NGL667			
Sampling Date		2020/07/29 13:30			2020/07/29 11:40			2020/07/29 10:30			
COC Number		731070-05-01			731070-02-01			731070-02-01			
	UNITS	PC-1	RDL	MDL	PE-16D	RDL	MDL	PC-30	RDL	MDL	QC Batch

Perfluorinated Compounds

Perfluorobutanoic acid (PFBA)	ug/L	0.040	0.020	0.0070	0.031	0.020	0.0070	0.024	0.020	0.0070	6880244
Perfluoropentanoic acid (PFPeA)	ug/L	0.15	0.020	0.0041	0.11	0.020	0.0041	0.065	0.020	0.0041	6880244
Perfluorohexanoic acid (PFHxA)	ug/L	0.14	0.020	0.0064	0.11	0.020	0.0064	0.084	0.020	0.0064	6880244
Perfluoroheptanoic acid (PFHpA)	ug/L	0.098	0.020	0.0071	0.068	0.020	0.0071	0.048	0.020	0.0071	6880244
Perfluorooctanoic acid (PFOA)	ug/L	0.063	0.020	0.0074	0.099	0.020	0.0074	0.038	0.020	0.0074	6880244
Perfluorononanoic acid (PFNA)	ug/L	0.058	0.020	0.0049	0.049	0.020	0.0049	0.057	0.020	0.0049	6880244
Perfluorodecanoic acid (PFDA)	ug/L	0.036	0.020	0.0041	0.011	0.020	0.0041	0.0077	0.020	0.0041	6880244
Perfluoroundecanoic acid (PFUnA)	ug/L	0.19	0.020	0.0043	0.025	0.020	0.0043	0.019	0.020	0.0043	6880244
Perfluorododecanoic acid (PFDoA)	ug/L	<0.0068	0.020	0.0068	<0.0068	0.020	0.0068	<0.0068	0.020	0.0068	6880244
Perfluorotridecanoic acid (PFTRDA)	ug/L	<0.0069	0.020	0.0069	<0.0069	0.020	0.0069	<0.0069	0.020	0.0069	6880244
Perfluorotetradecanoic acid (PFTEDA)	ug/L	<0.0067	0.020	0.0067	<0.0067	0.020	0.0067	<0.0067	0.020	0.0067	6880244
Perfluorobutanesulfonic acid (PFBS)	ug/L	0.013	0.020	0.0051	0.015	0.020	0.0051	0.014	0.020	0.0051	6880244
Perfluorohexanesulfonic acid (PFHxS)	ug/L	0.24	0.020	0.0052	0.26	0.020	0.0052	0.12	0.020	0.0052	6880244
Perfluoroheptanesulfonic acid (PFHpS)	ug/L	0.0082	0.020	0.0033	0.013	0.020	0.0033	0.0082	0.020	0.0033	6880244
Perfluorooctanesulfonic acid (PFOS)	ug/L	1.9	0.20	0.052	0.93	0.020	0.0052	1.1	0.20	0.052	6880244
Perfluorodecanesulfonic acid (PFDS)	ug/L	<0.0072	0.020	0.0072	<0.0072	0.020	0.0072	<0.0072	0.020	0.0072	6880244
Perfluorooctane Sulfonamide (PFOSA)	ug/L	0.0077	0.020	0.0066	0.016	0.020	0.0066	<0.0066	0.020	0.0066	6880244
EtFOSA	ug/L	<0.0090	0.020	0.0090	<0.0090	0.020	0.0090	<0.0090	0.020	0.0090	6880244
MeFOSA	ug/L	<0.0035	0.020	0.0035	<0.0035	0.020	0.0035	<0.0035	0.020	0.0035	6880244
EtFOSE	ug/L	<0.0094	0.020	0.0094	<0.0094	0.020	0.0094	<0.0094	0.020	0.0094	6880244
MeFOSE	ug/L	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	<0.0066	0.020	0.0066	6880244
6:2 Fluorotelomer sulfonic acid	ug/L	0.25	0.020	0.0059	0.25	0.020	0.0059	0.022	0.020	0.0059	6880244
8:2 Fluorotelomer sulfonic acid	ug/L	0.96	0.020	0.0059	0.017	0.020	0.0059	0.0074	0.020	0.0059	6880244

Surrogate Recovery (%)

13C2-4:2-Fluorotelomersulfonic Acid	%	93	N/A	N/A	87	N/A	N/A	89	N/A	N/A	6880244
13C2-6:2-Fluorotelomersulfonic Acid	%	91	N/A	N/A	91	N/A	N/A	93	N/A	N/A	6880244
13C2-8:2-Fluorotelomersulfonic Acid	%	94	N/A	N/A	97	N/A	N/A	101	N/A	N/A	6880244
13C2-Perfluorodecanoic acid	%	96	N/A	N/A	98	N/A	N/A	94	N/A	N/A	6880244
13C2-Perfluorododecanoic acid	%	95	N/A	N/A	94	N/A	N/A	91	N/A	N/A	6880244
13C2-Perfluorohexanoic acid	%	106	N/A	N/A	103	N/A	N/A	106	N/A	N/A	6880244
13C2-perfluorotetradecanoic acid	%	68	N/A	N/A	55	N/A	N/A	87	N/A	N/A	6880244
13C2-Perfluoroundecanoic acid	%	97	N/A	N/A	101	N/A	N/A	92	N/A	N/A	6880244
13C3-Perfluorobutanesulfonic acid	%	101	N/A	N/A	98	N/A	N/A	103	N/A	N/A	6880244
13C4-Perfluorobutanoic acid	%	104	N/A	N/A	100	N/A	N/A	102	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL665			NGL666			NGL667			
Sampling Date		2020/07/29 13:30			2020/07/29 11:40			2020/07/29 10:30			
COC Number		731070-05-01			731070-02-01			731070-02-01			
	UNITS	PC-1	RDL	MDL	PE-16D	RDL	MDL	PC-30	RDL	MDL	QC Batch
13C4-Perfluoroheptanoic acid	%	108	N/A	N/A	105	N/A	N/A	109	N/A	N/A	6880244
13C4-Perfluorooctanesulfonic acid	%	103	N/A	N/A	98	N/A	N/A	104	N/A	N/A	6880244
13C4-Perfluorooctanoic acid	%	110	N/A	N/A	102	N/A	N/A	106	N/A	N/A	6880244
13C5-Perfluorononanoic acid	%	107	N/A	N/A	103	N/A	N/A	105	N/A	N/A	6880244
13C5-Perfluoropentanoic acid	%	107	N/A	N/A	102	N/A	N/A	106	N/A	N/A	6880244
13C8-Perfluorooctane Sulfonamide	%	90	N/A	N/A	86	N/A	N/A	80	N/A	N/A	6880244
18O2-Perfluorohexanesulfonic acid	%	103	N/A	N/A	101	N/A	N/A	100	N/A	N/A	6880244
D3-MeFOSA	%	70	N/A	N/A	61	N/A	N/A	60	N/A	N/A	6880244
D5-EtFOSA	%	71	N/A	N/A	65	N/A	N/A	62	N/A	N/A	6880244
D7-MeFOSE	%	76	N/A	N/A	71	N/A	N/A	69	N/A	N/A	6880244
D9-EtFOSE	%	74	N/A	N/A	70	N/A	N/A	68	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable

BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL668			NGL669	NGL670	NGL671			
Sampling Date		2020/07/29 14:15			2020/07/29 13:25	2020/07/29 14:30	2020/07/29 15:00			
COC Number		731070-02-01			731070-02-01	731070-02-01	731070-02-01			
	UNITS	MW-12	RDL	MDL	MW-22	PC-28	EQUIP-BLANK2	RDL	MDL	QC Batch

Perfluorinated Compounds

Perfluorobutanoic acid (PFBA)	ug/L	0.091	0.020	0.0070	0.016	0.014	<0.0070	0.020	0.0070	6880244
Perfluoropentanoic acid (PFPeA)	ug/L	0.20	0.020	0.0041	0.039	0.034	<0.0041	0.020	0.0041	6880244
Perfluorohexanoic acid (PFHxA)	ug/L	0.19	0.020	0.0064	0.049	0.031	<0.0064	0.020	0.0064	6880244
Perfluoroheptanoic acid (PFHpA)	ug/L	0.12	0.020	0.0071	0.027	0.030	<0.0071	0.020	0.0071	6880244
Perfluorooctanoic acid (PFOA)	ug/L	0.22	0.020	0.0074	0.092	0.012	<0.0074	0.020	0.0074	6880244
Perfluorononanoic acid (PFNA)	ug/L	0.051	0.020	0.0049	0.014	0.010	<0.0049	0.020	0.0049	6880244
Perfluorodecanoic acid (PFDA)	ug/L	0.018	0.020	0.0041	0.0052	<0.0041	<0.0041	0.020	0.0041	6880244
Perfluoroundecanoic acid (PFUnA)	ug/L	0.021	0.020	0.0043	0.0047	0.0095	<0.0043	0.020	0.0043	6880244
Perfluorododecanoic acid (PFDoA)	ug/L	<0.0068	0.020	0.0068	<0.0068	<0.0068	<0.0068	0.020	0.0068	6880244
Perfluorotridecanoic acid (PFTRDA)	ug/L	<0.0069	0.020	0.0069	<0.0069	<0.0069	<0.0069	0.020	0.0069	6880244
Perfluorotetradecanoic acid (PFTEDA)	ug/L	<0.0067	0.020	0.0067	<0.0067	<0.0067	<0.0067	0.020	0.0067	6880244
Perfluorobutanesulfonic acid (PFBS)	ug/L	0.019	0.020	0.0051	0.015	0.0061	<0.0051	0.020	0.0051	6880244
Perfluorohexanesulfonic acid (PFHxS)	ug/L	0.90	0.020	0.0052	0.36	0.071	<0.0052	0.020	0.0052	6880244
Perfluoroheptanesulfonic acid (PFHpS)	ug/L	0.021	0.020	0.0033	0.0075	<0.0033	<0.0033	0.020	0.0033	6880244
Perfluorooctanesulfonic acid (PFOS)	ug/L	2.9	0.20	0.052	0.79	0.20	<0.0052	0.020	0.0052	6880244
Perfluorodecanesulfonic acid (PFDS)	ug/L	<0.0072	0.020	0.0072	<0.0072	<0.0072	<0.0072	0.020	0.0072	6880244
Perfluorooctane Sulfonamide (PFOSA)	ug/L	0.16	0.020	0.0066	0.023	<0.0066	<0.0066	0.020	0.0066	6880244
EtFOSA	ug/L	<0.0090	0.020	0.0090	<0.0090	<0.0090	<0.0090	0.020	0.0090	6880244
MeFOSA	ug/L	<0.0035	0.020	0.0035	<0.0035	<0.0035	<0.0035	0.020	0.0035	6880244
EtFOSE	ug/L	<0.0094	0.020	0.0094	<0.0094	<0.0094	<0.0094	0.020	0.0094	6880244
MeFOSE	ug/L	<0.0066	0.020	0.0066	<0.0066	<0.0066	<0.0066	0.020	0.0066	6880244
6:2 Fluorotelomer sulfonic acid	ug/L	0.060	0.020	0.0059	<0.0059	0.010	<0.0059	0.020	0.0059	6880244
8:2 Fluorotelomer sulfonic acid	ug/L	0.018	0.020	0.0059	<0.0059	<0.0059	<0.0059	0.020	0.0059	6880244

Surrogate Recovery (%)

13C2-4:2-Fluorotelomersulfonic Acid	%	80	N/A	N/A	85	94	103	N/A	N/A	6880244
13C2-6:2-Fluorotelomersulfonic Acid	%	85	N/A	N/A	97	102	94	N/A	N/A	6880244
13C2-8:2-Fluorotelomersulfonic Acid	%	104	N/A	N/A	98	112	103	N/A	N/A	6880244
13C2-Perfluorodecanoic acid	%	101	N/A	N/A	93	102	101	N/A	N/A	6880244
13C2-Perfluorododecanoic acid	%	95	N/A	N/A	87	95	95	N/A	N/A	6880244
13C2-Perfluorohexanoic acid	%	107	N/A	N/A	106	118	105	N/A	N/A	6880244
13C2-perfluorotetradecanoic acid	%	79	N/A	N/A	78	85	91	N/A	N/A	6880244
13C2-Perfluoroundecanoic acid	%	104	N/A	N/A	93	102	99	N/A	N/A	6880244
13C3-Perfluorobutanesulfonic acid	%	107	N/A	N/A	101	113	99	N/A	N/A	6880244
13C4-Perfluorobutanoic acid	%	100	N/A	N/A	102	112	104	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

PERFLUOROALKYL SUBSTANCES (WATER)

BV Labs ID		NGL668			NGL669	NGL670	NGL671			
Sampling Date		2020/07/29 14:15			2020/07/29 13:25	2020/07/29 14:30	2020/07/29 15:00			
COC Number		731070-02-01			731070-02-01	731070-02-01	731070-02-01			
	UNITS	MW-12	RDL	MDL	MW-22	PC-28	EQUIP-BLANK2	RDL	MDL	QC Batch
13C4-Perfluoroheptanoic acid	%	105	N/A	N/A	111	118	108	N/A	N/A	6880244
13C4-Perfluorooctanesulfonic acid	%	99	N/A	N/A	96	108	99	N/A	N/A	6880244
13C4-Perfluorooctanoic acid	%	107	N/A	N/A	105	118	108	N/A	N/A	6880244
13C5-Perfluorononanoic acid	%	112	N/A	N/A	104	117	107	N/A	N/A	6880244
13C5-Perfluoropentanoic acid	%	105	N/A	N/A	104	116	104	N/A	N/A	6880244
13C8-Perfluorooctane Sulfonamide	%	86	N/A	N/A	81	92	91	N/A	N/A	6880244
18O2-Perfluorohexanesulfonic acid	%	103	N/A	N/A	102	114	102	N/A	N/A	6880244
D3-MeFOSA	%	62	N/A	N/A	61	62	59	N/A	N/A	6880244
D5-EtFOSA	%	63	N/A	N/A	61	62	62	N/A	N/A	6880244
D7-MeFOSE	%	69	N/A	N/A	65	68	74	N/A	N/A	6880244
D9-EtFOSE	%	72	N/A	N/A	64	69	72	N/A	N/A	6880244

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

TEST SUMMARY

BV Labs ID: NGL656
Sample ID: PFW-1
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6879899	2020/08/09	2020/08/10	Lovelpreet Thind

BV Labs ID: NGL657
Sample ID: PFW-5
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6879899	2020/08/09	2020/08/10	Lovelpreet Thind

BV Labs ID: NGL658
Sample ID: HSW-6
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6879899	2020/08/09	2020/08/10	Lovelpreet Thind

BV Labs ID: NGL659
Sample ID: OW-84
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL660
Sample ID: DUPLICATE
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL661
Sample ID: EQUIP-BLANK1
Matrix: Water

Collected: 2020/07/28
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL662
Sample ID: PC-6A
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

TEST SUMMARY

BV Labs ID: NGL663
Sample ID: PC-38
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL664
Sample ID: PC-11
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL665
Sample ID: PC-1
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL666
Sample ID: PE-16D
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL667
Sample ID: PC-30
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL668
Sample ID: MW-12
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL669
Sample ID: MW-22
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax



BUREAU
VERITAS

BV Labs Job #: COJ4359
Report Date: 2020/08/17

Barnstable County
Client Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY

TEST SUMMARY

BV Labs ID: NGL670
Sample ID: PC-28
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax

BV Labs ID: NGL671
Sample ID: EQUIP-BLANK2
Matrix: Water

Collected: 2020/07/29
Shipped:
Received: 2020/07/31

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
PFAS in water by SPE/LCMS	LCMS	6880244	2020/08/10	2020/08/11	Marian Godax



GENERAL COMMENTS

Sample NGL656 [PFW-1] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL658 [HSW-6] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL660 [DUPLICATE] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL662 [PC-6A] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL664 [PC-11] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL665 [PC-1] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL667 [PC-30] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL668 [MW-12] : Per- and polyfluoroalkyl substances (PFAS): Due to high concentrations of the target analytes, a reduced sample volume was extracted and analyzed. Detection limits were adjusted accordingly.

Sample NGL656, PFAS in water by SPE/LCMS: Test repeated.

Sample NGL657, PFAS in water by SPE/LCMS: Test repeated.

Sample NGL658, PFAS in water by SPE/LCMS: Test repeated.

Results relate only to the items tested.



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

QUALITY ASSURANCE REPORT

QA/QC	Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6874512	YPL	Spiked Blank		13C2-8:2-Fluorotelomersulfonic Acid	2020/08/10		88	%	50 - 150
				13C2-Perfluorodecanoic acid	2020/08/10		96	%	50 - 150
				13C2-Perfluorododecanoic acid	2020/08/10		84	%	50 - 150
				13C2-Perfluorohexanoic acid	2020/08/10		97	%	50 - 150
				13C2-perfluorotetradecanoic acid	2020/08/10		81	%	50 - 150
				13C2-Perfluoroundecanoic acid	2020/08/10		90	%	50 - 150
				13C3-Perfluorobutanesulfonic acid	2020/08/10		95	%	50 - 150
				13C4-Perfluorobutanoic acid	2020/08/10		102	%	50 - 150
				13C4-Perfluoroheptanoic acid	2020/08/10		95	%	50 - 150
				13C4-Perfluorooctanesulfonic acid	2020/08/10		98	%	50 - 150
				13C4-Perfluorooctanoic acid	2020/08/10		97	%	50 - 150
				13C5-Perfluorononanoic acid	2020/08/10		97	%	50 - 150
				13C5-Perfluoropentanoic acid	2020/08/10		96	%	50 - 150
				13C8-Perfluorooctane Sulfonamide	2020/08/10		86	%	50 - 150
				18O2-Perfluorohexanesulfonic acid	2020/08/10		94	%	50 - 150
				D3-MeFOSA	2020/08/10		72	%	50 - 150
				D5-EtFOSA	2020/08/10		71	%	50 - 150
				D7-MeFOSE	2020/08/10		83	%	50 - 150
				D9-EtFOSE	2020/08/10		82	%	50 - 150
				Perfluorobutanoic acid (PFBA)	2020/08/10		100	%	70 - 130
				Perfluoropentanoic acid (PFPeA)	2020/08/10		101	%	70 - 130
				Perfluorohexanoic acid (PFHxA)	2020/08/10		99	%	70 - 130
				Perfluoroheptanoic acid (PFHpA)	2020/08/10		101	%	70 - 130
				Perfluorooctanoic acid (PFOA)	2020/08/10		101	%	70 - 130
				Perfluorononanoic acid (PFNA)	2020/08/10		98	%	70 - 130
				Perfluorodecanoic acid (PFDA)	2020/08/10		97	%	70 - 130
				Perfluoroundecanoic acid (PFUnA)	2020/08/10		99	%	70 - 130
				Perfluorododecanoic acid (PFDoA)	2020/08/10		99	%	70 - 130
				Perfluorotridecanoic acid (PFTRDA)	2020/08/10		100	%	70 - 130
				Perfluorotetradecanoic acid (PFTEDA)	2020/08/10		98	%	70 - 130
				Perfluorobutanesulfonic acid (PFBS)	2020/08/10		103	%	70 - 130
				Perfluorohexanesulfonic acid (PFHxS)	2020/08/10		104	%	70 - 130
				Perfluoroheptanesulfonic acid PFHpS	2020/08/10		101	%	70 - 130
				Perfluorooctanesulfonic acid (PFOS)	2020/08/10		99	%	70 - 130
				Perfluorodecanesulfonic acid (PFDS)	2020/08/10		91	%	70 - 130
				Perfluorooctane Sulfonamide (PFOSA)	2020/08/10		101	%	70 - 130
				EtFOSA	2020/08/10		94	%	70 - 130
				MeFOSA	2020/08/10		95	%	70 - 130
				EtFOSE	2020/08/10		100	%	70 - 130
				MeFOSE	2020/08/10		99	%	70 - 130
				8:2 Fluorotelomer sulfonic acid	2020/08/10		100	%	70 - 130
6874512	YPL	Spiked Blank DUP		13C2-8:2-Fluorotelomersulfonic Acid	2020/08/10		89	%	50 - 150
				13C2-Perfluorodecanoic acid	2020/08/10		95	%	50 - 150
				13C2-Perfluorododecanoic acid	2020/08/10		85	%	50 - 150
				13C2-Perfluorohexanoic acid	2020/08/10		98	%	50 - 150
				13C2-perfluorotetradecanoic acid	2020/08/10		80	%	50 - 150
				13C2-Perfluoroundecanoic acid	2020/08/10		89	%	50 - 150
				13C3-Perfluorobutanesulfonic acid	2020/08/10		98	%	50 - 150
				13C4-Perfluorobutanoic acid	2020/08/10		104	%	50 - 150
				13C4-Perfluoroheptanoic acid	2020/08/10		96	%	50 - 150
				13C4-Perfluorooctanesulfonic acid	2020/08/10		95	%	50 - 150
				13C4-Perfluorooctanoic acid	2020/08/10		98	%	50 - 150



BUREAU
VERITAS

BV Labs Job #: COJ4359
Report Date: 2020/08/17

Barnstable County
Client Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY

QUALITY ASSURANCE REPORT(CONT'D)

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6874512	YPL	RPD	13C5-Perfluorononanoic acid	2020/08/10		97	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/10		97	%	50 - 150
			13C8-Perfluorooctane Sulfonamide	2020/08/10		86	%	50 - 150
			18O2-Perfluorohexanesulfonic acid	2020/08/10		96	%	50 - 150
			D3-MeFOSA	2020/08/10		75	%	50 - 150
			D5-EtFOSA	2020/08/10		81	%	50 - 150
			D7-MeFOSE	2020/08/10		82	%	50 - 150
			D9-EtFOSE	2020/08/10		81	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/10		102	%	70 - 130
			Perfluoropentanoic acid (PFPeA)	2020/08/10		103	%	70 - 130
			Perfluorohexanoic acid (PFHxA)	2020/08/10		101	%	70 - 130
			Perfluoroheptanoic acid (PFHpA)	2020/08/10		103	%	70 - 130
			Perfluorooctanoic acid (PFOA)	2020/08/10		102	%	70 - 130
			Perfluorononanoic acid (PFNA)	2020/08/10		102	%	70 - 130
			Perfluorodecanoic acid (PFDA)	2020/08/10		99	%	70 - 130
			Perfluoroundecanoic acid (PFUnA)	2020/08/10		102	%	70 - 130
			Perfluorododecanoic acid (PFDoA)	2020/08/10		101	%	70 - 130
			Perfluorotridecanoic acid (PFTRDA)	2020/08/10		106	%	70 - 130
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/10		100	%	70 - 130
			Perfluorobutanesulfonic acid (PFBS)	2020/08/10		100	%	70 - 130
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/10		104	%	70 - 130
			Perfluoroheptanesulfonic acid PFHpS	2020/08/10		102	%	70 - 130
			Perfluorooctanesulfonic acid (PFOS)	2020/08/10		104	%	70 - 130
			Perfluorodecanesulfonic acid (PFDS)	2020/08/10		93	%	70 - 130
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/10		102	%	70 - 130
			EtFOSA	2020/08/10		89	%	70 - 130
			MeFOSA	2020/08/10		102	%	70 - 130
			EtFOSE	2020/08/10		103	%	70 - 130
			MeFOSE	2020/08/10		102	%	70 - 130
			8:2 Fluorotelomer sulfonic acid	2020/08/10		102	%	70 - 130
			Perfluorobutanoic acid (PFBA)	2020/08/10	2.3		%	30
			Perfluoropentanoic acid (PFPeA)	2020/08/10	1.7		%	30
			Perfluorohexanoic acid (PFHxA)	2020/08/10	2.0		%	30
			Perfluoroheptanoic acid (PFHpA)	2020/08/10	2.0		%	30
			Perfluorooctanoic acid (PFOA)	2020/08/10	1.6		%	30
			Perfluorononanoic acid (PFNA)	2020/08/10	3.4		%	30
			Perfluorodecanoic acid (PFDA)	2020/08/10	1.8		%	30
			Perfluoroundecanoic acid (PFUnA)	2020/08/10	2.4		%	30
			Perfluorododecanoic acid (PFDoA)	2020/08/10	2.5		%	30
			Perfluorotridecanoic acid (PFTRDA)	2020/08/10	5.5		%	30
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/10	2.2		%	30
			Perfluorobutanesulfonic acid (PFBS)	2020/08/10	2.8		%	30
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/10	0.40		%	30
			Perfluoroheptanesulfonic acid PFHpS	2020/08/10	0.55		%	30
			Perfluorooctanesulfonic acid (PFOS)	2020/08/10	5.0		%	30
			Perfluorodecanesulfonic acid (PFDS)	2020/08/10	2.7		%	30
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/10	0.52		%	30
			EtFOSA	2020/08/10	5.3		%	30
			MeFOSA	2020/08/10	6.9		%	30
			EtFOSE	2020/08/10	3.2		%	30
			MeFOSE	2020/08/10	3.0		%	30
			8:2 Fluorotelomer sulfonic acid	2020/08/10	1.9		%	30



BUREAU
VERITAS

BV Labs Job #: C0J4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

QUALITY ASSURANCE REPORT(CONT'D)

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6874512	YPL	Method Blank	13C2-8:2-Fluorotelomersulfonic Acid	2020/08/10		96	%	50 - 150
			13C2-Perfluorodecanoic acid	2020/08/10		98	%	50 - 150
			13C2-Perfluorododecanoic acid	2020/08/10		83	%	50 - 150
			13C2-Perfluorohexanoic acid	2020/08/10		98	%	50 - 150
			13C2-perfluorotetradecanoic acid	2020/08/10		79	%	50 - 150
			13C2-Perfluoroundecanoic acid	2020/08/10		91	%	50 - 150
			13C3-Perfluorobutanesulfonic acid	2020/08/10		97	%	50 - 150
			13C4-Perfluorobutanoic acid	2020/08/10		104	%	50 - 150
			13C4-Perfluoroheptanoic acid	2020/08/10		98	%	50 - 150
			13C4-Perfluorooctanesulfonic acid	2020/08/10		99	%	50 - 150
			13C4-Perfluorooctanoic acid	2020/08/10		101	%	50 - 150
			13C5-Perfluorononanoic acid	2020/08/10		96	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/10		98	%	50 - 150
			13C8-Perfluorooctane Sulfonamide	2020/08/10		86	%	50 - 150
			18O2-Perfluorohexanesulfonic acid	2020/08/10		95	%	50 - 150
			D3-MeFOSA	2020/08/10		61	%	50 - 150
			D5-EtFOSA	2020/08/10		61	%	50 - 150
			D7-MeFOSE	2020/08/10		77	%	50 - 150
			D9-EtFOSE	2020/08/10		77	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/10	<0.0070		ug/L	
			Perfluoropentanoic acid (PFPeA)	2020/08/10	<0.0041		ug/L	
			Perfluorohexanoic acid (PFHxA)	2020/08/10	<0.0064		ug/L	
			Perfluoroheptanoic acid (PFHpA)	2020/08/10	<0.0071		ug/L	
			Perfluorooctanoic acid (PFOA)	2020/08/10	<0.0074		ug/L	
			Perfluorononanoic acid (PFNA)	2020/08/10	<0.0049		ug/L	
			Perfluorodecanoic acid (PFDA)	2020/08/10	<0.0041		ug/L	
			Perfluoroundecanoic acid (PFUnA)	2020/08/10	<0.0043		ug/L	
			Perfluorododecanoic acid (PFDoA)	2020/08/10	<0.0068		ug/L	
			Perfluorotridecanoic acid (PFTRDA)	2020/08/10	<0.0069		ug/L	
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/10	<0.0067		ug/L	
			Perfluorobutanesulfonic acid (PFBS)	2020/08/10	<0.0051		ug/L	
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/10	<0.0052		ug/L	
			Perfluoroheptanesulfonic acid PFHpS	2020/08/10	<0.0033		ug/L	
			Perfluorooctanesulfonic acid (PFOS)	2020/08/10	<0.0052		ug/L	
			Perfluorodecanesulfonic acid (PFDS)	2020/08/10	<0.0072		ug/L	
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/10	<0.0066		ug/L	
			EtFOSA	2020/08/10	<0.0090		ug/L	
			MeFOSA	2020/08/10	<0.0035		ug/L	
			EtFOSE	2020/08/10	<0.0094		ug/L	
			MeFOSE	2020/08/10	<0.0066		ug/L	
			8:2 Fluorotelomer sulfonic acid	2020/08/10	<0.0059		ug/L	
6879899	LOV	Spiked Blank	13C2-6:2-Fluorotelomersulfonic Acid	2020/08/10		102	%	50 - 150
			6:2 Fluorotelomer sulfonic acid	2020/08/10		94	%	70 - 130
6879899	LOV	Spiked Blank DUP	13C2-6:2-Fluorotelomersulfonic Acid	2020/08/10		96	%	50 - 150
			6:2 Fluorotelomer sulfonic acid	2020/08/10		98	%	70 - 130
6879899	LOV	RPD	6:2 Fluorotelomer sulfonic acid	2020/08/10	4.0		%	30
6879899	LOV	Method Blank	13C2-6:2-Fluorotelomersulfonic Acid	2020/08/10		104	%	50 - 150
			6:2 Fluorotelomer sulfonic acid	2020/08/10	<0.0059		ug/L	
6880244	M_G	Spiked Blank	13C2-4:2-Fluorotelomersulfonic Acid	2020/08/11		97	%	50 - 150
			13C2-6:2-Fluorotelomersulfonic Acid	2020/08/11		91	%	50 - 150
			13C2-8:2-Fluorotelomersulfonic Acid	2020/08/11		94	%	50 - 150
			13C2-Perfluorodecanoic acid	2020/08/11		96	%	50 - 150



BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

QUALITY ASSURANCE REPORT(CONT'D)

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6880244	M_G	Spiked Blank DUP	13C2-Perfluorododecanoic acid	2020/08/11		95	%	50 - 150
			13C2-Perfluorohexanoic acid	2020/08/11		101	%	50 - 150
			13C2-perfluorotetradecanoic acid	2020/08/11		91	%	50 - 150
			13C2-Perfluoroundecanoic acid	2020/08/11		98	%	50 - 150
			13C3-Perfluorobutanesulfonic acid	2020/08/11		95	%	50 - 150
			13C4-Perfluorobutanoic acid	2020/08/11		101	%	50 - 150
			13C4-Perfluoroheptanoic acid	2020/08/11		100	%	50 - 150
			13C4-Perfluorooctanesulfonic acid	2020/08/11		104	%	50 - 150
			13C4-Perfluorooctanoic acid	2020/08/11		104	%	50 - 150
			13C5-Perfluorononanoic acid	2020/08/11		102	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/11		103	%	50 - 150
			13C8-Perfluorooctane Sulfonamide	2020/08/11		88	%	50 - 150
			18O2-Perfluorohexanesulfonic acid	2020/08/11		95	%	50 - 150
			D3-MeFOSA	2020/08/11		68	%	50 - 150
			D5-EtFOSA	2020/08/11		71	%	50 - 150
			D7-MeFOSE	2020/08/11		80	%	50 - 150
			D9-EtFOSE	2020/08/11		81	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/11		98	%	70 - 130
			Perfluoropentanoic acid (PFPeA)	2020/08/11		98	%	70 - 130
			Perfluorohexanoic acid (PFHxA)	2020/08/11		100	%	70 - 130
			Perfluoroheptanoic acid (PFHpA)	2020/08/11		100	%	70 - 130
			Perfluorooctanoic acid (PFOA)	2020/08/11		96	%	70 - 130
			Perfluorononanoic acid (PFNA)	2020/08/11		97	%	70 - 130
			Perfluorodecanoic acid (PFDA)	2020/08/11		101	%	70 - 130
			Perfluoroundecanoic acid (PFUnA)	2020/08/11		96	%	70 - 130
			Perfluorododecanoic acid (PFDoA)	2020/08/11		94	%	70 - 130
			Perfluorotridecanoic acid (PFTRDA)	2020/08/11		96	%	70 - 130
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/11		95	%	70 - 130
			Perfluorobutanesulfonic acid (PFBS)	2020/08/11		100	%	70 - 130
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/11		101	%	70 - 130
			Perfluoroheptanesulfonic acid PFHpS	2020/08/11		95	%	70 - 130
			Perfluorooctanesulfonic acid (PFOS)	2020/08/11		96	%	70 - 130
			Perfluorodecanesulfonic acid (PFDS)	2020/08/11		93	%	70 - 130
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/11		92	%	70 - 130
			EtFOSA	2020/08/11		86	%	70 - 130
			MeFOSA	2020/08/11		92	%	70 - 130
			EtFOSE	2020/08/11		91	%	70 - 130
			MeFOSE	2020/08/11		89	%	70 - 130
			6:2 Fluorotelomer sulfonic acid	2020/08/11		99	%	70 - 130
			8:2 Fluorotelomer sulfonic acid	2020/08/11		108	%	70 - 130
			13C2-4:2-Fluorotelomersulfonic Acid	2020/08/11		93	%	50 - 150
			13C2-6:2-Fluorotelomersulfonic Acid	2020/08/11		90	%	50 - 150
			13C2-8:2-Fluorotelomersulfonic Acid	2020/08/11		87	%	50 - 150
			13C2-Perfluorodecanoic acid	2020/08/11		97	%	50 - 150
			13C2-Perfluorododecanoic acid	2020/08/11		93	%	50 - 150
			13C2-Perfluorohexanoic acid	2020/08/11		101	%	50 - 150
			13C2-perfluorotetradecanoic acid	2020/08/11		87	%	50 - 150
			13C2-Perfluoroundecanoic acid	2020/08/11		97	%	50 - 150
			13C3-Perfluorobutanesulfonic acid	2020/08/11		95	%	50 - 150
			13C4-Perfluorobutanoic acid	2020/08/11		100	%	50 - 150
			13C4-Perfluoroheptanoic acid	2020/08/11		98	%	50 - 150
			13C4-Perfluorooctanesulfonic acid	2020/08/11		100	%	50 - 150



BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

QUALITY ASSURANCE REPORT(CONT'D)

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6880244	M_G	RPD	13C4-Perfluorooctanoic acid	2020/08/11		101	%	50 - 150
			13C5-Perfluorononanoic acid	2020/08/11		99	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/11		101	%	50 - 150
			13C8-Perfluorooctane Sulfonamide	2020/08/11		82	%	50 - 150
			18O2-Perfluorohexanesulfonic acid	2020/08/11		100	%	50 - 150
			D3-MeFOSA	2020/08/11		61	%	50 - 150
			D5-EtFOSA	2020/08/11		62	%	50 - 150
			D7-MeFOSE	2020/08/11		75	%	50 - 150
			D9-EtFOSE	2020/08/11		70	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/11		101	%	70 - 130
			Perfluoropentanoic acid (PFPeA)	2020/08/11		101	%	70 - 130
			Perfluorohexanoic acid (PFHxA)	2020/08/11		101	%	70 - 130
			Perfluoroheptanoic acid (PFHpA)	2020/08/11		103	%	70 - 130
			Perfluorooctanoic acid (PFOA)	2020/08/11		99	%	70 - 130
			Perfluorononanoic acid (PFNA)	2020/08/11		103	%	70 - 130
			Perfluorodecanoic acid (PFDA)	2020/08/11		102	%	70 - 130
			Perfluoroundecanoic acid (PFUnA)	2020/08/11		101	%	70 - 130
			Perfluorododecanoic acid (PFDoA)	2020/08/11		101	%	70 - 130
			Perfluorotridecanoic acid (PFTRDA)	2020/08/11		101	%	70 - 130
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/11		100	%	70 - 130
			Perfluorobutanesulfonic acid (PFBS)	2020/08/11		104	%	70 - 130
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/11		99	%	70 - 130
			Perfluoroheptanesulfonic acid PFHpS	2020/08/11		99	%	70 - 130
			Perfluorooctanesulfonic acid (PFOS)	2020/08/11		102	%	70 - 130
			Perfluorodecanesulfonic acid (PFDS)	2020/08/11		95	%	70 - 130
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/11		98	%	70 - 130
			EtFOSA	2020/08/11		89	%	70 - 130
			MeFOSA	2020/08/11		92	%	70 - 130
			EtFOSE	2020/08/11		106	%	70 - 130
			MeFOSE	2020/08/11		94	%	70 - 130
			6:2 Fluorotelomer sulfonic acid	2020/08/11		99	%	70 - 130
			8:2 Fluorotelomer sulfonic acid	2020/08/11		120	%	70 - 130
			Perfluorobutanoic acid (PFBA)	2020/08/11	2.2		%	30
			Perfluoropentanoic acid (PFPeA)	2020/08/11	3.0		%	30
			Perfluorohexanoic acid (PFHxA)	2020/08/11	0.67		%	30
			Perfluoroheptanoic acid (PFHpA)	2020/08/11	3.2		%	30
			Perfluorooctanoic acid (PFOA)	2020/08/11	3.9		%	30
			Perfluorononanoic acid (PFNA)	2020/08/11	5.4		%	30
			Perfluorodecanoic acid (PFDA)	2020/08/11	1.5		%	30
			Perfluoroundecanoic acid (PFUnA)	2020/08/11	5.0		%	30
			Perfluorododecanoic acid (PFDoA)	2020/08/11	7.2		%	30
			Perfluorotridecanoic acid (PFTRDA)	2020/08/11	5.4		%	30
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/11	5.1		%	30
			Perfluorobutanesulfonic acid (PFBS)	2020/08/11	3.7		%	30
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/11	2.8		%	30
			Perfluoroheptanesulfonic acid PFHpS	2020/08/11	3.4		%	30
			Perfluorooctanesulfonic acid (PFOS)	2020/08/11	5.9		%	30
			Perfluorodecanesulfonic acid (PFDS)	2020/08/11	2.5		%	30
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/11	6.2		%	30
			EtFOSA	2020/08/11	3.2		%	30
			MeFOSA	2020/08/11	0.73		%	30
			EtFOSE	2020/08/11	15		%	30



BUREAU
VERITAS

BV Labs Job #: COJ4359
Report Date: 2020/08/17

Barnstable County
Client Project #: 6206-BFTA
Site Location: BARNSTABLE COUNTY

QUALITY ASSURANCE REPORT(CONT'D)

QA/QC Batch	Init	QC Type	Parameter	Date Analyzed	Value	% Recovery	UNITS	QC Limits
6880244	M_G	Method Blank	MeFOSE	2020/08/11	6.2		%	30
			6:2 Fluorotelomer sulfonic acid	2020/08/11	0.12		%	30
			8:2 Fluorotelomer sulfonic acid	2020/08/11	10		%	30
			13C2-4:2-Fluorotelomersulfonic Acid	2020/08/11		105	%	50 - 150
			13C2-6:2-Fluorotelomersulfonic Acid	2020/08/11		98	%	50 - 150
			13C2-8:2-Fluorotelomersulfonic Acid	2020/08/11		98	%	50 - 150
			13C2-Perfluorodecanoic acid	2020/08/11		93	%	50 - 150
			13C2-Perfluorododecanoic acid	2020/08/11		87	%	50 - 150
			13C2-Perfluorohexanoic acid	2020/08/11		101	%	50 - 150
			13C2-perfluorotetradecanoic acid	2020/08/11		55	%	50 - 150
			13C2-Perfluoroundecanoic acid	2020/08/11		94	%	50 - 150
			13C3-Perfluorobutanesulfonic acid	2020/08/11		98	%	50 - 150
			13C4-Perfluorobutanoic acid	2020/08/11		101	%	50 - 150
			13C4-Perfluoroheptanoic acid	2020/08/11		101	%	50 - 150
			13C4-Perfluorooctanesulfonic acid	2020/08/11		97	%	50 - 150
			13C4-Perfluorooctanoic acid	2020/08/11		102	%	50 - 150
			13C5-Perfluorononanoic acid	2020/08/11		98	%	50 - 150
			13C5-Perfluoropentanoic acid	2020/08/11		101	%	50 - 150
			13C8-Perfluorooctane Sulfonamide	2020/08/11		81	%	50 - 150
			18O2-Perfluorohexanesulfonic acid	2020/08/11		97	%	50 - 150
			D3-MeFOSA	2020/08/11		60	%	50 - 150
			D5-EtFOSA	2020/08/11		62	%	50 - 150
			D7-MeFOSE	2020/08/11		71	%	50 - 150
			D9-EtFOSE	2020/08/11		76	%	50 - 150
			Perfluorobutanoic acid (PFBA)	2020/08/11	<0.0070		ug/L	
			Perfluoropentanoic acid (PFPeA)	2020/08/11	<0.0041		ug/L	
			Perfluorohexanoic acid (PFHxA)	2020/08/11	<0.0064		ug/L	
			Perfluoroheptanoic acid (PFHpA)	2020/08/11	<0.0071		ug/L	
			Perfluorooctanoic acid (PFOA)	2020/08/11	<0.0074		ug/L	
			Perfluorononanoic acid (PFNA)	2020/08/11	<0.0049		ug/L	
			Perfluorodecanoic acid (PFDA)	2020/08/11	<0.0041		ug/L	
			Perfluoroundecanoic acid (PFUnA)	2020/08/11	<0.0043		ug/L	
			Perfluorododecanoic acid (PFDoA)	2020/08/11	<0.0068		ug/L	
			Perfluorotridecanoic acid (PFTRDA)	2020/08/11	<0.0069		ug/L	
			Perfluorotetradecanoic acid(PFTEDA)	2020/08/11	<0.0067		ug/L	
			Perfluorobutanesulfonic acid (PFBS)	2020/08/11	<0.0051		ug/L	
			Perfluorohexanesulfonic acid(PFHxS)	2020/08/11	<0.0052		ug/L	
			Perfluoroheptanesulfonic acid PFHpS	2020/08/11	<0.0033		ug/L	
			Perfluorooctanesulfonic acid (PFOS)	2020/08/11	<0.0052		ug/L	
			Perfluorodecanesulfonic acid (PFDS)	2020/08/11	<0.0072		ug/L	
			Perfluorooctane Sulfonamide (PFOSA)	2020/08/11	<0.0066		ug/L	
			EtFOSA	2020/08/11	<0.0090		ug/L	
			MeFOSA	2020/08/11	<0.0035		ug/L	
			EtFOSE	2020/08/11	<0.0094		ug/L	
			MeFOSE	2020/08/11	<0.0066		ug/L	
			6:2 Fluorotelomer sulfonic acid	2020/08/11	<0.0059		ug/L	
			8:2 Fluorotelomer sulfonic acid	2020/08/11	<0.0059		ug/L	

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

Surrogate: A pure or isotopically labeled compound whose behavior mirrors the analytes of interest. Used to evaluate extraction efficiency.



BUREAU
VERITAS

BV Labs Job #: COJ4359

Report Date: 2020/08/17

Barnstable County

Client Project #: 6206-BFTA

Site Location: BARNSTABLE COUNTY

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by the following individual(s).

Colm McNamara, Senior Analyst, Liquid Chromatography

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Bureau Veritas Laboratories
6740 Campbell Road, Mississauga, Ontario Canada L5N 2L8 Tel: (905) 817-5700 Toll-free 800-563-6266 Fax: (905) 817-5777 www.bvlabs.com

CHAIN OF CUSTODY RECORD

Page 1 of 2

INVOICE TO:		REPORT TO:		PROJECT INFORMATION:		Laboratory Use Only:	
Company Name: #29803 Barnstable County		Company Name: Steven Tebo		Quotation #: B57344		BV Labs Job #:	
Attention: Accounts Payable		Attention: Roger Thibault		P.O. #:		Bottle Order #:	
Address: 3195 Main Street PO Box 427		Address: rthibault@beta-inc.com		Project: W000-BETA		731070	
Barnstable MA 02630		BETA Group		Project Name: Barnstable County		COC #:	
Tel: (508) 362-3828 Ext: 1234		Tel: (508) 375-6603		Site #:		Project Manager: Patricia Legette	
Fax: eocconnell@barnstablecounty.org, stebo@barnstableco		Fax: stebo@barnstablecounty.org, rthibault@noverarmstrong		Sampled By: M. Mendes C. Oien		Turnaround Time (TAT) Required:	
Email: eocconnell@barnstablecounty.org, stebo@barnstableco		Email: stebo@barnstablecounty.org, rthibault@noverarmstrong		ANALYSIS REQUESTED (PLEASE BE SPECIFIC)		Please provide advance notice for rush projects	
MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE BV LABS DRINKING WATER CHAIN OF CUSTODY		Special Instructions: include all reports 23 PFAS compounds		Field Filtered (please circle): Metals / Hg / Cr VI		Regular (Standard) TAT: (will be applied if Rush TAT is not specified)	
Regulation 153 (2011)		Other Regulations		Matrix		Standard TAT = 5-7 Working days for most tests.	
<input type="checkbox"/> Table 1 <input type="checkbox"/> Res/Park <input type="checkbox"/> Medium/Fine		<input type="checkbox"/> CCME <input type="checkbox"/> Sanitary Sewer Bylaw		GW		Please note: Standard TAT for certain tests such as BOD and Dioxins/Furans are > 5 days - contact your Project Manager for details.	
<input type="checkbox"/> Table 2 <input type="checkbox"/> Ind/Comm <input type="checkbox"/> Coarse		<input type="checkbox"/> Reg 558 <input type="checkbox"/> Storm Sewer Bylaw		AQ		Job Specific Rush TAT (if applies to entire submission)	
<input type="checkbox"/> Table 3 <input type="checkbox"/> Agri/Other <input type="checkbox"/> For RSC		<input type="checkbox"/> MISA Municipality		V		Date Required: Time Required:	
<input type="checkbox"/> Table		<input type="checkbox"/> PWOO		GW		Rush Confirmation Number: (call lab for #)	
<input type="checkbox"/> Other		<input type="checkbox"/> Other				# of Bottles Comments	
Include Criteria on Certificate of Analysis (Y/N)?							
Sample Barcode Label	Sample (Location) Identification	Date Sampled	Time Sampled	Matrix			
1	PFW-1	20/07/28	1425	GW	X		2
2	PFW-5	20/07/28			X		2
3	HSW-6	20/07/28	1420		X		2
4	OW-8A	20/07/29			X		2
5	Duplicate	20/07/28	1100		X		2
6	EQUIP-BLANK 1	20/07/28	1500	AQ	X		2
7	PC-6A	20/07/29	1225		X		2
8	PC-38	20/07/29	1040		X		2
9	PC-11	20/07/29	1230	V	X		2
10	PC-1	20/07/29	1330	GW	X		2
* RELINQUISHED BY: (Signature/Print)		Date: (YY/MM/DD)	Time	RECEIVED BY: (Signature/Print)	Date: (YY/MM/DD)	Time	# jars used and not submitted
Mykel Mendes		20/07/30	1300	Mykel Mendes	20/07/31	12:45	
UNLESS OTHERWISE AGREED TO IN WRITING, WORK SUBMITTED ON THIS CHAIN OF CUSTODY IS SUBJECT TO BV LABS' STANDARD TERMS AND CONDITIONS. SIGNING OF THIS CHAIN OF CUSTODY DOCUMENT IS ACKNOWLEDGMENT AND ACCEPTANCE OF OUR TERMS WHICH ARE AVAILABLE FOR VIEWING AT WWW.BVLABS.COM/TERMS-AND-CONDITIONS.						Time Sensitive	
IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.						Temperature (°C) on Receipt	
SAMPLE CONTAINER, PRESERVATION, HOLD TIME AND PACKAGE INFORMATION CAN BE VIEWED AT WWW.BVLABS.COM/RESOURCES/CHAIN-OF-CUSTODY-FORMS.						Custody Seal Present	
						Intact	
						White: BV Labs Yellow: Client	
						SAMPLER MUST BE KEPT COOL (< 10° C) FROM TIME OF SAMPLING UNTIL DELIVERY TO BV LABS	

Bureau Veritas Canada (2019) Inc.



Bureau Veritas Laboratories
6740 Campbell Road, Mississauga, Ontario Canada L5N 2L8 Tel (905) 817-5700 Toll-free 800-563-6266 Fax (905) 817-5777 www.bvlab.com

CHAIN OF CUSTODY RECORD

Page 22

INVOICE TO:		REPORT TO:		PROJECT INFORMATION:		Laboratory Use Only:	
Company Name: #29803 Barnstable County		Company Name: Steven Tebo		Quotation #: B57344		BV Labs Job #:	
Attention: Accounts Payable		Attention: Roger Thibault		P.O. #:		Bottle Order #:	
Address: 3195 Main Street PO Box 427		Address: rthibault@bvt-inc.com		Project: 6206 - BETA		COC #:	
Barnstable MA 02630		BETA Group		Project Name: Barnstable County		Project Manager:	
Tel: (508) 362-3828 Ext: 1234		Tel: (508) 375-6603		Site #:		Patricia Legette	
Email: eoconnell@barnstablecounty.org, stebo@barnstableco		Email: stebo@barnstablecounty.org, rthibault@barnstableco		Sampled By: M. Mendes, C. Oien		C#731070-02-01	

MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN CONSUMPTION MUST BE SUBMITTED ON THE BV LABS DRINKING WATER CHAIN OF CUSTODY						ANALYSIS REQUESTED (PLEASE BE SPECIFIC)												Turnaround Time (TAT) Required: Please provide advance notice for rush projects.				
Regulation 153 (2011)			Other Regulations			Special Instructions			Field Filtered (please circle): Metals / Hg / Cr VI												Regular (Standard) TAT: (will be applied if Rush TAT is not specified). Standard TAT = 5-7 Working days for most tests. Please note: Standard TAT for certain tests such as BOD and Dioxins/Furans are > 5 days - contact your Project Manager for details.	
<input type="checkbox"/> Table 1	<input type="checkbox"/> Res/Park	<input type="checkbox"/> Medium/Fine	<input type="checkbox"/> CCME	<input type="checkbox"/> Sanitary Sewer Bylaw	include all (23) reportable PFAS compounds	Total PFAS 537 m												Job Specific Rush TAT (if applies to entire submission)				
<input type="checkbox"/> Table 2	<input type="checkbox"/> Ind/Comm	<input type="checkbox"/> Coarse	<input type="checkbox"/> Reg 558	<input type="checkbox"/> Storm Sewer Bylaw														Date Required: _____ Time Required: _____				
<input type="checkbox"/> Table 3	<input type="checkbox"/> Agri/Other	<input type="checkbox"/> For RSC	<input type="checkbox"/> MISA	<input type="checkbox"/> Municipality														Rush Confirmation Number: _____ (call lab for #)				
<input type="checkbox"/> Table	<input type="checkbox"/> PWQO	<input type="checkbox"/> Other																				
Include Criteria on Certificate of Analysis (Y/N)?																						
Sample Barcode Label	Sample (Location) Identification	Date Sampled	Time Sampled	Matrix													# of Bottles	Comments				
1	PC-16D	20/07/29	1140	GW													2					
2	PC-30	20/07/29	1030														2					
3	MW-12	20/07/29	1415														2					
4	MW-22	20/07/29	1325														2					
5	PC-28	20/07/29	1430	GW													2					
6	EQUIP-BLANK2	20/07/29	1500	AR													2					
7																						
8																						
9																						
10																						

* RELINQUISHED BY: (Signature/Print)		Date: (YY/MM/DD)	Time	RECEIVED BY: (Signature/Print)		Date: (YY/MM/DD)	Time	# jars used and not submitted	Laboratory Use Only				
Mykel Mendes		20/07/30	1200	[Signature]		20/07/31	1245		Time Sensitive	Temperature (°C) on Receipt	Custody Seal	Yes	No
										7.2/3.9/4.7	Present		✓
											Intact		

* UNLESS OTHERWISE AGREED TO IN WRITING, WORK SUBMITTED ON THIS CHAIN OF CUSTODY IS SUBJECT TO BV LABS' STANDARD TERMS AND CONDITIONS. SIGNING OF THIS CHAIN OF CUSTODY DOCUMENT IS-ACKNOWLEDGMENT AND ACCEPTANCE OF OUR TERMS WHICH ARE AVAILABLE FOR VIEWING AT WWW.BVLABS.COM/TERMS-AND-CONDITIONS.

* IT IS THE RESPONSIBILITY OF THE RELINQUISHER TO ENSURE THE ACCURACY OF THE CHAIN OF CUSTODY RECORD. AN INCOMPLETE CHAIN OF CUSTODY MAY RESULT IN ANALYTICAL TAT DELAYS.

** SAMPLE CONTAINER, PRESERVATION, HOLD TIME AND PACKAGE INFORMATION CAN BE VIEWED AT WWW.BVLABS.COM/RESOURCES/CHAIN-OF-CUSTODY-FORMS.

SAMPLES MUST BE KEPT COOL (< 10° C) FROM TIME OF SAMPLING UNTIL DELIVERY TO BV LABS

White: BV Labs Yellow: Client



September 2020

Mark S. Ells, Town Manager
Town of Barnstable
200 Main Street
Hyannis, MA 02601

RE: Immediate Response Action Status and Remedial Monitoring Report #44
Barnstable County Fire and Rescue Training Academy
155 South Flint Rock Road
Barnstable, Massachusetts
DEP Release Tracking No. 4-26179
Project File #6206

Dear Mr. Ells,

As required by the Massachusetts Contingency Plan (MCP) 310 CMR 40.1403(3)(e) and 40.1403(6), BETA Group, Inc. (BETA) is notifying you on behalf of our client, Barnstable County, that an Immediate Response Action (IRA) Status and Remedial Monitoring Report (RMR) No. 44 is being submitted to the Massachusetts Department of Environmental Protection – Bureau of Waste Site Cleanup (MassDEP – BWSC) for the release site referenced as the Barnstable County Fire and Rescue Training Academy (BCFRTA) located at 155 South Flint Rock Road in Barnstable, Massachusetts (the site). This Report summarizes the IRA activities that occurred from July 1 to July 31, 2020.

Pursuant to the Massachusetts Contingency Plan (310 CMR 40.0480), an Initial Site Investigation has been performed at the site. A release of oils and/or hazardous materials has occurred at the site. In August 2016, MassDEP Southeast Regional Office issued a Notice of Responsibility (NOR) to Barnstable County, as current owner and operator of the Barnstable County Fire and Rescue Training Academy (BCFRTA), that the detection of elevated concentrations of poly- and perfluoralkyl substances (PFAS) in groundwater at the site constituted a release under the MCP. MassDEP issued Release Tracking Number (RTN) 4-26179 to this release. As summarized in the NOR, based on the detected PFAS concentrations in soil and groundwater at the BCFRTA and the inferred groundwater flow, MassDEP determined that the releases of PFAS from the use of aqueous film-forming foam (AFFF) at the BCFRTA is a source of PFAS detected in the Mary Dunn wells.

During the July 2020 reporting period, the treatment system was operable for approximately 31 days. The overall (average) system flow rate and total gallons of groundwater treated are based on the available Effluent flow totalizer readings reported for both systems by the O&M contractor. For the July 2020 reporting period, both systems treated an approximate combined 0.83 million gallons of groundwater from the downgradient recovery well PRW-4 at an average total (of the two systems) effluent flow rate of 18.5 gpm.

Approximately 0.006 kilograms of PFAs were estimated to have been removed from the plume area during this reporting period. PFAs breakthrough into the effluent from the activated carbon treatment system was not observed.


At this time, IRA activities are ongoing. Continuing IRA activities will include operation and monitoring of the on-Site Groundwater Pump and Treatment Systems (GWPTS), including performance sampling of GWPTS, review and evaluation of the on-Site GWPTS operation and maintenance activities as they affect groundwater treatment, and periodic groundwater monitoring. Additional details regarding the continuing IRA activities are included in the IRA Status and RMR No. 44 report document.

The IRA Status and RMR document is available electronically via the searchable sites database of the MassGOV / MassDEP website via the following link:

<https://eeonline.eea.state.ma.us/portal#!/wastesite/4-0026179>

If you have any questions or comments, please do not hesitate to contact our office.

Sincerely,
BETA Group, Inc.



Roger P. Thibault, P.E., LSP
Senior Environmental Engineer

Copies: Mass Department of Environmental Protection
Southeast Regional Office
20 Riverside Drive
Lakeville, MA 02347

Thomas McKean, Director
Town of Barnstable Health Division
200 Main Street
Hyannis, MA 02601

Hans Keijser, Supervisor
Town of Barnstable Water Supply Division
47 Old Yarmouth Road
Hyannis, MA 02601