Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Barnstable County Purchasing Department

Contract BC-26-8110

Road Construction Items and Materials

Robert B. Our Co. Inc.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Barnstable County

Bid No. 8110

Roadway Construction Items and Materials

Table of Contents

Title Sheet ---------- Pages 1

Table of Contents ---------- Pages 1

Advertisement ---------- Pages 1

E-bidding Instructions ---------- Pages 1 - 3

Notice to Contractors Submitting General Bids ---------- Pages 1 - 7

Form for General Bid----------Pages 1 – 6

Form for References----------Pages 1

Contract Form (Including General, Special Provisions & Prevailing Wage)---------- Pages 1 – 108

Appendix A – Commonly Used Forms ----------Pages 1 - 8

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Barnstable County

Regional Government of Cape Cod
Purchasing Department
Jennifer L.V. Frates, Chief Procurement Officer

Advertisement

Barnstable County on behalf of the Towns in the County requests bids from qualified contractors for **Road Construction Items and Materials per Bid No. 8110**

The bid documents may be obtained electronically online at https://barnstablecounty.bonfirehub.com where they are publicly available as of December 31, 2025 at 8:00AM.

Bids are due January 28,2026, at 11:00AM. **THIS PROJECTS IS BEING ELECTRONICALLY BID AND HARD COPY BIDS WILL NOT BE ACCEPTED**. It is the bidder's sole responsibility to familiarize themselves with the Bonfire Online Bid Submission Platform and the online bid submission process and requirements.

The County of Barnstable reserves the right to accept or reject any or all bids, to waive any informality contained therein, and to award the contract as decided to be in the best interest of the County.

All submissions for this project are subject to the provisions of Massachusetts General Laws, Chapter 30, 39M. Prevailing wages apply, where applicable. MassDOT Prequalification will be required on some items.

Awarding Authority reserves the right to extend the contract for one (1) additional 12 month option. Valuation for purposes of MassDOT Prequalification is based on first year times two (2) to arrive at an estimated total value of all bid items. The estimated value provided in this Invitation to Bid is for one year. Vendors are expected to be able to provide their services over two (2) years at two (2) times the initial estimated value.

MassDOT prequalification of contractors will be required for various items as listed with the class of work and estimated value for each one on https://barnstablecounty.bonfirehub.com under the bid opportunity for IFB # 8110 – Road Construction Items and Materials.

The County of Barnstable fully complies with federal, state, and local laws and directives governing equal opportunity, affirmative action and non-discrimination in all county activities and actively solicits bids/proposals from MBE/WBE businesses in accordance with County policy.

Jennifer Frates
Chief Procurement Officer

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Submission Instructions for Suppliers

Please follow these instructions to submit via our Public Portal.

1. Prepare your submission materials:

Requested Information

Name	Type	# Files	Requirement	Instructions
Signed Form for General Bid	File Type: PDF (.pdf)	1	Required	
Bid Bond 5%	File Type: PDF (.pdf)	1	Required	
List of Subcontractors	File Type: PDF (.pdf)	1	Optional	
8110 Road Construction Items and Materials (BT-35AF)	BidTable: Excel (.xlsx)	1	Required	You will need to fill out the provided Response Template for this BidTable. The Response Template can be downloaded from the project listing on the Bonfire portal.
References	File Type: PDF (.pdf)	Multiple	Required	

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Commodity Codes

Commodity Set	Commodity Code	Title	Description
UNSPSC	3012	Roads and landscape	
UNSPSC	301215	Bituminous derivatives	
UNSPSC	301216	Asphalts	
UNSPSC	301217	Road and railroad construction materials	

Requested Documents:

Please note the type and number of files allowed. The maximum upload file size is 1000 MB.

Please do not embed any documents within your uploaded files, as they will not be accessible or evaluated.

Requested BidTables:

The BidTable Response Templates can be obtained at https://barnstablecounty.bonfirehub.com/opportunities/209406.

Please note that BidTables may take a significant amount of time to prepare.

2. Upload your submission at:

https://barnstablecounty.bonfirehub.com/opportunities/209406

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The Question period for this opportunity starts Dec 31, 2025 8:00 AM EST. The Question period for this opportunity ends Jan 21, 2026 5:00 PM EST. You will not be able to send messages after this time.

Your submission must be uploaded, submitted, and finalized prior to the Closing Time of **Jan 28, 2026 11:00 AM EST.** We strongly recommend that you give yourself sufficient time and **at least ONE (1) day** before Closing Time to begin the uploading process and to finalize your submission.

Important Notes:

Each item of Requested Information will only be visible after the Closing Time.

Uploading large documents may take significant time, depending on the size of the file(s) and your Internet connection speed.

You will receive an email confirmation receipt with a unique confirmation number once you finalize your submission.

Minimum system requirements: Microsoft Edge, Google Chrome, or Mozilla Firefox. Javascript must be enabled. Browser cookies must be enabled.

Need Help?

Barnstable County, MA uses a Euna Procurement portal for accepting and evaluating proposals digitally. Please contact Euna Procurement at support.bonfire@eunasolutions.com for technical questions related to your submission. You can also visit their help forum at https://customer.eunasolutions.com/public/s/knowledge-base/bonfire-hub/vendor-submission-support

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

NOTICE TO BIDDERS

1. Project Description/Scope of Work
2. Examination of Site & Documents
3. Sub-Contractors
4. Fair Employment Practices
5. Substitute Material and Equipment
6. Pre-Bid Meeting
7. Bid Response Instructions
8. Required Bid Response Date
9. Bid Security
10. Bid Signature
11. Official Date and Time
12. Time for Bid Acceptance
13. Modification or Withdrawal of Bids, Mistakes, and Minor Informalities
14. Bid Prices to Remain Firm
15. Questions and County POC
16. Changes & Addenda
17. References
18. Wages
19. References to General Laws
20. Cost of Preparation
21. County Tax Exemption
22. Political Activity Prohibited, Anti-Boycott Warranty
23. Contractor Compliance
24. Public Record Request
25. Bid Evaluation Process
26. Vendor Self Service (VSS) – Online Supplier Portal
27. Collective Purchasing

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

IFB# 8110
Roadway Construction Items & Materials

Barnstable County on behalf of the Towns in the County requests bids from qualified contractors for Roadway Construction Items and Materials.

1. **Project Description/Scope of Work**

   Bidders are to submit responses based upon the item specifications as outlined within "Special Provisions" All pricing should be inclusive all cost associated with providing services as specified.

   ALL BIDS FOR THIS PROJECT ARE SUBJECT TO THE PROVISIONS OF MASS. GENERAL LAW CHAPTER 149 SECTION 44A-44J AS AMENDED.

   The General Contractor shall provide all labor, materials, environmental notifications and permits, transportation and equipment required.

   The Towns will require a Payment Bond in the amount of Fifty Percent (50%) on a project by project basis for any project over $25,000.

2. **Examination of Site and Documents**

   Before submitting a Bid, each Bidder must (a) examine the Contract Documents thoroughly, (b) visit the Towns or location to familiarize themselves with local conditions that may in any manner affect cost, progress or performance of the Work, (c) familiarize himself with federal, state and local laws, by laws, rules and regulations that may in any manner affect cost, progress or performance of the Work; and (d) study and carefully correlate Bidder's observations with the Contract Documents.

   The submission of a Bid will constitute an incontrovertible representation by the Bidder that they have complied with every requirement of this Article and that the Contract Documents are sufficient in scope and detail to indicate and convey understanding of all terms and conditions for performance of the Work.

3. **Sub Contractors**

   If the General Conditions require the identity of certain Subcontractors and other persons and organizations to be submitted in advance of the Notice of Award, the apparent Successful Bidder, and any other Bidder so requested, will within seven days after the day of the Bid opening submit a list of all Subcontractors and other persons and organizations (including those who are to furnish the principal items of material and equipment) proposed for those portions of the Work as to which such identification is so required. Such list shall be accompanied by an experience statement with pertinent information as to similar projects and other evidence of qualification for each such Subcontractor, person and organization if requested. If, after due investigation, reasonable objection exists to any proposed Subcontractor, other person or organization, the apparent Successful Bidder will be requested to submit an acceptable substitute without an increase in Bid price.

   If the apparent Successful Bidder declines to make any such substitution, the Contract shall not be awarded to such Bidder. Any Subcontractor, other person or organization so listed and for whom the County has no written objection is submitted prior to the giving of the Notice of Award will be deemed acceptable.

   No Contractor shall be required to employ any Subcontractor, other person or organization against whom they has reasonable objection.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

4. **Fair Employment Practices.**

During the performance of this project, the Bidder and all of their Subcontractors, for themselves , their assignees, and successors in interest, agree as follows: The Bidder, in the performance of all work during, after and prior to completion of work under this Agreement, will not discriminate on grounds of race, color, religious creed, national origin, age or sex in employment practices, in the selection or retention of subcontractors, or in the procurement of materials and rentals of equipment. (Fair Employment Practices law of the Commonwealth M.G.L. Chapter 151B.) The Bidder by signing this Agreement agrees to abide by the above paragraph to the best of their ability.

5. **Substitute Material and Equipment.**

The Contract, if awarded, will be on the basis of material and equipment described/specified in the Contract Specifications. Whenever it is indicated in the Contract Specifications that a substitute or "approved equivalent" item of material or equipment may be furnished or used by Contractor if acceptable, application for such acceptance will not be considered by the County until after the "effective date of the Agreement".

6. **Pre-Bid Meeting**

A pre-bid meeting has not been schedule for this IFB.

7. **Bid Response Instructions**

All bid responses will be received online prior to the date and time specified below for the project titled IFB **# 8110: Roadway Construction Items & Materials** to the Bonfire Online Bidding Tool which can be accessed online at https://barnstablecounty.bonfirehub.com All required documents must be submitted in the format specified, all fields must be completed as specified and the documents must be submitted to the correct project folder in order for the bid response to be complete. ***Hard copy bid responses will not be accepted.*** It is the bidder's sole responsibility to familiarize themselves with the Bonfire Online Bid Submission Platform and the online bid submission process and requirements.

8. **Required Bid Response Date**

Vendors who wish to be considered for this project should submit their bids per the instructions above to the County prior to the date and time specified below.

Bids are due on or before **11:00 AM on January 28, 2026**. No late bids will be accepted.

Bids will be opened publicly online immediately after the bid closes through Microsoft Teams. A link is provided in the Bonfire Submission Instructions for any member of the public who would like to join.

9. **Bid Security**

Bid Security shall be made payable to the County in an amount of five percent (5%) of the Bidder's maximum Bid price and in the form of a Bid Bond.

The Bid Security of the Successful Bidder will be retained until such Bidder has executed the Agreement and furnished the required Contract Security (Payment & Performance Bonds, when required) and Insurance Binders, where upon it will be returned; if the Successful Bidder fails to execute and deliver the Agreement and furnish the required documents within five (5) working days of the Notice of Award, the County may

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

annul the Notice of Award and the Bid Security of that Bidder will be forfeited. The Bid Security of any Bidder whom the County believes to have a reasonable chance of receiving the award may be retained by the County until the earlier of the seventh (7th) day after the "effective date of the Agreement" (which term is defined in the General Conditions) by the County to Contractor and the required Contract Security is furnished or the sixty first (61st) day after the Bid opening. Bid Security of other Bidders will be returned within seven (7) days of the Bid opening.

10. Bid Signature

A bid must be signed as follows: 1) if the bidder is an individual, by her/him personally; 2) if the bidder is a partnership, by the name of the partnership, followed by the signature of each general partner; and 3) if the bidder is a corporation, by the authorized officer, whose signature must be attested to by the clerk/secretary of the corporation, and with the corporate seal affixed.

11. Official Date & Time

A bid will not be considered delivered unless the bid has been received online by the Bonfire Online Bidding Tool (in the correct project) which can be accessed at https://barnstablecounty.bonfirehub.com prior to the date and time specified in the documents. The official date and time shall be the date and time shown online at https://barnstablecounty.bonfirehub.com

12. Time for Bid Acceptance

The contract will be awarded within 30 days after the bid opening.

13. Modification or Withdrawal of Bids, Mistakes, and Minor Informalities

Any bids may be withdrawn or modified prior to the date and time stated in the bid for the opening of bids. Such withdrawal or modification must be done by the bidder online through the Bonfire Online Bidding Tool.

After the bid opening, a Bidder may not change any provision of the bid in a manner prejudicial to the interests of the County for fair competition. Minor informalities will be waived or the Bidder will be allowed to correct them. If a mistake and the intended bid are clearly evident on the face of the bid document, the mistake will be corrected to reflect the intended correct bid, and the Bidder will be notified in writing; the Bidder may not withdraw the bid. A Bidder may withdraw a bid if a mistake is clearly evident on the face of the bid document, but the intended correct bid is not similarly evident.

If this bid is received electronically, Bidders are solely responsible for obtaining and completing required attachments that are identified in this bid and for checking for any addenda or modifications that are subsequently made to this bid or attachments. Barnstable County accepts no liability and will provide no accommodation to Bidders who fail to check for amended bids and submit inadequate or incorrect responses.

Bidders may not alter (manually or electronically) the bid language or any bid documents. Unauthorized modifications to the body of the bid, specifications, terms or conditions, or which change the intent of this bid are prohibited and may disqualify a response.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

14. Bid Prices to Remain Firm

All bid prices submitted in response to this bid must remain firm for 60 days following the bid opening.

15. Questions and County POC

No interpretation of the meaning of the plans, specifications or other pre-bid documents will be made to any bidder orally. All information given to bidders other than by means of the plans, specifications, or by addenda, as described below, is given informally and shall not be used as the basis of a claim against the Owner.

Any clarification of requirements or requests for additional information by proposers must be made in writing to the Bonfire Public Q&A https://barnstablecounty.bonfirehub.com and submitted no later than the deadline as referenced in the Submission instructions. Answers to all questions will be made in writing and posted online as an addendum to the **IFB # 8110: Roadway Construction Items & Materials** on the bid website as an attachment under the bid information: https://barnstablecounty.bonfirehub.com

Vendors with multiple questions shall submit up to 10,000 words in a single post within the Public Q&A section of Bonfire.

16. Changes & Addenda

Failure of any bidder to receive any such addendum or interpretation shall not relieve such bidder from any obligation under his bid as submitted. All addenda so issued shall become part of the Contract Documents.

17. References

Provide the contact information (entity name, contact name, title, phone number & email address) for three client references on projects of similar type, scale, and complexity.

18. Wages

All bids for this project are subject to the provisions of either or both Mass. G. L., Chapter 30, Section 39M as amended and/or Mass. G. L. Chapter 149, Section 44A - 44J inclusive as amended. Attention is directed to the minimum wage rates to be paid on the work as determined by the Commissioner of Labor and Industries under the provisions of Mass. G. L. Chapter 149, Section 26 - 27D inclusive. The Awarding Authority reserves the right to waive any informality in or to reject any and all bids if the Awarding Authority determines it is in the public interest so to do.

Please note prevailing wages do not apply to materials Item numbers 200 – 218

19. Reference to General Laws

Whenever in the bid, contract, plans, drawings or specifications, reference is made to General Laws it shall be construed to include all amendments thereto effective as of the date of issue of invitation to bid on the proposed work.

20. Cost of Preparation

The cost of preparation and delivery of the bids will be borne solely by the Vendor.

21. County Tax Exemption

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Any material furnished to Barnstable County is to be exempt from Massachusetts Sales Tax (Massachusetts Sales Tax Exemption No. E-04-6001419).

22. Political Activity Prohibited, Anti-Boycott Warranty

The Contractor may not use any Contract funds and none of the services to be provided by the Contractor may be used for any partisan political activity or to further the election or defeat of any candidate for public office. During the term of this Contract, neither the Contractor nor any controlled group, within the meaning of s.993 (a) (3) of the Internal Revenue Code, as amended, shall participate in or cooperate with any international boycott, as defined in s.999 (b) (3) and (4) of the Internal Revenue Code of 1954, as amended; nor shall either engage in conduct declared to be unlawful by M.G.L. c.151Es.2.

23. Contractor Compliance

The successful Contractor must comply with provisions of The Copeland Anti-Kickback Act (18 USC 874) as supplemented in Department of Labor 29 CFR Part 3, the Davis-Bacon Act (40 USC 276a et.seq.), Sections 103 and 107 of the contract Work Hours and Safety Standard Act (50 USC 327-330) as supplemented by Department of Labor Regulation 29 CFR Part 5, and the Clean Air Act of 1970 (42 USC 1857, et.seq.) to the extent that they are applicable.

24. Public Record Request

All bids received are subject to Massachusetts General Laws Chapter 4, Section 7, Section 26 and Chapter 66, Section 10 regarding public access to such documents. Statements or endorsements inconsistent with those statues will be disregarded.

25. Selection and Notice

The awarding authority may cancel an invitation for bids, a request for bids, or other solicitation, or may reject in whole or in part any and all bids or bids when the awarding authority determines that cancellation or rejection serves the best interests of the County of Barnstable.

Basis for Acceptance:

Any bid made will be accepted only on the basis that the Bidder represents that it is made in good faith without fraud, collusion or connection of any kind with any other Bidder for the same work; that the Bidder is competing solely in its own behalf without connection with, or obligation to, any undisclosed person, firm or corporation; that no other person, firm or corporation has any interest in the contract; that no officer, agent or employee of the County is financially interested in the contract; that the Bidder is fully informed in regard to all provisions of the Contract Documents, including, without limitation, the specifications and drawings, if any; the damages, bonds and insurance, if any. The awarding of the contract is subject to the approval of the Barnstable County Commissioners.

Rule for Award:

Bid selection will be by each item and will be based on the lowest, qualified, responsible, and responsive bid for each item for each Town. Any exception is noted on the General Bid Form for items that are grouped or if items are awarded to the two lowest.

Contract Award:

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The Chief Procurement Officer shall award the contract by written notice to the selected Bidder within 30 days of the IFB deadline. The parties may extend the time for acceptance by mutual agreement. In accordance with M.G.L. c.30B, the awarding of the contract is subject to the approval of the Barnstable County Commissioners.

26. Vendor Self Service (VSS) – Online Supplier Portal

For Vendors doing business with the Departments within the County Regional Government, Vendor Self Service (VSS) is available to enter and maintain contact and remittance information, discount and payment terms, designated contact persons, view current and prior 1099 data, purchase orders, invoices and checks.

Vendors are encouraged to visit: https://selfservice.capecod.gov/vss to register and click Vendor Self Service. Instructions are available on the landing page to help with the registration.

If you have done business with the County before, please be sure to have your vendor number and register as an existing vendor.

If you need your login information or have general questions, please email accounts.payable@capecod.gov, purchasing questions, please email purchasing@capecod.gov and banking information questions, please email treasury@capecod.gov

Registration process takes 1-5 business days to finalize upon receipt of a completed, correct and signed W-9. For a blank W-9 form, visit IRS Website for the most recent version.

27. Collective Purchasing

In the event that the County is the lead agency in the procurement of goods and services on behalf of the Towns in Barnstable County and Political Subdivisions listed in Attachment A, the following shall apply:

A. *Participating Entities:* Reserve the right to reject their portion of the bid, waive any informalities.

Towns and Agencies not included in the bid and/or award will not be allowed to "piggyback" on this procurement.

B. *Contractual Terms and Conditions:* A Barnstable County contract for services will be executed as part of this procurement process.
Termination of a contract or services by any municipality shall not invalidate or alter the terms of a contract or services with any other municipality.
Some Towns or suppliers may require entering into their own specific agreements in addition to the execution of the County contract. Please note that the terms and conditions of these additional agreements shall not supersede the County contract terms and conditions. Participants are encouraged to submit these documents to their legal counsel for review.

C. *Supplier Disputes:* Participating entities are to attempt to resolve any matters directly with the Supplier with no involvement from the County. Only in the event of an unresolved dispute will the County attempt to settle the issue if they pertain to the services provided in the subject contract.

END OF IFB

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

GENERAL BID FORM

FORM FOR GENERAL BID

The undersigned also hereby certify under the penalties of perjury that they are the only persons interested in this proposal; that it is made without any connection with any other person making any bid for the same work; that no person acting for, or employed by, Barnstable County is directly or indirectly interested in this proposal, or in any contract which be made under it, or in expected profits to arise therefrom; and without directly or indirectly influencing or attempting to influence any other person or corporation to bid or to refrain from bidding or to influence the amount of the bid of any other person or corporation; and that this proposal is made in good faith without collusion or connection with any other person bidding for the same work; and that this proposal is made with distinct reference and relation to the plans and specifications prepared for this contract and herein mentioned. The undersigned further declare that in regard to the conditions affecting the work to be done and the labor and materials needed, this proposal is based solely on their own investigation and research and not in reliance upon any representation of any employee, officer or agent of Barnstable County.

Any proposals may be withdrawn or modified prior to the date and time stated in the proposal for the opening of proposals. Such withdrawal or modification must be done by the bidder online through the Bonfire Online Bidding Tool.

After the bid opening, a bidder may not change any provision of the bid in a manner prejudicial to the interests of the County for fair competition. Minor informalities will be waived or the bidder will be allowed to correct them. If a mistake and the intended bid are clearly evident on the face of the bid document, the mistake will be corrected to reflect the intended correct bid, and the bidder will be notified in writing; the bidder may not withdraw the bid. A bidder may withdraw a bid if a mistake is clearly evident on the face of the bid document, but the intended correct bid is not similarly evident.

If this bid is received electronically, bidders are solely responsible for obtaining and completing required attachments that are identified in this bid and for checking for any addenda or modifications that are subsequently made to this bid or attachments. Barnstable County accepts no liability and will provide no accommodation to bidders who fail to check for amended bids and submit inadequate or incorrect responses.

Bidders may not alter (manually or electronically) the bid language or any bid documents. Unauthorized modifications to the body of the bid, specifications, terms or conditions, or which change the intent of this bid are prohibited and may disqualify a response.

Name of General Bidder: Robert B. Our Co., Inc

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

PROJECT NO. 8110

Each Town has provided estimated quantities for each bid item that it presently intends to order. These estimated quantities are for bid purposes only and cannot be guaranteed. The estimated amounts are also a total aggregate which the town intends to use during the contract period and the bidder should familiarize themselves with the minimum job quantities defined in the individual specifications for each item.

THIS BID IS SUBMITTED TO:

(Name and Address of Owner)

Office of the County Commissioners
Superior Court House
P.O. Box 427
Barnstable, Massachusetts 02630

A. The undersigned proposes to furnish all labor and materials required for **IFB #8110 Roadway Construction Items and Materials** in accordance with the accompanying plans and specifications by Barnstable County.

B. The undersigned BIDDER proposes and agrees, if the Bid is accepted to enter into an Agreement with the County, to complete all Work as specified or indicated in the Contract Documents for the Contract Unit Prices during the contract period of April 1, 2026 to March 31, 2027 with one, one year option to renew.

C. In submitting this Bid, BIDDER represents, as more fully set forth in the Agreement, that the BIDDER has examined copies of all the Contract Documents and of the following addenda:

Bidder acknowledges addenda numbered 1

D. Bidders are to complete the Bid Table provided in the Bonfire Online Bidding Tool.

E. Bid comparison will be based on each item unit price provided for each Town. Bidders may bid on any or all items for any or all Towns listed. Bid selection will be by each item by Town and will be based on the lowest, qualified, responsible, and responsive bid for each item for each Town.

F. It is the intent to award a contract to the two (2) lowest, qualified, responsible, and responsive bidders for Item Numbers: **1- 7, 18 and 19.**

It is the intent to award a contract to the two (2) lowest, qualified, responsible, and responsive bidders for Bid Items **115 to 122.**

It is the intent to group items **100-107A** together and award to one vendor.

It is the intent to award Item **200** based on the shortest distance and cost.

The undersigned BIDDER proposes and agrees, if the Bid is accepted to enter into an Agreement with the County, to complete all Work as specified or indicated in the Contract Documents.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

BIDDER accepts all the terms and conditions of the Notice to Bidders. The Bidder agrees that this bid shall be good and may not be withdrawn for a period of 30 days, Saturdays, Sundays and legal holidays excluded, after the opening of bids.

BIDDER will sign the Agreement and submit other documents (e.g. Bonds, Insurance Binders) required by the Contract Documents within ten (10) working days after the date of the County's Notice of Award.

BIDDER will complete all the Work assigned for the lump sum price listed in the Bid Form.

Bid selected will be awarded to the qualified, responsive and responsible Bidder, offering the lowest price.

The undersigned also certifies: that they are able to furnish labor that can work in harmony with all other elements of labor employed or to be employed in the work; and, that all employees at the worksite will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration at the time the employee begins work and who shall furnish documentation of successful completion of said course with the first certified payroll report for each employee.

The undersigned further certifies under the penalties of perjury that this bid is in all respects bona fide, fair and made without collusion or fraud with any other person. As used in this subsection the word "person" shall mean any natural person, joint venture, partnership, corporation or other business or legal entity. The undersigned further certifies under penalty of perjury that the said undersigned is not presently debarred from doing public construction work in the Commonwealth under the provisions of section twenty-nine F of chapter twenty-nine, or any other applicable debarment provisions of any other chapter of the General Laws or any rule or regulation promulgated there under.

Should the notice to contractors, bid form, contract, plans or specifications require submission of special data to accompany the bid, the Awarding Authority reserves the right to rule the bidders failure to submit such data an informality and to receive said data subsequently, within a reasonable time as set by the Awarding Authority.

Project No. 8110

Date 1/28/26

Robert B. Our Co., Inc
(Name of General Bidder)

By _____
(Name of Person Signing Bid and Title)

Abigail Rose, Vice President

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The following information is furnished by the bidder for the information of the County.

If a Corporation:

Incorporated in what State MA

President Christopher W. Our Treasurer Joan A. Our

Secretary Joan A. Our

If a foreign corporation, are you registered to do business in Mass.? Yes _____ No _____

If selected for this work you are required under Mass. G.L. C30 S39L to obtain from the Secretary of State, Foreign Corp. Section, State House, Boston, a certificate stating that your corporation is registered: and furnish said certificate to the awarding authority prior to the award.

If a Partnership: (Name all partners)

Name of partner _____ Residence_____

Name of partner _____ Residence_____

If an Individual:

Name _____ Residence_____

If an Individual doing business under a firm name:

Name of firm_____

Business Address_____

Name of Individual_____ Residence_____


Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

CERTIFICATE OF COMPLIANCE WITH STATE TAX LAWS AND WITH UNEMPLOYMENT COMPENSATION CONTRIBUTION REQUIREMENTS

Pursuant to M.G.L., Ch. 62C, s. 49A and M.G.L. Ch. 151A, s. 1 9A, I, Abigail Rose authorized signatory for Robert B. Our Co., Inc whose principal place of business is at 24 Great Western Road, Harwich MA 02645 do hereby certify under penalties of perjury that Robert B. Our Co., Inc. has filed all state tax returns and paid all taxes as required by law and has complied with all state laws pertaining to contributions to the unemployment compensation fund and to payments in lieu of contributions.

The Business Organization Federal Identification Number or Social Security Number is 04-2319318

Signed under the penalties of perjury the 28th day of January 20 26

Signature: 

Name and Title: Abigail Rose, Vice President

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Please see, attached.

If a corporation, complete below or attach to each signed copy of a Contract a notarized copy of vote of corporation authorizing the signatory to sign this Contract. If attesting clerk is same as individual executing Contract have signature notarized below.

At a duly authorized meeting of the Board of Directors of the _____
(Name of Corporation)

held on _____ at which all the Directors were present or waived notice,
(Date)

it was **VOTED** That,

_____ _____
(Name) (Officer)

of this company be and hereby is authorized to execute Contract and bonds in the name and behalf of said company, and affix its corporate seal thereto, and such execution of and Contract or obligation in this company's name on its behalf by such _____ of the company,
(Officer)
shall be valid and binding upon this company.

I hereby certify that I am the Clerk of the _____

_____ that _____ is duly elected

_____ of said company, and that the above has not been amended or rescinded
(Officer)
and remains in full force and effect as of the date of this Contract.

a true copy,

ATTEST _____
Clerk

Place Of Business _____

Corporate
_____ Seal

SWORN TO AND SUBSCRIBED BEFORE ME THIS _____ DAY OF _____, 20 ____

_____
NOTARY PUBLIC

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

ROBERT B. OUR CO., INC.
SITE & UTILITY CONSTRUCTION
HARWICH, MA

CERTIFICATE OF VOTE

Pursuant to a regular and duly filed waiver of notice, a special meeting of the Board of Directors of Robert B. Our Co., Inc. was duly called and held at 24 Great Western Road, Harwich, Massachusetts, on December 1, 2021 at ten o'clock in the morning. All the Directors and Stockholders were present and/or in writing waived notice and assented to all action taken thereat. I certify that the following vote, which has never been rescinded or revoked, was passed:

"VOTED: That Abigail J. Rose, Vice President of Robert B. Our Co., Inc. be and she is hereby authorized and empowered, in the name and on behalf of the Corporation and upon such terms as she may deem necessary, proper or advisable, to sign, seal, execute and deliver any and all agreements and contracts which she may from time to time deem necessary, proper or advisable, for the business of the Corporation;

"VOTED: That Abigail J. Rose, Vice President of Robert B. Our Co., Inc. be and she is hereby authorized and empowered, in the name and on behalf of the Corporation and upon such terms as she may deem necessary, proper or advisable, to sign, seal, execute and deliver any and all applications for Bonds and Bonds relative to work performance of said Corporation, and to do any and all related acts which she may from time to time deem necessary, proper or advisable, for the business of the Corporation;

I do further certify that Robert B. Our Co., Inc. is a duly organized Corporation; that the foregoing Vote is in accordance with the charter and by-laws of said Corporation; that Abigail J. Rose is a duly elected and qualified Vice President of the Corporation, and that I am the duly elected and qualified Clerk of the Corporation.

Dated: December 1, 2021

A true extract record.

ATTEST:

Joan A. Our
Clerk

CORPORATE SEAL

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Document A310™ – 2010

Conforms with The American Institute of Architects AIA Document 310

Bid Bond

CONTRACTOR:
(Name, legal status and address)
Robert B. Our Co., Inc.
24 Great Western Road
Harwich, MA 02645

SURETY:
(Name, legal status and principal place of business)
Fidelity and Deposit Company of Maryland
1299 Zurich Way
Schaumburg, IL 60196-1056
Mailing Address for Notices

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

OWNER:
(Name, legal status and address)
Barnstable County
3195 Main Street
Barnstable, MA 02630

BOND AMOUNT: 5% Five Percent of Amount Bid

PROJECT:
(Name, location or address, and Project number, if any)
IFB # 8110: Roadway Construction Items & Materials

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

Signed and sealed this 28th day of January, 2026.

(Witness)

Robert B. Our Co., Inc.
(Principal) *(Seal)*

By:
(Title) Abigail Rose, Vice President

(Witness)

Fidelity and Deposit Company of Maryland
(Surety) *(Seal)*

By:
(Title) Anne M. Higginbotham Attorney-in-Fact

Fidelity and Deposit Company of Maryland CORPORATE SEAL 1890 Illinois

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Bond No. **Bid Bond**

Obligee: **Barnstable County**

ZURICH AMERICAN INSURANCE COMPANY
COLONIAL AMERICAN CASUALTY AND SURETY COMPANY
FIDELITY AND DEPOSIT COMPANY OF MARYLAND
POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS: That the ZURICH AMERICAN INSURANCE COMPANY, a corporation of the State of New York, the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, a corporation of the State of Illinois, and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND a corporation of the State of Illinois (herein collectively called the "Companies"), by Christopher Nolan, Vice President, in pursuance of authority granted by Article V, Section 8, of the By-Laws of said Companies, which are set forth on the reverse side hereof and are hereby certified to be in full force and effect on the date hereof, do hereby nominate, constitute, and appoint **Anne M. Higginbottom**, its true and lawful agent and Attorney-in-Fact, to make, execute, seal and deliver, for, and on its behalf as surety, and as its act and deed: **any and all bonds and undertakings,** and the execution of such bonds or undertakings in pursuance of these presents, shall be as binding upon said Companies, as fully and amply, to all intents and purposes, as if they had been duly executed and acknowledged by the regularly elected officers of the ZURICH AMERICAN INSURANCE COMPANY at its office in New York, New York., the regularly elected officers of the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY at its office in Owings Mills, Maryland., and the regularly elected officers of the FIDELITY AND DEPOSIT COMPANY OF MARYLAND at its office in Owings Mills, Maryland., in their own proper persons.

The said Vice President does hereby certify that the extract set forth on the reverse side hereof is a true copy of Article V, Section 8, of the By-Laws of said Companies, and is now in force.

IN WITNESS WHEREOF, the said Vice-President has hereunto subscribed his/her names and affixed the Corporate Seals of the said **ZURICH AMERICAN INSURANCE COMPANY, COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and FIDELITY AND DEPOSIT COMPANY OF MARYLAND**, this 7th day of February, A.D. 2025.



ATTEST:
ZURICH AMERICAN INSURANCE COMPANY
COLONIAL AMERICAN CASUALTY AND SURETY COMPANY
FIDELITY AND DEPOSIT COMPANY OF MARYLAND

By: Christopher Nolan
Vice President

By: Dawn E. Brown
Secretary

State of Maryland
County of Baltimore

On this 7th day of February, A.D. 2025, before the subscriber, a Notary Public of the State of Maryland, duly commissioned and qualified, **Christopher Nolan, Vice President and Dawn E. Brown, Secretary** of the Companies, to me personally known to be the individuals and officers described in and who executed the preceding instrument, and acknowledged the execution of same, and being by me duly sworn, deposeth and saith, that he/she is the said officer of the Company aforesaid, and that the seals affixed to the preceding instrument are the Corporate Seals of said Companies, and that the said Corporate Seals and the signature as such officer were duly affixed and subscribed to the said instrument by the authority and direction of the said Corporations.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed my Official Seal the day and year first above written.



Genevieve M. Maison
Notary Public
My Commission Expire January 27, 2029

Authenticity of this bond can be confirmed at bondvalidator.zurichna.com or 410-559-8790

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

EXTRACT FROM BY-LAWS OF THE COMPANIES

"Article V, Section 8, Attorneys-in-Fact. The Chief Executive Officer, the President, or any Executive Vice President or Vice President may, by written instrument under the attested corporate seal, appoint attorneys-in-fact with authority to execute bonds, policies, recognizances, stipulations, undertakings, or other like instruments on behalf of the Company, and may authorize any officer or any such attorney-in-fact to affix the corporate seal thereto; and may with or without cause modify of revoke any such appointment or authority at any time."

CERTIFICATE

I, the undersigned, Vice President of the ZURICH AMERICAN INSURANCE COMPANY, the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY, and the FIDELITY AND DEPOSIT COMPANY OF MARYLAND, do hereby certify that the foregoing Power of Attorney is still in full force and effect on the date of this certificate; and I do further certify that Article V, Section 8, of the By-Laws of the Companies is still in force.

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the ZURICH AMERICAN INSURANCE COMPANY at a meeting duly called and held on the 15th day of December 1998.

RESOLVED: "That the signature of the President or a Vice President and the attesting signature of a Secretary or an Assistant Secretary and the Seal of the Company may be affixed by facsimile on any Power of Attorney...Any such Power or any certificate thereof bearing such facsimile signature and seal shall be valid and binding on the Company."

This Power of Attorney and Certificate may be signed by facsimile under and by authority of the following resolution of the Board of Directors of the COLONIAL AMERICAN CASUALTY AND SURETY COMPANY at a meeting duly called and held on the 5th day of May, 1994, and the following resolution of the Board of Directors of the FIDELITY AND DEPOSIT COMPANY OF MARYLAND at a meeting duly called and held on the 10th day of May, 1990.

RESOLVED: "That the facsimile or mechanically reproduced seal of the company and facsimile or mechanically reproduced signature of any Vice-President, Secretary, or Assistant Secretary of the Company, whether made heretofore or hereafter, wherever appearing upon a certified copy of any power of attorney issued by the Company, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

IN TESTIMONY WHEREOF, I have hereunto subscribed my name and affixed the corporate seals of the said Companies, this 28th day of January, 2026.



MJ Pethick

Mary Jean Pethick
Vice President

TO REPORT A CLAIM WITH REGARD TO A SURETY BOND, PLEASE SUBMIT A COMPLETE DESCRIPTION OF THE CLAIM INCLUDING THE PRINCIPAL ON THE BOND, THE BOND NUMBER, AND YOUR CONTACT INFORMATION TO:

Zurich Surety Claims
1299 Zurich Way
Schaumburg, IL 60196-1056
reportsfclaims@zurichna.com
800-626-4577

Authenticity of this bond can be confirmed at bondvalidator.zurichna.com or 410-559-8790

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

BARNSTABLE COUNTY

This agreement, made this 25 day of March 2026 between Barnstable County hereinafter called the County, and Robert B. Our Co., Inc. a corporation, partnership, individual organized under the laws of the state of Massachusetts and having a usual place of business in 24 Great Western Road, Harwich, MA 02645 in the county of Barnstable hereinafter called the Contractor.

Witnesseth, That the parties to this agreement, each in consideration of the agreements on the part of the other herein contained, do hereby agree, the County Abigail Rose, Vice President (authorized agent of general Contractor) for Robert B. Our Co., Inc. (general Contractor) and All heirs, executors, administrators, successors assigns, as follows:

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

General Conditions
Table of Contents

ARTICLE 1 – DEFINITION OF TERMS

ARTICLE 2 – CONTRACT DOCUMENTS, INTENT, AMENDING, AND REUSE

ARTICLE 3 – CONTRACTOR'S LIABILITY INSURANCE

ARTICLE 4 – CONTRACTOR'S RESPONSIBILITIES

ARTICLE 5 – UNIT PRICE WORK

ARTICLE 6 – WARRANTY AND GUARANTEE; TESTS AND INSPECTION;
CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK

ARTICLE 7 – PAYMENT BONDS

ARTICLE 8 – EFFECTIVE DATE

ARTICLE 9 – CHANGES IN THE WORK

ARTICLE 10 – ENGINEER

ARTICLE 11 – WAGE RATES

ARTICLE 12 – TERMINATION OF CONTRACT

ARTICLE 13 – MISCELLANEOUS

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

ARTICLE I - DEFINITIONS OF TERMS

1. County means the County of Barnstable, MA through the County Commissioners.

2. Successful Bidder means the lowest, qualified, responsible, and responsive Bidder to whom the County makes an award.

3. Owner means the following entities/municipalities participating in this contract in Massachusetts: Barnstable, Brewster, Dennis, Eastham, Falmouth, Harwich, Orleans, Sandwich, Wellfleet and Yarmouth.

4. Town means the individual town identified in the "Owner"

5. Designer, Architect, Engineer or any pronoun or phrase in place thereof: N/A Designer(s) shall perform the duties and exercise the rights herein conferred. In the case of death, resignation, inability or refusal of said Designer to act, or the termination of his employment, the County may appoint another person as Designer of which notice shall be given in writing to the Contractor, which person shall perform all the duties and exercise all the rights of the Designer hereunder.

6. Contractor or General Contractor or a pronoun in place of it: the party or parties Contracting to perform the work covered by this Contract or the legal representatives of said party or parties.

7. Superintendent or Construction Supervisor or a pronoun in place of it: the competent, responsible employee regularly employed by the Contractor and designated to be in full time attendance at the project site throughout the prosecution and progress of the work and who shall have complete authority to act for the Contractor.

8. As Directed, As Permitted, As Required, As Determined or words of like effect: the direction, permission, requirement or determination of the Designer. Similarly, approved, acceptable, satisfactory or words of like import shall mean approved by or acceptable or satisfactory to the Designer, except as may be otherwise determined by the Director.

9. Or equal or words of like import: equal in the opinion of the Designer except as may be otherwise determined by the County pursuant to the provisions of G.L. Chapter 30, section 39M.

10. Contract Documents or Contract: the Notice to Contractors, Information to Bidders, Form of General Bid, Contract, General Conditions, Specifications and Plans and all addenda issued during the bidding period, change orders and policies and procedures of the County attached hereto or referred to, all of which constitute one instrument.

11. Mass State Building Code: all applicable rules and regulations to which the County is subject and which are contained in the code authorized by Chapter 802 of the Acts of 1972 including all amendments thereto.

12. Plan(s):drawing(s).

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

13. Change Order: a written order not requiring the consent of the Contractor, signed by the Awarding Authority or the Director and designated as an approved change order, directing the Contractor to make changes in the work within the general scope of the Contract, or, any written or oral order from the Awarding Authority or the Director which causes any change in the work, provided that the Contractor gives the County written notice stating the date, circumstances, and source of the order and that the Contractor regards the order as a change order.

14. Contract Modification: any written alteration in plans or specifications, period of performance, price, quantity, or any other provisions of the Contract accomplished by mutual action of the parties to the Contract.

Where reference is made in the Contract documents to Publications, Standards or Codes issued by Associations or Societies, the intent shall be to specify the current edition of such publication or standard including revision in effect on the date of the Contract advertisement notwithstanding any reference to a particular date.

ARTICLE 2 – CONTRACT DOCUMENTS, INTENT, AMENDING, AND REUSE

Intent:

2.1 The Contract Documents comprise the entire Agreement between the COUNTY and CONTRACTOR concerning the Work. The Contract Documents are complementary: what is called for by one is as binding as if called for by all. The Contract Documents will be construed in accordance with the law of the place of the Project.

2.2 It is the intent of the Contract Documents to describe a functionally complete Project or Service (or part thereof) to be constructed in accordance with the Contract Documents. Any Work, materials or equipment that may reasonably be inferred from the Contract Documents as being required to produce the intended result will be supplied whether or not specifically called for. When words which have a well-known technical or trade meaning are used to describe Work, materials or equipment such words shall be interpreted in accordance with that meaning. Reference to standard specifications, manuals or codes of any technical society, organization or association, or to the Laws or Regulations of any governmental authority, whether such reference be specific or by implication, shall mean the latest standard specification, manual, code or Laws or Regulations in effect at the time of opening of Bids (or, on the Effective Date of the Agreement if there were no Bids), except as may be otherwise specifically stated. However, no provision of any referenced standard specification, manual or code (whether or not specifically incorporated by reference in the Contract Documents) shall be effective to change the duties and responsibilities of the County, the Towns or CONTRACTOR, or any of their agents or employees from those set forth in the Contract Documents, nor the Notice to Proceed.

ARTICLE 3 CONTRACTOR'S LIABILITY INSURANCE

3.1 CONTRACTOR shall purchase and maintain such comprehensive general liability and other insurance as is appropriate for the Work being performed and furnished and as will provide protection from claims set forth below which may arise out of or result from CONTRACTOR'S performance and furnishing of the Work and CONTRACTOR'S other obligations under the Contract Documents, whether it is to be performed or furnished by CONTRACTOR, by any Subcontractor, by anyone directly or indirectly

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

employed by any of them to perform or furnish any of the Work, or by anyone for whose acts any of them may be liable:

3.1.1 Claims under workers' or workmen's compensation, disability benefits and other similar employee benefit acts;

3.1.2 Claims for damages because of bodily injury, occupational sickness or disease, or death of CONTRACTOR'S employees;

3.1.3 Claims for damages because of bodily injury, sickness or disease, or death of any person other than CONTRACTOR'S employees;

3.1.4 Claims for damages insured by personal injury liability coverage which are sustained (a) by any person as a result of an offense directly or indirectly related to the employment of such person by CONTRACTOR, or (b) by any other person for any other reason;

3.1.5 Claims for damages, other than to the Work itself, because of injury to or destruction of tangible property wherever located, including loss of use resulting therefrom;

3.1.6 Claims arising out of operation of Laws or Regulations for damages because of bodily injury or death of any person or for damage to property; and

3.1.7 Claims for damages because of bodily injury or death of any person or property damage arising out of the ownership, maintenance or use of any motor vehicle.

The insurance required above shall include the specific coverages and be written for not less than the limits of liability and coverages provided as follows:

1. Workmen's Compensation: In accordance with the Workmen's Compensation Laws that are applicable to the employees engaged in the Work. The limit of Employer's Liability Insurance shall be not less than $500,000 each accident.

2. Public Liability Insurance for Personal Injury:
   a. Individual limit of $1,000,000 each person.
   b. Total limit of $ 3,000,000 for each accident.

3. Property Damage Insurance:
   a. Each claim $ 1,000,000.
   b. Aggregate $ 3,000,000.

4. If the CONTRACTOR sublets any portion of his work, then he shall also provide:
   a. Contractor's Protective Liability Insurance:
      (1) Individual limit for personal injury of $1,000,000.
      (2) Total limit for personal injury for one accident of $3,000,000.
   b. Contractor's Protective Property Damage Insurance with a limit of $1,000,000/$3,000,000.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Any Subcontractor under contract with CONTRACTOR to perform Work on the Project shall hold the County, the Towns and agents harmless, and purchase and maintain such comprehensive general liability and other insurance as will provide protection from claims set forth herein.

The County and the Towns shall be specifically named as additional insureds on all required insurance policies of the CONTRACTOR and any Subcontractors.

In addition, CONTRACTOR shall maintain such completed operations insurance for at least one year after final payment and furnish the County with evidence of continuation of such insurance at final payment.

ARTICLE 4 – CONTRACTOR'S RESPONSIBILITIES

Supervision and Superintendence:

4.1 CONTRACTOR shall supervise and direct the Work competently and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the Work in accordance with the Contract Documents. CONTRACTOR shall be solely responsible for the means, methods, techniques, sequences and procedures of construction, but CONTRACTOR shall not be responsible for the negligence of others in the design or selection of a specific means, method, technique, sequence or procedure of construction which is indicated in and required by the Contract Documents. CONTRACTOR shall be responsible to see that the finished Work complies accurately with the Contract Documents.

Labor, Materials and Equipment

4.2 CONTRACTOR shall provide competent, suitably qualified personnel to survey and lay out the Work and perform construction as required by the Contract Documents. CONTRACTOR shall at all times maintain good discipline and order at the site. Except in connection with the safety or protection of persons or the Work or property at the site or adjacent thereto, and except as otherwise indicated in the Contract Documents, all Work at the site shall be performed during regular working hours, and CONTRACTOR will not permit overtime work or the performance of Work on Saturday, Sunday or any legal holiday without the County or Owner's written consent.

4.3 All materials and equipment shall be of good quality and new, except as otherwise provided in the Contract Documents. If required by the County or a Owner, CONTRACTOR shall furnish satisfactory evidence (including reports of required tests) as to the kind and quality of materials and equipment. All materials and equipment shall be applied, installed, connected, erected, used, cleaned and conditioned in accordance with the instructions of the applicable Supplier.

Laws and Regulations

4.4 CONTRACTOR shall give all notices and comply with all Laws and Regulations applicable to furnishing and performance of the Work. Except where otherwise expressly required by applicable Laws and Regulations, the County or Owners shall not be responsible for monitoring CONTRACTOR'S compliance with any Laws or Regulations.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Taxes

4.5 State taxes will be excluded from all General and Sub-bids. The Towns shall provide their exemption certificate number(s) to the CONTRACTOR. CONTRACTOR shall pay all taxes required to be paid by CONTRACTOR in accordance with the Laws and Regulations of the place of the Project which are applicable during the performance of the Work.

Use of Premises

4.6 CONTRACTOR shall confine construction equipment, the storage of materials and equipment and the operations of workers to the Project site and land and areas identified in and permitted by the Contract Documents and other land and areas permitted by Laws and Regulations, rights-of-way, permits and easements, and shall not unreasonably encumber the premises with construction equipment or other materials or equipment. CONTRACTOR shall assume full responsibility for any damage to any such land or area, or to the owner or occupant thereof or of any land or areas contiguous thereto, resulting from the performance of the Work. Should any claim be made against the County or any Town by any such owner or occupant because of the performance of the Work, CONTRACTOR shall promptly attempt to settle with such other party by agreement or otherwise resolve the claim by arbitration or at law. CONTRACTOR shall, to the fullest extent permitted by Laws and Regulations, indemnify and hold the County and all Towns harmless from and against all claims, damages, losses and expenses (including, but not limited to, fees of engineers, architects, attorneys and other professionals and court and arbitration costs) arising directly, indirectly or consequentially out of any action, legal or equitable, brought by any such other party against the County and all Towns to the extent based on a claim arising out of CONTRACTOR'S performance of the Work.

Safety and Protection

4.7 CONTRACTOR shall be responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work (examples: OSHA Regulations regarding Excavation safety: 29 CFR Part 1926 and Confined Space Procedures: 29 CFR 1910.146). CONTRACTOR shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury or loss to:

4.7.1 all employees on the Work and other persons and organizations who may be effected thereby:

4.7.2 all the Work and materials and equipment to be incorporated there-in, whether in storage on or off the site; and

4.7.3 other property at the site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities and Underground Facilities not designated for removal, relocation or replacement in the course of construction.

CONTRACTOR shall comply with all applicable Laws, regulations and Guidelines of any public body (examples: OSHA, DIGSAFE, MHD Work Zone Safety Guidelines) having jurisdiction for the safety of persons or property or to protect them from damage, injury or loss; and shall erect and maintain all

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

necessary safeguards for such safety and protection. CONTRACTOR shall notify owners of adjacent property and of Underground Facilities and utility owners when prosecution of the Work may affect them, and shall cooperate with them in the protection, removal, relocation and replacement of their property. All damage, injury or loss to any property referred to in paragraph 3.7.1 or 3.7.2 caused, directly or indirectly, in whole or in part, by CONTRACTOR, any sub-contractor, supplier or any other person or organization directly or indirectly employed by any of them to perform or furnish any of the Work or anyone for whose acts any of them may be liable, shall be remedied by CONTRACTOR (except damage or loss attributable to the fault of Drawings or Specifications or to the acts or omissions of the County or any Towns or anyone employed or contracted by any of them or anyone for whose acts either of them may be liable, and not attributable, directly or indirectly, in whole or in part, to the fault or negligence of CONTRACTOR). CONTRACTOR'S duties and responsibilities for the safety and protection of the Work shall continue until such time as all the Work is completed.

Indemnification

4.8 To the fullest extent permitted by Laws and Regulations CONTRACTOR shall indemnify and hold harmless the County, the Towns and their consultants, agents and employees from and against all claims, damages, losses and expenses, direct, indirect or consequential (including but no limited to fees and charges of engineers, architects, attorneys and other professionals and court and arbitration costs) arising out of or resulting from the performance of the Work.

Separate Contracts

4.9 The Towns have the right to let other contracts in connection with the Work and the CONTRACTOR shall properly cooperate with any such other contractors.

Invoicing

4.10 Each Town shall be solely responsible for payment of invoices due to Contractor for quantities ordered and received by that Town only or for the project awarded.

4.10.1 "As per MGL, Chapter 7, section 22, each political subdivision participating in this bid is solely responsible for any payment due vendor for its share of such purchase. Barnstable County, as lead purchasing agent shall not be liable for payment or for any claim based upon a breach of warranty or defects in the design, manufacture or installation of material, supplies or equipment purchase pursuant to this bid."

4.11 Award Price.

The County or Towns shall pay and the Contractor shall receive as full compensation for everything furnished and done by the Contractor under the Contract, including all work required but not included in the items hereinafter mentioned, and also for all loss or damage arising out of the nature of the work aforesaid, or from the action of the elements or from any difficulty incurred by or in consequence of the suspension or discontinuance of the work as herein specified, and for well and faithfully completing the work, and the whole thereof, as herein provided, as follows:

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

ARTICLE 5 – UNIT PRICE WORK

5.1 Initially, the Contract Price will be deemed to include for Unit Price Work an amount equal to the established unit price for each separately identified item of Unit Price Work times the estimated quantity of each item as indicated in the Agreement. The estimated quantities of items of Unit Price Work are not guaranteed and are solely for the purpose of comparison of Bids and determining an initial Contract Price. Determinations of the actual quantities and classification of Unit Price Work performed by CONTRACTOR will be made by each Town.

5.2 Each unit price will be deemed to include an amount considered by CONTRACTOR to be adequate to cover CONTRACTOR'S overhead and profit for each separately identified item.

5.3 When the accepted quantities of Work vary from the estimated quantities, the CONTRACTOR shall accept as payment in full, so far as contract items are concerned, payment at the original Contract unit prices for the accepted quantities of Work done. No allowance will be made for any increased expenses, loss of expected reimbursement or loss of anticipated profits suffered or claimed by the Contractor, resulting either directly or indirectly from such increased or decreased quantities.

5.4 The CONTRACTOR shall make monthly estimates of the materials complete in place for the amount of Work performed in accordance with the Contract. The estimates will be itemized for review and approval by each Town. Each estimate will show the total value of the Work done to date, the total money due the CONTRACTOR since the previous estimate and the money paid the CONTRACTOR to date. This estimate will be considered approximate only and shall be subject to correction. Five (5%) percent of all payments due the CONTRACTOR for Work done and materials furnished will be withheld until final completion of the Work. The acceptance by the CONTRACTOR of the final payment, including the retainage of five (5%) percent, shall operate as a release to the specific Town of all claims and all liabilities to the CONTRACTOR for all Work done or materials furnished in connection with the Contract. Final payment shall be as provided in G.L. Ch.30, Section 39G. The payment to the CONTRACTOR of said final payment does not, however, release them or their sureties from any obligation under this contract.

5.5 It shall be the responsibility of the CONTRACTOR to inform each Town when the sum of all orders for units of work is within 90% of the total Contract price for that Town. The CONTRACTOR'S total billing cannot exceed the total Contract price without prior written approval by each Town.

5.6 All monies not paid when due hereunder shall bear interest at the maximum rate allowed by law at the place of the Project.

ARTICLE 6 – WARRANTY AND GUARANTEE; TESTS AND INSPECTION; CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Category	Items	Item#	Unit	QuantityEstimated	Town	Vendor	Unit Price	Second Lowest Vendor	Unit Price
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	7600	Bourne	PJ Keating	109.00	Lawrence-Lynch Corp	138.00
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	1000	Brewster	Coastal Paving LLC	123.00	Lawrence-Lynch Corp	136.00
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	4500	Chatham	Lawrence-Lynch Corp	130.50		
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	3000	Dennis	Coastal Paving LLC	123.00	Lawrence-Lynch Corp	128.25
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	4000	Falmouth	Lawrence-Lynch Corp	124.25		
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	1000	Sandwich	PJ Keating	116.00	Lawrence-Lynch Corp	118.00
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	750	Wellfleet	Lawrence-Lynch Corp	139.00		
Road Construction	Hot Mix Asphalt Pavement (Machine Placed) (OVER 400 TONS PER DAY)	1	TON	400	Yarmouth	Lawrence-Lynch Corp	128.25		
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	300	Bourne	PJ Keating	242.00	Coastal Paving LLC	250.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	100	Brewster	Coastal Paving LLC	250.00	Lawrence-Lynch Corp	280.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	500	Dennis	Coastal Paving LLC	250.00	Lawrence-Lynch Corp	280.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	250	Falmouth	Coastal Paving LLC	200.00	Lawrence-Lynch Corp	280.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	100	Orleans	Lawrence-Lynch Corp	280.00		
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	150	Sandwich	PJ Keating	242.41	Lawrence-Lynch Corp	280.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	150	Wellfleet	Lawrence-Lynch Corp	280.00		
Road Construction	Hot Mix Asphalt Pavement (Handwork Greater than 40 Tons/Day)	2	TON	100	Yarmouth	Lawrence-Lynch Corp	280.00		
Road Construction	Hot Mix Asphalt Pavement (Handwork Less than 40 Tons/Day)	3	TON	300	Bourne	Coastal Paving LLC	300.00	Lawrence-Lynch Corp	320.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Less than 40 Tons/Day)	3	TON	100	Brewster	Coastal Paving LLC	280.00	Lawrence-Lynch Corp	359.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Less than 40 Tons/Day)	3	TON	500	Dennis	Coastal Paving LLC	300.00	Lawrence-Lynch Corp	320.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Less than 40 Tons/Day)	3	TON	200	Falmouth	Coastal Paving LLC	300.00	Lawrence-Lynch Corp	320.00
Road Construction	Hot Mix Asphalt Pavement (Handwork Less than 40 Tons/Day)	3	TON	100	Orleans	Lawrence-Lynch Corp	359.00		
Road Construction	Hot Mix Asphalt Pavement (Handwork Less than 40 Tons/Day)	3	TON	100	Yarmouth	Lawrence-Lynch Corp	320.00		
Road Construction	Hot Mix Asphalt Pavement (Shim)	4	TON	100	Brewster	Coastal Paving LLC	128.00	Lawrence-Lynch Corp	152.00
Road Construction	Hot Mix Asphalt Pavement (Shim)	4	TON	4000	Dennis	Lawrence-Lynch Corp	136.50		
Road Construction	Hot Mix Asphalt Pavement (Shim)	4	TON	50	Orleans	Lawrence-Lynch Corp	162.00		
Road Construction	Hot Mix Asphalt Pavement (Shim)	4	TON	300	Sandwich	Lawrence-Lynch Corp	145.00		
Road Construction	Pavement Reclamation (Including FG&C)	5	SY	3000	Bourne	murray paving & reclamation inc	3.75	All States Construction, Inc.	5.45
Road Construction	Pavement Reclamation (Including FG&C)	5	SY	500	Brewster	murray paving & reclamation inc	5.25	Lawrence-Lynch Corp	8.90
Road Construction	Pavement Reclamation (Including FG&C)	5	SY	6000	Dennis	murray paving & reclamation inc	3.10	All States Construction, Inc.	4.45
Road Construction	Pavement Reclamation (Including FG&C)	5	SY	4000	Falmouth	murray paving & reclamation inc	4.35	All States Construction, Inc.	4.65
Road Construction	Pavement Reclamation (Including FG&C and Calcium Chloride)	6	SY	500	Brewster	murray paving & reclamation inc	6.75	Lawrence-Lynch Corp	10.70
Road Construction	Pavement Reclamation (Including FG&C and Calcium Chloride)	6	SY	17000	Chatham	murray paving & reclamation inc	3.90	All States Construction, Inc.	4.75
Road Construction	Pavement Reclamation (Including FG&C and Calcium Chloride)	6	SY	13168	Orleans	murray paving & reclamation inc	4.10	All States Construction, Inc.	4.75
Road Construction	Pavement Reclamation (Including FG&C and Calcium Chloride)	6	SY	5000	Sandwich	murray paving & reclamation inc	4.60	All States Construction, Inc.	4.95
Road Construction	Bituminous Concrete Excavation by Cold Planer	7	SY	57000	Bourne	PJ Keating	2.68	Garrity Asphalt Reclaiming	3.00
Road Construction	Bituminous Concrete Excavation by Cold Planer	7	SY	3000	Brewster	Coastal Paving LLC	2.70	Lawrence-Lynch Corp	4.00
Road Construction	Bituminous Concrete Excavation by Cold Planer	7	SY	5000	Dennis	Coastal Paving LLC	2.70	Lawrence-Lynch Corp	3.65
Road Construction	Bituminous Concrete Excavation by Cold Planer	7	SY	10000	Falmouth	Coastal Paving LLC	2.70	Garrity Asphalt Reclaiming	3.50
Road Construction	Bituminous Concrete Excavation by Cold Planer	7	SY	19000	Orleans	Garrity Asphalt Reclaiming	3.00	Rafferty Fine Grading, Inc.	3.93
Road Construction	Bituminous Concrete Excavation by Cold Planer	7	SY	5000	Sandwich	Lawrence-Lynch Corp	3.65	PJ Keating	4.00
Road Construction	Bituminous Concrete Excavation by Cold Planer	7	SY	4000	Yarmouth	Lawrence-Lynch Corp	3.65	Garrity Asphalt Reclaiming	7.00
Road Construction	Cold Planed (Milled) Paving Joints	8	SY	300	Bourne	Lawrence-Lynch Corp	85.00		
Road Construction	Cold Planed (Milled) Paving Joints	8	SY	100	Brewster	Lawrence-Lynch Corp	60.00		
Road Construction	Cold Planed (Milled) Paving Joints	8	SY	600	Dennis	Garrity Asphalt Reclaiming	50.00		
Road Construction	Cold Planed (Milled) Paving Joints	8	SY	200	Falmouth	Lawrence-Lynch Corp	60.00		
Road Construction	Cold Planed (Milled) Paving Joints	8	SY	100	Orleans	Lawrence-Lynch Corp	60.00		
Road Construction	Cold Planed (Milled) Paving Joints	8	SY	250	Sandwich	Lawrence-Lynch Corp	60.00		
Road Construction	Microsurfacing (One Lift)	9	SY	5000	Sandwich	Sealcoating, Inc. d/b/a indus	7.08		
Road Construction	Microsurfacing (Two Lifts)	10	SY	30000	Falmouth	Sealcoating, Inc. d/b/a indus	6.65		
Road Construction	Asphalt-Rubber Surface Treatment (20% Rubber)	11	SY	60000	Dennis	All States Construction, Inc.	6.45		
Road Construction	Asphalt-Rubber Surface Treatment (20% Rubber)	11	SY	15000	Falmouth	All States Construction, Inc.	6.45		
Road Construction	Asphalt-Rubber Surface Treatment (20% Rubber)	11	SY	34800	Orleans	All States Construction, Inc.	6.45		
Road Construction	Asphalt-Rubber Surface Treatment (20% Rubber)	11	SY	20000	Sandwich	All States Construction, Inc.	6.45		
Road Construction	Asphalt-Rubber Surface Treatment (20% Rubber)	11	SY	15000	Yarmouth	All States Construction, Inc.	6.45		
Road Construction	Asphalt-Rubber Surface Treatment (10% Rubber)	12	SY	60000	Dennis	All States Construction, Inc.	5.45		
Road Construction	Asphalt-Rubber Surface Treatment (10% Rubber)	12	SY	80000	Sandwich	All States Construction, Inc.	5.45		
Road Construction	Asphalt-Rubber Surface Treatment (10% Rubber)	12	SY	100000	Yarmouth	All States Construction, Inc.	5.45		
Road Construction	Single Stone Seal Surface Treatment	13	SY	30000	Falmouth	All States Construction, Inc.	4.40		
Road Construction	Porous Pavement Full Depth Construction	15	SY	1500	Dennis	Lawrence-Lynch Corp	173.00		
Road Construction	Porous Pavement Full Depth Construction	15	SY	500	Yarmouth	Lawrence-Lynch Corp	173.00		
Road Construction	Porous Pavement Sidewalk Construction	16	SY	500	Dennis	Lawrence-Lynch Corp	250.00		
Road Construction	Partial Depth Pavement Patch	18	SY	700	Bourne	Coastal Paving LLC	53.00	Lawrence-Lynch Corp	62.00
Road Construction	Partial Depth Pavement Patch	18	SY	100	Brewster	Coastal Paving LLC	55.00	Lawrence-Lynch Corp	62.00
Road Construction	Partial Depth Pavement Patch	18	SY	600	Dennis	Coastal Paving LLC	53.00	Lawrence-Lynch Corp	62.00
Road Construction	Partial Depth Pavement Patch	18	SY	50	Orleans	Lawrence-Lynch Corp	62.00		
Road Construction	Partial Depth Pavement Patch	18	SY	500	Sandwich	Lawrence-Lynch Corp	62.00		
Road Construction	Partial Depth Pavement Patch	18	SY	1500	Yarmouth	Lawrence-Lynch Corp	62.00		
Road Construction	Miscellaneous Pavement Patch	19	TON	125	Bourne	Coastal Paving LLC	300.00	Lawrence-Lynch Corp	320.00
Road Construction	Miscellaneous Pavement Patch	19	TON	50	Brewster	Coastal Paving LLC	300.00	Lawrence-Lynch Corp	330.00
Road Construction	Miscellaneous Pavement Patch	19	TON	400	Dennis	Coastal Paving LLC	300.00	Lawrence-Lynch Corp	320.00
Road Construction	Miscellaneous Pavement Patch	19	TON	175	Falmouth	Coastal Paving LLC	300.00	Lawrence-Lynch Corp	320.00
Road Construction	Miscellaneous Pavement Patch	19	TON	100	Orleans	Lawrence-Lynch Corp	330.00		
Road Construction	Miscellaneous Pavement Patch	19	TON	100	Sandwich	Lawrence-Lynch Corp	320.00		
Road Construction	Miscellaneous Pavement Patch	19	TON	200	Yarmouth	Lawrence-Lynch Corp	320.00		
Road Construction	Cape Seal w/Single Stone Seal Surface Treatment	21	SY	5000	Sandwich	Sealcoating, Inc. d/b/a indus	14.44		
Road Construction	Cape Seal w/Double Stone Seal Surface Treatment	22	SY	30000	Falmouth	Sealcoating, Inc. d/b/a indus	13.33		
Road Construction	Street Sweeping	24	DAY	30	Barnstable	K5 Corporation	1,960.0000		
Road Construction	Street Sweeping	24	DAY	10	Brewster	K5 Corporation	1,960.0000		
Road Construction	Street Sweeping	24	DAY	10	Orleans	K5 Corporation	1,960.0000		
Road Construction	Street Sweeping	24	DAY	10	Sandwich	K5 Corporation	1,960.0000		
Road Construction	Street Sweeping	24	DAY	15	Yarmouth	K5 Corporation	1,960.0000		
Road Construction	HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (UNDER 400 TONS PER DAY)	1A	TON	200	Bourne	Coastal Paving LLC	130.00		
Road Construction	HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (UNDER 400 TONS PER DAY)	1A	TON	500	Brewster	Coastal Paving LLC	130.00		
Road Construction	HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (UNDER 400 TONS PER DAY)	1A	TON	600	Dennis	Coastal Paving LLC	130.00		
Road Construction	HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (UNDER 400 TONS PER DAY)	1A	TON	1400	Orleans	Lawrence-Lynch Corp	136.00		
Road Construction	HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (UNDER 400 TONS PER DAY)	1A	TON	400	Sandwich	Lawrence-Lynch Corp	145.00		
Road Construction	HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (UNDER 400 TONS PER DAY)	1A	TON	400	Yarmouth	Lawrence-Lynch Corp	145.00		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	1100000	Barnstable	K5 Corporation	0.0850		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	45000	Barnstable	K5 Corporation	0.7000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Arrows & Miscellaneous Markings	102	SF	11250	Barnstable	K5 Corporation	2.2500		
Miscellaneous Public Works	Thermoplastic Paint for 4" Reflectorized Lines	103	LF	28000	Barnstable	K5 Corporation	0.5500		
Miscellaneous Public Works	Thermoplastic Paint for Stop Bars & Crosswalks	104	LF	1000	Barnstable	K5 Corporation	3.7500		
Miscellaneous Public Works	Thermoplastic Paint for Arrows & Miscellaneous Markings	105	SF	1000	Barnstable	K5 Corporation	6.5000		
Miscellaneous Public Works	Epoxy Paint for 4" Reflectorized Lines	106	LF	4000	Barnstable	K5 Corporation	0.4300		
Miscellaneous Public Works	Pavement Marking Removal	107	SF	10000	Barnstable	K5 Corporation	1.0000		
Miscellaneous Public Works	CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4” REFLECTORIZED LINE	100A	LF	1100000	Barnstable	K5 Corporation	0.1700		
Miscellaneous Public Works	THERMOPLASTIC PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	103A	LF	28000	Barnstable	K5 Corporation	1.0000		
Miscellaneous Public Works	EPOXY PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	106A	LF	4000	Barnstable	K5 Corporation	0.8600		
Miscellaneous Public Works	Pavement Marking Removal for Items 101, 102, 104 & 105 Detail Work	107A	SF	10000	Barnstable	K5 Corporation	1.0000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	125000	Bourne	K5 Corporation	0.0850		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	5000	Bourne	K5 Corporation	0.7000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Arrows & Miscellaneous Markings	102	SF	1000	Bourne	K5 Corporation	2.2500		
Miscellaneous Public Works	Thermoplastic Paint for 4" Reflectorized Lines	103	LF	40000	Bourne	K5 Corporation	0.5500		
Miscellaneous Public Works	Thermoplastic Paint for Stop Bars & Crosswalks	104	LF	1000	Bourne	K5 Corporation	3.7500		
Miscellaneous Public Works	Thermoplastic Paint for Arrows & Miscellaneous Markings	105	SF	500	Bourne	K5 Corporation	6.5000		
Miscellaneous Public Works	CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4” REFLECTORIZED LINE	100A	LF	100000	Bourne	K5 Corporation	0.1700		
Miscellaneous Public Works	THERMOPLASTIC PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	103A	LF	20000	Bourne	K5 Corporation	1.0000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	600000	Brewster	K5 Corporation	0.0850		

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	1500	Brewster	K5 Corporation	0.7000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Arrows & Miscellaneous Markings	102	SF	2500	Brewster	K5 Corporation	2.2500		
Miscellaneous Public Works	CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4” REFLECTORIZED LINE	100A	LF	300000	Brewster	K5 Corporation	0.1700		
Miscellaneous Public Works	Thermoplastic Paint for Stop Bars & Crosswalks	104	LF	200	Chatham	K5 Corporation	3.7500		
Miscellaneous Public Works	THERMOPLASTIC PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	103A	LF	10000	Chatham	K5 Corporation	1.0000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	250000	Dennis	K5 Corporation	0.0850		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	500	Dennis	K5 Corporation	0.7000		
Miscellaneous Public Works	Thermoplastic Paint for 4" Reflectorized Lines	103	LF	10000	Dennis	K5 Corporation	0.5500		
Miscellaneous Public Works	Thermoplastic Paint for Stop Bars & Crosswalks	104	LF	2000	Dennis	K5 Corporation	3.7500		
Miscellaneous Public Works	Thermoplastic Paint for Arrows & Miscellaneous Markings	105	SF	300	Dennis	K5 Corporation	6.5000		
Miscellaneous Public Works	Epoxy Paint for 4" Reflectorized Lines	106	LF	10000	Dennis	K5 Corporation	0.4300		
Miscellaneous Public Works	Pavement Marking Removal	107	SF	5000	Dennis	K5 Corporation	1.0000		
Miscellaneous Public Works	CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4” REFLECTORIZED LINE	100A	LF	125000	Dennis	K5 Corporation	0.1700		
Miscellaneous Public Works	THERMOPLASTIC PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	103A	LF	40000	Dennis	K5 Corporation	1.0000		
Miscellaneous Public Works	EPOXY PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	106A	LF	150000	Dennis	K5 Corporation	0.8600		
Miscellaneous Public Works	Pavement Marking Removal for Items 101, 102, 104 & 105 Detail Work	107A	SF	500	Dennis	K5 Corporation	1.0000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	49090	Orleans	K5 Corporation	0.0850		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	1000	Orleans	K5 Corporation	0.7000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Arrows & Miscellaneous Markings	102	SF	1500	Orleans	K5 Corporation	2.2500		
Miscellaneous Public Works	Thermoplastic Paint for 4" Reflectorized Lines	103	LF	500	Orleans	K5 Corporation	0.5500		
Miscellaneous Public Works	Thermoplastic Paint for Stop Bars & Crosswalks	104	LF	200	Orleans	K5 Corporation	3.7500		
Miscellaneous Public Works	Thermoplastic Paint for Arrows & Miscellaneous Markings	105	SF	200	Orleans	K5 Corporation	6.5000		
Miscellaneous Public Works	Pavement Marking Removal	107	SF	100	Orleans	K5 Corporation	1.0000		
Miscellaneous Public Works	CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4” REFLECTORIZED LINE	100A	LF	116822	Orleans	K5 Corporation	0.1700		
Miscellaneous Public Works	THERMOPLASTIC PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	103A	LF	500	Orleans	K5 Corporation	1.0000		
Miscellaneous Public Works	Pavement Marking Removal for Items 101, 102, 104 & 105 Detail Work	107A	SF	100	Orleans	K5 Corporation	1.0000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	75000	Sandwich	K5 Corporation	0.0850		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	1500	Sandwich	K5 Corporation	0.7000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Arrows & Miscellaneous Markings	102	SF	200	Sandwich	K5 Corporation	2.2500		
Miscellaneous Public Works	Thermoplastic Paint for 4" Reflectorized Lines	103	LF	5000	Sandwich	K5 Corporation	0.5500		
Miscellaneous Public Works	Thermoplastic Paint for Stop Bars & Crosswalks	104	LF	500	Sandwich	K5 Corporation	3.7500		
Miscellaneous Public Works	Thermoplastic Paint for Arrows & Miscellaneous Markings	105	SF	100	Sandwich	K5 Corporation	6.5000		
Miscellaneous Public Works	Epoxy Paint for 4" Reflectorized Lines	106	LF	2500	Sandwich	K5 Corporation	0.4300		
Miscellaneous Public Works	Pavement Marking Removal	107	SF	1000	Sandwich	K5 Corporation	1.0000		
Miscellaneous Public Works	CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4” REFLECTORIZED LINE	100A	LF	75000	Sandwich	K5 Corporation	0.1700		
Miscellaneous Public Works	THERMOPLASTIC PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	103A	LF	5000	Sandwich	K5 Corporation	1.0000		
Miscellaneous Public Works	EPOXY PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES	106A	LF	2500	Sandwich	K5 Corporation	0.8600		
Miscellaneous Public Works	Pavement Marking Removal for Items 101, 102, 104 & 105 Detail Work	107A	SF	500	Sandwich	K5 Corporation	1.0000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	100000	Wellfleet	K5 Corporation	0.0850		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	2000	Wellfleet	K5 Corporation	0.7000		
Miscellaneous Public Works	Thermoplastic Paint for 4" Reflectorized Lines	103	LF	5000	Wellfleet	K5 Corporation	0.5500		
Miscellaneous Public Works	Thermoplastic Paint for Stop Bars & Crosswalks	104	LF	1000	Wellfleet	K5 Corporation	3.7500		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for 4" Reflectorized Lines	100	LF	450000	Yarmouth	K5 Corporation	0.0850		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Stop Bars & Crosswalks	101	LF	4000	Yarmouth	K5 Corporation	0.7000		
Miscellaneous Public Works	Chlorinated Rubber Paint and Beads for Arrows & Miscellaneous Markings	102	SF	2500	Yarmouth	K5 Corporation	2.2500		
Miscellaneous Public Works	Pavement Marking Removal	107	SF	500	Yarmouth	K5 Corporation	1.0000		
Miscellaneous Public Works	CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4” REFLECTORIZED LINE	100A	LF	310000	Yarmouth	K5 Corporation	0.1700		
Miscellaneous Public Works	Drainage Pipe Cleaning	108	DAY	10	Barnstable	R.J. GABRIEL CONST. CO. INC.	4,500.00		
Miscellaneous Public Works	Drainage Pipe Cleaning	108	DAY	5	Dennis	R.J. GABRIEL CONST. CO. INC.	4,500.00		
Miscellaneous Public Works	Drainage Pipe Cleaning	108	DAY	5	Falmouth	R.J. GABRIEL CONST. CO. INC.	4,500.00		
Miscellaneous Public Works	Drainage Pipe Cleaning	108	DAY	5	Sandwich	R.J. GABRIEL CONST. CO. INC.	4,500.00		
Miscellaneous Public Works	Drainage Pipe Cleaning	108	DAY	5	Orleans	R.J. GABRIEL CONST. CO. INC.	4,500.00		
Miscellaneous Public Works	Drainage Pipe Cleaning	108	DAY	5	Wellfleet	R.J. GABRIEL CONST. CO. INC.	4,500.00		
Miscellaneous Public Works	Drainage Pipe Cleaning	108	DAY	5	Brewster	R.J. GABRIEL CONST. CO. INC.	4,500.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Clamshell (w/Disposal)	109	EA	50	Orleans	R.J. GABRIEL CONST. CO. INC.	175.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Clamshell (w/Disposal)	109	EA	1000	Brewster	R.J. GABRIEL CONST. CO. INC.	52.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Clamshell (w/Disposal)	109	EA	2500	Barnstable	R.J. GABRIEL CONST. CO. INC.	64.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Clamshell (w/Disposal)	109	EA	100	Falmouth	R.J. GABRIEL CONST. CO. INC.	120.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Clamshell (w/Disposal)	109	EA	2000	Dennis	R.J. GABRIEL CONST. CO. INC.	52.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Clamshell (w/o Disposal)	110	EA	50	Orleans	R.J. GABRIEL CONST. CO. INC.	60.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Clamshell (w/o Disposal)	110	EA	1500	Sandwich	R.J. GABRIEL CONST. CO. INC.	50.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/Disposal)	111	EA	30	Wellfleet	Robert B Our Co Inc	375.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/Disposal)	111	EA	500	Barnstable	Robert B Our Co Inc	350.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/Disposal)	111	EA	100	Dennis	Robert B Our Co Inc	350.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/Disposal)	111	EA	100	Falmouth	Robert B Our Co Inc	350.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/Disposal)	111	EA	50	Orleans	Robert B Our Co Inc	350.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/Disposal)	111	EA	25	Brewster	Robert B Our Co Inc	350.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/o Disposal)	112	EA	100	Sandwich	Robert B Our Co Inc	300.00		
Miscellaneous Public Works	Drainage Structure Cleaning By Vaccuum Truck (w/o Disposal)	112	EA	50	Orleans	Robert B Our Co Inc	275.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	100	Barnstable	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	12	Brewster	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	25	Dennis	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	50	Falmouth	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	10	Orleans	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	45	Sandwich	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	15	Yarmouth	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Adjusted	113	EA	65	Bourne	Lawrence-Lynch Corp	994.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	25	Barnstable	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	12	Brewster	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	20	Dennis	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	25	Falmouth	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	10	Orleans	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	20	Sandwich	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	15	Yarmouth	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Drainage Structure Rebuilt	114	EA	35	Bourne	Lawrence-Lynch Corp	1,300.00		
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail (Single Faced/Wood Posts)	115	LF	500	Dennis	Bartlett Consolidated DE LLC	55.00	Steelco Chain Link Fence Erec	58.90
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail (Single Faced/Wood Posts)	115	LF	100	Sandwich	Bartlett Consolidated DE LLC	55.00	Steelco Chain Link Fence Erec	58.90
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail (Single Faced/Wood Posts)	115	LF	300	Barnstable	Bartlett Consolidated DE LLC	55.00	Steelco Chain Link Fence Erec	58.90
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail (Single Faced/Wood Posts)	115	LF	2300	Yarmouth	Steelco Chain Link Fence Erecting C	51.90	Bartlett Consolidated DE LLC	55.00
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail (Single Faced/Wood Posts) (Including Removal and Stacking of Existing Gua	116	LF	4000	Barnstable	Steelco Chain Link Fence Erecting C	51.90	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail (Single Faced/Wood Posts) (Including Removal and Stacking of Existing Gua	116	LF	500	Dennis	Steelco Chain Link Fence Erecting C	58.90	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail (Single Faced/Wood Posts) (Including Removal and Stacking of Existing Gua	116	LF	100	Sandwich	Steelco Chain Link Fence Erecting C	58.90	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail-Terminal End WITH WOOD POSTS	117	EA	100	Barnstable	Steelco Chain Link Fence Erecting C	424.00	Bartlett Consolidated DE LLC	800.00
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail-Terminal End WITH WOOD POSTS	117	EA	10	Dennis	Steelco Chain Link Fence Erecting C	424.00	Bartlett Consolidated DE LLC	800.00
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail-Terminal End WITH WOOD POSTS	117	EA	5	Sandwich	Steelco Chain Link Fence Erecting C	424.00	Bartlett Consolidated DE LLC	800.00
Miscellaneous Public Works	Steel Beam (Weathering) Highway Guardrail-Terminal End WITH WOOD POSTS	117	EA	10	Yarmouth	Steelco Chain Link Fence Erecting C	424.00	Bartlett Consolidated DE LLC	800.00
Miscellaneous Public Works	Steel Beam Highway Guardrail (Single Faced/Wood Posts)	118	LF	500	Barnstable	Steelco Chain Link Fence Erecting C	46.90	Bartlett Consolidated DE LLC	50.00
Miscellaneous Public Works	Steel Beam Highway Guardrail (Single Faced/Wood Posts)	118	LF	500	Falmouth	Steelco Chain Link Fence Erecting C	46.90	Bartlett Consolidated DE LLC	50.00
Miscellaneous Public Works	Steel Beam Highway Guardrail (Single Faced/Wood Posts)	118	LF	500	Orleans	Steelco Chain Link Fence Erecting C	46.90	Bartlett Consolidated DE LLC	50.00
Miscellaneous Public Works	Steel Beam Highway Guardrail (Single Faced/Wood Posts)	118	LF	100	Sandwich	Steelco Chain Link Fence Erecting C	46.90	Bartlett Consolidated DE LLC	50.00
Miscellaneous Public Works	Steel-Backed Timber Guardrail	119	LF	300	Orleans	Bartlett Consolidated DE LLC	140.00	Steelco Chain Link Fence Erec	152.00
Miscellaneous Public Works	Steel-Backed Timber Guardrail	119	LF	300	Barnstable	Bartlett Consolidated DE LLC	140.00	Steelco Chain Link Fence Erec	152.00
Miscellaneous Public Works	Steel-Backed Timber Guardrail	119	LF	250	Brewster	Bartlett Consolidated DE LLC	140.00	Steelco Chain Link Fence Erec	152.00
Miscellaneous Public Works	Steel-Backed Timber Guardrail	119	LF	200	Dennis	Bartlett Consolidated DE LLC	140.00	Steelco Chain Link Fence Erec	152.00
Miscellaneous Public Works	Steel-Backed Timber Guardrail	119	LF	100	Sandwich	Bartlett Consolidated DE LLC	140.00	Steelco Chain Link Fence Erec	152.00
Miscellaneous Public Works	Wooden Guardrail	120	LF	500	Barnstable	Steelco Chain Link Fence Erecting C	52.00	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Wooden Guardrail	120	LF	250	Brewster	Steelco Chain Link Fence Erecting C	62.00	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Wooden Guardrail	120	LF	200	Dennis	Steelco Chain Link Fence Erecting C	62.00	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Wooden Guardrail	120	LF	500	Falmouth	Steelco Chain Link Fence Erecting C	62.00	Bartlett Consolidated DE LLC	65.00

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Miscellaneous Public Works	Wooden Guardrail	120	LF	500	Orleans	Steelco Chain Link Fence Erecting C	62.00	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Wooden Guardrail	120	LF	100	Sandwich	Steelco Chain Link Fence Erecting C	62.00	Bartlett Consolidated DE LLC	65.00
Miscellaneous Public Works	Granite Curb Type VB-Straight	121	LF	200	Orleans	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Granite Curb Type VB-Straight	121	LF	300	Barnstable	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Granite Curb Type VB-Straight	121	LF	500	Falmouth	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Granite Curb Type VB-Straight	121	LF	300	Sandwich	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Granite Curb Type VB-Straight	121	LF	1000	Dennis	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Granite Curb Type VA4-Straight	122	LF	200	Orleans	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Granite Curb Type VA4-Straight	122	LF	500	Sandwich	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Granite Curb Type VA4-Straight	122	LF	300	Barnstable	Lawrence-Lynch Corp	90.00		
Miscellaneous Public Works	Pave Shield Pavement Sealing (1500 Square Yards or Greater)	123	SY	5000	Barnstable	Sealcoating, Inc. d/b/a indus	3.47		
Miscellaneous Public Works	Pave Shield Pavement Sealing (1500 Square Yards or Greater)	123	SY	6000	Dennis	Sealcoating, Inc. d/b/a indus	3.27		
Miscellaneous Public Works	Pave Shield Pavement Sealing (1500 Square Yards or Greater)	123	SY	5000	Sandwich	Sealcoating, Inc. d/b/a indus	3.42		
Miscellaneous Public Works	Pave Shield Pavement Sealing (1500 Square Yards or Greater)	123	SY	1500	Yarmouth	Sealcoating, Inc. d/b/a indus	6.53		
Miscellaneous Public Works	Pave Shield Pavement Sealing (Under 1500 Square Yards)	124	SY	1000	Orleans	Sealcoating, Inc. d/b/a indus	8.44		
Miscellaneous Public Works	Pave Shield Pavement Sealing (Under 1500 Square Yards)	124	SY	1000	Dennis	Sealcoating, Inc. d/b/a indus	8.44		
Miscellaneous Public Works	Pave Shield Pavement Sealing (Under 1500 Square Yards)	124	SY	1500	Barnstable	Sealcoating, Inc. d/b/a indus	6.37		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	15000	Barnstable	Sealcoating, Inc. d/b/a indus	14.28		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	200	Falmouth	Sealcoating, Inc. d/b/a indus	35.46		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	1000	Brewster	Sealcoating, Inc. d/b/a indus	18.15		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	5000	Yarmouth	Sealcoating, Inc. d/b/a indus	14.30		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	200	Orleans	Sealcoating, Inc. d/b/a indus	35.46		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	3000	Wellfleet	Sealcoating, Inc. d/b/a indus	14.47		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	3200	Bourne	Sealcoating, Inc. d/b/a indus	14.47		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	10000	Dennis	Sealcoating, Inc. d/b/a indus	14.47		
Miscellaneous Public Works	Modified Asphalt-Fiber Crackfiller	125	GAL	7000	Sandwich	Sealcoating, Inc. d/b/a indus	14.13		
Miscellaneous Public Works	Rubber Crackfiller	126	GAL	200	Orleans	Sealcoating, Inc. d/b/a indus	46.38		
Miscellaneous Public Works	Rubber Crackfiller	126	GAL	15000	Barnstable	Sealcoating, Inc. d/b/a indus	24.56		
Miscellaneous Public Works	Rubber Crackfiller	126	GAL	1000	Sandwich	Sealcoating, Inc. d/b/a indus	24.05		
Miscellaneous Public Works	Rubber Crackfiller	126	GAL	500	Brewster	Sealcoating, Inc. d/b/a indus	24.56		
Miscellaneous Public Works	Rubber Crackfiller	126	GAL	1000	Dennis	Sealcoating, Inc. d/b/a indus	24.56		
Miscellaneous Public Works	STEEL BEAM (WEATHERING) HIGHWAY GUARDRAIL (SINGLE FACED/STEEL POSTS)	115A	LF	1000	Barnstable	Bartlett Consolidated DE LLC	50.00	Steelco Chain Link Fence Erec	64.90
Miscellaneous Public Works	STEEL BEAM (WEATHERING) HIGHWAY GUARDRAIL (SINGLE FACED/STEEL POSTS)	115A	LF	50	Yarmouth	Bartlett Consolidated DE LLC	50.00	Steelco Chain Link Fence Erec	64.90
Miscellaneous Public Works	STEEL BEAM (WEATHERING) HIGHWAY GUARDRAIL (SINGLE FACED/STEEL POSTS)	115A	LF	100	Sandwich	Bartlett Consolidated DE LLC	50.00	Steelco Chain Link Fence Erec	64.90
Miscellaneous Public Works	STEEL BEAM (WEATHERING) HIGHWAY GUARDRAIL (SINGLE FACED/STEEL POSTS)	115A	LF	1000	Wellfleet	Bartlett Consolidated DE LLC	50.00	Steelco Chain Link Fence Erec	64.90
Miscellaneous Public Works	STEEL BEAM (WEATHERING) HIGHWAY GUADRAIL-TERMINAL END WITH STEEL POSTS	117A	EA	100	Barnstable	Steelco Chain Link Fence Erecting C	540.00	Bartlett Consolidated DE LLC	750.00
Miscellaneous Public Works	STEEL BEAM (WEATHERING) HIGHWAY GUADRAIL-TERMINAL END WITH STEEL POSTS	117A	EA	5	Sandwich	Steelco Chain Link Fence Erecting C	540.00	Bartlett Consolidated DE LLC	750.00
Miscellaneous Public Works	STEEL BEAM (WEATHERING) HIGHWAY GUADRAIL-TERMINAL END WITH STEEL POSTS	117A	EA	10	Wellfleet	Steelco Chain Link Fence Erecting C	540.00	Bartlett Consolidated DE LLC	750.00
Miscellaneous Public Works	MASH COMPLIANT SKT TREATMENT WITH TRANSITION COATING	117B	EA	100	Barnstable	Steelco Chain Link Fence Erecting C	3,500.00	Bartlett Consolidated DE LLC	11,220.00
Miscellaneous Public Works	MASH COMPLIANT SKT TREATMENT WITH TRANSITION COATING	117B	EA	10	Dennis	Steelco Chain Link Fence Erecting C	3,500.00	Bartlett Consolidated DE LLC	11,220.00
Miscellaneous Public Works	MASH COMPLIANT SKT TREATMENT WITH TRANSITION COATING	117B	EA	15	Yarmouth	Steelco Chain Link Fence Erecting C	3,500.00	Bartlett Consolidated DE LLC	11,220.00
Roadway Materials	Hot Mix Asphalt Pavement (Loaded on Town Trucks)	200	TON	200	Falmouth	Lawrence-Lynch Corp	90.00		
Roadway Materials	Hot Mix Asphalt Pavement (Loaded on Town Trucks)	200	TON	1000	Barnstable	Lawrence-Lynch Corp	90.00		
Roadway Materials	Hot Mix Asphalt Pavement (Loaded on Town Trucks)	200	TON	500	Dennis	Amrize	98.00		
Roadway Materials	Hot Mix Asphalt Pavement (Loaded on Town Trucks)	200	TON	250	Orleans	Lawrence-Lynch Corp	90.00		
Roadway Materials	Hot Mix Asphalt Pavement (Loaded on Town Trucks)	200	TON	450	Sandwich	PJ Keating	82.00		
Roadway Materials	Hot Mix Asphalt Pavement (Loaded on Town Trucks)	200	TON	250	Wellfleet	Amrize	98.00		
Roadway Materials	Hot Mix Asphalt Pavement (Loaded on Town Trucks)	200	TON	500	Yarmouth	Amrize	98.00		
Roadway Materials	Sand Borrow	201	TON	200	Sandwich	Cape Cod Aggregates Corp.	27.75		
Roadway Materials	Sand Borrow	201	TON	300	Falmouth	Cape Cod Aggregates Corp.	25.85		
Roadway Materials	Sand Borrow	201	TON	500	Barnstable	Cape Cod Aggregates Corp.	28.75		
Roadway Materials	Sand Borrow	201	TON	200	Dennis	Cape Cod Aggregates Corp.	30.65		
Roadway Materials	Sand Borrow	201	TON	100	Brewster	Cape Cod Aggregates Corp.	32.55		
Roadway Materials	Sand Borrow	201	TON	100	Orleans	Cape Cod Aggregates Corp.	32.55		
Roadway Materials	Sand Borrow	201	TON	500	Wellfleet	Cape Cod Aggregates Corp.	36.40		
Roadway Materials	Loam Borrow	202	TON	100	Brewster	Robert B Our Co Inc	22.00		
Roadway Materials	Loam Borrow	202	TON	500	Dennis	Robert B Our Co Inc	22.00		
Roadway Materials	Loam Borrow	202	TON	500	Barnstable	Robert B Our Co Inc	24.00		
Roadway Materials	Loam Borrow	202	TON	100	Orleans	Robert B Our Co Inc	24.00		
Roadway Materials	Loam Borrow	202	TON	200	Sandwich	Robert B Our Co Inc	26.00		
Roadway Materials	Loam Borrow	202	TON	200	Falmouth	Robert B Our Co Inc	26.00		
Roadway Materials	Loam Borrow	202	TON	100	Wellfleet	Robert B Our Co Inc	24.00		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	500	Bourne	Cape Cod Aggregates Corp.	30.65		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	200	Sandwich	Cape Cod Aggregates Corp.	30.65		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	1500	Falmouth	Cape Cod Aggregates Corp.	30.65		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	100	Barnstable	Cape Cod Aggregates Corp.	32.55		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	500	Yarmouth	Cape Cod Aggregates Corp.	34.45		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	500	Dennis	Cape Cod Aggregates Corp.	34.45		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	100	Brewster	Cape Cod Aggregates Corp.	36.40		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	150	Orleans	Cape Cod Aggregates Corp.	36.40		
Roadway Materials	1-1/2" Crushed Stone (Double Washed)	203	TON	100	Wellfleet	Cape Cod Aggregates Corp.	38.30		
Roadway Materials	3/4" Crushed Stone (Double Washed)	204	TON	200	Sandwich	Cape Cod Aggregates Corp.	30.65		
Roadway Materials	3/4" Crushed Stone (Double Washed)	204	TON	500	Bourne	Cape Cod Aggregates Corp.	30.65		
Roadway Materials	3/4" Crushed Stone (Double Washed)	204	TON	50	Barnstable	Cape Cod Aggregates Corp.	32.55		
Roadway Materials	3/4" Crushed Stone (Double Washed)	204	TON	500	Dennis	Cape Cod Aggregates Corp.	34.45		
Roadway Materials	3/4" Crushed Stone (Double Washed)	204	TON	100	Brewster	Cape Cod Aggregates Corp.	36.40		
Roadway Materials	3/4" Crushed Stone (Double Washed)	204	TON	150	Orleans	Cape Cod Aggregates Corp.	36.40		
Roadway Materials	3/4" Crushed Stone (Double Washed)	204	TON	100	Wellfleet	Cape Cod Aggregates Corp.	38.30		
Roadway Materials	3/8" Peastone (Double Washed)	205	TON	100	Yarmouth	Cape Cod Aggregates Corp.	34.45		
Roadway Materials	3/8" Peastone (Double Washed)	205	TON	200	Sandwich	Cape Cod Aggregates Corp.	30.65		
Roadway Materials	3/8" Peastone (Double Washed)	205	TON	50	Barnstable	Cape Cod Aggregates Corp.	32.55		
Roadway Materials	3/8" Peastone (Double Washed)	205	TON	200	Dennis	Cape Cod Aggregates Corp.	34.45		
Roadway Materials	3/8" Peastone (Double Washed)	205	TON	100	Brewster	Cape Cod Aggregates Corp.	36.40		
Roadway Materials	3/8" Peastone (Double Washed)	205	TON	200	Orleans	Cape Cod Aggregates Corp.	36.40		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	200	Sandwich	Cape Cod Aggregates Corp.	28.65		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	2000	Falmouth	Cape Cod Aggregates Corp.	28.65		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	500	Barnstable	Cape Cod Aggregates Corp.	30.55		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	1500	Yarmouth	Cape Cod Aggregates Corp.	36.30		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	250	Orleans	Cape Cod Aggregates Corp.	34.40		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	1500	Dennis	Cape Cod Aggregates Corp.	32.45		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	500	Brewster	Cape Cod Aggregates Corp.	34.40		
Roadway Materials	3/4" Dense Graded Crushed Stone	206	TON	100	Wellfleet	Cape Cod Aggregates Corp.	36.30		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	10	Chatham	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	10	Falmouth	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	8	Orleans	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	10	Yarmouth	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	10	Barnstable	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	10	Brewster	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	20	Dennis	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	8	Sandwich	Acme-Shorey Precast	489.00		
Roadway Materials	4'x4' Precast Leaching Galley	208	EA	10	Wellfleet	Acme-Shorey Precast	489.00		
Roadway Materials	1000 Gallon Precast Catch Basin	209	EA	10	Orleans	Acme-Shorey Precast	1,344.00		
Roadway Materials	1000 Gallon Precast Catch Basin	209	EA	10	Barnstable	Acme-Shorey Precast	1,344.00		
Roadway Materials	1000 Gallon Precast Catch Basin	209	EA	10	Brewster	Acme-Shorey Precast	1,344.00		
Roadway Materials	1000 Gallon Precast Catch Basin	209	EA	5	Dennis	Acme-Shorey Precast	1,344.00		
Roadway Materials	1000 Gallon Precast Catch Basin	209	EA	25	Falmouth	Acme-Shorey Precast	1,344.00		
Roadway Materials	1000 Gallon Precast Catch Basin	209	EA	5	Sandwich	Acme-Shorey Precast	1,344.00		
Roadway Materials	1000 Gallon Precast Catch Basin	209	EA	5	Wellfleet	Acme-Shorey Precast	1,344.00		
Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	10	Orleans	Acme-Shorey Precast	1,027.00		

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	10	Barnstable	Acme-Shorey Precast	1,027.00		
Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	10	Brewster	Acme-Shorey Precast	1,027.00		
Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	10	Dennis	Acme-Shorey Precast	1,027.00		
Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	50	Falmouth	Acme-Shorey Precast	1,027.00		
Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	5	Sandwich	Acme-Shorey Precast	1,027.00		
Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	5	Wellfleet	Acme-Shorey Precast	1,027.00		
Roadway Materials	1000 Gallon Precast Leach Pit	210	EA	5	Yarmouth	Acme-Shorey Precast	1,027.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	10	Orleans	Acme-Shorey Precast	819.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	10	Barnstable	Acme-Shorey Precast	819.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	6	Brewster	Acme-Shorey Precast	819.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	10	Dennis	Acme-Shorey Precast	819.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	20	Falmouth	Acme-Shorey Precast	819.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	5	Sandwich	Acme-Shorey Precast	819.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	4	Wellfleet	Acme-Shorey Precast	819.00		
Roadway Materials	4' Diameter Precast Catch Basin w/Offset Top	211	EA	5	Yarmouth	Acme-Shorey Precast	819.00		
Roadway Materials	Precast Gutter Inlet	212	EA	5	Orleans	Acme-Shorey Precast	341.00		
Roadway Materials	Precast Gutter Inlet	212	EA	10	Barnstable	Acme-Shorey Precast	341.00		
Roadway Materials	Precast Gutter Inlet	212	EA	6	Brewster	Acme-Shorey Precast	341.00		
Roadway Materials	Precast Gutter Inlet	212	EA	10	Dennis	Acme-Shorey Precast	341.00		
Roadway Materials	Precast Gutter Inlet	212	EA	25	Falmouth	Acme-Shorey Precast	341.00		
Roadway Materials	Precast Gutter Inlet	212	EA	5	Sandwich	Acme-Shorey Precast	341.00		
Roadway Materials	Precast Gutter Inlet	212	EA	6	Wellfleet	Acme-Shorey Precast	341.00		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	10	Barnstable	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	5	Orleans	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	5	Yarmouth	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	12	Brewster	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	5	Dennis	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	50	Falmouth	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	20	Sandwich	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Cover w/1 inch vent hole	213	EA	12	Wellfleet	Cape Cod Winwater Works	672.95		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	5	Orleans	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	5	Yarmouth	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	25	Barnstable	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	12	Brewster	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	10	Dennis	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	12	Brewster	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	10	Dennis	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	50	Falmouth	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	20	Sandwich	Cape Cod Winwater Works	614.00		
Roadway Materials	8" Frame and Grate Municipal Standard	214	EA	12	Wellfleet	Cape Cod Winwater Works	614.00		
Roadway Materials	12" Hood	215	EA	5	Orleans	Cape Cod Winwater Works	308.41		
Roadway Materials	12" Hood	215	EA	12	Brewster	Cape Cod Winwater Works	308.41		
Roadway Materials	12" Hood	215	EA	10	Dennis	Cape Cod Winwater Works	308.41		
Roadway Materials	12" Hood	215	EA	10	Sandwich	Cape Cod Winwater Works	308.41		
Roadway Materials	12" Hood	215	EA	12	Wellfleet	Cape Cod Winwater Works	308.41		
Roadway Materials	12" Corrugated Plastic (Polyethylene) Pipe	217	LF	100	Barnstable	Cape Cod Winwater Works	12.26		
Roadway Materials	12" Corrugated Plastic (Polyethylene) Pipe	217	LF	200	Brewster	Cape Cod Winwater Works	12.26		
Roadway Materials	12" Corrugated Plastic (Polyethylene) Pipe	217	LF	500	Dennis	Cape Cod Winwater Works	12.26		
Roadway Materials	12" Corrugated Plastic (Polyethylene) Pipe	217	LF	250	Falmouth	Cape Cod Winwater Works	12.26		
Roadway Materials	12" Corrugated Plastic (Polyethylene) Pipe	217	LF	100	Orleans	Cape Cod Winwater Works	12.26		
Roadway Materials	12" Corrugated Plastic (Polyethylene) Pipe	217	LF	200	Sandwich	Cape Cod Winwater Works	12.26		
Roadway Materials	12" Corrugated Plastic (Polyethylene) Pipe	217	LF	500	Wellfleet	Cape Cod Winwater Works	12.26		

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Warranty and Guarantee

6.1 CONTRACTOR warrants and guarantees to the County and the Towns that all Work will be in accordance with the Contract Documents and will not be DEFECTIVE. Prompt notice of all defects shall be given to CONTRACTOR. All DEFECTIVE Work, whether or not in place, may be rejected, corrected or accepted as provided in this Article.

Access to Work

6.2 The County's or Town's representatives, testing agencies and governmental agencies with jurisdictional interests will have access to the Work at reasonable times for their observation, inspecting and testing. CONTRACTOR shall provide proper and safe conditions for such access.

Tests and Inspections

6.3 CONTRACTOR shall give each Town timely notice of readiness of the Work for all required inspections, tests or approvals. CONTRACTOR shall furnish written information to each Town stating the original sources of all materials manufactured away from the actual site of the Work. In order to insure a proper time sequence for required inspection and approval, this information shall be furnished at least two weeks in advance of the incorporation in the Work of any such materials.

6.4 If any Work (including the work of others) that is to be inspected, tested or approved is covered without written concurrence of a specific Town, it must, if requested by that Town, be uncovered for observation. Such uncovering shall be at CONTRACTOR'S expense unless CONTRACTOR has given that Town timely notice of CONTRACTOR'S intention to cover the same and that Town has not acted with reasonable promptness in response to such notice.

6.5 Neither observations by the County or a Town, nor inspection, tests or approvals by others shall relieve CONTRACTOR from CONTRACTOR'S obligations to perform the Work in accordance with the Contract Documents.

Two Year Correction Period

6.6 If within two (2) years after the date of Completion or such longer period of time as may be prescribed by Laws or Regulations or by the terms of any applicable special guarantee required by the Contract Documents or by any specific provision of the Contract Documents, any Work is found to be DEFECTIVE, CONTRACTOR shall promptly, without cost to the Town and in accordance with Town's written instructions, either correct such DEFECTIVE Work, or, if it has been rejected by the Town, remove it from the site and replace it with NONDEFECTIVE Work. If CONTRACTOR does not promptly comply with the terms of such instructions, or in an emergency where delay would cause serious risk of loss or damage, the Town may have the DEFECTIVE Work corrected or the rejected Work removed and replaced, and all direct, indirect and consequential costs of such removal and replacement (including but not limited to fees and charges of engineers, architects, attorneys and other professionals) will be paid by CONTRACTOR. In special circumstances where a particular item of equipment is placed in continuous

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

service before Completion of all the Work, the correction period for that item may start to run from an earlier date if so provided in the Specifications or by Written Amendment.

ARTICLE 7 – PAYMENT BONDS

7.1 CONTRACTOR shall furnish a Labor and Materials Bonds in an amount of 50% of the Contract Price as security for the faithful payment of all CONTRACTOR'S obligations under the Contract Documents. These Bonds shall remain in effect at least until two (2) years after the date when final payment becomes due, except as otherwise provided by Law or Regulation or by the Contract Documents. CONTRACTOR shall also furnish such other Bonds as are required by the Supplementary Conditions. All Bonds shall be in the forms prescribed by Law or Regulation or by the Contract Documents and be executed by such sureties as are named in the current list of "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies" as published in Circular 570 (amended) by the Audit Staff Bureau of Accounts, U.S. Treasury Department. All Bonds signed by an agent must be accompanied by a certified copy of the authority to act.

Payment bonds in the amount of 50% are required for work over $25,000. Contractors shall supply the required bonds to each municipality as the result of a Notice to proceed process as required by MA General Law Chapter 30, 39m.

7.2 If the surety on any Bond furnished by CONTRACTOR is declared bankrupt or becomes insolvent or its right to do business is terminated in any state where any part of the Project is located or it ceases to meet the requirements of paragraph 6.1, CONTRACTOR shall within five (5) days thereafter substitute another Bond and Surety, both of which must be acceptable to the County and the Towns.

ARTICLE 8 – EFFECTIVE DATE

The Effective Date of the Agreement shall be the date that the County determines that the Contract is complete, signs the Agreement and forwards a Notice to Proceed to CONTRACTOR.

ARTICLE 9 - CHANGES IN THE WORK

9.1 The County or any Town, without invalidating the Contract may order Changes in the Work consisting of additions, deletions, or modifications, the Contract Sum and the Contract Time being adjusted accordingly. All such changes in the Work shall be authorized by written Change Order signed by the County, Town or the Engineer as their duly authorized agent.

9.2 The Contract Sum and the Contract Time may be changed only by Change Order.

9.3 The cost or credit to the Town from a Change in the Work shall be determined by mutual agreement.

ARTICLE 10 - WAGE RATES

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

10.1 Full compliance with applicable federal, state and local wage laws is required on all Work done for any Town.

10.2 The County and Towns shall not be held liable should the CONTRACTOR fail to compensate any person(s) in accordance with the prevailing (minimum) wage rates included herein. The CONTRACTOR claims full responsibility to compensate the person(s) associated with the project accordingly and will assume any liability on behalf of the County and Towns, should a person(s) associated with the project file a claim pursuant to MGL Chapter 149.

10.3 The "work classifications" provided by the CONTRACTOR on the required "Weekly Payroll Report Form" shall exactly match the classifications provided in the "Minimum Wage Rates". Should the CONTRACTOR use an unlisted classification, it shall be the CONTRACTOR's responsibility to contact the Department of Labor and Industries in order to determine a matching classification or obtain minimum wage rate for the new classification.

ARTICLE 11 - ENGINEER

11.1 The Engineer (as designated by each Town) will provide general administration of the Contract and will be the Town's representative during the construction period.

11.2 The Engineer shall at all times have access to the Work wherever it is in preparation and progress.

11.3 The Engineer will make periodic visits to the site to become generally familiar with the progress and quality of the Work in accordance with the Contract Documents. On the basis of on-site observations by the Engineer, he will keep the Town informed of the progress of the Work, and will endeavor to guard the Town against defects and deficiencies in the Work of the CONTRACTOR. The Engineer will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work. The Engineer will not be responsible for construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the Work, and he will not be responsible for the CONTRACTOR'S failure to carry out the Work in accordance with the Contract Documents.

11.4 Based on such observations and the CONTRACTOR'S Application for Payment, the Engineer will determine the amounts owed to the CONTRACTOR.

11.5 The Engineer will be, in the first instance, the interpreter of the requirements of the Contract Documents.

11.6 The Engineer will have authority to reject Work which does not conform to the Contract Documents.

ARTICLE 12 - TERMINATION OF CONTRACT

The County and the Towns reserve the right to terminate this Contract or Services whenever it deems that the CONTRACTOR is in violation of laws, regulations and/or provisions of this Contract. Termination

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

of a Contract or Services by any Town shall not invalidate or alter the terms of a similar Contract or Services with any other Town.

ARTICLE 13 – MISCELLANEOUS

13.1 No assignment by a party hereto of any rights under or interests in the Contract Documents will be binding on another party hereto without the written consent of the party sought to be bound; and, specifically, but without limitation, moneys that may become due and monies that are due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law), and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignor from any duty or responsibility under the Contract Documents.

13.2 The County and CONTRACTOR each binds himself, his partners, successors, assigns and legal representatives in respect to all covenants, agreements and obligations contained in the Contract Documents.

13.3 This CONTRACT shall be deemed to include all terms and requirements imposed by laws related to the performance of the Work on the Project or Services.

13.4 This is not an exclusive contract to provide services or materials to the County and Towns. The County and Towns reserve the right to contract for similar services or materials.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

PREVAILING WAGES

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

THE COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE OF LABOR AND WORKFORCE DEVELOPMENT
DEPARTMENT OF LABOR STANDARDS
Prevailing Wage Rates

MAURA HEALY
Governor
KIM DRISCOLL
Lt. Governor

As determined by the Director under the provisions of the Massachusetts General Laws, Chapter 149, Sections 26 to 27H

LAUREN JONES
Secretary
MICHAEL FLANAGAN
Director

Awarding Authority:	Barnstable County	**City/Town:**	BARNSTABLE
Contract Number:	8110		
Description of Work:	Barnstable County on behalf of the Towns in the County requests bids from qualified contractors for Roadway Construction Items and Materials.		
Job Location:	varies		

Information about Prevailing Wage Schedules for Awarding Authorities and Contractors

- The wage rates will remain in effect for the duration of the project, except in the case of multi-year public construction projects. For construction projects lasting longer than one year, awarding authorities must request an updated wage schedule no later than two weeks before the anniversary of the date the contract was executed by the awarding authority and the general contractor. For multi-year CM AT RISK projects, the awarding authority must request an annual update no later than two weeks before the anniversary date, determined as the earlier of: (a) the execution date of the GMP Amendment, or (b) the execution date of the first amendment to permit procurement of construction services. The updated wage schedule must be provided to all contractors, including general and sub-contractors, working on the construction project.
- This annual update requirement is generally not applicable to 27F “rental of equipment” contracts. For such contracts, the prevailing wage rates issued by DLS shall remain in effect for the duration of the contract term. However, if the prevailing wage rate sheet issued does not contain wage rates for each year covered by the contract term, the Awarding Authority must request updated rate sheets from DLS and provide them to the contractor to ensure the correct rates are being paid throughout the duration of the contract. Additionally, if an Awarding Authority exercises an option to renew or extend the contract term, they must request updated rate sheets form DLS and provide them to the contractor.
- This wage schedule applies only to the specific project referenced at the top of this page and uniquely identified by the “Wage Request Number” on all pages of this schedule.
- An Awarding Authority must request an updated wage schedule if it has not opened bids or selected a contractor within 90 days of the date of issuance of the wage schedule. For CM AT RISK projects (bid pursuant to G.L. c.149A), the earlier of: (a) the execution date of the GMP Amendment, or (b) the bid for the first construction scope of work must be within 90-days of the wage schedule issuance date.
- The wage schedule shall be incorporated in any advertisement or call for bids for the project as required by M.G.L. c. 149, § 27. The wage schedule shall be made a part of the contract awarded for the project. The wage schedule must be posted in a conspicuous place at the work site for the life of the project in accordance with M.G.L. c. 149 § 27. The wages listed on the wage schedule must be paid to employees performing construction work on the project whether they are employed by the prime contractor, a filed sub-bidder, or a sub-contractor.
- Apprentices working on the project are required to be registered with the Massachusetts Division of Apprentice Standards (DAS). Apprentices must keep their apprentice identification card on their persons during all work hours on the project. An apprentice registered with DAS may be paid the lower apprentice wage rate at the applicable step as provided on the prevailing wage schedule. **Any apprentice not registered with DAS regardless of whether they are registered with another federal, state, local, or private agency must be paid the journeyworker's rate.**
- Every contractor or subcontractor working on the construction project must submit weekly payroll reports and a Statement of Compliance directly to the awarding authority by mail or email and keep them on file for three years. Each weekly payroll report must contain: the employee’s name, address, occupational classification, hours worked, and wages paid. Do not submit weekly payroll reports to DLS. For a sample payroll reporting form go to http://www.mass.gov/dols/pw.
- Contractors with questions about the wage rates or classifications included on the wage schedule have an affirmative obligation to inquire with DLS at (617) 626-6953.
- Contractors must obtain the wage schedules from awarding authorities. Failure of a contractor or subcontractor to pay the prevailing wage rates listed on the wage schedule to all employees who perform construction work on the project is a violation of the law and subjects the contractor or subcontractor to civil and criminal penalties.
- Employees not receiving the prevailing wage rate set forth on the wage schedule may file a complaint with the Fair Labor Division of the office of the Attorney General at (617) 727-3465.

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
(2 AXLE) DRIVER - EQUIPMENT TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/1/2025	$40.95	$15.57	$21.78	$0.00	$0.00	$78.30
	1/1/2026	$40.95	$16.17	$21.78	$0.00	$0.00	$78.90
	6/1/2026	$41.95	$16.17	$21.78	$0.00	$0.00	$79.90
	12/1/2026	$41.95	$16.17	$23.52	$0.00	$0.00	$81.64
	1/1/2027	$41.95	$16.77	$23.52	$0.00	$0.00	$82.24
(3 AXLE) DRIVER - EQUIPMENT TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/1/2025	$41.02	$15.57	$21.78	$0.00	$0.00	$78.37
	1/1/2026	$41.02	$16.17	$21.78	$0.00	$0.00	$78.97
	6/1/2026	$42.02	$16.17	$21.78	$0.00	$0.00	$79.97
	12/1/2026	$42.02	$16.17	$23.52	$0.00	$0.00	$81.71
	1/1/2027	$42.02	$16.77	$23.52	$0.00	$0.00	$82.31
(4 & 5 AXLE) DRIVER - EQUIPMENT TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/1/2025	$41.14	$15.57	$21.78	$0.00	$0.00	$78.49
	1/1/2026	$41.14	$16.17	$21.78	$0.00	$0.00	$79.09
	6/1/2026	$42.14	$16.17	$21.78	$0.00	$0.00	$80.09
	12/1/2026	$42.14	$16.17	$23.52	$0.00	$0.00	$81.83
	1/1/2027	$42.14	$16.77	$23.52	$0.00	$0.00	$82.43
ADS/SUBMERSIBLE PILOT PILE DRIVER LOCAL 56 PILE DRIVER LOCAL 56 (ZONE 2) For apprentice rates see "Apprentice- PILE DRIVER"	8/1/2024	$117.16	$10.08	$11.62	$12.67	$0.00	$151.53
AIR TRACK OPERATOR LABORERS LABORERS - ZONE 2	12/1/2025	$41.97	$10.15	$9.50	$9.11	$0.00	$70.73
	6/1/2026	$43.41	$10.15	$9.50	$9.11	$0.00	$72.17
	12/1/2026	$44.85	$10.15	$9.50	$9.11	$0.00	$73.61
	6/1/2027	$46.30	$10.15	$9.50	$9.11	$0.00	$75.06
	12/1/2027	$47.75	$10.15	$9.50	$9.11	$0.00	$76.51
	6/1/2028	$49.25	$10.15	$9.50	$9.11	$0.00	$78.01
	12/1/2028	$50.75	$10.15	$9.50	$9.11	$0.00	$79.51
For apprentice rates see "Apprentice- LABORER"							
AIR TRACK OPERATOR (HEAVY & HIGHWAY) LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2025	$41.97	$10.15	$9.50	$9.21	$0.00	$70.83
	6/1/2026	$43.41	$10.15	$9.50	$9.21	$0.00	$72.27
	12/1/2026	$44.85	$10.15	$9.50	$9.21	$0.00	$73.71
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
ASBESTOS WORKER (PIPES & TANKS) HEAT & FROST INSULATORS LOCAL 6 HEAT & FROST INSULATORS LOCAL 6 (SOUTHERN MASS)	12/1/2025	$44.80	$14.50	$4.30	$6.75	$0.00	$70.35
ASPHALT RAKER LABORERS LABORERS - ZONE 2	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
ASPHALT RAKER (HEAVY & HIGHWAY) LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2025	$41.47	$10.15	$9.50	$9.21	$0.00	$70.33
	6/1/2026	$42.91	$10.15	$9.50	$9.21	$0.00	$71.77
	12/1/2026	$44.35	$10.15	$9.50	$9.21	$0.00	$73.21
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)							
ASPHALT/CONCRETE/CRUSHER PLANT-ON SITE OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$59.28	$16.05	$13.25	$3.25	$0.00	$91.83
	6/1/2026	$60.58	$16.05	$13.25	$3.25	$0.00	$93.13
	12/1/2026	$62.03	$16.05	$13.25	$3.25	$0.00	$94.58
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
BACKHOE/FRONT-END LOADER OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$59.28	$16.05	$13.25	$3.25	$0.00	$91.83
	6/1/2026	$60.58	$16.05	$13.25	$3.25	$0.00	$93.13
	12/1/2026	$62.03	$16.05	$13.25	$3.25	$0.00	$94.58
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
BARCO-TYPE JUMPING TAMPER LABORERS LABORERS - ZONE 2	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
BLOCK PAVER, RAMMER / CURB SETTER LABORERS LABORERS - ZONE 2	12/1/2025	$41.97	$10.15	$9.50	$9.11	$0.00	$70.73
	6/1/2026	$43.41	$10.15	$9.50	$9.11	$0.00	$72.17
	12/1/2026	$44.85	$10.15	$9.50	$9.11	$0.00	$73.61
	6/1/2027	$46.30	$10.15	$9.50	$9.11	$0.00	$75.06
	12/1/2027	$47.75	$10.15	$9.50	$9.11	$0.00	$76.51
	6/1/2028	$49.25	$10.15	$9.50	$9.11	$0.00	$78.01
	12/1/2028	$50.75	$10.15	$9.50	$9.11	$0.00	$79.51
For apprentice rates see "Apprentice- LABORER"							
BLOCK PAVER, RAMMER / CURB SETTER (HEAVY & HIGHWAY) LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2025	$41.97	$10.15	$9.50	$9.21	$0.00	$70.83
	6/1/2026	$43.41	$10.15	$9.50	$9.21	$0.00	$72.27
	12/1/2026	$44.85	$10.15	$9.50	$9.21	$0.00	$73.71
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)							
BOILER MAKER BOILERMAKERS LOCAL 29 BOILERMAKERS LOCAL 29	1/1/2024	$48.12	$7.07	$14.60	$6.00	$0.00	$75.79

Apprentice: BOILER MAKER

Effective Date: 1/1/2024

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	65.00	$31.28	$7.07	$9.32	$3.90	$0.00	$51.57
2	65.00	$31.28	$7.07	$9.32	$3.90	$0.00	$51.57
3	70.00	$33.68	$7.07	$10.03	$4.20	$0.00	$54.98

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY WATERPROOFING) BRICKLAYERS LOCAL 3 BRICKLAYERS LOCAL 3 (NEW BEDFORD)	8/1/2025	$67.95	$11.49	$15.57	$8.02	$0.00	$103.03
	2/1/2026	$69.30	$11.49	$15.57	$8.02	$0.00	$104.38
	8/1/2026	$71.50	$11.49	$15.57	$8.02	$0.00	$106.58
	2/1/2027	$72.90	$11.49	$15.57	$8.02	$0.00	$107.98

Apprentice: BOILER MAKER

Effective Date: 1/1/2024

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
4	75.00	$36.09	$7.07	$10.74	$4.50	$0.00	$58.40
5	80.00	$38.50	$7.07	$11.45	$4.80	$0.00	$61.82
6	85.00	$40.90	$7.07	$12.18	$5.10	$0.00	$65.25
7	90.00	$43.31	$7.07	$12.88	$5.40	$0.00	$68.66
8	95.00	$45.71	$7.07	$13.62	$5.70	$0.00	$72.10

Apprentice to Journeyworker Ratio: 1:4

Apprentice: BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY WATERPROOFING)

Effective Date: 8/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$33.98	$11.49	$15.57	$8.02	$0.00	$69.06
2	60.00	$40.77	$11.49	$15.57	$8.02	$0.00	$75.85
3	70.00	$47.57	$11.49	$15.57	$8.02	$0.00	$82.65
4	80.00	$54.36	$11.49	$15.57	$8.02	$0.00	$89.44
5	90.00	$61.16	$11.49	$15.57	$8.02	$0.00	$96.24

Apprentice: BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY WATERPROOFING)

Effective Date: 2/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$34.65	$11.49	$15.57	$8.02	$0.00	$69.73
2	60.00	$41.58	$11.49	$15.57	$8.02	$0.00	$76.66
3	70.00	$48.51	$11.49	$15.57	$8.02	$0.00	$83.59
4	80.00	$55.44	$11.49	$15.57	$8.02	$0.00	$90.52
5	90.00	$62.37	$11.49	$15.57	$8.02	$0.00	$97.45

Apprentice to Journeyworker Ratio: 1:5

BULLDOZER/GRADER/SCRAPER OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

CAISSON & UNDERPINNING BOTTOM MAN LABORERS LABORERS - FOUNDATION AND MARINE	12/1/2025	$49.85	$10.15	$9.50	$9.80	$0.00	$79.30
	6/1/2026	$51.40	$10.15	$9.50	$9.80	$0.00	$80.85
	12/1/2026	$52.90	$10.15	$9.50	$9.80	$0.00	$82.35

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- LABORER"							
CAISSON & UNDERPINNING LABORER	12/1/2025	$48.70	$10.15	$9.50	$9.80	$0.00	$78.15
LABORERS	6/1/2026	$50.25	$10.15	$9.50	$9.80	$0.00	$79.70
LABORERS - FOUNDATION AND MARINE	12/1/2026	$51.75	$10.15	$9.50	$9.80	$0.00	$81.20
For apprentice rates see "Apprentice- LABORER"							
CAISSON & UNDERPINNING TOP MAN	12/1/2025	$49.03	$10.15	$9.50	$9.80	$0.00	$78.48
LABORERS	6/1/2026	$50.58	$10.15	$9.50	$9.80	$0.00	$80.03
LABORERS - FOUNDATION AND MARINE	12/1/2026	$52.08	$10.15	$9.50	$9.80	$0.00	$81.53
For apprentice rates see "Apprentice- LABORER"							
CARBIDE CORE DRILL OPERATOR	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
LABORERS	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
LABORERS - ZONE 2	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
CARPENTER	9/1/2025	$50.35	$10.33	$11.47	$8.50	$0.00	$80.65
CARPENTERS	3/1/2026	$51.60	$10.33	$11.47	$8.50	$0.00	$81.90
CARPENTERS -ZONE 2 (Eastern Massachusetts)	9/1/2026	$52.85	$10.33	$11.47	$8.50	$0.00	$83.15
	3/1/2027	$54.10	$10.33	$11.47	$8.50	$0.00	$84.40

Apprentice: CARPENTER

Effective Date: 9/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	45.00	$22.66	$10.33	$0.00	$1.73	$0.00	$34.72
2	45.00	$22.66	$10.33	$0.00	$1.73	$0.00	$34.72
3	55.00	$27.69	$10.33	$0.00	$3.40	$0.00	$41.42
4	55.00	$27.69	$10.33	$0.00	$3.40	$0.00	$41.42
5	70.00	$35.25	$10.33	$11.41	$5.10	$0.00	$62.09
6	70.00	$35.25	$10.33	$11.41	$5.10	$0.00	$62.09
7	80.00	$40.28	$10.33	$11.44	$6.80	$0.00	$68.85
8	80.00	$40.28	$10.33	$11.44	$6.80	$0.00	$68.85

Apprentice: CARPENTER

Effective Date: 3/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	45.00	$23.22	$10.33	$0.00	$1.73	$0.00	$35.28
2	45.00	$23.22	$10.33	$0.00	$1.73	$0.00	$35.28
3	55.00	$28.38	$10.33	$0.00	$3.40	$0.00	$42.11
4	55.00	$28.38	$10.33	$0.00	$3.40	$0.00	$42.11

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
CARPENTER WOOD FRAME CARPENTERS CARPENTERS-ZONE 3 (Wood Frame) All Aspects of New Wood Frame Work	10/1/2025	$27.75	$7.02	$3.80	$1.00	$0.00	$39.57
	10/1/2026	$28.85	$7.02	$3.80	$1.00	$0.00	$40.67

Apprentice: CARPENTER

Effective Date: 3/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
5	70.00	$36.12	$10.33	$11.41	$5.10	$0.00	$62.96
6	70.00	$36.12	$10.33	$11.41	$5.10	$0.00	$62.96
7	80.00	$41.28	$10.33	$11.44	$6.80	$0.00	$69.85
8	80.00	$41.28	$10.33	$11.44	$6.80	$0.00	$69.85

Apprentice to Journeyworker Ratio: 1:5

Apprentice: CARPENTER WOOD FRAME

Effective Date: 10/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	60.00	$16.65	$7.02	$0.00	$0.00	$0.00	$23.67
2	60.00	$16.65	$7.02	$0.00	$0.00	$0.00	$23.67
3	65.00	$18.04	$7.02	$0.00	$1.00	$0.00	$26.06
4	70.00	$19.43	$7.02	$0.00	$1.00	$0.00	$27.45
5	75.00	$20.81	$7.02	$3.80	$1.00	$0.00	$32.63
6	80.00	$22.20	$7.02	$3.80	$1.00	$0.00	$34.02
7	85.00	$23.59	$7.02	$3.80	$1.00	$0.00	$35.41
8	90.00	$24.98	$7.02	$3.80	$1.00	$0.00	$36.80

Apprentice: CARPENTER WOOD FRAME

Effective Date: 10/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	60.00	$17.31	$7.02	$0.00	$0.00	$0.00	$24.33
2	60.00	$17.31	$7.02	$0.00	$0.00	$0.00	$24.33
3	65.00	$18.75	$7.02	$0.00	$1.00	$0.00	$26.77
4	70.00	$20.20	$7.02	$0.00	$1.00	$0.00	$28.22
5	75.00	$21.64	$7.02	$3.80	$1.00	$0.00	$33.46
6	80.00	$23.08	$7.02	$3.80	$1.00	$0.00	$34.90
7	85.00	$24.52	$7.02	$3.80	$1.00	$0.00	$36.34
8	90.00	$25.97	$7.02	$3.80	$1.00	$0.00	$37.79

Apprentice to Journeyworker Ratio: 1:5

CEMENT MASONRY/PLASTERING BRICKLAYERS LOCAL 3 BRICKLAYERS LOCAL 3 (NEW BEDFORD)	7/1/2024	$49.19	$13.35	$16.43	$7.78	$1.80	$88.55

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Apprentice: CEMENT MASONRY/PLASTERING

Effective Date: 7/1/2024

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$24.60	$13.35	$16.43	$0.00	$0.00	$54.38
2	60.00	$29.51	$13.35	$16.43	$2.78	$1.80	$63.87
3	65.00	$31.97	$13.35	$16.43	$3.78	$1.80	$67.33
4	70.00	$34.43	$13.35	$16.43	$4.78	$1.80	$70.79
5	75.00	$36.89	$13.35	$16.43	$5.78	$1.80	$74.25
6	80.00	$39.35	$13.35	$16.43	$6.78	$1.80	$77.71
7	90.00	$44.27	$13.35	$16.43	$7.78	$1.80	$83.63

Apprentice to Journeyworker Ratio: 1:3

CHAIN SAW OPERATOR LABORERS LABORERS - ZONE 2	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
CLAM SHELLS/SLURRY BUCKETS/HEADING MACHINES OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$60.48	$16.05	$13.25	$3.25	$0.00	$93.03
	6/1/2026	$61.81	$16.05	$13.25	$3.25	$0.00	$94.36
	12/1/2026	$63.29	$16.05	$13.25	$3.25	$0.00	$95.84
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
COMPRESSOR OPERATOR OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$37.97	$16.05	$13.25	$3.25	$0.00	$70.52
	6/1/2026	$38.83	$16.05	$13.25	$3.25	$0.00	$71.38
	12/1/2026	$39.78	$16.05	$13.25	$3.25	$0.00	$72.33
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
DELEADER (BRIDGE) PAINTERS LOCAL 35 PAINTERS LOCAL 35 - ZONE 2	7/1/2025	$58.51	$10.30	$11.95	$12.50	$0.00	$93.26
	1/1/2026	$59.56	$10.35	$12.00	$12.60	$0.00	$94.51

Apprentice: DELEADER (BRIDGE)

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$29.26	$10.30	$0.00	$0.00	$0.00	$39.56
2	55.00	$32.18	$10.30	$0.00	$6.88	$0.00	$49.36
3	60.00	$35.11	$10.30	$0.00	$7.50	$0.00	$52.91
4	65.00	$38.03	$10.30	$0.00	$8.13	$0.00	$56.46
5	70.00	$40.96	$10.30	$11.95	$8.75	$0.00	$71.96
6	75.00	$43.88	$10.30	$11.95	$9.38	$0.00	$75.51

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Apprentice: DELEADER (BRIDGE)

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
7	80.00	$46.81	$10.30	$11.95	$10.00	$0.00	$79.06
8	90.00	$52.66	$10.30	$11.95	$11.25	$0.00	$86.16

Apprentice: DELEADER (BRIDGE)

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$29.78	$10.35	$0.00	$0.00	$0.00	$40.13
2	55.00	$32.76	$10.35	$0.00	$6.93	$0.00	$50.04
3	60.00	$35.74	$10.35	$0.00	$7.56	$0.00	$53.65
4	65.00	$38.71	$10.35	$0.00	$8.19	$0.00	$57.25
5	70.00	$41.69	$10.35	$12.00	$8.82	$0.00	$72.86
6	75.00	$44.67	$10.35	$12.00	$9.45	$0.00	$76.47
7	80.00	$47.65	$10.35	$12.00	$10.08	$0.00	$80.08
8	90.00	$53.60	$10.35	$12.00	$11.34	$0.00	$87.29

Apprentice to Journeyworker Ratio: 1:1

DEMO: ADZEMAN LABORERS LABORERS - ZONE 2	12/1/2025	$48.75	$10.15	$9.50	$9.65	$0.00	$78.05
	6/1/2026	$50.30	$10.15	$9.50	$9.65	$0.00	$79.60
	12/7/2026	$51.80	$10.15	$9.50	$9.65	$0.00	$81.10
	6/7/2027	$53.40	$10.15	$9.50	$9.65	$0.00	$82.70
	12/6/2027	$55.00	$10.15	$9.50	$9.65	$0.00	$84.30
	6/5/2028	$56.68	$10.15	$9.50	$9.65	$0.00	$85.98
	12/4/2028	$58.35	$10.15	$9.50	$9.65	$0.00	$87.65
For apprentice rates see "Apprentice- LABORER"							
DEMO: BACKHOE/LOADER/HAMMER OPERATOR LABORERS LABORERS - ZONE 2	12/1/2025	$49.75	$10.15	$9.50	$9.65	$0.00	$79.05
	6/1/2026	$51.30	$10.15	$9.50	$9.65	$0.00	$80.60
	12/7/2026	$52.80	$10.15	$9.50	$9.65	$0.00	$82.10
	6/7/2027	$54.40	$10.15	$9.50	$9.65	$0.00	$83.70
	12/6/2027	$56.00	$10.15	$9.50	$9.65	$0.00	$85.30
	6/5/2028	$57.68	$10.15	$9.50	$9.65	$0.00	$86.98
	12/4/2028	$59.35	$10.15	$9.50	$9.65	$0.00	$88.65
For apprentice rates see "Apprentice- LABORER"							
DEMO: BURNERS LABORERS LABORERS - ZONE 2	12/1/2025	$49.50	$10.15	$9.50	$9.65	$0.00	$78.80
	6/1/2026	$51.05	$10.15	$9.50	$9.65	$0.00	$80.35
	12/7/2026	$52.55	$10.15	$9.50	$9.65	$0.00	$81.85
	6/7/2027	$54.15	$10.15	$9.50	$9.65	$0.00	$83.45
	12/6/2027	$55.75	$10.15	$9.50	$9.65	$0.00	$85.05
	6/5/2028	$57.43	$10.15	$9.50	$9.65	$0.00	$86.73
	12/4/2028	$59.10	$10.15	$9.50	$9.65	$0.00	$88.40
For apprentice rates see "Apprentice- LABORER"							

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
DEMO: CONCRETE CUTTER/SAWYER LABORERS LABORERS - ZONE 2	12/1/2025	$49.75	$10.15	$9.50	$9.65	$0.00	$79.05
	6/1/2026	$51.30	$10.15	$9.50	$9.65	$0.00	$80.60
	12/7/2026	$52.80	$10.15	$9.50	$9.65	$0.00	$82.10
	6/7/2027	$54.40	$10.15	$9.50	$9.65	$0.00	$83.70
	12/6/2027	$56.00	$10.15	$9.50	$9.65	$0.00	$85.30
	6/5/2028	$57.68	$10.15	$9.50	$9.65	$0.00	$86.98
	12/4/2028	$59.35	$10.15	$9.50	$9.65	$0.00	$88.65
For apprentice rates see "Apprentice- LABORER"							
DEMO: JACKHAMMER OPERATOR LABORERS LABORERS - ZONE 2	12/1/2025	$49.50	$10.15	$9.50	$9.65	$0.00	$78.80
	6/1/2026	$51.05	$10.15	$9.50	$9.65	$0.00	$80.35
	12/7/2026	$52.55	$10.15	$9.50	$9.65	$0.00	$81.85
	6/7/2027	$54.15	$10.15	$9.50	$9.65	$0.00	$83.45
	12/6/2027	$55.75	$10.15	$9.50	$9.65	$0.00	$85.05
	6/5/2028	$57.43	$10.15	$9.50	$9.65	$0.00	$86.73
	12/4/2028	$59.10	$10.15	$9.50	$9.65	$0.00	$88.40
For apprentice rates see "Apprentice- LABORER"							
DEMO: WRECKING LABORER LABORERS LABORERS - ZONE 2	12/1/2025	$48.75	$10.15	$9.50	$9.65	$0.00	$78.05
	6/1/2026	$50.30	$10.15	$9.50	$9.65	$0.00	$79.60
	12/7/2026	$51.80	$10.15	$9.50	$9.65	$0.00	$81.10
	6/7/2027	$53.40	$10.15	$9.50	$9.65	$0.00	$82.70
	12/6/2027	$55.00	$10.15	$9.50	$9.65	$0.00	$84.30
	6/5/2028	$56.68	$10.15	$9.50	$9.65	$0.00	$85.98
	12/4/2028	$58.35	$10.15	$9.50	$9.65	$0.00	$87.65
For apprentice rates see "Apprentice- LABORER"							
DIRECTIONAL DRILL MACHINE OPERATOR OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
DIVER PILE DRIVER LOCAL 56 PILE DRIVER LOCAL 56 (ZONE 2)	8/1/2024	$78.11	$10.08	$11.62	$12.67	$0.00	$112.48
as of 8-1-24, Apprentices with diving licenses begin at second year. % of Diver wage 70/80/90 2A $69.83, 3A $91.79,4A $102.14 Total Rate							
DIVER TENDER PILE DRIVER LOCAL 56 PILE DRIVER LOCAL 56 (ZONE 2)	8/1/2024	$51.97	$10.08	$11.62	$12.67	$0.00	$86.34
as of 8-1-24, Apprentices with diving licenses begin at second year. % of Piledriver wage 70/80/90 2A $54.20, 3A $73.93,4A $82.05 Total Rate							
DIVER TENDER (EFFLUENT) PILE DRIVER LOCAL 56 PILE DRIVER LOCAL 56 (ZONE 2)	8/1/2024	$83.69	$10.08	$11.62	$12.67	$0.00	$118.06
For apprentice rates see "Apprentice- PILE DRIVER"							
DIVER/SLURRY (EFFLUENT) PILE DRIVER LOCAL 56 PILE DRIVER LOCAL 56 (ZONE 2)	8/1/2024	$117.16	$10.08	$11.62	$12.67	$0.00	$151.53
For apprentice rates see "Apprentice- PILE DRIVER"							

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
DRAWBRIDGE OPERATOR (Construction) DRAWBRIDGE - SEIU LOCAL 888 DRAWBRIDGE - SEIU LOCAL 888	7/1/2020	$26.77	$6.67	$3.93	$0.00	$0.16	$37.53
ELECTRICIAN ELECTRICIANS LOCAL 223 ELECTRICIANS LOCAL 223	9/1/2025	$52.25	$12.25	$14.86	$3.75	$0.00	$83.11
	9/1/2026	$54.72	$12.50	$15.56	$4.00	$0.00	$86.78

Apprentice: ELECTRICIAN

Effective Date: 9/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	40.00	$20.90	$12.25	$0.63	$0.00	$0.00	$33.78
2	45.00	$23.51	$12.25	$0.71	$0.00	$0.00	$36.47
3	50.00	$26.13	$12.25	$0.78	$0.00	$0.00	$39.16
4	55.00	$28.74	$12.25	$6.61	$2.50	$0.00	$50.10
5	60.00	$31.35	$12.25	$7.21	$2.50	$0.00	$53.31
6	65.00	$33.96	$12.25	$7.82	$2.50	$0.00	$56.53
7	70.00	$36.58	$12.25	$8.41	$2.50	$0.00	$59.74
8	75.00	$39.19	$12.25	$9.02	$2.50	$0.00	$62.96

Apprentice: ELECTRICIAN

Effective Date: 9/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	40.00	$21.89	$12.50	$0.66	$0.00	$0.00	$35.05
2	45.00	$24.62	$12.50	$0.74	$0.00	$0.00	$37.86
3	50.00	$27.36	$12.50	$0.82	$0.00	$0.00	$40.68
4	55.00	$30.10	$12.50	$6.92	$2.75	$0.00	$52.27
5	60.00	$32.83	$12.50	$7.54	$2.75	$0.00	$55.62
6	65.00	$35.57	$12.50	$8.18	$2.75	$0.00	$59.00
7	70.00	$38.30	$12.50	$8.81	$2.75	$0.00	$62.36
8	75.00	$41.04	$12.50	$9.43	$2.75	$0.00	$65.72

Apprentice to Journeyworker Ratio: 2:3

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
ELEVATOR CONSTRUCTOR ELEVATOR CONSTRUCTORS LOCAL 4 ELEVATOR CONSTRUCTORS LOCAL 4	1/1/2025	$74.17	$16.28	$10.96	$10.40	$0.00	$111.81
	1/1/2026	$77.26	$16.38	$11.06	$10.70	$0.00	$115.40
	1/1/2027	$80.55	$16.48	$11.16	$11.00	$0.00	$119.19

Apprentice: ELEVATOR CONSTRUCTOR

Effective Date: 1/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$37.09	$0.00	$0.00	$0.00	$0.00	$37.09
2	55.00	$40.79	$16.28	$10.96	$10.40	$0.00	$78.43
3	65.00	$48.21	$16.28	$10.96	$10.40	$0.00	$85.85

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Apprentice: ELEVATOR CONSTRUCTOR

Effective Date: 1/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
4	70.00	$51.92	$16.28	$10.96	$10.40	$0.00	$89.56
5	80.00	$59.34	$16.28	$10.96	$10.40	$0.00	$96.98

Apprentice: ELEVATOR CONSTRUCTOR

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$38.63	$0.00	$0.00	$0.00	$0.00	$38.63
2	55.00	$42.49	$16.38	$11.06	$10.70	$0.00	$80.63
3	65.00	$50.22	$16.38	$11.06	$10.70	$0.00	$88.36
4	70.00	$54.08	$16.38	$11.06	$10.70	$0.00	$92.22
5	80.00	$61.81	$16.38	$11.06	$10.70	$0.00	$99.95

Apprentice to Journeyworker Ratio: 1:1

ELEVATOR CONSTRUCTOR HELPER	1/1/2025	$51.92	$16.28	$10.96	$10.40	$0.00	$89.56
ELEVATOR CONSTRUCTORS LOCAL 4	1/1/2026	$54.08	$16.38	$11.06	$10.07	$0.00	$91.59
ELEVATOR CONSTRUCTORS LOCAL 4	1/1/2027	$56.39	$16.48	$11.16	$11.00	$0.00	$95.03
For apprentice rates see "Apprentice - ELEVATOR CONSTRUCTOR"							
FENCE & GUARD RAIL ERECTOR (HEAVY & HIGHWAY)	12/1/2025	$41.47	$10.15	$9.50	$9.21	$0.00	$70.33
LABORERS	6/1/2026	$42.91	$10.15	$9.50	$9.21	$0.00	$71.77
LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2026	$44.35	$10.15	$9.50	$9.21	$0.00	$73.21
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
FIELD ENG.INST.PERSON-BLDG,SITE,HVY/HWY	11/1/2025	$53.56	$16.05	$13.25	$3.25	$0.00	$86.11
OPERATING ENGINEERS LOCAL 4	5/1/2026	$55.00	$16.05	$13.25	$3.25	$0.00	$87.55
OPERATING ENGINEERS LOCAL 4	11/1/2026	$56.29	$16.05	$13.25	$3.25	$0.00	$88.84
	5/1/2027	$57.72	$16.05	$13.25	$3.25	$0.00	$90.27
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
FIELD ENG.PARTY CHIEF-BLDG,SITE,HVY/HWY	11/1/2025	$55.17	$16.05	$13.25	$3.25	$0.00	$87.72
OPERATING ENGINEERS LOCAL 4	5/1/2026	$56.62	$16.05	$13.25	$3.25	$0.00	$89.17
OPERATING ENGINEERS LOCAL 4	11/1/2026	$57.92	$16.05	$13.25	$3.25	$0.00	$90.47
	5/1/2027	$59.37	$16.05	$13.25	$3.25	$0.00	$91.92
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
FIELD ENG.ROD PERSON-BLDG,SITE,HVY/HWY	11/1/2025	$26.03	$16.05	$13.25	$3.25	$0.00	$58.58
OPERATING ENGINEERS LOCAL 4	5/1/2026	$26.88	$16.05	$13.25	$3.25	$0.00	$59.43
OPERATING ENGINEERS LOCAL 4	11/1/2026	$27.64	$16.05	$13.25	$3.25	$0.00	$60.19
	5/1/2027	$28.49	$16.05	$13.25	$3.25	$0.00	$61.04
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
FIRE ALARM INSTALLER	9/1/2025	$52.25	$12.25	$14.86	$3.75	$0.00	$83.11

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
ELECTRICIANS LOCAL 223 ELECTRICIANS LOCAL 223	9/1/2026	$54.72	$12.50	$15.56	$4.00	$0.00	$86.78
For apprentice rates see "Apprentice- ELECTRICIAN"							
FIRE ALARM REPAIR / MAINTENANCE	9/1/2025	$52.25	$12.25	$14.86	$3.75	$0.00	$83.11
/ COMMISSIONING ELECTRICIANS LOCAL 223 ELECTRICIANS LOCAL 223	9/1/2026	$54.72	$12.50	$15.56	$4.00	$0.00	$86.78
For apprentice rates see "Apprentice- TELECOMMUNICATIONS TECHNICIAN"							
FIREMAN (ASST. ENGINEER)	12/1/2025	$47.69	$16.05	$13.25	$3.25	$0.00	$80.24
OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	6/1/2026	$48.75	$16.05	$13.25	$3.25	$0.00	$81.30
	12/1/2026	$49.93	$16.05	$13.25	$3.25	$0.00	$82.48
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
FLAGGER & SIGNALER (HEAVY & HIGHWAY)	12/1/2025	$28.09	$10.15	$9.50	$9.21	$0.00	$56.95
LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	6/1/2026	$29.21	$10.15	$9.50	$9.21	$0.00	$58.07
	12/1/2026	$29.21	$10.15	$9.50	$9.21	$0.00	$58.07
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
FLOORCOVERER FLOORCOVERERS LOCAL 2168 FLOORCOVERERS LOCAL 2168 ZONE II	3/1/2024	$48.93	$10.33	$11.47	$8.80	$0.00	$79.53

Apprentice: FLOORCOVERER

Effective Date: 3/1/2024

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$24.47	$10.33	$0.00	$1.76	$0.00	$36.56
2	55.00	$26.91	$10.33	$0.00	$1.76	$0.00	$39.00
3	60.00	$29.36	$10.33	$0.00	$3.52	$0.00	$43.21
4	65.00	$31.80	$10.33	$0.00	$3.52	$0.00	$45.65
5	70.00	$34.25	$10.33	$11.47	$5.28	$0.00	$61.33
6	75.00	$36.70	$10.33	$11.47	$5.28	$0.00	$63.78
7	80.00	$39.14	$10.33	$11.47	$7.04	$0.00	$67.98
8	85.00	$41.59	$10.33	$11.47	$7.04	$0.00	$70.43

Apprentice Notes

Steps are 750 hrs.

Apprentice to Journeyworker Ratio: 1:1

FORK LIFT/CHERRY PICKER	12/1/2025	$59.28	$16.05	$13.25	$3.25	$0.00	$91.83
OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	6/1/2026	$60.58	$16.05	$13.25	$3.25	$0.00	$93.13
	12/1/2026	$62.03	$16.05	$13.25	$3.25	$0.00	$94.58
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
GENERATOR/LIGHTING PLANT/HEATERS	12/1/2025	$37.97	$16.05	$13.25	$3.25	$0.00	$70.52
OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	6/1/2026	$38.83	$16.05	$13.25	$3.25	$0.00	$71.38
	12/1/2026	$39.78	$16.05	$13.25	$3.25	$0.00	$72.33

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
GLAZIER (GLASS PLANK/AIR BARRIER/INTERIOR SYSTEMS) GLAZIERS LOCAL 1333 GLAZIERS LOCAL 1333	6/1/2025	$43.13	$10.80	$8.25	$5.50	$0.00	$67.68
	6/1/2026	$44.73	$11.20	$8.40	$6.05	$0.00	$70.38
	6/1/2027	$46.73	$11.60	$8.55	$6.60	$0.00	$73.48
	6/1/2028	$48.73	$12.00	$8.70	$7.20	$0.00	$76.63

Apprentice: GLAZIER (GLASS PLANK/AIR BARRIER/INTERIOR SYSTEMS)

Effective Date: 6/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$21.57	$10.80	$8.25	$5.50	$0.00	$46.12
2	56.25	$24.26	$10.80	$8.25	$5.50	$0.00	$48.81
3	62.50	$26.96	$10.80	$8.25	$5.50	$0.00	$51.51
4	68.75	$29.65	$10.80	$8.25	$5.50	$0.00	$54.20
5	75.00	$32.35	$10.80	$8.25	$5.50	$0.00	$56.90
6	81.25	$35.04	$10.80	$8.25	$5.50	$0.00	$59.59
7	87.50	$37.74	$10.80	$8.25	$5.50	$0.00	$62.29
8	93.75	$40.43	$10.80	$8.25	$5.50	$0.00	$64.98

Apprentice: GLAZIER (GLASS PLANK/AIR BARRIER/INTERIOR SYSTEMS)

Effective Date: 6/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$22.37	$11.20	$8.40	$6.05	$0.00	$48.02
2	56.25	$25.16	$11.20	$8.40	$6.05	$0.00	$50.81
3	62.50	$27.96	$11.20	$8.40	$6.05	$0.00	$53.61
4	68.75	$30.75	$11.20	$8.40	$6.05	$0.00	$56.40
5	75.00	$33.55	$11.20	$8.40	$6.05	$0.00	$59.20
6	81.25	$36.34	$11.20	$8.40	$6.05	$0.00	$61.99
7	87.50	$39.14	$11.20	$8.40	$6.05	$0.00	$64.79
8	93.75	$41.93	$11.20	$8.40	$6.05	$0.00	$67.58

Apprentice to Journeyworker Ratio: 3:1

HOISTING ENGINEER/CRANES/GRADALLS OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$59.28	$16.05	$13.25	$3.25	$0.00	$91.83
	6/1/2026	$60.58	$16.05	$13.25	$3.25	$0.00	$93.13
	12/1/2026	$62.03	$16.05	$13.25	$3.25	$0.00	$94.58

Apprentice: HOISTING ENGINEER/CRANES/GRADALLS

Effective Date: 12/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	55.00	$32.88	$0.00	$0.00	$0.00	$0.00	$32.88
2	60.00	$35.87	$16.05	$13.25	$3.25	$0.00	$68.42
3	65.00	$38.86	$16.05	$13.25	$3.25	$0.00	$71.41
4	70.00	$41.85	$16.05	$13.25	$3.25	$0.00	$74.40

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Apprentice: HOISTING ENGINEER/CRANES/GRADALLS

Effective Date: 12/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
5	75.00	$44.84	$16.05	$13.25	$3.25	$0.00	$77.39
6	80.00	$47.82	$16.05	$13.25	$3.25	$0.00	$80.37
7	85.00	$50.81	$16.05	$13.25	$3.25	$0.00	$83.36
8	90.00	$53.80	$16.05	$13.25	$3.25	$0.00	$86.35

Apprentice: HOISTING ENGINEER/CRANES/GRADALLS

Effective Date: 6/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	55.00	$33.32	$0.00	$0.00	$0.00	$0.00	$33.32
2	60.00	$36.35	$16.05	$13.25	$3.25	$0.00	$68.90
3	65.00	$39.38	$16.05	$13.25	$3.25	$0.00	$71.93
4	70.00	$42.41	$16.50	$13.25	$3.25	$0.00	$75.41
5	75.00	$45.44	$16.50	$13.25	$3.25	$0.00	$78.44
6	80.00	$48.46	$16.50	$13.25	$3.25	$0.00	$81.46
7	85.00	$51.49	$16.50	$13.25	$3.25	$0.00	$84.49
8	90.00	$54.52	$16.50	$13.25	$3.25	$0.00	$87.52

Apprentice to Journeyworker Ratio: 1:6

HVAC (DUCTWORK) SHEETMETAL WORKERS LOCAL 17 SHEETMETAL WORKERS LOCAL 17 - B	10/1/2025 4/1/2026	$44.05 $45.55	$14.91 $14.91	$13.35 $13.35	$6.15 $6.15	$2.24 $2.24	$80.70 $82.20
For apprentice rates see "Apprentice- SHEET METAL WORKER"							
HVAC (ELECTRICAL CONTROLS) ELECTRICIANS LOCAL 223 ELECTRICIANS LOCAL 223	9/1/2025 9/1/2026	$52.25 $54.72	$12.25 $12.50	$14.86 $15.56	$3.75 $4.00	$0.00 $0.00	$83.11 $86.78
For apprentice rates see "Apprentice- ELECTRICIAN"							
HVAC (TESTING AND BALANCING - AIR) SHEETMETAL WORKERS LOCAL 17 SHEETMETAL WORKERS LOCAL 17 - B	10/1/2025 4/1/2026	$44.05 $45.55	$14.91 $14.91	$13.35 $13.35	$6.15 $6.15	$2.24 $2.24	$80.70 $82.20
For apprentice rates see "Apprentice- SHEET METAL WORKER"							
HVAC (TESTING AND BALANCING -WATER) PLUMBERS & PIPEFITTERS LOCAL 51 PLUMBERS & PIPEFITTERS LOCAL 51	8/25/2025	$55.24	$10.80	$16.80	$4.60	$0.00	$87.44
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"							
HVAC MECHANIC PLUMBERS & PIPEFITTERS LOCAL 51 PLUMBERS & PIPEFITTERS LOCAL 51	8/25/2025	$55.24	$10.80	$16.80	$4.60	$0.00	$87.44
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"							
HYDRAULIC DRILLS	12/1/2025	$41.97	$10.15	$9.50	$9.11	$0.00	$70.73

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
LABORERS LABORERS - ZONE 2	6/1/2026	$43.41	$10.15	$9.50	$9.11	$0.00	$72.17
	12/1/2026	$44.85	$10.15	$9.50	$9.11	$0.00	$73.61
	6/1/2027	$46.30	$10.15	$9.50	$9.11	$0.00	$75.06
	12/1/2027	$47.75	$10.15	$9.50	$9.11	$0.00	$76.51
	6/1/2028	$49.25	$10.15	$9.50	$9.11	$0.00	$78.01
	12/1/2028	$50.75	$10.15	$9.50	$9.11	$0.00	$79.51
For apprentice rates see "Apprentice- LABORER"							
HYDRAULIC DRILLS (HEAVY & HIGHWAY)	12/1/2025	$41.97	$10.15	$9.50	$9.21	$0.00	$70.83
LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	6/1/2026	$43.41	$10.15	$9.50	$9.21	$0.00	$72.27
	12/1/2026	$44.85	$10.15	$9.50	$9.21	$0.00	$73.71
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
INSULATOR (PIPES & TANKS) HEAT & FROST INSULATORS LOCAL 6 HEAT & FROST INSULATORS LOCAL 6 (SOUTHERN MASS)	9/1/2025	$54.31	$14.75	$9.52	$10.09	$0.00	$88.67
	9/1/2026	$57.38	$14.75	$9.52	$10.09	$0.00	$91.74

Apprentice: INSULATOR (PIPES & TANKS)

Effective Date: 9/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$27.16	$14.75	$9.27	$5.05	$0.00	$56.23
2	60.00	$32.59	$14.75	$9.32	$6.05	$0.00	$62.71
3	70.00	$38.02	$14.75	$9.37	$7.06	$0.00	$69.20
4	80.00	$43.45	$14.75	$9.42	$8.07	$0.00	$75.69

Apprentice: INSULATOR (PIPES & TANKS)

Effective Date: 9/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$28.69	$14.75	$9.27	$5.05	$0.00	$57.76
2	60.00	$34.43	$14.75	$9.32	$6.05	$0.00	$64.55
3	70.00	$40.17	$14.75	$9.37	$7.06	$0.00	$71.35
4	80.00	$45.90	$14.75	$9.42	$8.07	$0.00	$78.14

Apprentice to Journeyworker Ratio: 1:4

IRONWORKER/WELDER IRONWORKERS LOCAL 37 IRONWORKERS LOCAL 37	3/16/2021	$42.46	$7.70	$12.10	$5.00	$0.00	$67.26

Apprentice: IRONWORKER/WELDER

Effective Date: 3/16/2021

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	70.00	$29.72	$7.70	$12.10	$5.00	$0.00	$54.52
2	75.00	$31.85	$7.70	$12.10	$5.00	$0.00	$56.65

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
Apprentice: IRONWORKER/WELDER							
Effective Date: 3/16/2021							
Step / Percent		**Apprentice Base Wage**					
3 / 80.00		$33.97	$7.70	$12.10	$5.00	$0.00	$58.77
4 / 85.00		$36.09	$7.70	$12.10	$5.00	$0.00	$60.89
5 / 90.00		$38.21	$7.70	$12.10	$5.00	$0.00	$63.01
6 / 95.00		$40.34	$7.70	$12.10	$5.00	$0.00	$65.14
Apprentice to Journeyworker Ratio: 1:4							
JACKHAMMER & PAVING BREAKER OPERATOR LABORERS LABORERS - ZONE 2	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
LABORER LABORERS LABORERS - ZONE 2	12/1/2025	$41.22	$10.15	$9.50	$9.11	$0.00	$69.98
	6/1/2026	$42.66	$10.15	$9.50	$9.11	$0.00	$71.42
	12/1/2026	$44.10	$10.15	$9.50	$9.11	$0.00	$72.86
	6/1/2027	$45.55	$10.15	$9.50	$9.11	$0.00	$74.31
	12/1/2027	$47.00	$10.15	$9.50	$9.11	$0.00	$75.76
	6/1/2028	$48.50	$10.15	$9.50	$9.11	$0.00	$77.26
	12/1/2028	$50.00	$10.15	$9.50	$9.11	$0.00	$78.76
Apprentice: LABORER							
Effective Date: 12/1/2025							
Step / Percent		**Apprentice Base Wage**					
1 / 60.00		$25.03	$10.15	$9.50	$9.11	$0.00	$53.79
2 / 70.00		$29.20	$10.15	$9.50	$9.11	$0.00	$57.96
3 / 80.00		$33.38	$10.15	$9.50	$9.11	$0.00	$62.14
4 / 90.00		$37.55	$10.15	$9.50	$9.11	$0.00	$66.31
Apprentice: LABORER							
Effective Date: 6/1/2026							
Step / Percent		**Apprentice Base Wage**					
1 / 60.00		$25.60	$10.15	$9.50	$9.11	$0.00	$54.36
2 / 70.00		$29.86	$10.15	$9.50	$9.11	$0.00	$58.62
3 / 80.00		$34.13	$10.15	$9.50	$9.11	$0.00	$62.89
4 / 90.00		$38.39	$10.15	$9.50	$9.11	$0.00	$67.15
Apprentice to Journeyworker Ratio: 1:5							

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
LABORER (HEAVY & HIGHWAY) LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2025	$41.22	$10.15	$9.50	$9.21	$0.00	$70.08
	6/1/2026	$42.66	$10.15	$9.50	$9.21	$0.00	$71.52
	12/1/2026	$44.10	$10.15	$9.50	$9.21	$0.00	$72.96

Apprentice: LABORER (HEAVY & HIGHWAY)

Effective Date: 12/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	60.00	$25.03	$10.15	$9.50	$9.21	$0.00	$53.89
2	70.00	$29.20	$10.15	$9.50	$9.21	$0.00	$58.06
3	80.00	$33.38	$10.15	$9.50	$9.21	$0.00	$62.24
4	90.00	$37.55	$10.15	$9.50	$9.21	$0.00	$66.41

Apprentice: LABORER (HEAVY & HIGHWAY)

Effective Date: 6/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	60.00	$25.60	$10.15	$9.50	$9.21	$0.00	$54.46
2	70.00	$29.86	$10.15	$9.50	$9.21	$0.00	$58.72
3	80.00	$34.13	$10.15	$9.50	$9.21	$0.00	$62.99
4	90.00	$38.39	$10.15	$9.50	$9.10	$0.00	$67.14

Apprentice to Journeyworker Ratio: 1:5

LABORER: CARPENTER TENDER LABORERS LABORERS - ZONE 2	12/1/2025	$41.22	$10.15	$9.50	$9.11	$0.00	$69.98
	6/1/2026	$42.66	$10.15	$9.50	$9.11	$0.00	$71.42
	12/1/2026	$44.10	$10.15	$9.50	$9.11	$0.00	$72.86
	6/1/2027	$45.55	$10.15	$9.50	$9.11	$0.00	$74.31
	12/1/2027	$47.00	$10.15	$9.50	$9.11	$0.00	$75.76
	6/1/2028	$48.50	$10.15	$9.50	$9.11	$0.00	$77.26
	12/1/2028	$50.00	$10.15	$9.50	$9.11	$0.00	$78.76

For apprentice rates see "Apprentice- LABORER"

LABORER: CEMENT FINISHER TENDER LABORERS LABORERS - ZONE 2	12/1/2025	$41.22	$10.15	$9.50	$9.11	$0.00	$69.98
	6/1/2026	$42.66	$10.15	$9.50	$9.11	$0.00	$71.42
	12/1/2026	$44.10	$10.15	$9.50	$9.11	$0.00	$72.86
	6/1/2027	$45.55	$10.15	$9.50	$9.11	$0.00	$74.31
	12/1/2027	$47.00	$10.15	$9.50	$9.11	$0.00	$75.76
	6/1/2028	$48.50	$10.15	$9.50	$9.11	$0.00	$77.26
	12/1/2028	$50.00	$10.15	$9.50	$9.11	$0.00	$78.76

For apprentice rates see "Apprentice- LABORER"

LABORER: HAZARDOUS WASTE/ASBESTOS REMOVER LABORERS LABORERS - ZONE 2	12/1/2025	$41.31	$10.15	$9.50	$9.65	$0.00	$70.61
	6/1/2026	$42.75	$10.15	$9.50	$9.65	$0.00	$72.05
	12/7/2026	$44.19	$10.15	$9.50	$9.65	$0.00	$73.49
	6/7/2027	$45.64	$10.15	$9.50	$9.65	$0.00	$74.94
	12/6/2027	$47.09	$10.15	$9.50	$9.65	$0.00	$76.39
	6/5/2028	$48.59	$10.15	$9.50	$9.65	$0.00	$77.89

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
	12/4/2028	$50.09	$10.15	$9.50	$9.65	$0.00	$79.39
For apprentice rates see "Apprentice- LABORER"							
LABORER: MASON TENDER	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
LABORERS	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
LABORERS - ZONE 2	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
LABORER: MASON TENDER (HEAVY & HIGHWAY)	12/1/2025	$41.47	$10.15	$9.50	$9.21	$0.00	$70.33
LABORERS	6/1/2026	$42.91	$10.15	$9.50	$9.21	$0.00	$71.77
LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2026	$44.35	$10.15	$9.50	$9.21	$0.00	$73.21
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
LABORER: MULTI-TRADE TENDER	12/1/2025	$41.22	$10.15	$9.50	$9.11	$0.00	$69.98
LABORERS	6/1/2026	$42.66	$10.15	$9.50	$9.11	$0.00	$71.42
LABORERS - ZONE 2	12/1/2026	$44.10	$10.15	$9.50	$9.11	$0.00	$72.86
	6/1/2027	$45.55	$10.15	$9.50	$9.11	$0.00	$74.31
	12/1/2027	$47.00	$10.15	$9.50	$9.11	$0.00	$75.76
	6/1/2028	$48.50	$10.15	$9.50	$9.11	$0.00	$77.26
	12/1/2028	$50.00	$10.15	$9.50	$9.11	$0.00	$78.76
For apprentice rates see "Apprentice- LABORER"							
LABORER: TREE REMOVER	12/1/2025	$41.22	$10.15	$9.50	$9.11	$0.00	$69.98
LABORERS	6/1/2026	$42.66	$10.15	$9.50	$9.11	$0.00	$71.42
LABORERS - ZONE 2	12/1/2026	$44.10	$10.15	$9.50	$9.11	$0.00	$72.86
	6/1/2027	$45.55	$10.15	$9.50	$9.11	$0.00	$74.31
	12/1/2027	$47.00	$10.15	$9.50	$9.11	$0.00	$75.76
	6/1/2028	$48.50	$10.15	$9.50	$9.11	$0.00	$77.26
	12/1/2028	$50.00	$10.15	$9.50	$9.11	$0.00	$78.76
This classification applies to the removal of standing trees, and the trimming and removal of branches and limbs when related to public works construction or site clearance incidental to construction . For apprentice rates see "Apprentice- LABORER"							
LASER BEAM OPERATOR	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
LABORERS	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
LABORERS - ZONE 2	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
LASER BEAM OPERATOR (HEAVY & HIGHWAY)	12/1/2025	$41.47	$10.15	$9.50	$9.21	$0.00	$70.33
LABORERS	6/1/2026	$42.91	$10.15	$9.50	$9.21	$0.00	$71.77
LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2026	$44.35	$10.15	$9.50	$9.21	$0.00	$73.21
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
MARBLE & TILE FINISHERS	8/1/2025	$52.08	$11.49	$15.57	$6.05	$0.00	$85.19

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
BRICKLAYERS LOCAL 3 BRICKLAYERS LOCAL 3 - MARBLE & TILE	2/1/2026	$53.16	$11.49	$15.57	$6.05	$0.00	$86.27
	8/1/2026	$54.92	$11.49	$15.57	$6.05	$0.00	$88.03
	2/1/2027	$56.04	$11.49	$15.57	$6.05	$0.00	$89.15

Apprentice: MARBLE & TILE FINISHERS

Effective Date: 8/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$26.04	$11.49	$15.57	$6.05	$0.00	$59.15
2	60.00	$31.25	$11.49	$15.57	$6.05	$0.00	$64.36
3	70.00	$36.46	$11.49	$15.57	$6.05	$0.00	$69.57
4	80.00	$41.66	$11.49	$15.57	$6.05	$0.00	$74.77
5	90.00	$46.87	$11.49	$15.57	$6.05	$0.00	$79.98

Apprentice: MARBLE & TILE FINISHERS

Effective Date: 2/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$26.58	$11.49	$15.57	$6.05	$0.00	$59.69
2	60.00	$31.90	$11.49	$15.57	$6.05	$0.00	$65.01
3	70.00	$37.21	$11.49	$15.57	$6.05	$0.00	$70.32
4	80.00	$42.53	$11.49	$15.57	$6.05	$0.00	$75.64
5	90.00	$47.84	$11.49	$15.57	$6.05	$0.00	$80.95

Apprentice to Journeyworker Ratio: 1:5

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
MARBLE MASONS,TILELAYERS & TERRAZZO MECH	8/1/2025	$67.97	$11.49	$15.57	$7.99	$0.00	$103.02
BRICKLAYERS LOCAL 3 BRICKLAYERS LOCAL 3 - MARBLE & TILE	2/1/2026	$69.32	$11.49	$15.57	$7.99	$0.00	$104.37
	8/1/2026	$71.52	$11.49	$15.57	$7.99	$0.00	$106.57
	2/1/2027	$72.92	$11.49	$15.57	$7.99	$0.00	$107.97

Apprentice: MARBLE MASONS,TILELAYERS & TERRAZZO MECH

Effective Date: 8/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$33.99	$11.49	$15.57	$7.99	$0.00	$69.04
2	60.00	$40.78	$11.49	$15.57	$7.99	$0.00	$75.83
3	70.00	$47.58	$11.49	$15.57	$7.99	$0.00	$82.63
4	80.00	$54.38	$11.49	$15.57	$7.99	$0.00	$89.43
5	90.00	$61.17	$11.49	$15.57	$7.99	$0.00	$96.22

Apprentice: MARBLE MASONS,TILELAYERS & TERRAZZO MECH

Effective Date: 2/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Apprentice: MARBLE MASONS,TILELAYERS & TERRAZZO MECH

Effective Date: 2/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$34.66	$11.49	$15.57	$7.99	$0.00	$69.71
2	60.00	$41.59	$11.49	$15.57	$7.99	$0.00	$76.64
3	70.00	$48.52	$11.49	$15.57	$7.99	$0.00	$83.57
4	80.00	$55.46	$11.49	$15.57	$7.99	$0.00	$90.51
5	90.00	$62.39	$11.49	$15.57	$7.99	$0.00	$97.44

Apprentice to Journeyworker Ratio: 1:5

MECH. SWEEPER OPERATOR (ON CONST. SITES) OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
MECHANICS MAINTENANCE OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
MILLWRIGHT (Zone 2) MILLWRIGHTS LOCAL 1121 MILLWRIGHTS LOCAL 1121 - Zone 2	1/6/2025	$45.03	$10.08	$11.47	$10.00	$0.00	$76.58
	1/5/2026	$47.36	$10.08	$11.47	$10.00	$0.00	$78.91

Apprentice: MILLWRIGHT (Zone 2)

Effective Date: 1/6/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	55.00	$24.77	$10.08	$0.00	$5.50	$0.00	$40.35
2	65.00	$29.27	$10.08	$0.00	$6.50	$0.00	$45.85
3	75.00	$33.77	$10.08	$11.47	$7.50	$0.00	$62.82
4	85.00	$38.28	$10.08	$11.47	$8.50	$0.00	$68.33

Apprentice: MILLWRIGHT (Zone 2)

Effective Date: 1/5/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	55.00	$26.05	$10.08	$0.00	$5.50	$0.00	$41.63
2	65.00	$30.78	$10.08	$0.00	$6.50	$0.00	$47.36
3	75.00	$35.52	$10.08	$11.47	$7.50	$0.00	$64.57
4	85.00	$40.26	$10.08	$11.47	$8.50	$0.00	$70.31

Apprentice Notes

Step 1&2 Appr. indentured after 1/6/2020 receive no pension,

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
Apprentice to Journeyworker Ratio: 1:4							
MORTAR MIXER LABORERS LABORERS - ZONE 2	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
OILER (OTHER THAN TRUCK CRANES,GRADALLS) OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$25.68	$16.05	$13.25	$3.25	$0.00	$58.23
	6/1/2026	$26.27	$16.05	$13.25	$3.25	$0.00	$58.82
	12/1/2026	$26.94	$16.05	$13.25	$3.25	$0.00	$59.49
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
OILER (TRUCK CRANES, GRADALLS) OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$31.65	$16.05	$13.25	$3.25	$0.00	$64.20
	6/1/2026	$32.37	$16.05	$13.25	$3.25	$0.00	$64.92
	12/1/2026	$33.17	$16.05	$13.25	$3.25	$0.00	$65.72
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
OTHER POWER DRIVEN EQUIPMENT - CLASS II OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
PAINTER (BRIDGES/TANKS) PAINTERS LOCAL 35 PAINTERS LOCAL 35 - ZONE 2	7/1/2025	$58.51	$10.30	$11.95	$12.50	$0.00	$93.26
	1/1/2026	$59.56	$10.35	$12.00	$12.50	$0.00	$94.41

Apprentice: PAINTER (BRIDGES/TANKS)

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$29.26	$10.30	$0.00	$0.00	$0.00	$39.56
2	55.00	$32.18	$10.30	$0.00	$6.88	$0.00	$49.36
3	60.00	$35.11	$10.30	$0.00	$7.50	$0.00	$52.91
4	65.00	$38.03	$10.30	$0.00	$8.13	$0.00	$56.46
5	70.00	$40.96	$10.30	$11.95	$8.75	$0.00	$71.96
6	75.00	$43.88	$10.30	$11.95	$9.38	$0.00	$75.51
7	80.00	$46.81	$10.30	$11.95	$10.00	$0.00	$79.06
8	90.00	$52.66	$10.30	$11.95	$11.25	$0.00	$86.16

Apprentice: PAINTER (BRIDGES/TANKS)

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
PAINTER (SPRAY OR SANDBLAST, NEW) *	7/1/2025	$49.41	$10.30	$11.95	$12.50	$0.00	$84.16
* If 30% or more of surfaces to be painted are new construction, NEW paint rate shall be used.	1/1/2026	$50.46	$10.35	$12.00	$12.60	$0.00	$85.41
PAINTERS LOCAL 35							
PAINTERS LOCAL 35 - ZONE 2							

Apprentice: PAINTER (BRIDGES/TANKS)

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$29.78	$10.35	$0.00	$0.00	$0.00	$40.13
2	55.00	$32.76	$10.35	$0.00	$6.93	$0.00	$50.04
3	60.00	$35.74	$10.35	$0.00	$7.56	$0.00	$53.65
4	65.00	$38.71	$10.35	$0.00	$8.19	$0.00	$57.25
5	70.00	$41.69	$10.35	$12.00	$8.82	$0.00	$72.86
6	75.00	$44.67	$10.35	$12.00	$9.45	$0.00	$76.47
7	80.00	$47.65	$10.35	$12.00	$10.08	$0.00	$80.08
8	90.00	$53.60	$10.35	$12.00	$11.34	$0.00	$87.29

Apprentice to Journeyworker Ratio: 1:1

Apprentice: PAINTER (SPRAY OR SANDBLAST, NEW) *

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$24.71	$10.30	$0.00	$0.00	$0.00	$35.01
2	55.00	$27.18	$10.30	$0.00	$6.88	$0.00	$44.36
3	60.00	$29.65	$10.30	$0.00	$7.50	$0.00	$47.45
4	65.00	$32.12	$10.30	$0.00	$8.13	$0.00	$50.55
5	70.00	$34.59	$10.30	$11.95	$8.75	$0.00	$65.59
6	75.00	$37.06	$10.30	$11.95	$9.38	$0.00	$68.69
7	80.00	$39.53	$10.30	$11.95	$10.00	$0.00	$71.78
8	90.00	$44.47	$10.30	$11.95	$11.25	$0.00	$77.97

Apprentice: PAINTER (SPRAY OR SANDBLAST, NEW) *

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$25.23	$10.35	$0.00	$0.00	$0.00	$35.58
2	55.00	$27.75	$10.35	$0.00	$6.93	$0.00	$45.03
3	60.00	$30.28	$10.35	$0.00	$7.56	$0.00	$48.19
4	65.00	$32.80	$10.35	$0.00	$8.19	$0.00	$51.34
5	70.00	$35.32	$10.35	$12.00	$8.82	$0.00	$66.49
6	75.00	$37.85	$10.35	$12.00	$9.45	$0.00	$69.65
7	80.00	$40.37	$10.35	$12.00	$10.08	$0.00	$72.80
8	90.00	$45.41	$10.35	$12.00	$11.34	$0.00	$79.10

Apprentice to Journeyworker Ratio: 1:1

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
PAINTER (SPRAY OR SANDBLAST, REPAINT) PAINTERS LOCAL 35 PAINTERS LOCAL 35 - ZONE 2	7/1/2025	$47.47	$10.30	$11.95	$12.50	$0.00	$82.22
	1/1/2026	$48.52	$10.35	$12.00	$12.60	$0.00	$83.47

Apprentice: PAINTER (SPRAY OR SANDBLAST, REPAINT)

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$23.74	$10.30	$0.00	$0.00	$0.00	$34.04
2	55.00	$26.11	$10.30	$0.00	$6.88	$0.00	$43.29
3	60.00	$28.48	$10.30	$0.00	$7.50	$0.00	$46.28
4	65.00	$30.86	$10.30	$0.00	$8.13	$0.00	$49.29
5	70.00	$33.23	$10.30	$11.95	$8.75	$0.00	$64.23
6	75.00	$35.60	$10.30	$11.95	$9.38	$0.00	$67.23
7	80.00	$37.98	$10.30	$11.95	$10.00	$0.00	$70.23
8	90.00	$42.72	$10.30	$11.95	$11.25	$0.00	$76.22

Apprentice: PAINTER (SPRAY OR SANDBLAST, REPAINT)

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$24.26	$10.35	$0.00	$0.00	$0.00	$34.61
2	55.00	$26.69	$10.35	$0.00	$6.93	$0.00	$43.97
3	60.00	$29.11	$10.35	$0.00	$7.56	$0.00	$47.02
4	65.00	$31.54	$10.35	$0.00	$8.19	$0.00	$50.08
5	70.00	$33.96	$10.35	$12.00	$8.82	$0.00	$65.13
6	75.00	$36.39	$10.35	$12.00	$9.45	$0.00	$68.19
7	80.00	$38.82	$10.35	$12.00	$10.08	$0.00	$71.25
8	90.00	$43.67	$10.35	$12.00	$11.34	$0.00	$77.36

Apprentice to Journeyworker Ratio: 1:1

PAINTER / TAPER (BRUSH, NEW) * * If 30% or more of surfaces to be painted are new construction, NEW paint rate shall be used. PAINTERS LOCAL 35 PAINTERS LOCAL 35 - ZONE 2	7/1/2025	$48.01	$10.30	$11.95	$12.50	$0.00	$82.76
	1/1/2026	$49.06	$10.35	$12.00	$12.60	$0.00	$84.01

Apprentice: PAINTER / TAPER (BRUSH, NEW) *

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$24.01	$10.30	$0.00	$0.00	$0.00	$34.31
2	55.00	$26.41	$10.30	$0.00	$6.88	$0.00	$43.59
3	60.00	$28.81	$10.30	$0.00	$7.50	$0.00	$46.61
4	65.00	$31.21	$10.30	$0.00	$8.13	$0.00	$49.64
5	70.00	$33.61	$10.30	$11.95	$8.75	$0.00	$64.61
6	75.00	$36.01	$10.30	$11.95	$9.38	$0.00	$67.64

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
PAINTER / TAPER (BRUSH, REPAINT) PAINTERS LOCAL 35 PAINTERS LOCAL 35 - ZONE 2	7/1/2025	$46.07	$10.30	$11.95	$12.50	$0.00	$80.82
	1/1/2026	$47.12	$10.35	$12.00	$12.60	$0.00	$82.07

Apprentice: PAINTER / TAPER (BRUSH, NEW) *

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
7	80.00	$38.41	$10.30	$11.95	$10.00	$0.00	$70.66
8	90.00	$43.21	$10.30	$11.95	$11.25	$0.00	$76.71

Apprentice: PAINTER / TAPER (BRUSH, NEW) *

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$24.53	$10.35	$0.00	$0.00	$0.00	$34.88
2	55.00	$26.98	$10.35	$0.00	$6.93	$0.00	$44.26
3	60.00	$29.44	$10.35	$0.00	$7.56	$0.00	$47.35
4	65.00	$31.89	$10.35	$0.00	$8.19	$0.00	$50.43
5	70.00	$34.34	$10.35	$12.00	$8.82	$0.00	$65.51
6	75.00	$36.80	$10.35	$12.00	$9.45	$0.00	$68.60
7	80.00	$39.25	$10.35	$12.00	$10.08	$0.00	$71.68
8	90.00	$44.15	$10.35	$12.00	$11.34	$0.00	$77.84

Apprentice to Journeyworker Ratio: 1:1

Apprentice: PAINTER / TAPER (BRUSH, REPAINT)

Effective Date: 7/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$23.04	$10.30	$0.00	$0.00	$0.00	$33.34
2	55.00	$25.34	$10.30	$0.00	$6.88	$0.00	$42.52
3	60.00	$27.64	$10.30	$0.00	$7.50	$0.00	$45.44
4	65.00	$29.95	$10.30	$0.00	$8.13	$0.00	$48.38
5	70.00	$32.25	$10.30	$11.95	$8.75	$0.00	$63.25
6	75.00	$34.55	$10.30	$11.95	$9.38	$0.00	$66.18
7	80.00	$36.86	$10.30	$11.95	$10.00	$0.00	$69.11
8	90.00	$41.46	$10.30	$11.95	$11.25	$0.00	$74.96

Apprentice: PAINTER / TAPER (BRUSH, REPAINT)

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$23.56	$10.35	$0.00	$0.00	$0.00	$33.91
2	55.00	$25.92	$10.35	$0.00	$6.93	$0.00	$43.20

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
Apprentice: PAINTER / TAPER (BRUSH, REPAINT)							
Effective Date: 1/1/2026							
Step / Percent		**Apprentice Base Wage**					
3 / 60.00		$28.27	$10.35	$0.00	$7.56	$0.00	$46.18
4 / 65.00		$30.63	$10.35	$0.00	$8.19	$0.00	$49.17
5 / 70.00		$32.98	$10.35	$12.00	$8.82	$0.00	$64.15
6 / 75.00		$35.34	$10.35	$12.00	$9.45	$0.00	$67.14
7 / 80.00		$37.70	$10.35	$12.00	$10.08	$0.00	$70.13
8 / 90.00		$42.41	$10.35	$12.00	$11.34	$0.00	$76.10
Apprentice to Journeyworker Ratio: 1:1							
PAINTER TRAFFIC MARKINGS (HEAVY/HIGHWAY) LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2025	$41.22	$10.15	$9.50	$9.21	$0.00	$70.08
	6/1/2026	$42.66	$10.15	$9.50	$9.21	$0.00	$71.52
	12/1/2026	$44.10	$10.15	$9.50	$9.21	$0.00	$72.96
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)							
PANEL & PICKUP TRUCKS DRIVER TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/1/2025	$40.78	$15.57	$21.78	$0.00	$0.00	$78.13
	1/1/2026	$40.78	$16.17	$21.78	$0.00	$0.00	$78.73
	6/1/2026	$41.78	$16.17	$21.78	$0.00	$0.00	$79.73
	12/1/2026	$41.78	$16.17	$23.52	$0.00	$0.00	$81.47
	1/1/2027	$41.78	$16.77	$23.52	$0.00	$0.00	$82.07
PIER AND DOCK CONSTRUCTOR (UNDERPINNING AND DECK) PILE DRIVER LOCAL 56 PILE DRIVER LOCAL 56 (ZONE 2)	8/1/2024	$51.97	$10.08	$11.62	$12.67	$0.00	$86.34
For apprentice rates see "Apprentice- PILE DRIVER"							
PILE DRIVER PILE DRIVER LOCAL 56 PILE DRIVER LOCAL 56 (ZONE 2)	8/1/2024	$51.97	$10.08	$11.62	$12.67	$0.00	$86.34
Apprentice: PILE DRIVER							
Effective Date: 8/1/2024							
Step / Percent		**Apprentice Base Wage**					
1 / 45.00		$23.39	$10.08	$0.00	$2.53	$0.00	$36.00
2 / 55.00		$28.58	$10.08	$0.00	$5.07	$0.00	$43.73
3 / 70.00		$36.38	$10.08	$11.62	$7.60	$0.00	$65.68
4 / 80.00		$41.58	$10.08	$11.62	$10.14	$0.00	$73.42
Apprentice to Journeyworker Ratio: 1:5							
PIPELAYER LABORERS LABORERS - ZONE 2	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
PIPELAYER (HEAVY & HIGHWAY)	12/1/2025	$41.47	$10.15	$9.50	$9.21	$0.00	$70.33
LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	6/1/2026	$42.91	$10.15	$9.50	$9.21	$0.00	$71.77
	12/1/2026	$44.35	$10.15	$9.50	$9.21	$0.00	$73.21
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
PLUMBER & PIPEFITTER PLUMBERS & PIPEFITTERS LOCAL 51 PLUMBERS & PIPEFITTERS LOCAL 51	8/25/2025	$55.24	$10.80	$16.80	$4.60	$0.00	$87.44

Apprentice: PLUMBER & PIPEFITTER

Effective Date: 8/25/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	40.00	$22.10	$10.15	$2.50	$0.00	$0.00	$34.75
2	50.00	$27.62	$10.15	$2.50	$0.00	$0.00	$40.27
3	60.00	$33.14	$10.15	$8.40	$0.50	$0.00	$52.19
4	70.00	$38.67	$10.15	$13.44	$0.80	$0.00	$63.06
5	80.00	$44.19	$10.15	$16.80	$1.00	$0.00	$72.14

Apprentice to Journeyworker Ratio: 1:3

PNEUMATIC CONTROLS (TEMP.) PLUMBERS & PIPEFITTERS LOCAL 51 PLUMBERS & PIPEFITTERS LOCAL 51	8/25/2025	$55.24	$10.80	$16.80	$4.60	$0.00	$87.44
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"							
PNEUMATIC DRILL/TOOL OPERATOR	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
LABORERS LABORERS - ZONE 2	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
PNEUMATIC DRILL/TOOL OPERATOR (HEAVY & HIGHWAY)	12/1/2025	$41.47	$10.15	$9.50	$9.21	$0.00	$70.33
LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	6/1/2026	$42.91	$10.15	$9.50	$9.21	$0.00	$71.77
	12/1/2026	$44.35	$10.15	$9.50	$9.21	$0.00	$73.21
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
POWDERMAN & BLASTER	12/1/2025	$42.22	$10.15	$9.50	$9.11	$0.00	$70.98
LABORERS LABORERS - ZONE 2	6/1/2026	$43.66	$10.15	$9.50	$9.11	$0.00	$72.42
	12/1/2026	$45.10	$10.15	$9.50	$9.11	$0.00	$73.86
	6/1/2027	$46.55	$10.15	$9.50	$9.11	$0.00	$75.31
	12/1/2027	$48.00	$10.15	$9.50	$9.11	$0.00	$76.76
	6/1/2028	$49.50	$10.15	$9.50	$9.11	$0.00	$78.26

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
	12/1/2028	$51.00	$10.15	$9.50	$9.11	$0.00	$79.76
For apprentice rates see "Apprentice- LABORER"							
POWDERMAN & BLASTER (HEAVY & HIGHWAY)	12/1/2025	$42.22	$9.90	$9.50	$9.21	$0.00	$70.83
LABORERS	6/1/2026	$43.66	$9.90	$9.50	$9.21	$0.00	$72.27
LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2026	$45.10	$9.90	$9.50	$9.21	$0.00	$73.71
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
POWER SHOVEL/DERRICK/TRENCHING MACHINE	12/1/2025	$59.28	$16.05	$13.25	$3.25	$0.00	$91.83
OPERATING ENGINEERS LOCAL 4	6/1/2026	$60.58	$16.05	$13.25	$3.25	$0.00	$93.13
OPERATING ENGINEERS LOCAL 4	12/1/2026	$62.03	$16.05	$13.25	$3.25	$0.00	$94.58
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
PUMP OPERATOR (CONCRETE)	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
OPERATING ENGINEERS LOCAL 4	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
OPERATING ENGINEERS LOCAL 4	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
PUMP OPERATOR (DEWATERING, OTHER)	12/1/2025	$37.97	$16.05	$13.25	$3.25	$0.00	$70.52
OPERATING ENGINEERS LOCAL 4	6/1/2026	$38.83	$16.05	$13.25	$3.25	$0.00	$71.38
OPERATING ENGINEERS LOCAL 4	12/1/2026	$39.78	$16.05	$13.25	$3.25	$0.00	$72.33
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
READY-MIX CONCRETE DRIVER	8/1/2023	$25.00	$13.91	$6.90	$0.00	$0.00	$45.81
TEAMSTERS 653							
TEAMSTERS 653 - Southeastern Concrete (Weymouth)							
RECLAIMERS	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
OPERATING ENGINEERS LOCAL 4	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
OPERATING ENGINEERS LOCAL 4	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
RIDE-ON MOTORIZED BUGGY OPERATOR	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
LABORERS	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
LABORERS - ZONE 2	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
ROLLER/SPREADER/MULCHING MACHINE	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
OPERATING ENGINEERS LOCAL 4	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
OPERATING ENGINEERS LOCAL 4	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
ROOFER (Inc.Roofer Waterproofng &Roofer Damproofg)	8/1/2025	$53.53	$13.28	$12.67	$9.03	$0.00	$88.51
ROOFERS LOCAL 33	2/1/2026	$54.78	$13.28	$12.67	$9.03	$0.00	$89.76
ROOFERS LOCAL 33							

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
ROOFER SLATE / TILE / PRECAST CONCRETE ROOFERS LOCAL 33 ROOFERS LOCAL 33	8/1/2025	$53.78	$13.28	$12.67	$9.03	$0.00	$88.76
	2/1/2026	$55.03	$13.28	$12.67	$9.03	$0.00	$90.01

For apprentice rates see "Apprentice- ROOFER"

Apprentice: ROOFER (Inc.Roofer Waterproofng &Roofer Damproofg)

Effective Date: 8/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$26.77	$13.28	$6.52	$9.03	$0.00	$55.60
2	60.00	$32.12	$13.28	$12.67	$9.03	$0.00	$67.10
3	65.00	$34.79	$13.28	$12.67	$9.03	$0.00	$69.77
4	75.00	$40.15	$13.28	$12.67	$9.03	$0.00	$75.13
5	85.00	$45.50	$13.28	$12.67	$9.03	$0.00	$80.48

Apprentice: ROOFER (Inc.Roofer Waterproofng &Roofer Damproofg)

Effective Date: 2/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$27.39	$13.28	$6.52	$9.03	$0.00	$56.22
2	60.00	$32.87	$13.28	$12.67	$9.03	$0.00	$67.85
3	65.00	$35.61	$13.28	$12.67	$9.03	$0.00	$70.59
4	75.00	$41.09	$13.28	$12.67	$9.03	$0.00	$76.07
5	85.00	$46.56	$13.28	$12.67	$9.03	$0.00	$81.54

Apprentice Notes

** 1:5, 2:6-10, the 1:10; Reroofing: 1:4, then 1:1

Apprentice to Journeyworker Ratio: 1:5

SHEETMETAL WORKER SHEETMETAL WORKERS LOCAL 17 SHEETMETAL WORKERS LOCAL 17 - B	10/1/2025	$44.05	$14.91	$13.35	$6.15	$2.24	$80.70
	4/1/2026	$45.55	$14.91	$13.35	$6.15	$2.24	$82.20

Apprentice: SHEETMETAL WORKER

Effective Date: 10/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	40.00	$17.62	$14.91	$4.27	$0.00	$1.09	$37.89
2	45.00	$19.82	$14.91	$4.80	$0.00	$1.17	$40.70
3	50.00	$22.03	$14.91	$12.28	$0.00	$1.45	$50.67
4	55.00	$24.23	$14.91	$12.28	$0.00	$1.52	$52.94
5	60.00	$26.43	$14.91	$12.28	$3.69	$1.64	$58.95
6	65.00	$28.63	$14.91	$12.28	$4.00	$1.71	$61.53
7	70.00	$30.84	$14.91	$12.28	$4.31	$1.78	$64.12
8	75.00	$33.04	$14.91	$12.28	$4.61	$1.86	$66.70

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Apprentice: SHEETMETAL WORKER

Effective Date: 10/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
9	80.00	$35.24	$14.91	$12.28	$4.92	$1.93	$69.28
10	85.00	$37.44	$14.91	$12.28	$5.23	$2.00	$71.86

Apprentice: SHEETMETAL WORKER

Effective Date: 4/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	40.00	$18.22	$14.91	$4.27	$0.00	$1.09	$38.49
2	45.00	$20.50	$14.91	$4.80	$0.00	$1.17	$41.38
3	50.00	$22.78	$14.91	$12.28	$0.00	$1.45	$51.42
4	55.00	$25.05	$14.91	$12.28	$0.00	$1.52	$53.76
5	60.00	$27.33	$14.91	$12.28	$3.69	$1.64	$59.85
6	65.00	$29.61	$14.91	$12.28	$4.00	$1.71	$62.51
7	70.00	$31.89	$14.91	$12.28	$4.31	$1.78	$65.17
8	75.00	$34.16	$14.91	$12.28	$4.61	$1.86	$67.82
9	80.00	$36.44	$14.91	$12.28	$4.92	$1.93	$70.48
10	85.00	$38.72	$14.91	$12.28	$5.23	$2.00	$73.14

Apprentice to Journeyworker Ratio: 1:4

SPECIALIZED EARTH MOVING EQUIP < 35 TONS TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/1/2025	$41.24	$15.57	$21.78	$0.00	$0.00	$78.59
	1/1/2026	$41.24	$16.17	$21.78	$0.00	$0.00	$79.19
	6/1/2026	$42.24	$16.17	$21.78	$0.00	$0.00	$80.19
	12/1/2026	$42.24	$16.17	$23.52	$0.00	$0.00	$81.93
	1/1/2027	$42.24	$16.77	$23.52	$0.00	$0.00	$82.53
SPECIALIZED EARTH MOVING EQUIP > 35 TONS TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/1/2025	$41.53	$15.57	$21.78	$0.00	$0.00	$78.88
	1/1/2026	$41.53	$16.17	$21.78	$0.00	$0.00	$79.48
	6/1/2026	$42.53	$16.17	$21.78	$0.00	$0.00	$80.48
	12/1/2026	$42.53	$16.17	$23.52	$0.00	$0.00	$82.22
	1/1/2027	$42.53	$16.77	$23.52	$0.00	$0.00	$82.82
SPRINKLER FITTER SPRINKLER FITTERS LOCAL 550 SPRINKLER FITTERS LOCAL 550 - (Section B) Zone 2	10/1/2025	$64.85	$12.25	$7.40	$19.50	$0.00	$104.00
	1/1/2026	$64.85	$13.45	$7.45	$18.25	$0.00	$104.00

Apprentice: SPRINKLER FITTER

Effective Date: 10/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	35.00	$22.70	$12.25	$14.22	$0.00	$0.00	$49.17
2	0.00	$25.94	$12.25	$15.20	$0.00	$0.00	$53.39
3	0.00	$29.18	$12.25	$16.18	$0.00	$0.00	$57.61

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate

Apprentice: SPRINKLER FITTER

Effective Date: 10/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
4	0.00	$32.43	$12.25	$17.15	$0.00	$0.00	$61.83
5	0.00	$35.67	$12.25	$18.12	$0.00	$0.00	$66.04
6	0.00	$38.91	$12.25	$19.10	$0.00	$0.00	$70.26
7	65.00	$42.15	$12.25	$20.08	$0.00	$0.00	$74.48
8	0.00	$45.40	$12.25	$21.05	$0.00	$0.00	$78.70
9	0.00	$48.64	$12.25	$22.02	$0.00	$0.00	$82.91
10	0.00	$51.88	$12.25	$23.00	$0.00	$0.00	$87.13

Apprentice: SPRINKLER FITTER

Effective Date: 1/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	0.00	$22.70	$13.45	$13.84	$0.00	$0.00	$49.99
2	0.00	$25.94	$13.45	$14.75	$0.00	$0.00	$54.14
3	0.00	$29.18	$13.45	$15.67	$0.00	$0.00	$58.30
4	0.00	$32.43	$13.45	$16.57	$0.00	$0.00	$62.45
5	0.00	$35.67	$13.45	$17.49	$0.00	$0.00	$66.61
6	0.00	$38.91	$13.45	$18.40	$0.00	$0.00	$70.76
7	0.00	$42.15	$13.45	$19.32	$0.00	$0.00	$74.92
8	0.00	$45.40	$13.45	$20.22	$0.00	$0.00	$79.07
9	0.00	$48.64	$13.45	$21.15	$0.00	$0.00	$83.24
10	0.00	$51.88	$13.45	$22.05	$0.00	$0.00	$87.38

Apprentice Notes

Apprentice entered prior 9/30/10:

Apprentice to Journeyworker Ratio: 1:3

STEAM BOILER OPERATOR	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
OPERATING ENGINEERS LOCAL 4	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
OPERATING ENGINEERS LOCAL 4	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

TAMPERS, SELF-PROPELLED OR TRACTOR DRAWN	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
OPERATING ENGINEERS LOCAL 4	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
OPERATING ENGINEERS LOCAL 4	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

TELECOMMUNICATION TECHNICIAN	9/1/2025	$42.52	$12.00	$12.05	$3.25	$0.00	$69.82
TELECOMMUNICATION TECHNICIAN	9/1/2026	$44.41	$12.25	$12.59	$3.50	$0.00	$72.75
ELECTRICIANS LOCAL 223	9/1/2027	$46.51	$12.50	$13.18	$3.75	$0.00	$75.94
ELECTRICIANS LOCAL 223							

For apprentice rates and ratios see "Apprentice- ELECTRICIAN"

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
TERRAZZO FINISHERS BRICKLAYERS LOCAL 3 BRICKLAYERS LOCAL 3 - MARBLE & TILE	8/1/2025	$66.89	$11.49	$15.57	$8.02	$0.00	$101.97
	2/1/2026	$68.24	$11.49	$15.57	$8.02	$0.00	$103.32
	8/1/2026	$70.44	$11.49	$15.57	$8.02	$0.00	$105.52
	2/1/2027	$71.84	$11.49	$15.57	$8.02	$0.00	$106.92

Apprentice: TERRAZZO FINISHERS

Effective Date: 8/1/2025

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$33.45	$11.49	$15.57	$8.02	$0.00	$68.53
2	60.00	$40.13	$11.49	$15.57	$8.02	$0.00	$75.21
3	70.00	$46.82	$11.49	$15.57	$8.02	$0.00	$81.90
4	80.00	$53.51	$11.49	$15.57	$8.02	$0.00	$88.59
5	90.00	$60.20	$11.49	$15.57	$8.02	$0.00	$95.28

Apprentice: TERRAZZO FINISHERS

Effective Date: 2/1/2026

Step	Percent	Apprentice Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
1	50.00	$34.12	$11.49	$15.57	$8.02	$0.00	$69.20
2	60.00	$40.94	$11.49	$15.57	$8.02	$0.00	$76.02
3	70.00	$47.77	$11.49	$15.57	$8.02	$0.00	$82.85
4	80.00	$54.59	$11.49	$15.57	$8.02	$0.00	$89.67
5	90.00	$61.42	$11.49	$15.57	$8.02	$0.00	$96.50

Apprentice to Journeyworker Ratio: 1:5

TEST BORING DRILLER LABORERS LABORERS - FOUNDATION AND MARINE	12/1/2025	$52.70	$10.15	$9.50	$9.80	$0.00	$82.15
	6/1/2026	$54.25	$10.15	$9.50	$9.80	$0.00	$83.70
	12/1/2026	$55.75	$10.15	$9.50	$9.80	$0.00	$85.20
For apprentice rates see "Apprentice- LABORER"							
TEST BORING DRILLER HELPER LABORERS LABORERS - FOUNDATION AND MARINE	12/1/2025	$48.82	$10.15	$9.50	$9.80	$0.00	$78.27
	6/1/2026	$50.37	$10.15	$9.50	$9.80	$0.00	$79.82
	12/1/2026	$51.87	$10.15	$9.50	$9.80	$0.00	$81.32
For apprentice rates see "Apprentice- LABORER"							
TEST BORING LABORER LABORERS LABORERS - FOUNDATION AND MARINE	12/1/2025	$48.70	$10.15	$9.50	$9.80	$0.00	$78.15
	6/1/2026	$50.25	$10.15	$9.50	$9.80	$0.00	$79.70
	12/1/2026	$51.75	$10.15	$9.50	$9.80	$0.00	$81.20
For apprentice rates see "Apprentice- LABORER"							
TRACTORS/PORTABLE STEAM GENERATORS OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$58.62	$16.05	$13.25	$3.25	$0.00	$91.17
	6/1/2026	$59.90	$16.05	$13.25	$3.25	$0.00	$92.45
	12/1/2026	$61.34	$16.05	$13.25	$3.25	$0.00	$93.89
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							
TRAILERS FOR EARTH MOVING EQUIPMENT	12/1/2025	$41.82	$15.57	$21.78	$0.00	$0.00	$79.17

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	1/1/2026	$41.82	$16.17	$21.78	$0.00	$0.00	$79.77
	6/1/2026	$42.82	$16.17	$21.78	$0.00	$0.00	$80.77
	12/1/2026	$42.82	$16.17	$23.52	$0.00	$0.00	$82.51
	1/1/2027	$42.82	$16.77	$23.52	$0.00	$0.00	$83.11
TUNNEL WORK - COMPRESSED AIR LABORERS LABORERS (COMPRESSED AIR)	12/1/2025	$60.93	$10.15	$9.50	$10.25	$0.00	$90.83
	6/1/2026	$62.48	$10.15	$9.50	$10.25	$0.00	$92.38
	12/1/2026	$63.98	$10.15	$9.50	$10.25	$0.00	$93.88
For apprentice rates see "Apprentice- LABORER"							
TUNNEL WORK - COMPRESSED AIR (HAZ. WASTE) LABORERS LABORERS (COMPRESSED AIR)	12/1/2025	$62.93	$10.15	$9.50	$10.25	$0.00	$92.83
	6/1/2026	$64.48	$10.15	$9.50	$10.25	$0.00	$94.38
	12/1/2026	$65.98	$10.15	$9.50	$10.25	$0.00	$95.88
For apprentice rates see "Apprentice- LABORER"							
TUNNEL WORK - FREE AIR LABORERS LABORERS (FREE AIR TUNNEL)	12/1/2025	$53.00	$10.15	$9.50	$10.25	$0.00	$82.90
	6/1/2026	$54.55	$10.15	$9.50	$10.25	$0.00	$84.45
	12/1/2026	$56.05	$10.15	$9.50	$10.25	$0.00	$85.95
For apprentice rates see "Apprentice- LABORER"							
TUNNEL WORK - FREE AIR (HAZ. WASTE) LABORERS LABORERS (FREE AIR TUNNEL)	12/1/2025	$55.00	$10.15	$9.50	$10.25	$0.00	$84.90
	6/1/2026	$56.55	$10.15	$9.50	$10.25	$0.00	$86.45
	12/1/2026	$58.05	$10.15	$9.50	$10.25	$0.00	$87.95
For apprentice rates see "Apprentice- LABORER"							
VAC-HAUL TEAMSTERS JOINT COUNCIL NO. 10 TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/1/2025	$41.24	$15.57	$21.78	$0.00	$0.00	$78.59
	1/1/2026	$41.24	$16.17	$21.78	$0.00	$0.00	$79.19
	6/1/2026	$42.24	$16.17	$21.78	$0.00	$0.00	$80.19
	12/1/2026	$42.24	$16.17	$23.52	$0.00	$0.00	$81.93
	1/1/2027	$42.24	$16.77	$23.52	$0.00	$0.00	$82.53
WAGON DRILL OPERATOR LABORERS LABORERS - ZONE 2	12/1/2025	$41.47	$10.15	$9.50	$9.11	$0.00	$70.23
	6/1/2026	$42.91	$10.15	$9.50	$9.11	$0.00	$71.67
	12/1/2026	$44.35	$10.15	$9.50	$9.11	$0.00	$73.11
	6/1/2027	$45.80	$10.15	$9.50	$9.11	$0.00	$74.56
	12/1/2027	$47.25	$10.15	$9.50	$9.11	$0.00	$76.01
	6/1/2028	$48.75	$10.15	$9.50	$9.11	$0.00	$77.51
	12/1/2028	$50.25	$10.15	$9.50	$9.11	$0.00	$79.01
For apprentice rates see "Apprentice- LABORER"							
WAGON DRILL OPERATOR (HEAVY & HIGHWAY) LABORERS LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/1/2025	$41.47	$10.15	$9.50	$9.21	$0.00	$70.33
	6/1/2026	$42.91	$10.15	$9.50	$9.21	$0.00	$71.77
	12/1/2026	$44.35	$10.15	$9.50	$9.21	$0.00	$73.21
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)"							
WASTE WATER PUMP OPERATOR OPERATING ENGINEERS LOCAL 4 OPERATING ENGINEERS LOCAL 4	12/1/2025	$59.28	$16.05	$13.25	$3.25	$0.00	$91.83
	6/1/2026	$60.58	$16.05	$13.25	$3.25	$0.00	$93.13
	12/1/2026	$62.03	$16.05	$13.25	$3.25	$0.00	$94.58
For apprentice rates see "Apprentice- OPERATING ENGINEERS"							

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Construction

Classification	Effective Date	Base Wage	Health	Pension	Annuity	Supplemental Unemployment	Total Rate
WATER METER INSTALLER PLUMBERS & PIPEFITTERS LOCAL 51 PLUMBERS & PIPEFITTERS LOCAL 51	8/25/2025	$55.24	$10.80	$16.80	$4.60	$0.00	$87.44

For apprentice rates see "Apprentice- PLUMBER/PIPEFITTER" or "PLUMBER/GASFITTER"

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Additional Apprentice Information

All apprentices must be registered with the Division of Apprenticeship Training(DAS) in accordance with M.G.L.c. 23, §§ 11E-11L. Minimum wage rates for apprentices employed on public works projects are listed above as a percentage of the hourly prevailing wage rate established by the Commissioner under the provisions of M.G.L.c. 149, §§ 26-27D.

Apprentice ratios are established by DAS pursuant to M.G.L.c. 23, §§ 11E-11L. Ratios are expressed as the allowable number of apprentices to journeymen or fraction thereof, unless otherwise specified. The ratios listed herein have been taken from relevant private collective bargaining agreements(CBAs) and are provided for illustrative purposes only. They have not been independently verified as being accurate or continuing to be accurate.

Parties having questions regarding what ratio to use should contact DAS.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Barnstable County

Regional Government of Cape Cod
Purchasing Department
Jennifer L.V. Frates, Chief Procurement Officer

Addendum NO. 1
January 12, 2026

To all Bidders on the Project titled:
Bid # 8110
Road Construction Items and Materials
Barnstable County

Reference Contract Documents (drawings and specifications) dated December 31, 2025

The attention of bidders submitting proposals for the above subject project is called to the following addendum to the specifications and drawings. The items set forth herein, whether of omission, addition, substitution, or clarifications are all to be included in and form a part of the proposal submitted.

QUESTIONS:

1. **I don't see the following items on your prequalified list, 9, 10, 21, 22, 123, 124, 126. Does this mean those items don't require prequalification? If they do require prequalification can you provide the category and the amount? Thank you.**

   Items that require a prequalification that were submitted by the Towns are listed on the main page of the bid opportunity and noted on the bid sheet.

2. **In order to determine if my company requires a MassDOT Prequalification waiver to bid some of the items on this bid I need to know how much the items that require MassDOT Prequal are valued at (monetary) and which MassDOT category they are listed under, for instance Crack Sealing or Pavement-Surfacing, or Pavement-Milling and Cold Planing, or Pavement - Reclamation, etc. This information is required on the MassDOT Waiver Request form which MassDOT requires a Contractor submit at least 2 weeks prior to a bid opening. They meet once a week to approve waivers. Would it be possible to receive this information asap so that I can submit any needed waiver in a timely manner? Thank you.**

   This information is listed on the main page of the bid opportunity. https://barnstablecounty.bonfirehub.com/opportunities/209406. Also the total value is available on the lists provided by MassDOT that are available for download on the list of documents.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

3. **What is the completion date police details are paid for by each respective town bid bond is made out to Barnstable County possible to receive previous years bid results?**

   The contract term for this bid is April 1, 2026 through March 31, 2027, with one option to renew. There is no single project completion date associated with this solicitation. Rather, individual Towns will coordinate directly with the awarded vendor(s) to establish project-specific schedules and completion dates based on their individual needs.

   The bid bond shall be made payable to Barnstable County.

   Previous bid results are available on the County's e-bidding platform under "Past Opportunities" at: https://barnstablecounty.bonfirehub.com

4. **On line #2-62 Drainage Structure Cleaning by Clamshell (w/disposal) you have 25000 for a quantity. Is this accurate?**

   Item #2-62 should be 2500. Due to this change the bid table has also been updated to reflect the corrected totals. ***Bidders must redownload the revised bid table and use the revised version in the final submission.***

5. **Due to the recent Federal Mandate on W/MBE Programs, is the requirement to use W/MBE participation still a requirement for the Barnstable County Road Construction Items and Materials Bid.**

   There are currently no M/WBE participation requirements associated with the Road Construction Items and Materials bid. At this time, no participating Town has identified M/WBE goals or requirements for items under this bid, nor has MassDOT imposed any such requirements. If M/WBE participation requirements are later determined to be applicable due to specific funding sources or regulatory conditions, such requirements would be addressed by the applicable Town through a separate process.

CHANGES:

Under the Special Provisions, Pricing Adjustments section, the MassDOT website has released the pricing for the month of December 2025 as follows:

Base Bid Price Liquid Asphalt (Ton): $625.00
Base Bid Price Diesel (Gallon): $2.724
Base Bid Price Gasoline (Gallon): $2.152

All other portions of the Bid Documents remain unchanged. NOTE: THE BID SUBMISSION DEADLINE DATE HAS NOT CHANGED.

Please be reminded to acknowledge this Addendum on the bid forms.

--- End of Addendum No. 1 ---

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Special Provisions
Table of Contents

SCOPE OF WORK
WORK SCHEDULE
OSHA REQUIREMENT
PROGRESS OF WORK
CONTRACT DOCUMENTS IN THE FIELD
POLICE SERVICES
PUBLIC SAFETY AND CONVENIENCE
CLEANUP
EMERGENCY CONTACTS
DIGSAFE
PROTECTION OF UTILITIES AND PROPERTY
PROVISIONS FOR TRAVEL AND PROSECUTION OF THE WORK
WORK DONE BY OTHERS
DISPOSAL OF SURPLUS MATERIALS
COMPACTION
PROPERTY BOUNDS
WEIGHING
DELIVERY OF ROADWAY MATERIALS
PRICE ADJUSTMENTS
TWO LOWEST BIDDERS
TIED BIDDERS
MASSDOT PREQUALIFICATION
CONSTRUCTION ITEMS (#1 - #23)
MISCELLANEOUS PUBLIC WORKS MATERIALS (#100 - # 126)
ROADWAY MATERIALS (#200 - #218)

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

SCOPE OF WORK

Barnstable County on behalf of the Towns in the County requests bids from qualified contractors for Miscellaneous Public Works and Roadway Materials.

The Work under this Contract consists of providing various materials as described herein to the Towns of Barnstable, Bourne, Brewster, Chatham, Dennis, Falmouth, Orleans, Sandwich, Wellfleet, and Yarmouth an Agreement with the County of Barnstable.

All Work done under this Contract shall be in conformance with the 1988 Massachusetts Highway Department (MassDOT) Standard Specifications for Highways and Bridges, the Supplemental Specifications, the 2005 Standard Special Provisions, the 2010 Construction Standard Details, and the 2009 Manual on Uniform Traffic Control Devices, all as amended, and these Special Provisions. The General Conditions and Special Provisions shall take precedence over the General Requirements of the Standard Specifications.

Bidders may wish to contact each Town to obtain actual quantities purchased during prior years. Bidders may bid on any or all items for any or all Towns. Bid selection will be by each item and will be based on the lowest, qualified, responsible, and responsive bid for each item for each Town.

WORK SCHEDULE

The Contractor shall commence Work within ten (10) working days of receiving a Notice to Proceed from the Owner. If the Contractor cannot begin work within the ten (10) working days, that Owner may order such services from such contractors as are available, and the Contractor shall reimburse that Owner for all expenses incurred above the Contract Price. When needing work completed for any items that will be awarded to the two (2) lowest bidders, each Town shall first forward by e-mail or fax a Notice to Proceed to the lower of the two lowest bidders. If the lowest bidder does not schedule the work requested within forty-eight (48) working hours of receiving the Notice to Proceed and/or cannot begin (and remain at) work within ten (10) working days, then the Town shall have the right to forward a Notice to Proceed to the second low bidder.

Work is restricted to a normal eight-hour day, five-day week, with Contractor and all subcontractors working on the same shift.

No Work shall be done on this Contract on Saturdays, Sundays or holidays or on the day before or the day after a long weekend which involves a holiday without prior approval by the specific Town or County.

OSHA REQUIREMENT

Any employee found on the worksite without documentation of the successful completion of a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration shall be subject to immediate removal. OSHA certifications must be submitted with the certified payrolls for all workers during the first week they work on a project.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

PROGRESS OF WORK

The Contractor shall promptly start and continue actual construction work under this Contract with the necessary equipment to properly execute and complete this Contract in the specified time. No cessation of

Contractor's operations will be allowed without the approval of the Engineer. The rate of progress shall be satisfactory to that Town and the Engineer. The Contractor shall furnish to the Engineer a schedule for the Work prior to the start of construction.

CONTRACT DOCUMENTS IN THE FIELD

The Contractor shall keep a copy of the Contract Documents at the work site at all times while work is being performed and said copy is to be available to those in charge of work.

POLICE SERVICES

Each Town shall provide all Town police services at no cost to the Contractor to direct traffic when such protection is required by that Town's Police Department. The Contractor shall be solely responsible for contacting and scheduling police services with the Police Department. If the Contractor must cancel police services, he must do so within the time limits set by the Police Department. If the Contractor does not cancel police services within the time limits, then Contractor shall be responsible to promptly pay the minimum required amount.

PUBLIC SAFETY AND CONVENIENCE

The Contractor shall be required without additional compensation to provide safe and convenient access to all abutters during the prosecution of the Work.

No excavation shall be left open during non-working hours.

MSDS sheets and information shall be available on site and copies submitted to a Town as requested.

NECESSARY ACCESS FOR FIRE APPARATUS AND OTHER EMERGENCY VEHICLES SHALL BE MAINTAINED AT ALL TIMES. THE CONTRACTOR SHALL COORDINATE WITH THE POLICE AND FIRE DEPARTMENTS AT ALL TIMES REGARDING ACCESS.

For the protection of life and property, all backfill operations shall follow closely behind completed work. The Contractor shall insure that no excavation be left open, unguarded, or water filled during any period of time when work is not actually in progress. It is the purpose and intent that all excavations and backfill, including consolidation operations, and temporary surfacing within an area be accomplished expeditiously before proceeding to other work areas.

Contractor shall comply with all applicable Laws, regulations and Guidelines of any public body (example: OSHA, DIGSAFE, MASSDOT Work Zone Safety Guidelines, Police) having jurisdiction for the safety of persons or property or to protect them from damage, injury or loss; and shall erect and maintain all necessary signs/ safeguards for such safety and protection at no extra cost to the Owner. See General Conditions also.

CLEANUP

Cleanup shall be done on a daily basis. At the end of each working period, the Contractor shall completely backfill all holes and trenches, and remove all equipment from the traveled way. The

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Contractor shall ensure that all safety marking and warning devices are satisfactorily in place prior to leaving any job.

During the course of the Work, the Contractor shall keep the site of his operations in as clean and neat condition as is possible. He shall dispose of all residue resulting from the construction work and, at the

conclusion of the work, he shall remove and haul away any surplus excavation, broken pavement, lumber,

equipment, temporary structures, and any other refuse remaining from the construction operations, and shall leave the entire site of the work in a neat and orderly condition.

Sweeping and cleaning of surfaces beyond the limits of the Project to clean up material caused by spillage or vehicular tracking during the various phases of the work shall be considered as incidental to the Work being performed under the Contract and there will be no additional compensation.

EMERGENCY CONTACTS

The Contractor shall maintain a 24-hour, 7-day a week telephone service and a local facility to handle emergency requirements such as settled trenches, clogged drains, rain damage, work zone safety issues, etc. A list of personnel (minimum of two) and their telephone numbers shall be submitted to the Engineer, the Highway Superintendent (or his designee), the Public Works Director and to the local Police and Fire Departments. This requirement shall apply during the entire length of the Project. or Service for each Town where work is being completed. This list shall be submitted on the Contractor's letterhead and shall state that

should an emergency arise during the implementation of this Project or Service, these people are to be contacted. The Contractor shall submit this letter to the Engineer prior to initiating construction. The Highway Superintendent for each Town or his designee has the right to determine whether or not an emergency exists and to require Contractor to promptly resolve the emergency at no cost to that Town. If Contractor can not respond in a timely manner as determined by the Highway Superintendent, the Town has the right to complete the necessary work and to bill Contractor for that work.

DIGSAFE

The Contractor shall notify "Mass. DIG SAFE" and the Local Water Department or District and procure a DIG SAFE number of each location prior to disturbing ground in any way.

"DIG-SAFE" Call Center: Telephone 1-888-344-7233

Commonwealth Electric has a policy regarding the location of electric utilities. Dig-Safe can no longer be relied upon to locate electric utilities that are "privately" owned. This can include electric cables located in Public ways that run from utility poles to buildings. It is therefore incumbent upon Contractor to ascertain if any electric cables are located in any area prior to excavation. This will be done at Contractor's expense.

The Contractor shall make his own investigation to assure that no damage to existing structures, drainage lines, traffic signal conduits, and other utilities will occur as a result of his operations

PROTECTION OF UTILITIES AND PROPERTY

The Contractor, in constructing or installing facilities alongside or near sanitary sewers, storm drains, water or gas pipes, electric or telephone conduits, poles, sidewalks, walls, vaults or other structures

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

shall, at his expense, sustain them securely in place, cooperating with the officers and agents of the various utility companies and municipal departments which control them, so that the services of these structures shall be maintained. The Contractor shall also be responsible for the repair or replacement, at his own expense, of any damage to such structures caused by his acts or neglect, and shall leave them in the same condition as they existed prior to commencement of the Work. In case of damage to utilities, the Contractor shall promptly notify the utility owner and shall, if requested by the Engineer, furnish labor and equipment to work temporarily under the owner's direction in providing access to the utility. Pipes or other structures damaged by the operation of the Contractor may be repaired by the municipality or by utility owner which suffers the loss. The cost of such repairs shall be borne by the Contractor, without compensation therefor.

If, as the Work progresses, it is found that any of the utility structures are so placed as to render it impracticable, in the judgment of the Engineer, to do the Work called for under this Contract, the Contractor shall protect and maintain the services in such utilities and structures and the Engineer will, as soon thereafter as reasonable, cause the position of the utilities to be changed or take such other actions deemed suitable and proper.

If live service connections are to be interrupted by excavations of any kind, the Contractor shall not break the service until new services are provided. Abandoned services shall be plugged off or otherwise made secure.

Full compensation for furnishing all labor, materials, tools, equipment and incidentals for doing all the work involved in protecting or repairing property as specified in this section, shall be considered included in the prices paid for the various Contract items of Work and no additional compensation will be allowed therefor.

PROVISIONS FOR TRAVEL AND PROSECUTION OF THE WORK

For the items that require traffic control, the Contractor shall supply and use traffic control devices, positioning and methodology, conforming with the Manual on Uniform Traffic Control Devices (MUTCD) and MASSDOT Work Zone Safety Guidelines at no additional cost to any Town. Traffic control devices required only during working hour operations shall be removed at the end of each working day. Signs having messages that are irrelevant to normal traffic conditions shall be removed or properly covered at the end of each work period. Signs shall be kept clean at all times and legends shall be distinctive and unmarred.

Particular care should be taken to establish and maintain methods and procedures which will not create unnecessary or unusual hazards to public safety.

WORK DONE BY OTHERS

Relocation and/or resetting to new grades of all private utilities, including utility poles, made necessary by the construction of this Project, will be accomplished by the respective utility companies.

DISPOSAL OF SURPLUS MATERIALS

All materials not required or needed for use on the Project, and not required to be removed and stacked, shall become the property of the CONTRACTOR and shall be removed from the site and legally disposed of. No separate payment will be made for this Work, but all costs in connection therewith shall be included in the prices bid for various Contract items.

COMPACTION

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Compaction of filled areas under pavement (no matter what type of fill material) shall be completed in 6" lifts. Compaction of filled areas elsewhere (no matter what type of fill material) shall be completed in 12" lifts. Appropriate compaction equipment shall be used.

PROPERTY BOUNDS

Any bounds or markers flagged by a Town and disturbed by the Contractor shall be replaced utilizing the services of a Registered Land Surveyor. The cost of replacing flagged bounds or markers disturbed by the Contractor's operations shall be at the Contractor's expense.

WEIGHING

All materials requiring payment by weight shall be weighed at a certified scale prior to delivery and the weigh slips shall be delivered to and signed by a Town representative. Each Town may provide use of its scale and require gross weights and vehicle tare weights verified at time of delivery.

DELIVERY OF ROADWAY MATERIALS

The vendor shall furnish manufacturer's certification that the materials conform to the specifications. All material shall be delivered to and off loaded at each Town's Highway Division yard or to a mutually agreeable site, except Hot Mix Asphalt which shall be loaded on Town trucks at the plant. All costs of transportation shall be included in the prices bid. If, at any time, the materials delivered are found to be sub- standard, the vendor shall be responsible for removing the offending material at their cost, within ten (10) working days after receiving notification from the Town.

All deliveries shall be made during each Town's normal business hours, Monday through Friday (except legal holidays), and in the presence of an authorized Town employee or agent.

Delivery shall be immediate unless the item is out of stock or not normally stocked, then the vendor shall notify the Town and shall make delivery within ten (10) days.

If at any time the vendor is unable to furnish materials or services as ordered by a Town:

* The vendor shall be obligated to obtain delivery from another supplier and will in tum invoice the Town at the price specified in the Contract, or
* The Town may order such materials or services from such places as are available, and the vendor shall reimburse the Town for all expenses incurred above the Contract price.

If services of the vendor are subsequently deemed to be unsatisfactory to any Town and/or are in violation of these specifications, a Town shall notify the said vendor in writing. If mutually agreeable arrangements cannot be achieved between the Town and the vendor, the terms of the Contract for that Town will be terminated. Notice of termination will be in writing and notification will be sent by registered or certified mail. Termination will become effective three (3) days after mailing said notification. Termination of a Contract by any Town shall not invalidate or alter the terms of a similar Contract with any other Town.

The vendor receiving an award shall, at no expense to any Town, adhere to Massachusetts General Law Chapter 111F - "Right to Know Law" as it shall apply to the items contained in the award notice.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

PRICE ADJUSTMENTS

The Massachusetts Department of Transportation (MassDOT) method for calculating price adjustments due to cost fluctuations in liquid asphalt, Portland cement, diesel fuel, gasoline, and structural steel shall apply to this bid.

Liquid asphalt (variance from base price of 5% or more) adjustment will be allowed for Bid Item Numbers: 1-4, and 9-16, 18, 19, 21, 22, 125 & 126. Diesel fuel (variance from base price of 5% or more) adjustment will be allowed for Bid Item Numbers: 1-4, and 9-16, 18, 19, 21 and 22. Gasoline (variance from base price of 5% or more) adjustment will be allowed for Bid Item Numbers: 5-8.

MASSDOT procedures shall be used to determine the adjustments, except as noted herein. The price adjustments shall be based on the difference between the "base price" and the "order price". The "base price" shall be determined from the most recent MASSDOT published liquid asphalt, diesel fuel, gasoline, Portland cement, or steel price that precedes the bid date. The "order price" shall be the most recent published MASSDOT liquid asphalt, diesel fuel, gasoline, Portland cement, or steel price available on the day that the item is placed. A Town ordering work shall be provided with only one (1) invoice for each project. This invoice shall include the name of the item(s) installed, the quantity installed, the original unit bid price(s), and the price adjustment(s) (including back-up information such as calculations, MASSDOT publication) for each project. A second invoice for the adjustment(s) submitted at a later date shall not be acceptable. The base bid pricing shall be the price posted on the MassDOT Website for the month of ***December 2025*** as follows:

Base Bid Price Liquid Asphalt (Ton): 625.00
Base Bid Price Diesel (Gallon): TBD
Base Bid Price Gasoline (Gallon): TBD

TWO LOWEST BIDDERS

It is the intent to award a contract to the two (2) lowest, qualified, responsible, and responsive bidders for Bid Items 1-7, 18, 19, and 115 to 122. When needing work completed for each of these items, each Town shall first forward by e-mail or fax a Notice to Proceed to the lower of the two lowest bidders. If the lowest bidder does not schedule the work requested within forty-eight (48) working hours of receiving the Notice to Proceed and/or cannot begin (and remain at) work within ten (10) working days, then the Town shall have the right to forward a Notice to Proceed to the second low bidder.

TIED BIDS

In the case of tied bids, the County tied bid policy will be used to determine the awarded bidder.

MASSDOT PREQUALIFICATION

The Towns presently intend to use Chapter 90 (State) funds to finance some of the bid items. Items noted in the Bid Table require vendors to be prequalified by Massachusetts Department of Transportation (MassDOT). Vendors who are not on the MA Highway list of pre-qualified bidders cannot be awarded bids for these items. Only bidders whose companies name appears on the MassDOT list of certified bidders will be awarded bids for the items identified on the bid form.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

NOTE: For all paving, no separate payments will be made to mobilize to different locations.

Item No. 1 : HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (OVER 400 TONS PER DAY)

The Work shall include the furnishing and placement of top course, binder course, and/or levelling course for new pavements and existing pavement overlays by self-powered mechanical pavers. Any Town may specify any job - mix formula from Section M3.11.00 of the Standard Specifications.

A tack coat of liquid bituminous material (RS-1 or equal) shall be furnished and applied to existing pavements at the rate of 0.10 gallon per square yard immediately prior to placement of pavement overlay and the cost shall be included in the unit price bid. The tack coat shall be machine applied and sprayed uniformly. Hand application will not be allowed.

When bituminous concrete berm (Cape Cod berm) is required, the Work shall also include the berm construction and the cost shall be included in the unit price bid.

If requested by the Town, Contractor shall provide and install Mass Highway approved temporary pavement markings at no additional cost to the Town.

The measured quantity will be paid for at the Contract unit price per ton, which price shall include all labor, materials, equipment, mobilization (may include multiple locations) and incidental costs required to complete the Work. Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Item No. 1A : HOT MIX ASPHALT PAVEMENT, MACHINE PLACED (UNDER 400 TONS PER DAY)

The Work shall include the furnishing and placement of top course, binder course, and/or levelling course for new pavements and existing pavement overlays by self-powered mechanical pavers. Any Town may specify any job - mix formula from Section M3.11.00 of the Standard Specifications.

A tack coat of liquid bituminous material (RS-1 or equal) shall be furnished and applied to existing pavements at the rate of 0.10 gallon per square yard immediately prior to placement of pavement overlay and the cost shall be included in the unit price bid. The tack coat shall be machine applied and sprayed uniformly. Hand application will not be allowed.

When bituminous concrete berm (Cape Cod berm) is required, the Work shall also include the berm construction and the cost shall be included in the unit price bid.

If requested by the Town, Contractor shall provide and install Mass Highway approved temporary pavement markings at no additional cost to the Town.

The measured quantity will be paid for at the Contract unit price per ton, which price shall include all labor, materials, equipment, mobilization (may include multiple locations) and incidental costs required to complete the Work. Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Item Nos. 2 & 3: HOT MIX ASPHALT PAVEMENT, HANDWORK

The Work shall include the furnishing and placement of top course and binder course material by mechanical and hand methods for sidewalk resurfacing, berm, driveway, aprons, and other construction. Any Town may specify any job - mix formula from Section M3.11.00 of the Standard Specifications.

A tack coat of liquid bituminous material (RS-1 or equal) shall be applied to existing pavements at the rate of 0.10 gallon per square yard immediately prior to placement of pavement and the cost shall be included in the unit price bid.

The measured quantity will be paid for at the Contract unit price per ton, which price shall include all labor, materials, equipment, and incidental costs required to complete the Work. Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Item No. 4: HOT MIX ASPHALT SHIM

This work consists of the skilled placement of hot mix asphalt in irregularly shaped areas of various thicknesses in order to restore roadway profiles or cross-section. Typical HMA placement will be where the shimming will vary in thickness form 0.0" to 2". The contractor shall be prepared to drag the screed of their

paver and rake edges as necessary to place the mix in areas designated by the town. To obtain this rate mix placement at multiple locations may be required.
Mix and mix placement shall be in conformance with Mass DOT *Standard specifications for Highways and Bridges.*

The intent of this item is that it is to be used independent of any other hot-mix machine placed item work for the same location and timeframe. Any shimming done prior to machine work or leveling courses shall be paid for per the unit price for hot mix asphalt.

Responsibilities of the Town:

- Pre-sweep
- Traffic control
- Temporary pavement markings
- Project supervision and plan preparation when needed.

Responsibilities of the Contractor:

- Mark out areas for leveling based on directions from the town – i.e. the town will give a budget in tons for each road and will point out deficiencies/problem areas such as puddles, roughness, or plow hazards. The marking is subject to approval by the town.
- Removal of fines- It shall be noted that there may be residual fines left in depressions by the town's sweeper. The contractor shall come equipped with a portable blower capable of removing fines from the marked areas. This equipment shall also be capable of removing minor puddles and drying pavement if necessary.
- Tack – All marked out areas shall be tacked with RS-1 emulsion applied at a uniform rate of 0.05 gallons per square yard with pressurized asphalt distributer
- Mix – Mass DOT Dense Top mix.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

- Mix placement – Mix shall be placed with a paver that has performance specifications similar to a Lee Boy 8500. The paver shall be adjustable from 8 – 15 feet and be able to place mix on patches narrower than 8 feet as marked. The paver shall break in the middle to allow crown to be placed in the road if necessary. The paver shall have a vibratory screed. Spreading by grader or loader is not acceptable. All structures shall sprayed/covered and uncovered after the mix is placed. The contractor shall have adequate and competent staff to rake/lute/shovel as necessary before the mix is compacted. Multiple lifts may be required.
- Compaction – Contractor shall compact mix with a vibratory roller with a minimum rating of 8 tons.

  Measurement and Payment
  Hot mix asphalt shim shall be measured for payment by the ton of mix placed and accepted by the Town and shall be paid at the contract unit price per ton which shall include all labor, materials, equipment and incidental costs required to satisfactorily complete the work. Including cleanup and tack.

Item No. 5: PAVEMENT RECLAMATION (Including FG&C)

The Work under this item shall conform to the provisions of Section 170 & 403 of the Standard Specifications and the following:

Fine grading and compacting (FG&C) of the subgrade shall be included in the work for this item. If requested by a Town, the Contractor shall negotiate a reasonable additional cost for related work (e.g., excavating and hauling away excess materials).

The measured quantity will be paid for at the Contract unit price per square yard, which price shall include all labor, materials, equipment, fine grading, compacting, and incidental costs required to complete the Work.

Item No. 6: PAVEMENT RECLAMATION (Including FG&C and Calcium Chloride)

The Work under this item shall conform to the provisions of Section 170 & 403 of the Standard Specifications and the following:
Fine grading and compacting (FG&C) of the subgrade, and adding and mixing liquid calcium chloride to the pulverized mass shall be included in the work for this item. If requested by a Town, the Contractor shall negotiate a reasonable additional cost for related work (e.g., excavating and hauling away excess materials).

The calcium chloride solution shall be provided by the manufacturer as a true solution and shall not be reconstituted from flake calcium chloride. The calcium shall meet the following material specifications (see ASTM Designation D98; AASHTO-M144):

Calcium Chloride	35% +/-1%
Alkali Chloride as NaCl	2% max.
Magnesium as MgCl	0.1%

Typical (Pounds per gallon)

Calcium Chloride	5.05

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Sodium Chloride	0.2
Magnesium Chloride	0.004
Calcium Sulfate	0.004
Water	6.002
	11.26

The measured quantity will be paid for at the Contract unit price per square yard, which price shall include all labor, materials, equipment, fine grading, compacting, and incidental costs required to complete the Work.

Item No. 7: BITUMINOUS CONCRETE EXCAVATION BY COLD PLANER

The Work under this item shall conform to the relevant provisions of Section 120 of the Standard Specifications and the following:

The work shall include the cold planing of existing bituminous concrete pavement surface to various depths to shape the pavement cross-section (crown or super elevation), to meet driveways, and/or to produce a uniform surface for the application of the pavement surfacing.

Pavement areas abutting utility structures and other areas which cannot be planed by the principal cold planing machine shall be excavated with smaller mechanical cold planing equipment designed for this purpose or by manual methods at no additional cost to any Town.

The machine shall be capable of being operated at speeds from 10 to 40 feet per minute and designed so that the operator can at all times observe the planing operation without leaving his control area. Pneumatic rubber-tire mounted equipment shall be used only for trimming and edging operations.

The equipment furnished by the Contractor shall be maintained in good repair at all times.

No pavement cuttings shall remain on the project at the end of each work period. The pavement cuttings shall become the property of the Town and the Contractor shall be responsible to remove, haul, and deposit the pavement cuttings at no additional cost to a site as directed by the Town.

The measured quantity will be paid for at the Contract unit price per square yard, which price shall include all labor, materials, equipment, removal, hauling, and incidental costs required to complete the Work.

Item No. 8: COLD PLANED (MILLED) PAVING JOINTS

The work shall include the cold planing of existing bituminous concrete pavement surface to create key ways (paving joints) for the purpose of overlaying pavement. All work is to be performed no more than forty eight (48) hours prior to the scheduled start of paving.

The machine shall be capable of milling to a depth of two (2) inches and a minimum width of twenty-four (24) inches. The cutter head must be able to rotate 15 degrees to provide a beveled cut. All key ways shall be one (1) to two (2) inches in depth and twenty-four (24) inches to forty-eight (48) inches in width at the discretion of the Town. The Contractor is responsible milling and clean up of all excavated materials.

The equipment furnished by the Contractor shall be maintained in good repair at all times.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

No pavement cuttings shall remain on the project at the end of each work period. The pavement cuttings shall become the property of the Town and the Contractor shall be responsible to remove, haul, and deposit the pavement cuttings at no additional cost to a site as directed by the Town.

The measured quantity will be paid for at the Contract unit price per square yard, which price shall include all labor, materials, equipment, removal, hauling, and incidental costs required to complete the Work.

Item Nos. 9 & 10: MICROSURFACING (ONE AND TWO LIFTS)

The Work under this item shall conform to the relevant provisions of the Standard Specifications and the following:

Description

Microsurfacing is a tough and durable thin overlay material which can restore the original service properties to worn but structurally sound pavements. Its properties are based on a blend of select crushed aggregate and a chemical formulation of asphalt cement, cationic emulsifiers, adhesives, and latex. This specification covers all materials, equipment, construction and application procedures for rutfilling and/or surfacing of existing paved surfaces. The microsurfacing shall be a mixture of cationic latex modified asphalt emulsion, mineral aggregate, mineral and field control additives, and water, properly proportioned, mixed and spread on the paved surface in accordance with this specification and as directed by any Town.

Materials

Emulsified Asphalt: The emulsified asphalt shall be a quick-set latex modified cationic type CSS-1H emulsion and shall conform to the requirements specified in AASHTO M208 and ASTM 2397. It shall pass all applicable storage and settlement tests. The latex shall be milled into the emulsion. The cement mixing test shall be waived for this emulsion.

Special Residue Properties: Distillation of residue will be at a temperature of 350 degrees F for 20 minutes. Softening point of the residue shall be 140 degrees F minimum. Viscosity, absolute at 140 degrees F, shall be 8,000 poise minimum.

Aggregate

General: The mineral aggregate used shall be of the type and grade specified for micro-surfacing. The aggregate shall be manufactured crushed stone such as granite, slag, limestone, chat, or other high-quality aggregate or combination thereof.

Aggregate Physical Requirements: The aggregate including natural fines when tested by AASHTO methods T11 or T27 or ASTM C117 or C136, should met the referenced gradation requirements. To limit the permissible amount of clay like fines in an aggregate, a sand equivalent value of 65 or higher is required when tested by ASTM 2419. The aggregate shall have a weighted loss of not more than 15% when the sodium sulfate test is used or 20% when the magnesium sulfate test is used. The aggregate wear, from resistance to abrasion, shall be a maximum of 35% when using AASHTO T96 or ASTM C131 test methods.

Water

The water shall be potable and shall be free of harmful soluble salts.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Modifier

Special quick-setting emulsifier agents shall be milled into the asphalt emulsion. The emulsified asphalt shall be so formulated that when the paving mixture is applied at thickness of one inch with the relative humidity at not more than 50% and the ambient air temperature of at least 75 degrees F. the material will cure sufficiently so that rolling traffic can be allowed in one hour with no damage to the surface.

Additives

A mineral additive shall be introduced to the mineral aggregate and may be any recognized brand of nonairentrained 27 portland cement or hydrated lime that is free of lumps, or other approved mineral additive.

The amount of mineral additive needed shall be determined by the laboratory mix design and will be considered as part of the material gradation requirement. A liquid field control additive is introduced and blended with water to provide effective control of the required quick-set properties. This additive shall be made available by the chemical supplier or emulsion manufacturer and certifiable as being compatible with the mixture.

Engineering

General: Before work commences, the Contractor shall submit a signed mix design covering the specific material to be used on the project. This design shall be performed by a qualified laboratory, suitable to the Town. Once the materials are approved, no substitution will be permitted unless first tested and approved by the laboratory preparing the mix design.

Mix Design: The qualified laboratory shall develop the job mix design and present certified test results for the Contractor's approval. Compatibility of the aggregate and emulsion shall be verified by the mix design. The job mix formula shall provide a minimum Marshall stability of 1,800 pounds and a flow of 6 to 16 units when tested according to the ASTM 1559 or AASHTO 245 procedure as modified. All component material used in the mix design shall be representative of the material proposed by the Contractor for use on the project.

Specifications: The Contractor shall guarantee the design mix and all microsurfacing materials and methods prior to use. The component materials shall be within the following limits.

Residual Asphalt	5% to 9% by dry weight of aggregate
Mineral Additive	0.5% to 3% by dry weight of aggregate
Latex Modifier	As required to provide specified properties
Field Control Additive	As required to provide the specified properties
Water	As required to produce Consistency

Aggregate Gradations:

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Screen Size	Type II % Passing	Type III % Passing
3/8”	100	100
#4	0-100	70-90
#8	65-90	45-65
#16	40-65	30-50
#30	25-45	19-34
#50	15-30	12-25
#100	10-21	7-18
#200	5-13	4-12

Suggested Application Rate:
Type II - Urban and Residential Streets Airport Runways: 18-22 lbs per sq. yd.
Type III- Primary and Interstate Routes: 25-30 lbs per sq. yd.
Wheel Ruts: Application rates as required.

Equipment
General: All equipment, tools, and machines used in the performance of this work shall be maintained in satisfactory working condition at all times to ensure a high quality product.

Mixing Equipment: The material shall be mixed by a self-propelled microsurfacing mixing machine which shall be a **continuous flow** mixing unit able to accurately deliver and proportion the aggregate, emulsified asphalt, mineral and field control additives, and water to a revolving multi-blade twin shafted mixer and discharge the mixed product on a continuous flow basis. The machine shall have sufficient storage capacity for aggregate, emulsified asphalt, mineral and field control additives, and water to maintain an adequate supply to the proportioning controls. **The machine may be equipped with self-loading devices which provide for the loading of materials while continuing to lay microsurfacing, thereby minimizing construction joints.**

Proportioning Devices: Individual volume or weight controls for proportioning each material to be added to the mix, i.e., aggregate, emulsified asphalt, mineral and field control additives, and water shall be provided and properly marked. These proportioning devices are usually revolution counters or similar devices and are used in material calibration and determining the materials output at any time.

Emulsion Pump: The emulsion pump shall be a heated positive displacement type.

Spreading Equipment: The surfacing mixture shall be spread uniformly by means of a mechanical type spreader box attached to the mixer, equipped with paddles to agitate and spread the materials throughout the box. A front seal shall provided to insure no loss of the mixture at the road contact point. The rear seal shall act as final strike off and shall be adjustable. The mixture shall be spread to fill cracks and minor surface irregularities and leave a uniform skid resistant application of material on the surface, The spreader box and rear strike off shall be so designed and operated that a uniform consistency is achieved to produce a free flow of material to the rear strike off. The longitudinal joint where two passes join shall be neat appearing,
uniform and lapped.

All excess material shall be removed from the job site prior to opening the road. The spreader box shall have suitable means provided to side shift the box to compensate for variations in pavement width and

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

longitudinal alignment. A Rut Box shall be available to prefill wheel ruts when necessary prior to overlay to eliminate puddles or runoff interruption. The box shall be readily adjustable from 4' – 6' width with hydraulically adjusted strike off screeds to attain maximum grade and profile.

Auxiliary Equipment: Suitable surface cleaning equipment, traffic control equipment, hand tools and any support equipment shall be provided as necessary to perform the work.

Machine Calibration

Each mixing unit to be used in performance of the work shall be calibrated in the presence of the Town prior to construction, or previous calibration documentation covering the exact materials to be used may be acceptable provided they were made during that calendar year. The documentation shall include the individual calibration of each material at various settings, which can be related to the machine metering devices.

Weather Limitations

The material shall be spread only when the road surface and atmospheric temperatures are at least 45 degrees F and rising and the weather is not rainy and there is no forecast of temperatures below 32 degrees F within 48 hours from the time of placement of the mixture.

Traffic Control

Suitable methods shall be used by the Contractor to protect the microsurface from traffic until the new surface will support traffic without damage. All traffic control methods used shall be in accordance with the specifications and shall be employed in a safe manner.

Surface Preparation

General: The area to be surfaced shall be thoroughly cleaned, by the Contractor, of pavement markings (if needed), vegetation, loose aggregate and soil, particularly soil that is bound to the surface. Manholes, valve boxes and other service entrances shall be protected from the surfacing material.

Cracks in Surface: Cracks in the surface shall be filled prior to microsurfacing. Crackfilling shall be paid for separately.

Tack Coat: The Contractor shall apply a tack coat consisting of one part emulsified asphalt and three parts water with a distributor at .10-.15 gallons per square yard. This emulsified asphalt should be the CSS1H emulsion grade.

Stockpile

Precautions shall be taken to ensure that stockpiles do not become contaminated. The mineral aggregate shall be screened prior to being weighed for job site delivery. This weight shall be done by means of a certified scale.

Application

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

General: The surface shall be pre-wetted by fogging ahead of the spreader box when required by local conditions. The rate of application of the fog spray shall be adjusted during the day to suit temperatures, surface texture, humidity, and dryness of the pavement surface.

The microsurfacing mixture shall be of the desired consistency upon leaving the mixer and no additional materials should be added. A sufficient amount of material shall be carried in all parts of the spreader at all times so that a complete coverage is obtained. Overloading of the spreader shall be avoided. No lumping, balling, or unmixed aggregate shall be permitted.

No streaks, such as those caused by oversized aggregate, will be left in the finished surface. If excessive oversize develops, the job will be stopped until the Contractor proves to the Town that the situation has been corrected.

Joints: No excessive buildup, uncovered areas or unsightly appearances shall be permitted on longitudinal or transverse joints. The Contractor shall provide suitable width spreading equipment to produce a minimum number of longitudinal joints throughout the project. When possible, longitudinal joints shall be placed on lane lines. Half passes and odd width passes will be used only in minimum amounts. If half passes are used, they shall not be the last pass of any paved areas.

Mix Stability: The microsurfacing mixture shall possess sufficient stability so that premature breaking of the material in the spreader box does not occur. The mixture shall be homogeneous during and following mixing and spreading. It shall be free of excess water or emulsion and free of segregation of the emulsion and aggregate fines from the coarser aggregate.

Hand Work: Areas which cannot be reached with the mixing machine shall be surfaced using hand squeegees to provide complete and uniform coverage. The area to be handworked shall be lightly dampened prior to mix placement. Care shall be exercised to leave no unsightly appearance from handwork. The same type finish as applied by the spreader box shall be required. Handwork shall be completed at the time of the machine applying process.

Lines: Care shall be taken to insure straight lines along curbs and shoulders. No runoff on these areas will be permitted. Lines at intersections will be kept straight to provide a good appearance.

Rolling: If required, specified areas shall be rolled by a self-propelled 10 ton pneumatic roller with a tire pressure of 50 PSI and equipped with a water spray system.

Quality Control

Materials: The Contractor will permit each Town to take samples of the aggregate and asphalt emulsion to be used in the project at the Town's discretion. Gradation and sand equivalent tests may be run on the aggregate and residual asphalt content test on the emulsion. Test results will be compared to specifications. Tests will be run by a qualified laboratory at the expense of the Contractor. The Town shall notify the Contractor immediately if any test fails to meet the specifications.

Micro-Surfacing Mixture: Samples of the mixture should be taken daily and may be taken directly from the mixing unit(s). Consistency and residual asphalt content tests may be made on the samples and compared to the specifications. Tests will be run by a qualified laboratory at the expense of the Contractor. The Town must notify the Contractor immediately if any test fails to meet specifications.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Any Town may use the recorder and measuring facilities of the unit to determine application rates, asphalt emulsion content mineral and field control additives, and water.

Non-Compliance: If any two successive tests fail on the stockpile material, the job shall be stopped. It is the responsibility of the Contractor, at his own expense, to prove to the Town that the conditions have been corrected. If any two successive tests on the mix from the same machine fail, the use of the machine shall be
suspended. It will be the responsibility of the Contractor, at his own expense, to prove to the Town that the problems have been corrected and that the machine is working properly.

Performance

It is the intention of every Town not to award a contract for microsurfacing work under this or any other proposal if the bidder cannot furnish satisfactory evidence that he has the ability and experience to perform this class of work and that he has sufficient capital and equipment to enable him to prosecute the work successfully and to complete it within the time named in the Contract; and that every Town reserves the right to reject this or any other proposal or to award the Contract as is deemed to be to the best interest of said Town.

Performance Warranty

The Contractor shall furnish the following warranty after completion of the work and prior to final payment:

The Contractor hereby warrants that all workmanship and all materials furnished under the Contract comply fully with requirements of these microsurfacing specifications.

If at any time within two years after the date of the final inspection, any unfaithful or defective work should appear, which in the opinion of a Town is due to inferior materials or workmanship, the Contractor warrants to do whatever is necessary to remedy the defects immediately without cost to the Town. The Town shall notify the Contractor in writing of the defects and the repairs to be made, and the Contractor will begin repairs within a mutually agreed time frame.

Measurement and Payment

The quantity, for one or two lifts of microsurfacing, to be measured for payment will be the number of square yards of micrsurfacing actually completed. The accepted quantity of micrsurfacing will be paid for at the Contract unit price per square yard, which shall be full compensation for furnishing, transporting, handling and placing the material specified and furnishing of all labor, tools, equipment, pavement surface cleaning, and incidentals for the satisfactory completion of the work.

Item Nos. 11 & 12: ASPHALT-RUBBER SURFACE TREATMENT

The Work under this item shall include the furnishing, application, and compaction of hot asphalt and granulated rubber, and a crushed stone cover, and the sweeping of the roads before and after application.

Materials

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Asphalt Cement – Asphalt cement for the asphalt-rubber mixture shall be PG 58-28 OR P G 64-28 PG64-28 where needed to meet the requirements of ASTM D 6114 (type II), complying with the requirements of the Standard Specifications. The grade selected shall be based on laboratory testing by the asphalt-rubber supplier.

Anti-stripping Agent – An anti-stripping agent that is heat stable shall be incorporated into the asphalt-rubber material at the dosage required by the job-mix formula (up to 1.0% by weight of asphalt). It shall be added to the asphalt cement prior to blending with the granulated rubber.

Rubber – The granulated rubber shall be vulcanized rubber product from the ambient temperature processing of scrap, pneumatic tires. The granulated rubber shall meet the following gradations: No substitutions will be accepted.

Sieve Size	Percentage Passing
No.10	100
No.16	90 - 100
No.30	25 - 75
No.80	0 - 20

The use of rubber of multiple types from multiple sources is acceptable provided that the overall blend of rubber meets the gradation requirements. The length of the individual rubber particles shall not exceed 1/8". The rubber shall be accepted by certification from the rubber supplier.

Aggregate – The aggregate shall conform to the requirements of the Standard Specifications. The Flakiness Index shall be less than 30% (NFP 18-561 Test). Crushed gravel stone shall not be permitted. Percentage of wear as determined by the Los Angeles Abrasion Test (AASHTO-T96) shall be a maximum of 30. The aggregate shall be pre-heated to a temperature between 200ºF and 300ºF, and be pre-coated with 0.4% to 0.8% (by weight of aggregate) of AC-10 or AC-20 asphalt cement prior to application. The gradation of the aggregate shall meet the following limits:

Sieve Size	Percentage Passing Nominal Size ⅜"	Percentage Passing Nominal Size ½"
5/8"	100%	100%
1/2"	100%	85 - 100%
3/8"	85 - 100%	15 - 45%
No. 4	0 – 25%	0 - 15%
No. 8	0 - 5%	0 - 5%
No. 50	0 - 2%	0 - 2%
No.200	0 - 2%	0 - 2%

Materials Testing - A minimum of 60 days prior to construction, the Contractor shall send a representative sample of the asphalt cement and the aggregate proposed for use to the asphalt-rubber supplier for testing. Testing for stripping and asphalt content to determine and assure that appropriate characteristics are achieved when blended with the granulated rubber shall be performed.

Asphalt-rubber Mixing and Reaction

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Mixing and Reaction - The percent of rubber shall be 20 +/- 3% for Item No.7 and 10+% for Item No.8, as indicated by the mixture design for specific project requirements by weight of total mixture, that is, by total weight of asphalt cement, plus granulated rubber. The exact granulated rubber content shall be determined by the mix design submitted by the asphalt-rubber supplier based on laboratory testing.

The temperature of the asphalt shall be between 350°F and 425°F, at the time of addition of the granulated reclaimed rubber. The asphalt and rubber shall be combined and mixed together in a blender unit and reacted in the distributor for a period of time as required by the mix design. The temperature of the asphalt-rubber mixture shall be above 325°F, during the reaction period.

Delays - When a job delay occurs after full reaction, the asphalt-rubber may be allowed to cool. The asphalt-
rubber shall be reheated slowly just prior to application, but not to a temperature exceeding 375°F. An additional quantity of granulated rubber or additive not exceeding 3% by volume of the hot asphalt-rubber mixture may be added after reheating.

Viscosity - Viscosities shall be run, by the asphalt-rubber supplier, on each blended load of asphalt-rubber using a Haake-type field viscometer. The viscosity of the final product shall be in the range of 1,000 to 3,500 centipoise.

Equipment

Mechanical Blender – A mechanical blender shall be utilized for proper proportioning and thorough mixing of the PG asphalt binder and ground rubber. This unit shall have a Coriolis type mass flow meter capable of measuring and recording the total quantity of asphalt binder in tons. The quantity of ground rubber shall be determined by weight utilizing either a hopper equipped with load cells or a feeder equipped with a belt scale. The total weight in tons and percentage of ground rubber based on total asphalt rubber binder shall be recorded. All data shall be reported to the awarding authority.

A dedicated asphalt rubber reaction/storage tank equipped with a heating system to maintain the proper temperature of the binder and an internal mixing unit capable of maintaining a homogeneous mixture of asphalt and ground rubber.

Testing and Certification:
The materials shall be sampled once per lot at the point of manufacture, tested and certified by an AASHTO resource (formally AMRL) accredited laboratory approved for asphalt rubber binder testing. The laboratory shall certify that the material meets the requirements of ASTM D 6114 type II specifications. A lot shall be defined as each batch produced, but not to exceed the volume of the manufacturer's dedicated asphalt rubber reaction/storage tank. In addition to the ASTM D 6114 Type II specification, to ensure adequate blending residence time and superior binder quality, every lot shall be tested under:

Test (on the produced asphalt rubber binder)	Result
AASHTO T315 Original Binder 2mm DSR @ 82:	G*/sin(d) >1.00 kPA

Prior to starting the project, the contractor shall submit a Quality Control Plan from the Asphalt Rubber supplier meeting the requirements of AASHTO R-26 format. The contractor shall submit a weekly manufacturer's report for each lot of asphalt rubber produced that includes the following as a minimum:

Total quantity of asphalt binder in tons

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Tons and percentage of ground rubber based on total asphalt rubber binder
ASTM D 6114 certified test results
AASHTO T315 Original Binder 2mm DSR @ 82

Distributor Truck - On projects exceeding 35 tons of liquid asphalt rubber, at least two pressure-type bituminous distributor trucks in good condition shall be required. The distributor shall be equipped with an internal heating device capable of heating the material evenly up to 425° F; an internal mixing unit capable of maintaining a proper mixture of asphalt cement and granulated rubber; have adequate pump capacity to
maintain a high rate of circulation in the tank and to spray the asphalt-rubber at a viscosity of 1,000 to 3,500 centipoise; have adequate pressure devices and suitable manifolds to provide constant positive cut-off to prevent dripping from the nozzles. Distributor shall be equipped with an electronically controlled computerized compensation unit for controlling application rates at various width and speed changes. The application unit shall have electronic controls and a digital read out installed and operated from the inside of
the cab of the distributor. The distribution bar on the distributor shall be fully circulating. Any distributor that produces a streaked or irregular distribution of the material shall be promptly repaired or removed from the project.

Distributor equipment shall include a tachometer, pressure gauges, volume measuring devices, and a thermometer for reading temperature of tank contents. Controls for spray bar shall be located in cab of truck, for controlling width and rate of spray of product. It shall be so constructed that uniform applications may be made at the specified rate per square yard with a tolerance of plus or minus 0.05 gal. / sq. yd.

A “bootman” shall accompany the distributor and ride in a position so that all spray bar nozzles are in his full view and readily accessible for unplugging.

Hauling Equipment - Trucks for hauling cover material shall be rear discharge conveyor-fed or “live bottom” trucks and shall be equipped with a device to lock onto the hitch at the rear of the chip spreader to prevent aggregate spillage. Sufficient hauling vehicles shall be available to ensure continuous operation of the distributor and chip spreader.

Aggregate Spreader - The aggregate spreader shall be hydrostatically driven and self propelled. It must be equipped with a hydraulically controlled variable adjustable head that is capable of spreading stone in widths from 4.5 to 18 feet. The spreader shall be mounted on pneumatic tires, and shall apply the stone on the road
surface in a manner that ensures that the tires do not contact the road surface until after the stone has been
applied. The unit shall be equipped with an electronic radar type sensor used to measure ground speed and will automatically adjust the stone application rate depending on width of application and the speed of chip spreader. It shall have the ability to apply stone on any grade from 0 - 6%. The spreader shall be equipped with an integral hopper with a minimum capacity of 5 tons of stone which shall be filled by trucks in a manner which ensures that the truck tires never come in contact with asphalt treated road surfaces until the stone has been properly applied. To maintain constant stone application, a self-locking truck hitch will permit towing of aggregate trucks without stopping the chip spreader. It shall be capable of maintaining positive engagement over irregular terrain.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Pneumatic-Tired Roller - One (1) self-propelled, multiple wheel, pneumatic-tired rollers shall be used and shall weigh between 7 and 12 tons, each roller shall have a total compacting width of at least 56 inches, have a minimum tire pressure of 60 psi, and be equipped with a watering system.

Steel-Wheel Roller - One (1) self-propelled, 2-axle (tandem) steel-wheel roller shall be used and shall weigh between 8 and 12 tons, and be equipped with scrapers, wetting pads and watering system. Combination pneumatic and steel drum-type rollers are acceptable, as one unit only.

Construction Procedures

Preparation - Potholes, other areas of pavement failure, and major depressions in the existing pavement surface, shall be repaired by each Town. The Town shall be responsible for removal of all thermoplastic traffic markings

The Contractor shall, immediately prior to application of the asphalt-rubber, thoroughly sweep the surface. The Contractor shall be responsible for covering all utility irons just prior to application and uncovering after aggregate is spread.

Seasonal and Weather Limitations - The asphalt-rubber shall not be applied when weather conditions are unfavorable to obtaining a uniform spread. Construction shall proceed only when the atmospheric temperature is at least 50°F and rising. No water shall be present on the road surface.

Application - The asphalt-rubber mixture shall be applied at a temperature of 338°F to 419°F, at a rate of 0.55 to 0.65 gallons per square yard for Item No.7 or 0.35 to 0.50 gallons per square yard for Item No.8. Exact rate to be determined by the aggregate gradation, traffic volume and pavement condition.

Longitude joints shall be reasonably true to line and parallel to centerline. Where any construction joint occurs, the edges shall be broomed back and blended so there are no gaps and the elevations are the same, and free from ridges and depressions. Longitudinal joints shall be overlapped from 4 to 6 inches.

During application, adequate provision shall be made to prevent marring and discoloration of adjacent pavements, structures, vehicles, foliage or personal property.

Aggregate Application - The application of aggregate shall follow as close as possible behind the application of the hot asphalt-rubber which shall not be spread further in advance of the aggregate spread that can be immediately covered. Construction equipment or other vehicles shall not drive on the uncovered asphalt-rubber. The hot-precoated aggregate shall be spread uniformly by a self-propelled spreader at a rate of spread generally between 30 to 40 pounds per square yard for Item No.7 or 20 to 30 pounds per square yard for Item No.8.. Any deficient areas shall be covered with additional material.

Rolling - A minimum of three (3) rollers shall be used for aggregate compaction into the hot asphalt-rubber.

Two rollers must be pneumatic-tired and one must be steel-wheel. Rolling shall commence immediately following spread of aggregate. There shall be at least three (3) coverages by the pneumatic-tired rollers to embed the aggregate firmly into the asphalt-rubber. A coverage shall be as many passes as are necessary to cover the entire width being spread with a pass being one (1) movement of a roller in

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

either direction. Additional coverage of the steel-wheel roller will follow. Water shall be applied to the tires or wheels as required to limit sticking of the asphalt-rubber and aggregate to the rollers.

Sweeping – When the maximum amount of aggregate has been embedded into the asphalt-rubber and the pavement has cooled, all loose material shall be swept or otherwise removed to the satisfaction of the Town. This shall be done at a time and in a manner which will not displace any embedded aggregate or damage the asphalt-rubber. Pre and one post sweeping is the responsibility of the Contractor.

Staging Location
The awarding authority shall provide a staging area for equipment and materials to be used on the project. The Contractor and Director shall mutually review and agree that the location is of adequate size and condition to allow for safe and secure usage for the required operation(s).

Measurement and Payment

Asphalt-Rubber Surface Treatment shall be measured by the square yard and shall be the actual number of square yards applied. Price per square yard shall be full compensation for all labor, materials, equipment , and incidentals required to complete the work (including street sweeping before and after treatment).

Item No. 13: SINGLE STONE SEAL SURFACE TREATMENT

The Work under this item shall include the furnishing, application, and compaction of a latex modified emulsified asphalt binder and a crushed stone cover, furnishing and installing temporary warning signs, and
the sweeping of the roads before and after application. The temporary cardboard warning signs shall read “Fresh Oil, Loose Stone” (or similar wording) and shall be placed at locations as directed by the Engineer (as a minimum at all intersections).

Materials

1. Emulsified Asphalt – Emulsified asphalt for Stone Seal Surface Treatment shall be CRS-2 (cationic/3% latex) conforming to ASTM D2397 or RS-2 (36 nionic/3% latex) conforming to ASTM 977-86.

2. Latex Additive – The latex additive to the emulsified asphalt binder shall conform to the following properties. The latex shall be co-milled at the bulk emulsion facility, to ensure complete and balanced blending, and the emulsion manufacturing plant must be open to inspection by the Owner.

Properties	Anionic	Cationic
Monomer Ratio, Butadiene/Styrene	(76±2)/(24±2)	(76±2)/(24±2)
Solids Content, %	67	59
Solids Content, lbs./gal.	5.2	4.8
Coagulum on 80 mesh screen, max %	0.1	0.1
Mooney Viscosity of Polymer (ML 4 @ 212 deg.F) min.	100	100
Ph of latex	9.5 – 10.5	4.0 – 5.5
Surface Tension, dynes/cm	32	32

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Brookfield Viscosity, cps (Model RVT, #3 Spindle @ 20 RPM)	800 – 2,000	5,000 max.
Mechanical Stability	Excellent	Excellent

3. Cover Aggregate – The cover aggregate shall be blue quarry stone with 70% fractured face, and shall be compatible with the emulsified asphalt.

The crushed stone shall be thoroughly clean and free from deleterious matter, essentially one size, sharp and conform to the following gradation requirements as determined by California Test Method No. 202.

Sieve Size	Percentage Passing Medium 3/8" x No.6
1/2"	100%
3/8"	85-100%
1/4"	10 – 60%
No. 4	0 – 10%
No. 8	0 - 5%
No. 16	0 - 2%

Maximum passing the #200 sieve shall not exceed 1.0%. Stone shall be wet washed for all sized aggregates used in surface treatments.

Screening shall be non-cubical in nature and shall also conform to the following quality requirements:

Test	Method No.	Requirements
Loss in L.A. Rattler Test (After 100 Rev.)	211	10% Maximum
(After 500 Rev.)	211	40% Maximum
Film Stripping	302	25% Maximum
Cleanliness Value	227	75% Minimum

The successful bidder shall submit a 10-pound sample of material proposed to be supplied. Samples which, in the opinion of the Town, would result in excessive stripping shall be rejected.

The quantity of asphalt material to be used shall be in the range of 0.35 to 0.50 gallons per square yard. Cover aggregate shall be spread in the range of 20 to 30 pounds per square yard. The Contractor will use lab tests to design specific material quantities to meet existing field conditions. Variations in material quantities will be made without adjustment to contract unit price. The Contractor shall maintain a laboratory open to the inspection of any Town.

Quality Assurance

A certificate of compliance shall be issued to the Town prior to the application of the stone seal surface treatment which guarantees the compatibility of the emulsified asphalt with the cover aggregate. The

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

laboratory results from a pre-approved testing company shall be submitted with the certificate of compliance.

Emulsified asphalt and cover aggregate shall be matched to obtain compatible molecular charges.

Samples shall be supplied with the following information:
* quarry location
* gradation
* certificate of material compliance

Construction Equipment

The equipment used by the Contractor shall include, but not be limited to, one or more of the following:

a. Asphalt Distributor - The asphalt distributor shall contain suitable mechanical circulating and heating mechanisms to provide a uniform approved temperature of the entire mass of material. The distributor shall be capable of applying asphalt materials in accurately measured quantities at any rate between 0.1 to 2.0 gallons per square yard of roadway surface, at any length of spray bar up to twenty-four feet. The distributor shall be capable of maintaining a uniform rate of distribution of asphalt material regardless of change in grade, width or direction of the road. The spray nozzles and pressure system shall provide a sufficient and uniform fan-shaped spray of asphalt material throughout the entire length of the spray bar at all times while operating. The spray shall completely cover the roadway surface receiving the treatment.

b. Aggregate Spreader - The aggregate spreader shall be hydrostatically driven and self-propelled. It may be equipped with a hydraulically controlled variable adjustable head that is capable of spreading stone in widths from 4.5 to 18 feet. The spreader shall be mounted on pneumatic tires, and shall apply the stone on the road surface in a manner that ensures that the tires do not contact the road surface until after the stone has been applied. The unit shall be equipped with an electronic radar type sensor used to measure ground speed and will automatically adjust the stone application rate depending on width of application and the speed of chip spreader. It shall have the ability to apply stone on any grade from 0 – 6%. The spreader shall be equipped with an integral hopper with a minimum capacity of 5 tons of stone which shall be filled by trucks in a manner which ensures that the truck tires never come in contact with asphalt-treated road surfaces until the stone has been properly applied. To maintain constant stone application, a self-locking truck hitch will permit towing of aggregate trucks without stopping the chip spreader. It will be capable of maintaining positive engagement over irregular terrain.

c. Rollers - At least one rubber tired and one steel wheeled roller shall be used on each treated surface immediately after the stone has been applied. Each roller shall have a compacting width of not less than 5 feet. Each roller shall have a gross weight of not less than 8 tons and contact pressure adjustable from 200 to 300 psi.

d. Trucks - Rear discharge conveyor-fed trucks in sufficient number and size may be used to deliver stone to the spreader.

Construction Method

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The construction of Single Stone Seal Surface Treatment by the Contractor shall conform to recommended practices of the Asphalt Institute and the following.

1. Preparation of Existing Surface - Immediately before Work begins, the existing surface shall be adequately swept by the Contractor. The Contractor shall then oil and cover with tar paper all pavement surface utility hardware within project limits. Surface preparation, which may include pothole patching, truing and leveling, adjusting of street irons (valve covers, manhole covers, drop inlet gratings), etc., will be the responsibility of each Town and will be completed before the Contractor moves onto the job.

2. Weather Limitations - Work will not be done unless the road surface is dry. No work shall be done during rain or foggy periods, or if the local forecast calls for rain or fog on that day. No work shall be done if the ambient temperature is below fifty degrees Fahrenheit (50°F).

   WORK UNDER THIS CONTRACT SHALL BE PERFORMED FROM JUNE TO SEPTEMBER, AS AUTHORIZED BY EACH TOWN. EACH TOWN SHALL BE THE SOLE DETERMINING JUDGE OF WHEN THE WEATHER CONDITIONS ARE SUITABLE FOR BEGINNING WORK. ALL STREETS SELECTED FOR TREATMENT SHALL BE TREATED BEFORE OCTOBER.

3. Application of Emulsion – The pre-determined quantity of emulsified asphalt binder shall be sprayed uniformly onto the prepared surface. The asphalt material shall not be applied more than 300 feet in advance of the self-propelled aggregate spreader. AT NO TIME SHALL ANY ASPHALT MATERIAL BE ON ANY ROAD SURFACE FOR MORE THAN FIFTEEN (15) MINUTES BEFORE IT IS COVERED WITH STONE.

4. Application of Aggregate – A uniform application of the pre-determined quantity of aggregate shall immediately be spread over the emulsified asphalt binder.

5. Application Operation – The bituminous distributor and the aggregate spreader shall move at the same rate of speed. These units shall operate at a distance not exceeding 50 feet from each other.

6. Rolling – Rolling shall begin immediately after aggregate is spread and continue until at least two complete rollings have been completed over the entire width of each pass of the aggregate spreader. Rollers shall never be more than 100 feet behind the aggregate spreader.

Initial rolling shall be done with self-propelled pneumatic rollers immediately following the application of the cover aggregate. Final rolling on stone seal shall be done by steel roller weighing not less than 8 nor greater than 10 tons. The rollers shall be operated at a speed that will not displace the aggregate.

7. Traffic Control – During construction and 24 hours following construction, vehicle speed shall be posted to a maximum of 20 miles per hour. One lane of traffic shall remain open to vehicles at all times.

8. Street Sweeping/Clean Up – The roads shall be mechanically swept by the Contractor to remove excess aggregate as soon as possible but no later than 14 calendar days after the stone application as approved by the Town. The sweepings shall become the property of the Contractor unless a Town requests that the Contractor stockpile the sweepings in Town for it’s use. The tar paper covers over utility hardware shall also be removed by the Contractor.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Quality Control and Inspection

Each Town shall have access to all construction activities to closely supervise and inspect the rates of application and amount of rolling to ensure that proper methods are being adhered to.

1. Aggregate – The aggregate shall be washed to insure clean material. Immediately after the aggregate has substantially dried from the washing process, the stone shall be sprayed with a coating of emulsified asphalt at a rate of three (3) gallons per ton of aggregate.
2. Temperature of Emulsified Asphalt Binder – Temperature of asphalt emulsion at the time of application shall be not less than 130 deg. F nor more than 180 deg. F.
3. Latex Additive – Latex additive shall be added at the refinery or terminal. A certificate of compliance shall be submitted by the refinery or terminal attesting that the required rate of application has been provided. The latex addition should be at the rate of 3.0 gallons per 100 gallons of emulsified asphalt binder.
4. Weather - The minimum temperature shall be 50 deg.F and rising, with no rain predicted. Should any form of precipitation begin during construction, stone seal operation shall cease. Re-commencement of operations shall be as directed by each Town.
5. Sweeping - Excess aggregate shall be mechanically swept by the Contractor to the satisfaction of the Town as soon as possible after application but no later than 14 calendar days after the stone application.

Product Performance

The stone seal surface treatment elements that shall be retained on the road surface shall conform to the following minimum quantities:

1. Residual Asphalt Content: 0.20 to 0.25 gallons/square yard.
2. Stone Chips: 20 to 25 pounds/square yard (based on a specific gravity of 2.65. Quantity requirements will be adjusted based on the source of stone.)

Measurement and Payment

Single Stone Seal Surface Treatment will be measured for payment by the square yard of pavement surface area complete in place. Single Stone Seal Surface Treatment will be paid for at the Contract unit price per
square yard, which price shall include all labor, materials, equipment, disposal and incidental costs required to complete the Work (including furnishing and installing temporary warning signs, and street sweeping before and after stone application).

Item No. 14: DOUBLE STONE SEAL SURFACE TREATMENT

The Work under this item shall include the furnishing, application, and compaction of a latex modified emulsified asphalt binder and crushed stone covers applied in two courses, furnishing and installing temporary warning signs, and the sweeping of the roads before and after application. The temporary cardboard warning signs shall read “Fresh Oil, Loose Stone” (or similar wording) and shall be placed at locations as directed by the Engineer (as a minimum at all intersections). The Work shall be constructed

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

in conformance with the above specifications for SINGLE STONE SEAL SURFACE TREATMENT with the following differences:

The Contractor shall supply samples of stone and asphalt, and job mix formula to each Town for approval. The stone seal surface treatment elements that shall be retained on the road surface shall conform to the following minimum quantities:

Residual Asphalt Content: 0.45 to 0.65 gallons/square yard

Stone Chips Applied: 45 to 55 pounds/square yard

3/8" Crushed Stone

Sieve Size	Percentage Passing
1/2"	100%
3/8"	85-100%
1/4"	10-60%
No.4	0-10%
No.8	0-5%
No.16	0-2%

1/2" Crushed Stone

Sieve Size	Percentage Passing
5/8"	100%
1/2"	85-100%
3/8"	15-45%
No.4	0-10%
No.8	0-2%

Measurement and Payment

Double Stone Seal Surface Treatment will be measured for payment by the square yard of pavement surface area complete in place. Double Stone Seal Surface Treatment will be paid for at the Contract unit price per square yard, which price shall include all labor, materials, equipment, disposal and incidental costs required to complete the Work (including furnishing and installing temporary warning signs, and street sweeping before and after stone application).

Item No. 15: POROUS PAVEMENT FULL DEPTH CONSTRUCTION

The Work under this section shall conform to the relevant provisions of Sections 120, 460, M1, M2, M3, and M9 of the Standard Specifications (all as amended) and the following. The porous pavement shall meet the Standard Specifications for Polymer Modified Open-Graded Friction Course.

The Work shall include the full depth excavation and subsequent installation of a porous pavement full depth construction system consisting of, from top to bottom: a four (4) inch layer of porous pavement machine installed in separate two (2) inch lifts; an eight (8) inch layer of three eighths (3/8”) to three quarter inch (3/4”) blended crushed stone; and, a twelve inch (12”) layer of one and one half inch (1-1/2”) native (rounded) stone. Filter fabric (Mirafi 160N Non-Woven Geotextile) shall be installed along

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

all sides and ends (not the bottom) of the porous pavement system. **Each site shall be a guaranteed minimum of 200 square yards.**

The measured quantity will be paid for at the Contract unit price per square yard, which price shall include a complete porous pavement full depth construction system in-place including all labor, materials, equipment, pavement saw cutting, excavation, hauling, disposing, grading, compacting, tack coating pavement edges, porous pavement, stone, filter fabric, and incidental costs required to complete the Work. If needed, Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Item No. 16: POROUS PAVEMENT SIDEWALK CONSTRUCTION

The Work under this section shall conform to the relevant provisions of Sections 120, 460, M1, M2, M3, and M9 of the Standard Specifications (all as amended) and the following. The porous pavement shall meet the Standard Specifications for Polymer Modified Open-Graded Friction Course.

The Work shall include the full depth excavation and subsequent installation of a porous pavement full depth sidewalk construction system consisting of: a four (4) inch layer of porous pavement machine installed in separate two (2) inch lifts over an eight (8) inch layer of three eighths (3/8”) to three quarter inch (3/4”) blended crushed stone. Filter fabric (Mirafi 160N Non-Woven Geotextile) shall be installed along all sides and ends (not the bottom) of the porous pavement system. It is anticipated that the new sidewalk shall range between 4 and 6 feet wide.

The measured quantity will be paid for at the Contract unit price per square yard, which price shall include a complete porous pavement sidewalk construction system in-place including all labor, materials, equipment,
pavement saw cutting, excavation, hauling, disposing, grading, compacting, tack coating pavement edges, porous pavement, stone, filter fabric, and incidental costs required to complete the Work. If needed, Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Item No. 17: BITUMINOUS PAVEMENT REPAIR - INFRA-RED METHOD

The Work shall include the treatment of utility trench and other bituminous concrete patches to provide a permanent, uniform and durable patch matching the surface of the abutting pavement. The Work shall be performed by workmen skilled in the infra-red method, and with equipment and materials approved for use by the Engineer prior to start of Work. The following procedure shall be used:

* Adequately sweep the treatment area clean, and remove all loose and foreign material.

* Apply infrared heat to the patch area by carefully positioning an infra-red heater not to exceed 15,000 BTUs per square foot per hour for the period of time required to soften the pavement to

a depth which will allow adequate raking of the asphalt without oxidation of the bitumen in the pavement material (minimum depth of 1"). The Contractor shall remove all unsuitable oxidized material and replace same with bituminous concrete.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

* Introduce a suitable proven recycling agent additive amount as approved, to the softened area. Scarify to produce a uniform workable mix and regrade the patch to a uniform grade and surface, and to match the abutting pavement.

* Add additional Class I bituminous concrete Type I-1 material as necessary. A supply of the material shall be kept on hand in an infrared storage unit at a constant temperature during working hours. The stored material shall be kept at a temperature above 200 degrees F. No material with a temperature of less than 200 degrees F shall be used in the Work.

* After the proper consistency of the paving material and recycling agent has been attained, the combined mixture shall be raked to the desired grade and compacted with a steel wheel roller of sufficient weight to achieve a uniform density comparable to that of the adjacent pavement.

* Seal the edges of the repaired patch with an approved penetrating liquid asphalt emulsion to develop a stronger, more durable bond. Uniformly distribute a compatible approved petroleum resin sealant, and broadcast an approved mineral filler over the entire patch area to absorb any excess liquid and to prevent tracking.

* Test the compacted surface with a straight edge to verify that a uniform, depression free surface has been obtained. Repeat the treatment process to remove any depressions found by the test.

The measured quantity will be paid for at the Contract unit price per square yard, which price shall include all labor, materials (excluding additional bituminous concrete), equipment, disposal costs, and incidental costs required to complete the Work. The additional bituminous concrete shall be supplied by the Town's vendor at no cost to the Contractor; however, the Contractor shall pick-up the bituminous concrete at the Town's vendor's plant at no additional cost to the Town. Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Item No. 18: PARTIAL DEPTH PAVEMENT PATCH

The Work shall consist of the construction of partial depth pavement patches at various locations as directed by the Engineer. The Work shall include the following:

Partial depth pavement patch excavation shall consist of the removal and satisfactory disposal of all bound pavement materials, the removal of which is necessary for the proper completion of the work. The excavation will be made to a minimum depth of 1.5". Contractor shall make the excavation square or rectangular with faces straight and vertical. The Contractor may use any type of pavement saw-cutting or milling equipment that will not damage adjacent pavement. A jack-hammer and compressor will not be allowed for cutting the pavement surface.

The Contractor shall swab or paint the existing vertical faces of the pavement with an approved emulsified asphalt such that a uniform film of asphalt will remain when cured.

Hot Mix Asphalt Pavement shall be placed and properly compacted with a power roller. The surface shall not deviate more than 1/8" from a straight edge placed on the existing pavement.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The perimeter of the patch shall be painted with an emulsified asphalt or approved equal such that a 4" wide strip will be equally spaced on the new and existing pavement. The joint sealing material shall be dusted with stone screenings or stone dust such that no tracking or pick-up of the seal will occur.

Partial depth pavement patch will be measured for payment by the square yard complete in place. The measured quantity will be paid for at the Contract unit price per square yard, which price shall include all labor, materials, equipment, and incidental costs required to complete the Work. Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Item No. 19: MISC. PAVEMENT PATCH

The Work shall consist of the construction of miscellaneous pavement patches of various thicknesses on local roads at locations as directed by the Engineer. The Work shall include the following:

* Because the areas to be patched are typically in very poor condition, the Contractor shall use any method at his disposal to cut and completely remove the existing failed pavement/ subbase to the depth (minimum 3" depth) as directed by the Engineer.

* The subgrade area shall be fine graded and compacted in conformance with Section 170 of the Standard Specifications.

* Cut surfaces shall be sprayed or painted with a uniform, thin coat of RS-1 asphalt emulsion immediately before placement of bituminous concrete material against the surfaces.

* Class I Bituminous Concrete – Type I-1 shall be placed and compacted in 2 courses as a wearing surface (minimum 3" depth). Binder (2" minimum) and top (1" minimum) courses shall be installed on the same day allowing for adequate cooling between courses. The top course may be installed the next day if approved by the Engineer and if adequate safety signing/ measures are taken. In any case, the top course must be installed prior to weekends and/or holidays.

Miscellaneous pavement patches will be measured for payment by the ton complete in place. The measured
quantity will be paid for at the Contract unit price per ton, which price shall include all labor, materials, equipment, and incidental costs required to complete the Work. Contractor shall install Owner provided risers on gate valve boxes at no additional cost to the Town. Drainage and sewer casting adjustments are paid for under a separate item.

Item No. 20: VELOCITY SPRAY INJECTION POTHOLE REPAIR

Scope of Work:

The work under this item shall consist of furnishing all labor, equipment, materials (asphalt emulsion and aggregate) and incidentals required to perform repairs on distressed bituminous concrete pavement by the Velocity Spray Injection Method.

Equipment:

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

a. The distribution unit shall be a 33,000 GVW truck, equipped with a 6 cubic yard aggregate hopper, a 300 gallon asphalt emulsion tank, a 1000 pound anti-track material hopper and a delivery tube, air pressurized, to distribute the items above to the distressed pavement.
b. Aggregate shall be delivered to the tube by a nylon belt covered positive drive chain conveyor, emulsion shall be delivered by a pressurized system at 140 degrees F, and anti-track material shall be delivered to the tube as required. Each item is delivered to the tube by in-cab remote controls.

Item No. 21: CAPE SEAL w/ Single Stone Seal Surface Treatment
Item No. 22: CAPE SEAL w/ Double Stone Seal Surface Treatment

The work under these items consists of the furnishing, application, and cleanup of "Cape Seal", furnishing and installing temporary warning signs, and sweeping of roads before and after stone seal application.

"Cape Seal" shall be a combination of Stone Seal Surface Treatment and Microsurfacing completed in two successive operations with the micro surfacing completely covering and encapsulating the stone seal aggregate.

Both processes shall be completed within the same construction season and meeting the Town's desired schedule. The Microsurfacing shall not be applied sooner than seven (7) days after the stone seal is complete in order that the stone seal emulsion can be totally cured. An additional sweep may be required prior to the placement of the Microsurfacing to remove any surplus aggregate.

The first phase of the Cape Seal installation shall be completed in accordance with the Single Stone Seal Surface Treatment (Item No 12 above) or the Double Stone Seal Surface Treatment (Item No. 13 above) specification herein utilizing the CRS-2 emulsion without the 3% latex.

The second phase of the Cape Seal installation shall be completed in accordance with the Microsurfacing (Item No. 6 above) specification herein except that the application shall be a single lift of Type II material applied at not less 25 pounds per square yard (dry aggregate weight), and of sufficient thickness that none of the stone seal aggregate is exposed after curing of the Microsurfacing.

The quantity of Cape Seal to be measured for payment will be the number of square yards of Cape Seal actually completed. The accepted quantity of Cape Seal will be paid for at the Contract unit price per square yard, which shall be full compensation for furnishing, transporting, handling and placing the material specified and furnishing of all labor, tools, equipment, pavement surface cleaning, and incidentals for the satisfactory completion of the work.

Item No.23: TEXTURED SYNTHETIC PAVEMENT

The work under this item shall consist of preparing pavement surface and installation of eight to ten (8 – 10) foot wide Textured Synthetic Pavement at proposed crosswalk locations selected by the Town and in accordance with the following:

Preparation of Asphalt Surface

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The section of pavement to be replaced shall be sawcut in neat lines eight to ten feet apart in the direction of the proposed crosswalk. The final surface pavement shall then be cold planed to an approximate depth of 0.75 inches. The Contractor shall immediately remove all residual material resulting from this work. All excavated material shall be disposed of by the Contractor offsite.

Installation of Textured Synthetic Pavement

The Contractor shall be responsible for the preparation, placement and patterning of Textured Synthetic Pavement. This synthetic paving material shall be composed of a hot-applied, resin-based compound formulated with a color stable pigment throughout that can be surface textured to simulate a brick pattern. Said pattern shall be oriented such that the continuous lines of the brick pattern shall be perpendicular to the parallel edges of the proposed crosswalk. The Contractor will be required to overlay in previously prepared recessed pavement surfaces as described above, and as required and approved by the Town.

The Contractor must be a manufacturer authorized applicator, experienced with this specialized system, satisfactory to the Engineer. Contractor shall furnish shop drawings, from manufacturer, to confirm design intent. A manufacturer representative shall be present at all times during the placement and curing of the textured synthetic pavement materials.

Using manufacturer prescribed methods and equipment, the Contractor shall adequately heat and uniformly mix the synthetic material(s) together. Maximum heating temperature of the completed formulation is 440 degrees Fahrenheit.

The Contractor shall then apply the heated, mixed synthetic material to the surface of the hardened, structurally sound, asphalt pavement. The synthetic material shall be spread and leveled to the desired build thickness of 0.75 inches, using manufacturer's specialized ironing tools, heated sufficiently to smooth the surface to a state of readiness for texturing. No material shall be applied when precipitation is present.

The color and surface pattern shall be a red colored brick pattern.

Texturing will begin immediately after leveling has occurred, while the material is still hot enough to allow the mold selected, to adequately penetrate the surface and create the desired pattern or form.

Once the finished surface has cooled completely and has hardened to the manufacturer's specification to support vehicular and pedestrian traffic, the application area may be opened to vehicular and/or pedestrian traffic.

Any residual material resulting from this work shall be removed and disposed of in a proper manner off site. The completed work area shall be left in a neat and clean condition, satisfactory to the Engineer.

The products used in this surfacing system shall meet the material specifications outlined below and conform to the minimum following physical and performance properties: hot-applied resin-based compound developed specifically for use on asphalt or cement concrete, with superior adhesion, flexibility and abrasion resistance characteristics, as well as color stability, chemical resistance and scrub ability.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The Contractor, during the operation of work, to save from harm and injury, any structure, public or private, situated above or below the surface and lying within the scope of the project. If during the execution of the work, the Contractor, through willfulness or carelessness, permits or causes any damage, the cost of satisfactory repair or replacement shall be the financial responsibility of the Contractor.

Synthetic Pavement Material

The material to be used under this item shall be Textured Synthetic Pavement as manufactured by Jarvis Infrastructure Services, Kennesaw, Georgia. The material required shall be Grade 60 (HEAVY TRAFFIC) and shall conform to the relevant physical properties outlined as follows:

	Grade 60 (HEAVY TRAFFIC)
Average Temp. Range:	25 - 140 degrees F
Wheel Tracking @ 113 F:	less than 1 mm/ hr
Wheel Tracking @ 140 F:	less than 5 mm/hr
Density:	2.12
Cone Flow Test: (5 hrs. @ 194 F)	15% maximum
Plane Test: (5 hrs. @ 194 F)	5% maximum
Indent @ 104 F:	50 dmm maximum
Indent @ 122 F:	75 dmm maximum
Ash Content:	90% maximum
Skid Resistance Value:	55 - 70

Equipment Required

Contractor shall possess and be familiar with the specialized machinery necessary to perform the procedures as outlined and contained within this technical specification package, including, but not limited to, appropriate trucks, compressors, miscellaneous asphalt equipment, dispensers, applicators, cutters and/or specialized tools etc.

Compensation

Textured Synthetic Pavement shall be paid for at the Contract unit price per square yard in place, which price shall include all labor, materials, equipment, sawing, cold planning, cleanup, hauling, disposing, and incidental costs required to complete the work.

Item #24 Street Sweeping

The work under this item consists of sweeping streets, sidewalks, parking lots, and other impermeable surfaces at various locations owned by program participants. Work under this item shall be performed under the direction and to the satisfaction of the Director of Public Works, Highway Superintendent, or similar official. All workmanship shall be of the highest quality. Any workmanship determined to be

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

below the high standards of the particular craft involved will not be accepted, and will be corrected as required by the Director.

Scope of Work

The winning bidder shall provide sweepers and operators to perform street sweeping services in accordance with these specifications and typical municipal street sweeping practices and procedures. The work shall include fully sweeping both sides of paved roadways between the normal curb lines whether an actual curb exists or not. The work shall also include parking lots, sidewalks, or areas adjacent to paved roadways.

Sweeping activities shall remove regular day-to-day buildup of sediment, leaves, and typical debris from the paved surfaces. Any excessive, out of the ordinary, buildup including leaves deeper than three inches (3”), debris or material resulting from construction work, or other large amounts of debris from storms, high winds, or flooding shall be excluded from the contract unless otherwise agreed upon between the winning bidder and participant. Any areas determined to have excessive buildup shall be reported to the participant immediately for inspection. Sweeping shall not include any streets which would cause damage to the equipment used. The participant will not require the winning bidder to re-sweep areas that were blocked by parked cars. The winning bidder shall re-sweep any streets determined not to meet the specifications at no additional expense at the discretion of the Director.

Sweeper operators must have at least one (1) year of experience operating street sweepers. The participant reserves the right to lead or follow the contracted sweepers with a sweeper owned and operated by the participant if determined beneficial. The participant may also assign personnel in participant vehicles to accompany the sweepers in order to coordinate work and monitor progress.

The winning bidder shall supply all labor, equipment, and supplies necessary to mechanically sweep streets in accordance with the specifications and Contract Documents. All equipment and machines supplied and used by the winning bidder shall be maintained by the winning bidder.

The winning bidder agrees not to subcontract or assign this Contract in whole or in part without the written approval of the Director.

Equipment

Sweeping equipment shall be performed by mechanical means or Air Type Sweeper capable of picking up sand, salt, small stones, sediment, glass, leaves, debris, etc. normally found within municipal roadways. The equipment is not required to pick up larger items that would damage the equipment.

All equipment utilized by the winning bidder shall be in good condition and have all systems working properly. Sweepers shall have two side brooms and a main broom capable of sweeping a minimum eight-foot (8’) wide path. All brooms and pick-up assemblies shall be of good quality such that the equipment will sweep up normal road sediment and debris in one pass. All broom cycles shall operate independently of ground speed such that a reduction of ground speed will not affect brooming action. Sweepers shall be operated at speeds that effectively remove sediment and debris.

Street sweeping equipment used must be capable of unloading directly into participant-owned dump trucks (minimum 8’-6’” dump height) and/or containers without the need for a front-end loader or other mechanical equipment. Each sweeper shall have independent wet systems capable of controlling dust.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Sweepers and equipment shall be operated in accordance with manufacturer's recommended settings, standards, and procedures. A sufficient supply of spare brooms and parts must be kept on hand to insure continuous operation. All equipment used by the winning bidder will be maintained by them and shall be kept in good operating condition.

Sweepers utilized for this contract must be no more than ten (10) years old and must be in a good condition acceptable to the Director. The winning bidder must have proof of ownership or signed lease for the duration of the contract of at least one (1) machine which meets the above requirements before contract award. Sweepers must be properly registered and insured in accordance with Motor Vehicle Laws of the Commonwealth of Massachusetts and US DOT regulations.

The winning bidder may petition the Director in writing to allow for the use of an alternative type of sweeper. The winning bidder must provide the specifications of the proposed machine and a demonstration must be performed to the satisfaction of the Director. If approved, the participant maintains the right to reverse this decision if the Director has determined that this alternative sweeper has not performed satisfactorily.

Disposal

The winning bidder shall dump collected sweepings directly into trucks provided by the participant unless otherwise directed or agreed upon with the participant. The participant, at their discretion, may designate dumpsites for emptying sweepers if determined to be in the best interest of the participant. The winning bidder shall coordinate the location and dumping schedule with the participant a minimum of twenty-four (24) hours prior to any sweeping activities.

Once sweepings have been dumped by the winning bidder, the participant shall be responsible for handling, hauling, and disposal of the sweepings. The participant will dispose of the street sweepings under a separate contract.

Communication

The winning bidder must have a supervisor or foreman available to direct operations. This supervisor or foreman will report to the Director, or their designee, any problems as well as give progress reports. The winning bidder shall be required to report any spills or illegal discharges to the Director immediately.

The participant may choose to loan a portable radio to the contract sweeper such that communications may be made with participant to coordinate sweeper dumping. This radio shall be the winning bidder's responsibility and subject to replacement with a new radio if the winning bidder loses or damages said radio.

Schedule & Sequence of Cleaning

The participant will make available to the winning bidder Work Route Maps showing the sequence in which the winning bidder will proceed in street sweeping, authorized hydrant access, and dump sites if permitted. Prior to the commencement of any work, the winning bidder shall submit an estimated schedule to the participant for approval. Services will generally be performed on a regularly scheduled workday following a forty-eight (48) hour notice to the Town. Hours of operation shall be weekdays from 7:30 A.M. to 3:00 P.M. unless otherwise approved by the Director in writing. The Contractor will

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

not receive additional compensation for working outside of this window and the times and day to be approved by the Director. Contractor will not be paid “travel time” to or from the Town or other extras.

Once work begins, the winning bidder shall continuously prosecute the work in accordance with the Contract Documents and approved schedule unless otherwise authorized or directed by the participant. Any adjustments to the approved schedule must be approved in writing by the Director. The participant reserves the right to change the approved schedule or sequence of work at any time.

Use of Fire Hydrants

The winning bidder shall be allowed the use of certain fire hydrants, as designated by the participant, as may be necessary to prosecute the specified work. Water will be furnished free of charge by the participant for the tasks specified in the Contract only. The winning bidder will be charged for any unreasonable use of water.

A participant-issued meter and backflow preventor must be used at each hydrant connection. Only tools specifically manufactured for opening hydrants may be used on participant hydrants. The winning bidder must be familiar with the process of drawing hydrant water and closing of the valves and must supply all tools, hoses, and equipment to make the connections. The winning bidder shall make every effort possible not to disturb sediment in the water system when operating a hydrant.

The winning bidder shall maintain a log of all hydrant use including date, location, time, and estimated amount of water drawn from the hydrant. The logs must be submitted to the Director at the end of each week.

Water may also be made available from a participant-supplied truck mounted tanker.

Record Keeping

The winning bidder shall be responsible for maintaining a log of all sweeping activities conducted. Information should include the date and hours of sweeping activities, roads swept each day, overall miles of road swept, operator names, sweepers used, and approximate amount of sediment and debris removed. The winning bidder shall also report to the Director any roads with higher than normal sediment and debris loads. Logs shall be submitted to the participant at the end of each week in which sweeping activities have occurred.

The winning bidder shall also maintain a map which highlights each road that has been swept to date. The date the road was swept shall also be noted on the map. This map shall be provided to the participant every thirty (30) days and shall also be made available to the participant upon request at any time. The participant reserves the right to require each sweeper to carry a participant issued GPS device to track and monitor sweeping activities.

Traffic Control

The winning bidder is responsible for all traffic control and signage as is necessary to provide for the safety of workmen, equipment, and the traveling public. The winning bidder shall not block or stop the normal flow of traffic. Certain locations may require a police detail. Any required police details shall be paid for by the participant at no additional expense to the winning bidder. At no time shall sweeping be performed against the traffic flow.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Payment

Street sweeping shall be performed and measured on a per hour basis for one (1) sweeper. A minimum of four (4) hours of work is guaranteed during each calendar day that work is requested under this item. Work completed after the first four (4) hours during the same calendar day will be paid for at the hourly rate specified in the FORM OF GENERAL BID for each additional hour of work completed. Travel time to and from the participant will not be eligible for payment.

The unit bid price shall include all equipment, fuel, tools, transportation, traffic control, and labor incidental to the completion of the sweeping work in accordance with the provisions of these specifications. Mobilizations shall be included in the unit bid price; no additional payment will be made for mobilization, travel time to and from the participant, or unauthorized idle time.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

ITEM 100 CHLORINATED RUBBER PAINT AND BEADS FOR 4" REFLECTORIZED LINE
ITEM 100A CHLORINATED RUBBER PAINT AND BEADS FOR (DOUBLE) 4" REFLECTORIZED LINE
ITEM 101 CHLORINATED RUBBER PAINT AND BEADS FOR STOP BARS & CROSSWALKS
ITEM 102 CHLORINATED RUBBER PAINT AND BEADS FOR ARROWS & MISCELLANEOUS MARKINGS

The Work shall include the furnishing and installing of alkyd traffic paint modified with chlorinated rubber and glass beads conforming to Section M7 of the Standard Specifications. The white or yellow reflectorized traffic paint shall comply with Section 860 of the Standard Specifications.

Low VOC Chlorinated Rubber Traffic Paint

The durable, fast drying, Alkyd modified with chlorinated rubber traffic paint shall conform to the current V.O.C. regulations and the following:

Composition	White	Yellow (lead free)
Vehicle % by wt.	40-43	40-43
Pigment % by wt.	57-80	57-60
Total Solids % by wt.	74 min	74 min
Total Solids % by vol.	50 min	50 min
V.O.C. grams/liter	150 max	150 max
Titanium dioxide rutile (type II)	1 lb/gal min	.3 lbs/gal min
Organic yellow pigment (lead free)	n/a	.25 lbs/gal min
Chlorinated rubber	.5 lbs/gal min	.5 lbs/gal min
Detailed Requirements		
Wt/Gal	12.5 +/-.2	12.1 +/-.2
Viscosity K.U.	75-85	75-85
Dry Time 15 mils wet film @ 77 F Minutes	10 max	10 max
Dry Opacity @ 15 mils wet	.96 min	.96 min
Reflectance	84 min	50 min
Grind	3 min	3 min
CC Flash Point (F)	(-4 F) min	(-4 F) min

The application rates shall be 1 gallon of paint and 5 pounds of beads per 320 linear feet of 4" wide line.

Application Conditions

Temperature: 50°F (10°C) minimum, 110°F (43°C) maximum (air, surface, and material) and at least 5°F (2.8°C) above dew point
Relative humidity: 85% maximum

Equipment

The Contractor shall supply 1 long line spray truck, manufactured with stainless steel components to properly apply alkyd traffic paint modified with chlorinated rubber, capable of applying solid lines in a sharp and true manner. The unit must have a minimum paint tank capacity of 400 gallons and a minimum bead truck capacity of 2,000 pounds. The long line spray truck must be capable of producing

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

an acceptable 4" wide single or double line at the application rate of 5 pounds of beads per 4” line. The long line spray truck must be capable of applying 320 lineal feet of 4” reflectorized line per one gallon of paint while traveling at a minimum of 7 miles per hour or 320 lineal feet of double 4” reflectorized line per two gallons of paint at the same speed. ~~and 320 lineal feet per one gallon of paint while traveling at a minimum of 7 miles per hour.~~

The Contractor shall supply 1 cone truck (rack body with hydraulic tail gate) with 300 cones.

The above units shall include protective devices and warning signs for the painting operation. Each unit shall be radio controlled with a portable unit available for the Highway Division lead truck.

The Contractor shall supply 2 operating personnel for the spray truck and 3 cone setters/retriever personnel for the traffic cone setting truck.

The Contractor will place traffic cones on all freshly painted lines to reduce tracking.

Contractor Responsibilities

The Contractor shall complete the painting as indicated herein, subject to weather conditions, such as wet or extremely cold pavement. The Contractor shall have backup equipment available to him in the event of a breakdown.

The Contractor shall have a supervisor or foreman available to direct operations. The supervisor or foreman will report to the Highway Division Superintendent or his designee, any problem, as well as, give daily progress reports.

The Contractor must show by past performance that he is capable of performing a Contract of this magnitude.

On new road surfaces, the Contractor shall pre-mark the centerlines and fog lines, as needed, at no additional cost to the Town.

Measurement and Payment

The measured quantity for 4” Reflectorized Line, double reflectorized line, and 12” Stop Bars and Crosswalks will be paid at the Contract Unit Price per Linear Foot, which price shall include all labor, equipment, materials and incidental costs required to complete the Work. The measured quantity for Arrows and Miscellaneous Markings will be paid at the Contract Unit Price per Square Foot, which price shall include all labor, equipment, materials and incidental costs required to complete the Work.

ITEM 103 THERMOPLASTIC PAINT FOR 4” REFLECTORIZED LINES
ITEM 103A THERMOPLASTIC PAINT FOR (DOUBLE) 4” REFLECTORIZED LINES
ITEM 104 THERMOPLASTIC PAINT FOR STOP BARS & CROSSWALKS
ITEM 105 THERMOPLASTIC PAINT FOR ARROWS & MISCELLANEOUS MARKINGS

The Work under these items shall conform to the relevant provisions of Section 860 of the Standard Specifications and the following:

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Material used and method of installation shall conform with the relevant provisions of Subsection M7, M7.01.03, M7.01.04, M7.01.18, and 860 of the Standard Specifications. All dimensions and spacing shall be as directed by the Engineer.

The Contractor shall install all pavement markings at locations as directed by the Engineer. **On new road surfaces, the Contractor shall pre-mark the centerlines and fog lines, as needed, at no additional cost to the Town.**

Measurement and Payment

The measured quantity for Single 4" Reflectorized Line, Double 4" Reflectorized Line and 12" Stop Bars and Crosswalks will be paid at the Contract Unit Price per Linear Foot, which price shall include all labor, equipment, materials and incidental costs required to complete the Work. The measured quantity for Arrows and Miscellaneous Markings will be paid at the Contract Unit Price per Square Foot, which price shall include all labor, equipment, materials and incidental costs required to complete the Work.

ITEM 106 EPOXY PAINT FOR 4" REFLECTORIZED LINES
ITEM 106A EPOXY PAINT FOR (DOUBLE) 4" REFLECTORIZED LINES

Work under these items cover white and yellow epoxy reflectorized pavement marking material that is sprayed onto the pavement. Immediately following this, a surface application of glass beads is applied. The work, materials, and methods of installation under these items shall conform to the relevant provisions of Sections 860 and subsection M7 of the Standard Specifications. and the following:

The epoxy marking material shall be two-component (Part A and Part B), 100% solids type system formulated and designed to provide a simple volumetric mixing ratio (e.g. two volumes of Part A to one volume of Part B).

Part A of both white and yellow shall conform to the following requirements:
Percent by weight:

WHITE Pigment - 18 Minimum, Titanium Dioxide (ASTM D476, Type II) Epoxy Resin - 75 to 82
YELLOW Pigment - 18 Minimum, Titanium Dioxide (ASTM D476, Type II) 5 Minimum, Organic Yellow, Epoxy Resin – 73 to 77
The entire pigment composition shall consist of either titanium dioxide or titanium dioxide and organic yellow. No extender pigments are permitted. Yellow pigment shall be lead-free.
The work of these items shall only be performed when atmospheric and surface temperatures are 40˚F higher

On new road surfaces, the Contractor shall pre-mark the centerlines and fog lines, as needed, at no additional cost to the Town.

All dimensions and spacing shall be as directed by the Engineer.

The measured quantity for Epoxy Paint for 4" Reflectorized Lines and Epoxy Paint for 4" Double Reflectorized Lines will be paid at the Contract Unit Price per Linear Foot, which price shall include all labor, materials and incidental costs required to complete the work.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

ITEM 107 PAVEMENT MARKING REMOVAL

The Work under this section shall conform to the relevant provisions of Section 850.67 of the Standard Specifications and the following. Existing pavement markings shall be removed to the fullest extent possible by an approved method. Pavement removal methods shall not cause damage to the pavement or cause drastic change in texture, which could be construed as delineation at night, and shall be approved by the Town. It is not permissible to paint over existing markings with black paint in lieu of removal. Approved methods include but are not limited to:

1. High pressure air.
2. High pressure water (cold weather use not permitted).
3. Sand blasting.
4. Mechanical devices such as grinders, sanders, scrapers, scarifiers, and wire brushes.

Painting over a pavement marking by use of asphaltic liquids or paints will not be permitted. Conflicting pavement markings shall be removed before any change in the traffic pattern.
Material deposited on the pavement as a result of removing markings shall be removed as the work progresses. Accumulations of sand or other material, which might interfere with drainage or could constitute a hazard to traffic, will not be permitted.

Any damage to the pavement or surfacing caused by pavement marking removal shall be satisfactorily repaired at no additional cost to the Town.

Where the removal operation is being performed near a lane occupied by traffic, a vacuum attachment operating concurrently with the removal operation must be in use. All residues shall be removed immediately from the surface being treated.

The measured quantity will be paid for at the Contract Unit Price per Square Foot which price shall include all labor, equipment, vacuuming, sweeping, hauling, disposing, and incidental costs required to complete the Work.

ITEM 108 DRAINAGE PIPE CLEANING

The Work under this item consists of the cleaning of existing drainage pipes. Work under this item shall be performed under the direction and to the satisfaction of the Highway Division Superintendent or his designee.

Drainage pipe cleaning will be paid for at the Contract Unit Price per Day (8 working hours exclusive of travel time) broken down as follows:

* Drainage pipe cleaning performed between 0 and 4 hours will be paid for at half the Contract Unit Price per Day.

* Drainage pipe cleaning performed for a period greater than 4 hours will be paid for at a proportion of the full Contract Unit Price per Day.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The Contract Unit Price per Day shall include all labor, equipment, transportation and incidental costs required to complete the Work. The Work under this item does not include the removal and legal disposal of hazardous material.

ITEM 109 DRAINAGE STRUCTURE CLEANING BY CLAMSHELL (WITH DISPOSAL)

The Work under this item consists of the cleaning of existing drainage structures. The Work also includes the complete removal and legal disposal of the debris. Work under this item shall be performed under the direction and to the satisfaction of the Highway Division Superintendent or his designee.

Drainage structures shall be cleaned along their entire circumference. Debris shall be substantially (95%) removed from the structure walls and bottoms. The proposed equipment shall be submitted for approval by the Town Engineer or his designee.

The contractor shall be responsible for stockpile area management including confinement of debris, erosion control, loading, and removal of the debris. The contractor shall provide documentation of proper disposal to the town as a condition of payment. The contractor shall be responsible for any testing costs required for legal disposal of the catch basin cleanings. It is the responsibility of the Contractor to contact each Town and determine if a staging and stockpile area is available on town property or if the contractor will have to make alternative arrangements for a legal stockpile area.

The Contract Unit Price per Each shall include all labor, materials, equipment, transportation and incidental costs required to complete the Work. The Work under this item does not include the removal and legal disposal of hazardous material.

ITEM 110 DRAINAGE STRUCTURE CLEANING BY CLAMSHELL (W/O DISPOSAL)

The Work under this item consists of the cleaning of existing drainage structures. Work under this item shall be performed under the direction and to the satisfaction of the Highway Division Superintendent or his designee.

Drainage structures shall be cleaned along their entire circumference. Debris shall be substantially (95%) removed from the structure walls and bottoms. The proposed equipment shall be submitted for approval by the Town Engineer or his designee.

The town shall provide the contractor an area to dump the catch basin cleanings. The town will manage the stockpile area and legally dispose of the debris.

The Contract Unit Price per Each shall include all labor, materials, equipment, transportation and incidental costs required to complete the Work. The Work under this item does not include the removal and legal disposal of hazardous material.

ITEM 111 DRAINAGE STRUCTURE CLEANING BY VACUUM TRUCK (WITH DISPOSAL)

The Work under this item consists of the cleaning of existing drainage structures. The Work also includes the complete removal and legal disposal of the debris. Work under this item shall be

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

performed under the direction and to the satisfaction of the Highway Division Superintendent or his designee.

Drainage structures shall be cleaned along their entire circumference. Debris shall be substantially (95%) removed from the structure walls and bottoms. The proposed equipment shall be submitted for approval by the Highway Division Superintendent.

The contractor shall be responsible for stockpile area management including confinement of debris, erosion control, loading, and removal of the debris. The contractor shall provide documentation of proper disposal to the town as a condition of payment. The contractor shall be responsible for any testing costs required for legal disposal of the catch basin cleanings. It is the responsibility of the Contractor to contact each Town and determine if a staging and stockpile area is available on town property or if the contractor will have to make alternative arrangements for a legal stockpile area.

The Contract Unit Price per Each shall include all labor, materials, equipment, transportation and incidental costs required to complete the Work. The Work under this item does not include the removal and legal disposal of hazardous material.

ITEM 112 DRAINAGE STRUCTURE CLEANING BY VACUUM TRUCK (W/O DISPOSAL)

The Work under this item consists of the cleaning of existing drainage structures. The Work also includes the complete removal and legal disposal of the debris. Work under this item shall be performed under the direction and to the satisfaction of the Highway Division Superintendent or his designee.

Drainage structures shall be cleaned along their entire circumference. Debris shall be substantially (95%) removed from the structure walls and bottoms. The proposed equipment shall be submitted for approval by the Highway Division Superintendent.

The town shall provide the contractor an area to dump the catch basin cleanings. The town will manage the stockpile area and legally dispose of the debris.

The Contract Unit Price per Each shall include all labor, materials, equipment, transportation and incidental costs required to complete the Work. The Work under this item does not include the removal and legal disposal of hazardous material.

ITEM 113 DRAINAGE STRUCTURE ADJUSTED

The Work under this item shall consist of the adjustment of utility castings for overlays and minor reconstruction where said adjustment is no greater than 6 inches (rise or fall) from existing line and grade and shall conform to the relevant provisions of Sections 201, 202, and 220 of the Standard Specifications and the following:

The Contractor shall maintain the drainage (or sewer) system in the project areas or drainage facilities outside the project area affected by the work performed by the Contractor to provide continual drainage of the travel ways and construction areas. All drainage (or sewer) castings required to be raised to accommodate pavement overlays shall be paid for under this item.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

When in the judgment of the Engineer, the masonry below the casting shows deterioration and directs the contractor to remodel, the pay item shall be by the vertical foot and the cost per vertical foot as measured from the bottom of the existing casting, shall be paid as described in Item 108 Drainage Structure Rebuilt.

Clay brick conforming to Subsection M4.05.2 of the Standard Specifications shall be used to make grade adjustments of structure frames.

Any castings damaged due to the Contractor's operations shall be replaced with similar H-20 North American made cast iron castings at no cost to the Town.

A structure adjusted more than once by the Contractor, due to his plan of operation, will be paid for only once regardless of how many adjustments are made to the structure.

The Contract Unit Price per Each shall include all labor, materials, equipment, transportation and incidental costs required to complete the Work. No separate payment will be made for the maintenance of the existing drainage (or sewer) system, but all costs in connection therewith shall be included in the unit prices bid for the various Contract items.

ITEM 114 DRAINAGE STRUCTURE REBUILT

This item applies to the complete rebuilding of an existing structure and includes new masonry construction, backfilling around structures and other incidental work and shall conform to the relevant provisions of Sections 201 and 220 of the Standard Specifications and the following:

The Work shall consist of rebuilding, removing, replacing and adjusting the masonry units and adjusting the castings of existing structures. The casting and deteriorated masonry shall be removed in a neat manner until a clean sound base is obtained upon which concrete blocks and clay bricks may be set to rebuild the structure.

Sand borrow shall be furnished by each Town for backfill where required when excavated material is unsuitable.

Method of measurement shall be measured by the average height in vertical feet and tenths of feet from the bottom row of rebuilt masonry to the bottom of casting.

The cost of removing and replacing the casting, excavation, backfilling around structures and other incidental work shall be included in the unit price for this Item.

The Contract Unit Price per Vertical Foot shall include all labor, materials, equipment, transportation and incidental costs required to complete the Work.

ITEM 115 STEEL BEAM (WEATHERING) HIGHWAY GUARDRAIL (SINGLE FACED/WOOD POSTS)

The Work shall include the furnishing and installation of 12 gauge corrosion resistant (weathering) steel beam rails conforming to AASHTO M180 and wood posts (6" x 8" x 6') and offset blocks (6" x 6") conforming to relevant provisions of Sections 600 and M8.07.0 of the Standard Specifications and to the

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Construction Standards. Posts shall be set at 6 feet 3 inches on center. Standard reflectors (MHD Item 833.5 Demountable Reflectorized Delineator - Guardrail) shall be furnished and installed on every other panel at no additional cost to the Town. Contractor to install zinc inserts between overlapping guardrail sections of weathering steel beam rails.

The contractor shall be guaranteed a minimum of 100 linear feet/day

The measured quantity will be paid for at the Contract Unit Price per Linear Foot, which price shall include all labor, materials (including but not limited to reflectors and zinc insert), equipment, and incidental costs required to complete the Work. If requested by a Town, the Contractor shall negotiate a fair additional for end treatments.

ITEM 115A STEEL BEAM (WEATHERING) HIGHWAY GUARDRAIL (SINGLE FACED/STEEL POSTS)

The Work shall include the furnishing and installation of 12 gauge corrosion resistant (weathering) steel beam rails conforming to AASHTO M180 and steel posts conforming to relevant provisions of Sections 600 and M8.07.0 of the Standard Specifications and to the Construction Standards. Posts shall be set at 6 feet 3 inches on center. Standard reflectors (MHD Item 833.5 Demountable Reflectorized Delineator - Guardrail) shall be furnished and installed on every other panel at no additional cost to the Town. Contractor to install zinc inserts between overlapping guardrail sections of weathering steel beam rails.

The contractor shall be guaranteed a minimum of 100 linear feet/day

The measured quantity will be paid for at the Contract Unit Price per Linear Foot, which price shall include all labor, materials (including but not limited to reflectors and zinc insert), equipment, and incidental costs required to complete the Work. If requested by a Town, the Contractor shall negotiate a fair additional for end treatments.

ITEM 116 STEEL BEAM (WEATHERING) HIGHWAY GUARDRAIL (SINGLE FACED/WOOD POSTS)(INCLUDING REMOVAL AND STACKING OF EXISTING GUARDRAIL)

The Work shall include everything outlined above in the immediately preceding item plus the removal and stacking of existing guardrail of various types. If requested by a Town, the Contractor shall negotiate a fair additional cost for end treatments. Contractor to install zinc inserts between overlapping guardrail sections of weathering steel beam rails.

The contractor shall be guaranteed a minimum of 100 linear feet/day.

The measured quantity will be paid for at the Contract Unit Price per Linear Foot, which price shall include all labor, materials (including but not limited to reflectors and zinc insert), equipment, and incidental costs required to complete the Work. If requested by a Town, the Contractor shall negotiate a fair additional for end treatments.

ITEM 117 STEEL BEAM (WEATHERING) HIGHWAY GUADRAIL-TERMINAL END WITH WOOD POSTS

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The Work shall include the furnishing and installation of a steel beam (weathering steel) terminal end in conjunction with Items 115 & 116 which shall consist of curved guard rail section, wood posts, offset blocks, and "boxing glove" end, conforming to AASHTO M180 and wood posts (6" x 8" x 6') and offset blocks (6" x 6") conforming to relevant provisions of Sections 601 and M8.07.0 of the Standard Specifications and to the Construction Standards. Posts shall be set at 6 feet 3 inches on center. Contractor to install zinc inserts between overlapping guardrail sections of weathering steel beam rails.

The measured quantity will be paid for at the Contract Unit Price per Each, which price shall include all labor, materials (including but not limited to reflectors and zinc insert), equipment, and incidental costs required to complete the Work and shall include 13 ft long +/-curved guard rail section, wood posts, boxing glove end and Standard reflector (MHD Item 833.5 Demountable Reflectorized Delineator - Guardrail)

ITEM 117A STEEL BEAM (WEATHERING) HIGHWAY GUADRAIL-TERMINAL END WITH STEEL POSTS

The Work shall include the furnishing and installation of a steel beam (weathering steel) terminal end in conjunction with Items 115 & 116 which shall consist of curved guard rail section, steel posts, and "boxing glove" end, conforming to AASHTO M180 and steel posts conforming to relevant provisions of the Standard Specifications and to the Construction Standards. Posts shall be set at 6 feet 3 inches on center. Contractor to install zinc inserts between overlapping guardrail sections of weathering steel beam rails.

The measured quantity will be paid for at the Contract Unit Price per Each, which price shall include all labor, materials (including but not limited to reflectors and zinc insert), equipment, and incidental costs required to complete the Work and shall include 13 ft long +/-curved guard rail section, steel posts, boxing glove end and Standard reflector (MHD Item 833.5 Demountable Reflectorized Delineator - Guardrail)

ITEM 117B- MASH COMPLIANT SKT TREATMENT WITH TRANSITION COATING

MASH-compliant Sequential Kinking Terminal (MSKT) is 50' long and has eight posts spaced at 6'-3" centers and including 50' trailing anchorage transition piece into an existing or new NCHRP-350 guardrail. Refer to MassDOT Construction Standards 'Transition to NCHRP 350 Guardrail'. MSKT shall be factory painted to match existing weathered steel guardrails.

Galvanized steel beam guardrail painted to Federal standard color determined by the Towns:

- Brush blast the material, to remove any debris, with #100 sand, which is a finer sand, to a ½ MIL profile
- Apply an epoxy coating 3-5 MILS
- Apply an aliphatic polyurethane topcoat to specific paint spec,
- Federal Standard color code determined by Towns, in a semi-gloss finish
- Packaging-materials get stacked with protective foam in between each section

The measured quantity shall be paid for at the Contract Unit Price per Each, which price shall include all labor, materials, equipment, and incidental costs required to complete the Work and shall include 100'+/- transition and MSKT end, painting steel posts and standard reflector.

ITEM 118 STEEL BEAM HIGHWAY GUARDRAIL (SINGLE FACED/WOOD POSTS)

The Work shall include the furnishing and installation of steel beam guard rail and posts conforming to the Standard Specification subsection M 8.07.0. Posts shall be set at 6 feet 3 inches on center. Standard

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

reflectors (MHD Item 833.5 Demountable Reflectorized Delineator - Guardrail) shall be furnished and installed on every other panel at no additional cost to the Town.

Each site shall be a guaranteed minimum of 100 linear feet.

The measured quantity will be paid for at the Contract Unit Price per Linear Foot, which price shall include all labor, materials, equipment, and incidental costs required to complete the Work. If requested by a Town, the Contractor shall negotiate a fair additional cost for removal/disposal of existing guardrail and/or end treatments.

ITEM 119 STEEL-BACKED TIMBER GUARDRAIL

The Work under this Item shall conform to Sections 106, 601, 617, 710 and 716 of the U.S. Department of Transportation Federal Highway Administration Standard Specifications for Construction of Roads and Bridges on Federal Highway Projects (FP-85), all subsequent errata and addenda, to the applicable provisions of the Standard Specifications and the following:

Materials

Timber Rail: The timber shall conform to AASHTO M 168. Fabricate the 6 by 10 inch timber rail from dry, well seasoned, and dressed rough sawn Douglas Fir, Southern Pine, or other species having a stress grade of at least 1,500 psi.

Treat the timber rail and wood elements with CCA, ACZA, or ACA preservative treatment conforming to AWPA C14 except the minimum retention shall be 0.60 lbs/ft.
Steel: Fabricate the steel backing elements from 0.375 inch structural steel conforming to AASHTO M 222 M. Fastener hardware shall conform to AASHTO M 164, Type 3.

Wood Posts: The 10" by 12" inch guardrail posts shall conform to materials for timber rail as specified above.

Guardrail Hardware: Hardware shall conform to the AASHTO – AGC – ARTBA "A Guide to Standardized Highway Barrier Hardware," 1995 Edition.

Construction Methods

The Steel-Backed Timber Guardrail shall be Type A, and the Turn-down Terminal Section shall be Type FAT – 30 or Type FAT –20 as directed by each Town.

Posts shall be placed plumb, in hand or mechanically dug holes, then backfilled with approved gravel material placed in 6 inch layers and thoroughly compacted.

Where it is possible to maintain 2-feet minimum between the back of the guardrail post and the top of a slope 2:1 or steeper, the post length may be reduced to 7 feet.

Retreat field cuts of posts and rails, where required, with two coats of preservative treatment. Field cuts shall not be in contact with the ground.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Field cut steel rails and field drill holes in the steel splice plates at joints only where required to correspond to field cut wood rails at joints. Do not modify hole and slot dimensions. Do not use torch to cut holes, slots, plates or rails.

A wooden guardrail post that has a through check, shake or end split in the same plane as, or a plane parallel to the bolt hole and extending from the top of the post to within 3 inches of the bolt hole will be rejected.

Distance between wooden posts shall be 10 feet on center. Standard reflectors (MHD Item 833.5 Demountable Reflectorized Delineator - Guardrail) shall be provided and installed every 50' on average at no additional cost to the Town.

Construct terminal sections at the locations as directed by each Town. Terminal sections consist of posts, railing, hardware, and anchorage assembly necessary to construct the turn-down terminals.

Each site shall be a guaranteed minimum of 100 linear feet.

Measurement and Payment

Steel-Backed Timber Highway Guardrail (including reflectors and turn-down terminals) will be measured by the Linear Foot along the face of rail element, including terminal sections. The quantity for Steel-Backed Timber Highway Guardrail will be paid for at the Contract Unit Price bid per Linear Foot, which price shall be full compensation for all materials, tools, equipment and labor incidental to and necessary for the completion of the work in place to the satisfaction of each Town. If requested by a Town, the Contractor shall negotiate a fair additional cost for removal/disposal of existing guardrail and/or end treatments.

ITEM 120 WOODEN GUARDRAIL

The Work shall include the furnishing and installation of wooden guardrail and posts conforming to Section M8.07.0, paragraph B.2 Wood Posts and paragraph D, Bolts, Nuts and Washers of the Standard Specifications; and, the following specifications.

All posts shall be sawed off square prior to setting. Posts shall be set plumb and to line and grade. Post spacing shall be 4'-0" on center. Single wood rails shall be erected as to form a smooth, continuous rail conforming to the required line and grade. Wood rail elements shall butt firmly against each other and joints shall occur in the direct center of the post. All bolts shall be drawn tight. Ends shall be angled downward at approximately a 30 degree angle with a 1 foot tall post unless otherwise directed by the Engineer. The end of the angled rail shall be cut to butt firmly against the horizontal rail. Rails shall be 4" x 10" x 16' pressure treated Southern Yellow Pine. Standard reflectors (MHD Item 833.5 Demountable Reflectorized Delineator - Guardrail) shall be provided and installed every 50' on average at no additional cost to the Town.

Each site shall be a guaranteed minimum of 100 linear feet.

The measured quantity will be paid for at the Contract Unit Price per Linear Foot, which price shall include all labor, materials (including reflectors), equipment, and incidental costs required to complete

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

the Work. If requested by a Town, the Contractor shall negotiate a fair additional cost for removal/disposal of existing guardrail and/or end treatments.

ITEM 121 GRANITE CURB TYPE VB – STRAIGHT
ITEM 122 GRANITE CURB TYPE VA4 – STRAIGHT
Work under these items shall conform to the relevant provision of Section 501 of the Standard Specifications and the following:

All curbing shall be set on a bed of dry compacted gravel base. The spaces between the curb and the walls of the trench **(both front and back sides of the curb)** shall be filled with 4,000 PSI concrete to the depth directed, and shall then have a 2-inch base of Hot Mix Asphalt placed upon it. This shall ensure proper adhesion of the overlays to the existing surface.

The Contractor shall be responsible for saw cutting the existing pavement edge as directed by the Town, for excavating the area needed for the curbing and concrete installation, and for hauling and disposing of the excavated material.

The Contractor shall be responsible for meeting all current Federal and State architectural accessibility requirements. This includes but is not limited to: slopes; grades; and construction materials.

If requested by the Contractor, an additional cost per Linear Foot for transition and curved granite curbing equal to the demonstrated incremental item cost per Linear Foot can be negotiated. The incremental cost must be substantiated by invoiced costs or other means satisfactory to the Town.

The measured quantity will be paid for at the Contract Unit Price per Linear Foot and any additional cost demonstrated for transition and curved curbing, shall include all labor, materials, equipment, saw cutting, excavating, hauling, disposing, and incidental costs required to complete the Work.

ITEM 123 PAVE SHIELD PAVEMENT SEALING (1,500 SQUARE YARDS OR GREATER)
ITEM 124 PAVE SHIELD PAVEMENT SEALING (UNDER 1,500 SQUARE YARDS

The Work shall consist of providing and installing two coats of an Engineered resin emulsion seal coat slurry (PaveShield by Neyra Industries, Inc.) over aged and new hot mix asphalt concrete pavements, and shall conform to the relevant provisions of the Standard Specifications and the following:

Testing Methods and Practices

ASTM C 136 Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM D 244 Standard Test Method for Emulsified Asphalts
ASTM D 2939 Method for Testing Emulsified Bitumens used as Protective Coatings
ASTM D 3910 Practices for Design, Testing, and Construction of Slurry Seal
AASHTO T-04481 - Method for Testing the Solubility of Bituminous Materials in Organic Solvents

Materials

Sealer (Pavement Coating): PaveShield manufactured by Neyra Industries, Inc., Cincinnati, Ohio; or approved equivalent. An engineered resin emulsion specifically formulated to extend pavement life.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Physical Composition: Sealer shall meet the following requirements when tested in accordance with ASTM D2939:

Requirements	Max.	Min.
Non-Volatiles %	-	47
Water %	53	-
Ash of Non-Volatiles %	40	30
Specific Gravity	-	1.1

Drying Time: When tested according to ASTM D2939, sealer shall be "set to touch" in 1 hour, and exhibit "final set" in less than 8 hours.
Non-Flammability: The cured coating shall show no tendency to flash or ignite.
Adhesion & Resistance to Water: The cured coating shall exhibit no penetration, blistering, loss of adhesion, nor tendency to re-emulsify after immersion for 24 hours.

Oil Spot Primer: Neyra Petrobond manufactured by Neyra Industries, Inc., Cincinnati, Ohio; or approved equivalent. Water based acrylic oil spot primer compatible with pavement coating.

Sand: As recommended in printed data sheets by sealer manufacturer. Washed, dry silica sand free of dust, trash, clay, organic materials or other contaminates.
Gradation: To have an American Foundry Society grain fineness number that is no less than fifty (50) and no more than seventy (70), when tested in accordance with ASTM C 136.

Mixing Water: Potable and free from harmful soluble salts. Temperature of the water shall be a minimum fifty degrees (50) F.

Submittals

Contractor shall submit to the Owner: the trade name and manufacturer of the sealer and oil spot primer; and, the sealer and oil spot manufacturer's printed Product Data Sheets and Technical Specifications.
At its discretion, Owner may require submittal of references, list of similar sites where the same products have been installed by Contractor, and other information needed by the Owner to complete its evaluation (see Instructions to Bidders contained herein).

Equipment

Use equipment that keeps the mixture homogeneous at all times and is capable of applying required coating weights evenly over entire width of application mechanism to provide a uniformly coated surface.

Construction Procedures

Site Examination(s): Contractor shall inspect new and existing paving surfaces for condition and defects that will adversely affect quality of work, and which cannot be put into an acceptable condition through normal preparatory work as specified herein. Contractor shall notify the Owner in writing of the specific defects found. Owner shall not be required to fix said defects unless Owner wishes to continue with the

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

project and have the Contractor complete the sealing work. Contractor shall not be required to place the sealer over the noted defects without the defects being repaired by the Owner.

Preparation: Owner shall be responsible for: repairing any paving defects (if he chooses to continue with the work); for pre-sweeping the areas to be sealed; for providing and installing barriers needed to protect the
work; and, for providing and paying for police services, if needed. Contractor shall be responsible for: final cleaning (e.g., removal of fines, if needed) of the areas to be sealed; for cleaning oil spots and treating with oil spot primer; and, for protecting adjacent curbs, walks, fences, and other items from receiving primer and coating.

Sealing: Contractor shall apply coating (sealer) when pavement temperature is at least fifty (50) degrees F. and air temperature is fifty (50) degrees F. and rising, and shall apply coating during dry weather and when rain is not anticipated within eight (8) hours after application is completed. Because of the public nature of the work sites, Contractor understands and agrees that he may not be allowed to close off an entire area (e.g., a golf course or Town Hall parking lot) all at once and may be required to complete sealing of an area over two work cycles.

Contractor shall add water to the coating mix as required for application, quantity not to exceed twenty five (25) percent of engineered resin emulsion; and, shall add three (3) to five (5) pounds of sand per gallon to the engineered resin emulsion, and mix with power equipment to a homogeneous coating. Contractor shall apply all coats uniformly at a rate of 0.14 - 0.17 gallons per square yard using mixed and diluted material. Each coat shall be allowed to cure sufficiently to take traffic without scuffing. Final coat shall be allowed to cure a minimum of twenty four (24) hours under good drying conditions before allowing traffic.

For new paved areas, Contractor shall allow new asphalt to cure at least thirty (30) days before applying pavement coating. There shall be no difference in payment if the existing surface is new asphalt or aged asphalt.

Contractor shall remove primer and coating from surfaces other than those requiring primer and coating.

Materials:

The aggregate shall be 1/4" or 3/8" durable crushed rock, consisting of the angular fragments obtained by breaking and crushing solid or shattered natural rock, and free from a detrimental quantity of thin, flat, elongated or other objectionable pieces. The crushed stone shall have a maximum percentage of wear as determined by the Los Angeles Abrasion Test (AASHTO-T-96) and shall be uniformly blended meeting Section M2.01.6 of the Standard Specifications. Crushed gravel will not be permitted.

The asphalt emulsion shall be a Cationic Asphalt Emulsion CRS-2 or CMS-2.

Properties:

Viscosity, Saybolt Furol @ 122 degrees F (50 degrees C),s		300
Sieve Test, %	.02	
Residue by distillation, %		67

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Test on residue from distillation test:

Penetration, 77 degrees F (25 degrees C) 100g, 5 s	140
Ductility, 77 degrees F (25 degrees C), 5 cm/min, cm	60
Solubility in 66richloroethylene, %	99

SP-27

The anti-track material shall be Black Beauty, as manufactured by the Reed Minerals Slag Products, a division of HARCO Corp. in Highland, Indiana or an approved equal.

Measurement and Payment

The measured quantity will be paid for at the Contract Unit Price per Square Yard, which price shall include all labor, materials, equipment, and incidental costs required to satisfactorily complete the work (including oil spot cleaning and priming).

ITEM 125 MODIFIED ASPHALT-FIBER CRACKFILLER

The Work under this item shall include the preparation of cracks in existing bituminous concrete pavement which may be overlain with new bituminous concrete or stone seal, and the filling of the prepared cracks with a modified asphalt-fiber compound. Work shall be completed on bituminous concrete in an "as is" condition (e.g. Towns will not sweep areas beforehand).

The crack filling material shall be a modified asphalt-fiber compound designed especially for improving strength and performance of the parent asphalt sealant. The asphalt binder shall consist of a blend of neat asphalt binder and chemically modified crumb rubber (CMCR) that meets the following specifications:

PG 64-28 or PG 70-28 after modification.

Viscosity of not more than 3PaS at 300 degrees F.

Modification at a minimum shall consist of 5% CMCR and the maximum particle size for the CMCR shall be 80 mesh (#80 sieve).
The performance grade of the neat asphalt binder shall not exceed a PG 58-XX.

The asphalt supplier shall provide testing for the neat asphalt binder and modified asphalt binder in accordance with AASHTO M320.

Fiber reinforcing materials shall be short-length polyester fibers having the following properties:

Length*	0.25in.+0.02
Elongation at Break; ASTM D2256-90	38%
Melting Point; ASTM D3418-82	>475 degrees F (246 degrees C)
Crimps/Inc; ASTM D3937-90	None
Cross Section	Round
Denier; ASTM D1577-90	4.5 Nominal dpf
Tensile Strength; ASTM D2256-90	>70,000 psi
Diameter	0.0085 in. **
Specific Gravity; ASTM D792-91	1.32 to 1.40

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

* At temperatures ranging from ambient to maximum finished product mix temperature

** Subject to Normal Variations

Modified asphalt-fiber compound shall be mixed at a rate of 8% fiber weight to weight of asphalt cement.

Only cracks larger than 1/4-inch in width, as determined by the Engineer, shall be sealed. Overbanding shall not exceed 4" in width after placement. **Expansion of the overband by traffic or weather will result in a deduction in the total gallons applied equal to the ratio of the expansion to the overband.** (As an example, a 1" expansion of a 4" overband will result in a 25% deduction in the total gallons of crackfiller applied.)

The air compressor shall be portable and capable of furnishing not less than 100 cubic feet of air per minute at a pressure of not less than 90 pounds per square inch at the nozzle. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water. Manually operated, gas powered air-broom or self-propelled sweeper designed especially for use in cleaning roadway pavements shall be used to remove debris, dirt, and dust from the cracks.
The melting kettle required to melt the joint sealing compound shall be an indirect fired type double-walled boiler. The space between the inner and outer walls shall be filled with a suitable heat transfer oil or substitute having a flash point of not less than 600 degrees Fahrenheit. The kettle must be equipped with a satisfactory means of agitating the joint sealer at all times by continuous stirring with mechanically operated paddles and/or by a continuous circulating gear pump attached to the heating unit. The kettle must be equipped with a thermostatic control calibrated between 200 degrees F and 550 degrees F and must be capable of pumping an 8% fiber content blend.

The equipment used in the performance of the required Work shall be subject to the approval of the Engineer and shall be maintained in a satisfactory working condition at all times.

All cracks shall be thoroughly cleaned (including vegetation) by blowing with compressed air or other approved method just prior to the placement of the joint sealing material. All cracks shall be sterilized by use of a propane air torch generating 2,000 degrees F. and 3,000 foot/second velocity to eliminate all vegetation, dirt, moisture and seeds. All debris removed from the cracks shall be removed from the pavement surface immediately by means of a power sweeper, hand or air broom.
No crackfiller material shall be placed in wet cracks or where snow, ice, or frost are present, nor when the air temperature is below 32 degrees F.

The asphalt-fiber compound shall be thoroughly mixed for a minimum of one (1) hour before application can begin. Whenever material is added to the tank, sealing operations shall be suspended for one (1) hour to allow for the minimum required mixing time. Minimum application temperature shall be 320 degrees F.

Fibers and CMCR shall be added in the presence of the Engineer and shall be added only once for each individual batch mixed in order to insure a consistent concentration of fibers in the compound. Adding fibers and other materials "on-the-fly" will not be allowed.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Sealant shall be delivered to the pavement cracks through a high pressure hose line and applicator shoe. A boiler slag aggregate shall be broadcast over the cracks to prevent sealant from being picked up. Modified asphalt-fiber crack filler will be measured for payment by the actual number of gallons of filler applied to the pavement. Modified asphalt-fiber crack filler will be paid for at the Contract Unit Price per Gallon, which price shall include all labor, material, equipment and incidental costs required to complete the Work.

ITEM 126 RUBBER CRACK FILLER

Crack sealant material shall be asphalt-vulcanized rubber material conforming to the following requirements:

1. The asphalt shall have a maximum penetration of 150 when tested in accordance with the procedure specified by the applicable AASHTO specification.

2. The granulated curb rubber (100% vulcanized) shall meet the following requirements:

PASSING SIEVE PERCENT

No. 8, 100
No. 10, 98 – 100
No. 40, 0 – 100

The specific gravity of the granulated curb rubber shall be 1.15 ▯▯0.02 and shall be free of fabric, wire or other contaminated materials, except that up to four percent of calcium carbonate may be included to prevent particles from sticking together. Rubber materials shall be packaged in boxes of approximately 60-lb. weight, with a polyethylene liner. The boxes shall be placed on pallets and covered with a weather resistant covering. Equipment used by the Contractor shall be specifically manufactured for this purpose.

PREPARATION

1. Prior to application of hot asphalt-rubber sealant, joints and cracks shall be cleaned to remove dust, dirt, moisture and foreign material or old sealant.

2. Asphalt-rubber sealant material shall be unboxed and placed in joint and crack sealing machine for heating and mixing. The asphalt-rubber shall be heated to a minimum temperature of 300▯F. The material shall be held in the mixing tank at application temperature until very little separation of the rubber and asphalt occurs when a bead of sealant material is placed on the pavement. Sealant material may be added to the mix as long as the minimum temperature of 300▯F is maintained.

APPLICATION

1. Cracks shall be sealed from the bottom up. Sealant material shall be applied so it is flush with the surface.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

2. Traffic shall not be allowed on the material until it has cured or until it has been sanded to prevent tracking.

PAYMENT

Rubber crack filler will be measured for payment by the actual number of gallons of filler applied to the pavement. Rubber crack filler will be paid for at the Contract Unit Price per Gallon, which price shall include all labor, material, equipment and incidental costs required to complete the Work.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

ITEM 200 HOT MIX ASPHALT PAVEMENT (LOADED ON TOWN TRUCKS)

Bituminous Concrete (Hot Mix Asphalt) shall be manufactured in conformance with the material, composition, mixing, testing and plant requirements of Standard Specification Section M3. Top course mix, binder course mix and dense mix shall be furnished, as required, and loaded on Town trucks.

ITEM 201 SAND BORROW
ITEM 202 LOAM BORROW

Sand and Loam Borrow materials shall conform to the following Standard Specification subsections:

Sand Borrow - for Winter Maintenance - M 1.04.0 Type a (Washed)
Loam Borrow - M 1.05.0

Sand shall be washed and screened through a one quarter inch (1/4") screen. The sand must be coarse and free from clay, silty loam and other undesirable materials. Deliveries of sand shall be made during the vendor's normal business hours, Monday through Friday. A Town may require, at its discretion, that emergency deliveries must be made during other periods to include Saturdays, Sundays, Holidays and non-business hours Monday through Friday at no extra cost to the Town. The vendor shall complete normal and emergency deliveries within a 12 hour period after receiving a request for delivery (maximum delivery 1,000 tons per 12 hours).

Loam borrow shall be screened to removed all stones and other material larger than 1 inch.

ITEM 203 1-1/2" CRUSHED STONE (DOUBLE WASHED)
ITEM 204 3/4" CRUSHED STONE (DOUBLE WASHED)
ITEM 205 3/8" PEASTONE (DOUBLE WASHED)
ITEM 206 3/4" DENSE GRADES CRUSHED STONE

Aggregate materials shall conform to the following Standard Specification subsections:

Crushed Stone - M 2.01.1 through 2.01.6 (double washed)
Dense Graded Crushed Stone - M 2.01.7 (3/4")

A requirement for all grades of crushed stone (except dense graded) shall be that not more than 0.3% of unsatisfactory material shall pass a No.4 sieve.

ITEM 207 RECYCLED ASPHALT

The recycled asphalt material shall meet the following gradation requirements:

Sieve Designation	Percentage By Weight Passing Through
3"	100
1-1/2"	70 - 100
3/4"	50 - 85
#4	30 - 60
#50	8 - 24

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

The stone and sand material shall consist of inert material that is hard, angular, and durable, and free from cement concrete, brick, reinforcing steel, glass, wood, building rubble, loam and clay and other deleterious materials. Native round stone and materials that break up when alternately frozen and thawed or wetted and dried shall not be used. The material shall be "T-base" as manufactured by Aggregate Industries, Inc. or approved equivalent.

Each stockpile shall be tested (at no additional cost to the Town) for sieve analysis and California Bearing Ratio (CBR) by an independent, qualified Massachusetts laboratory. The certified results shall be equal to or

greater than that of gravel borrow (M1.03.0 type b), and the certifications shall be supplied to each Town. The processed material shall be stockpiled in such a manner as to minimize segregation of particle sizes. All recycled pavement material shall come from approved stockpiles.

The material shall be subject to review and approval by a Town prior to delivery.

ITEM 208 4'x4' PRECAST LEACH GALLEY
ITEM 209 1,000 GALLON PRECAST SOLID CATCH BASIN
ITEM 210 1,000 GALLON PRECAST LEACH BASIN
ITEM 211 4' DIAMETER PRECAST CATCH BASIN W/OFFSET TOP

All precast structures shall be capable of withstanding H-20 loading with a minimum concrete strength of 4,000 psi @ 28 days. Steel reinforcement shall be Grade 60 meeting ASTM-A-615 requirements.

The 1,000 Gallon Precast Solid Catch Basin shall have a solid bottom or include a 6' diameter Basin Pad meeting the same requirements as the structures. The cost of the Base Pad shall be included with the cost of the structure.

The 4' Diameter Precast Catch Basin w/Offset Top shall have separate top with an offset opening. The structure shall have a 4 foot deep sump below the outlet pipe.

The Town shall specify the hole diameter and hole location(s) at the time of order.

The manufacturer shall deliver the structure to the Town DPW or at the installation location as specified by the Town.

Payment for the precast drainage structures shall be by the Contract Unit Price per Each delivered.

ITEM 212 PRECAST GUTTER INLET EACH
ITEM 213 8" FRAME AND COVER EACH
ITEM 214 8" FRAME AND GRATE MUNICIPAL STANDARD EACH
ITEM 215 12" HOOD EACH
ITEM 216 12" REINFORCED CONCRETE PIPE (CLASS IV) EACH
ITEM 217 12" CORRUGATED PLASTIC (POLYETH.) PIPE EACH

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

All precast structures shall be capable of withstanding H-20 loading with a minimum concrete strength of 4,000 psi @ 28 days. Steel reinforcement shall be Grade 60 meeting ASTM-A-61 5 requirements. Gutter Inlets shall Acme-Shorey Model GI or similar with minimum outside dimensions of 30” by 30” and capable of withstanding an HS-20 load.

The word "DRAIN" shall be prominently cast in the top of all drain manhole covers. Frame and Covers shall be East Jordan Iron Works Massachusetts Standards Manhole Frame and Cover Type B or similar 8” frame and cover matching MassDOT Constructions Details E 202.7.0.

Frame and Grates shall be East Jordan Iron Works LF248-4-40 or similar 8” frame and grate matching MassDOT Construction Details E 201.6.0

Reinforced Concrete Pipe shall conform to MassDOT Section M5.02.1 and the AASHTO M170 for Standard Strength Reinforced Concrete Culvert Pipe for class III Pipe, Wall B. Pipes shall be of the bell and spigot type and capable of supporting an HS-20 live load. A preformed flexible plastic sealing compound of Butyl Mastic Rope Sealer ” 1" size, "EZ Stick" as manufactured by Concrete Products supply or an approved equal shall be provided for sealing watertight joints.

Corrugated Plastic (Polyethylene) Pipe shall conform to MassDOT Section M5.03.10. Pipe shall be smooth interior wall and corrugated exterior wall, and be water-tight. Pipe shall be minimum 12- inch diameter. Ends shall be bell-and-spigot and comply with the requirements for test methods, dimensions and markings found in AASHTO Designations M252 and M294. Pipe shall support an HS-20 live load with a maximum deflection of 5% of the minimum pipe diameter. Pipe and fittings shall be made from virgin polyethylene compounds which conform to the applicable current edition of the AASHTO Material Specifications for cell classification as defined and described in ASTM D3350. Nominal sizes of 12- to 60-inch shall be either AASHTO Type 'S' or Type 'D

Catch basin hoods shall protrude no more than 12 inches beyond the end of pipe into the structure. Acceptable hoods are Ground Water Rescue Inc. Eliminator, Best Management Practices Inc. Snout® or equal lightweight hood.

ITEM 218 RIPRAP

Material shall conform to the provisions of Section M2.02.2 of the latest Massachusetts Department of Transportation Standard Specifications and the following:

Stone for dumped riprap shall be hard, durable, angular in shape, resistant to weathering and shall meet the gradation requirement specified below. Rounded stones, boulders, sandstone or similar soft stone or relatively thin slabs will not be acceptable.

MAXIMUM PERCENT OF TOTAL WEIGHT

SIZE OF STONE	SMALLER THAN GIVEN SIZE
400 lb.	100
300 lb.	80
200 lb.	50
*25 lb.	10

*No more than 5% by weight shall pass a 2 in. sieve.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

Each stone shall weigh not less-than 50 pounds and at least 75% of the volume shall consist of stones weighing not less than 500 pounds each. The remainder of the stones shall be so graded that when placed with the larger stones the entire mass will be compact.

METHOD OF MEASUREMENT AND BASIS OF PAYMENT

Item A2 RIP RAP shall be paid at the price per TON, which shall be the full payment of all labor, materials, equipment, tools and other incidentals necessary for the delivery of the material to the Eastham DPW Yard, based on truck weight slips.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

CONTRACT SIGNATURES

In Witness whereof, the parties to these present have hereunto set their hands and seals, Barnstable County, who incurs no personal liability by reason of the execution hereof or anything herein contained, on the day and year hereinbefore first written and who hereby certifies under penalties of perjury that all the applicable provisions of General Laws, Chapter 149 Section 44J, have been complied with.

The undersigned further certifies under penalties of perjury that the said undersigned is not presently debarred from doing public construction work in the Commonwealth under provisions of section twenty-nine F of Chapter twenty-nine. or any other applicable debarment provisions of any other chapter of the General Laws or any rule or regulation promulgated thereunder.

BARNSTABLE COUNTY

BY Signed by: A0934ZDAG681496... _____ 3/26/2026

Michael Dutton, County Administrator — Date

FIRM NAME Robert B Our Co Inc

BY DocuSigned by: Abigail Rose 8A6AD273E0B642E... _____ 3/20/2026

Abigail Rose, Vice President — Date

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

APPENDIX - A

MOST COMMONLY USED STANDARD FORMS

Schedule for Participation by MBE/WBE

Change Order

Statement of Compliance

Certified Payroll

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

BARNSTABLE COUNTY

Project: _____ Title: _____

Project Location: _____

SCHEDULE FOR PARTICIPATION BY WOMEN/MINORITY BUSINESS ENTERPRISE

A. General Contractor must submit to the Office within (5) five working days of the award of Bids.

BIDDER CERTIFICATION:

A. Bidder agrees to expend at least the amount of the contract set forth below if awarded, for W/MBE. For the purposes of this commitment, the designation means a business that has been certified by SDO as such. The Bidder must indicate the W/MBE it intends to utilize in this document as follows: (Attach sheet if additional space is required.)

	Company Name &Address	W/MBE	Nature of Participation	If Supplier W/MBE%	Dollar Value of Participation
1.	_____	_____	_____	_____	_____
2.	_____	_____	_____	_____	_____
3.	_____	_____	_____	_____	_____
4.	_____	_____	_____	_____	_____
5.	_____	_____	_____	_____	_____
6.	_____	_____	_____	_____	_____
7.	_____	_____	_____	_____	_____

Total Dollar Value of WBE Commitment: $ _____

Total Dollar Value of MBE Commitment: $ _____

Total Dollar Amount $ _____

The undersigned hereby certifies that he or she read the terms of this condition and is authorized to bind the Bidder to the commitment herein set fourth.

Date _____ _____
Name of Firm

_____ _____
Authorized Signature Business Address

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

LETTER OF INTENT
(THIS FORM MAY BE PHOTOCOPIED)

Women/Minority Business Enterprise Participation
(To be Complete by W/MBE and Submitted by the General Bidder.)

Project: _____ Title: _____

Check one:
Project Location: _____ _____MBE ___ WBE

TO: _____
Name of General Bidder/filed Sub-bidder

1. My company intends to perform work in connection with the above project as:

_____ an individual

_____ a partnership

_____ a corporation

_____ a joint venture with _____

_____ other (explain) _____

2. My company has been certified by SDO and it has not changed its women/minority ownership, control, or management without notifying SDO within thirty (30) days of such a change.

3. My company understands that if your company is awarded the contract, your company intends to enter into an agreement with my company to perform the activity described below for the prices indicated. My firm also understands that your firm, as General Bidder, will make substitution only as allowed by the County Contract.

W/MBE PARTICIPATION

Item Number (if Applicable)	Description of Activity (with notation such as "Labor Only")	Quantity	Unit Price	Dollar Amount

$ _____
Total Amount

_____
W/MBE Authorized Agent

_____
W/MBE Company Name

_____
DATE

_____
W/MBE Address

_____
W/MBE Telephone No.

NOTE: To be submitted by the General contractor, to the Office within (5) FIVE WORKING DAYS of the opening Bid Award.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

INSTRUCTIONS REGARDING CHANGE ORDERS AND CONTRACT MODIFICATIONS

(Applicable to Projects Procured Under M.G.L. c. 30, §39M and M.G.L. c. 149)

1. **General Requirement**
   No changes, additions, substitutions, or eliminations in the approved **plans, specifications, quantities, or contract scope** shall be made **without prior written authorization**. This requirement applies to all public construction and public works projects procured under **M.G.L. c. 30, §39M** or **M.G.L. c. 149**.

2. **Authorized Approvals Only**
   The Contractor shall not commence any change in work until receipt of one of the following:

   - **(A)** An **Approved Change Order Form**, duly executed by the County's Authorized Official and the Contractor; **or**
   - **(B)** A **Written Authorization to Proceed**, signed by the County's Authorized Official, pending execution of the formal Change Order.

3. **Unauthorized Work**
   Any work performed **without written authorization** as described above is performed **at the Contractor's sole risk and expense.** The County shall not be responsible for the cost of unauthorized work, materials, or delays caused thereby.

4. **Change Order Procedure**

   - **a. Initiation:** Change requests may originate from the County, the Project Designer/Engineer, or the Contractor.
   - **b. Review and Approval:** All proposed changes shall be reviewed for compliance with the applicable Massachusetts General Laws, the project scope, available funding, and any grant or reimbursement requirements.
   - **c. Documentation:** Each approved change shall be documented using the County's Change Order Form and shall include:
     - A description of the change and reason
     - Reference to the affected drawing/specification section
     - Cost impact (increase or decrease)
     - Schedule impact (if any)
     - Signatures of authorized representatives

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

- **d. Recordkeeping:** All approved change orders shall be numbered sequentially and become part of the official contract record.

5. **Emergency Conditions**
   In cases of **immediate hazard to life, safety, property, or essential operations**, the Contractor may proceed only after receiving **verbal authorization** from the County's Authorized Official or Project Manager. Such authorization must be **confirmed in writing within 48 hours** and followed by an executed Change Order.

6. **Contractor Responsibility**
   The Contractor is responsible for ensuring that all work performed is consistent with the approved contract documents and authorized modifications. Failure to adhere to these requirements may result in rejection of the work and/or nonpayment for unauthorized work.

7. **Statutory Reference**
   These procedures are established pursuant to:

   - **M.G.L. c. 30, §39I and §39M**, governing public works and materials contracts; and
   - **M.G.L. c. 149, §§44A–44J**, governing building construction contracts.
     Both statutes require that any change to the contract's plans, specifications, or price be made **only through written approval** by the awarding authority.

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

BARNSTABLE COUNTY CHANGE ORDER

CHANGE ORDER #: _____ DATE: _____

CONTRACT #: _____ PROJECT #: _____

CONTRACT TITLE: _____

CONTRACTOR'S NAME: _____

CONTRACTOR'S ADDRESS: _____

_____

Original Amount of this Contract: _____

Amount of this Change Order: _____
(decrease) (increase)

REVISED CONTRACT AMOUNT: _____

An (increase) (decrease) (no change) of _____ days in the contract is hereby authorized

The work to be completed under this change order is as follows:

The work to be covered by this order shall be performed under the same terms and conditions as included in the original contract.

By: _____ Date: _____
Contractor

Title: _____

Barnstable County

By: _____ Date: _____

By: _____ Date: _____

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

WEEKLY PAYROLL RECORDS REPORT
& STATEMENT OF COMPLIANCE

In accordance with Massachusetts General Law c. 149, §27B, a true and accurate record must be kept of all persons employed on the public works project for which the enclosed rates have been provided. A Payroll Form is available from the Department of Labor Standards (DLS) at www.mass.gov/dols/pw and includes all the information required to be kept by law. Every contractor or subcontractor is required to keep these records and preserve them for a period of three years from the date of completion of the contract.

On a weekly basis, every contractor and subcontractor is required to submit a certified copy of their weekly payroll records to the awarding authority; this includes the payroll forms and the Statement of Compliance form. The certified payroll records must be submitted either by regular mail or by e-mail to the awarding authority. Once collected, the awarding authority is required to preserve those records for three years from the date of completion of the project.

Each such contractor and subcontractor shall furnish weekly **and** within 15 days after completion of its portion of the work, to the awarding authority directly by first-class mail or e-mail, a statement, executed by the contractor, subcontractor or by any authorized officer thereof who supervised the payment of wages, this form, accompanied by their payroll:

STATEMENT OF COMPLIANCE

_____, 20_____

I,_____,_____
(Name of signatory party) (Title)

do hereby state:

That I pay or supervise the payment of the persons employed by

_____ on the _____
(Contractor, subcontractor or public body) (Building or project)

and that all mechanics and apprentices, teamsters, chauffeurs and laborers employed on said project have been paid in accordance with wages determined under the provisions of sections twenty-six and twenty-seven of chapter one hundred and forty nine of the General Laws.

Signature _____

Title _____

Docusign Envelope ID: EFAAEEE4-8503-400C-8D46-CA8A556363D1

MASSACHUSETTS WEEKLY CERTIFIED PAYROLL REPORT FORM

Company's Name:	Address:	Phone No.:	Payroll No.:

Employer's Signature:	Title:	Contract No:	Tax Payer ID Number	Work Week Ending:

Awarding Authority's Name:	Public Works Project Name:	Public Works Project Location:	Min. Wage Rate Sheet Number

General / Prime Contractor's Name:	Subcontractor's Name:		"Employer" Hourly Fringe Benefit Contributions			
						(B+C+D+E) (A x F)

Employee Name & Complete Address	Work Classification:	Employee is OSHA 10 certified (?)	Appr. Rate (%)	Hours Worked Su.	Mo.	Tu.	We.	Th.	Fr.	Sa.	Project Hours (A) All Other Hours	Hourly Base Wage (B)	Health & Welfare Insurance (C)	ERISA Pension Plan (D)	Supp. Unemp. (E)	Total Hourly Prev. Wage (F)	Project Gross Wages Total Gross Wages	Check No. (H)

Are all apprentice employees identified above currently registered with the MA DLS's Division of Apprentice Standards? YES ☐ NO ☐

For all apprentices performing work during the reporting period, attach a copy of the apprentice identification card issued by the Massachusetts Department of Labor Standards / Division of Apprentice Standards. No apprentices are identified above ☐

NOTE: Pursuant to MGL c. 149, s. 27B, every contractor and subcontractor is required to submit a **true and accurate** copy of their certified weekly payroll records to the awarding authority by first-class mail or e-mail. In addition, each weekly payroll must be accompanied by a statement of compliance signed by the employer. Failure to comply may result in the commencement of a criminal action or the issuance of a civil citation.

Date Received by Awarding Authority
/ /